345. If any tension reinforcement in a beam attains its yield stress during loading before the concrete in the compression zone fails due to crushing, the beam is said to be

(a) Under-reinforced (b) Over-reinforced
(c) Balanced (d) Non homogeneous

TSGENCO_2015

Ans. (a) : In any tension reinforcement in a beam attains its yield stress during loading before the concrete in the compression zone fails due to crushing, the beam is said to be Under-reinforced.

346. According to ISI recommendations, the maximum depth of stress block for balanced section of a beam of effective depth 'd' is :

(a) 0.43 d (b) 0.55 d
(c) 0.68 d (d) 0.85 d

TRB Poly. Lect. Tech. 2017

Ans. (b) According to ISI recommendations, the maximum depth of stress block for balanced section of a beam of effective depth 'd' is 0.55 d.

347. Under service loads the crack width in concrete should not exceed under mild exposure as per IS 456 is :

(a) 0.1 mm (b) 0.3 mm
(c) 0.2 mm (d) 0.4 mm

TRB Poly. Lect. Tech. 2017

Ans. (b) : Under service loads the crack width in concrete should not exceed 0.3 mm under mild exposure as per IS 456.

348. Flexural strength of concrete can be assumed as

(a) $0.7 \times f_{ck}$ (b) $7\sqrt{f_{ck}}$
(c) $0.7 \times \sqrt{f_{ck}}$ (d) None of the above

BPSC Poly. Tech. Lect. 2016

Ans. (c) : Flexural strength of concrete i.e.,

$$f_{cr} = 0.7\sqrt{f_{ck}}$$

f_{ck} = characteristic strength of concrete.

- modulus of elasticity of concrete (As per IS 456-2000) = $E_c = 5000\sqrt{f_{ck}}$ N/mm^2

349. For aggressive environment (exposure condition as severe), the assessed surface width of cracks should not exceed

(a) 0.1 mm (b) 0.3 mm
(c) 0.2 mm (d) 0.4 mm

BPSC AE Aug. 2019 Paper-V

Ans. (a) : As per **IS 456 : 2000, (Cl - 35.3.2)**- For structures in aggressive environmental condition, the assessed surface width of cracks should not exceed 0.1 mm.
Generally, surface width of cracks should not exceed 0.3mm.

350. The estimated flexural strength (MPa) of a concrete having a measured compressive strength of 64 MPa would be (as per IS 456)

(a) 7.2 (b) 6.4
(c) 5.6 (d) 4.8

UPRVUNL AE 2016

Ans.: (c) Given – $f_{ck} = 64$ MPa
Flexural Strength $= 0.7\sqrt{f_{ck}}$
$\therefore \quad = 0.7\sqrt{64}$
$= 8 \times 0.7$
$= 5.6$ MPa

351. The factor of safety for steel in working stress method is

(a) 1.7-1.8 (b) 3
(c) 1.15 (d) 1.5

GPSC AE June 2019


Ans. (a) : The factor of safety for steel in working stress method is 1.7 to 1.8.
For concrete in WSM = 3

352. For earthquake resistant design, both ends of vertical stirrups on a beam should be bent at an angle of

(a) 45 (b) 90
(c) 135 (d) 175

GPSC AE June 2019

Ans. (c) : The ends of stirrups are bent at 135°. Such stirrups do not open during strong earthquake shaking.



353. As per code, minimum grade of concrete in reinforced concrete design, where concrete surface is exposed of sea water spray is

(a) M30 (b) M40
(c) M35 (d) M20

GPSC AE June 2019

Ans. (c) : As per IS 456 : 2000, M 35 minimum grade of concrete in reinforced concrete design, where the concrete surface is exposed to sea water spray.

354. The Young's modulus of M25 grade concrete?

(a) 25×10^4 N/mm^2 (b) 25×10^5 N/mm^2
(c) 25×10^3 MPa (d) 25×10^6 MPa

GPSC AE June 2019

Ans. (c) : Grade of concrete = M25
Young's modulus = $5000\sqrt{f_{ck}}$
$= 5000\sqrt{25}$
$= 25 \times 10^3$ MPa

355. The ultimate tensile strain in steel is in the range of

(a) 0.012–0.020 (b) 0.0012–0.0020
(c) 0.12–0.20 (d) None of these

GPSC AE June 2019

Ans. (b) : The ultimate tensile strain in steel is in the range of 0.0012 – 0.0020.

356. If, in any given plane, one end of the column is unrestrained, its unsupported length '*l*' shall not exceed ..... Where 'b' is width and 'D' is depth of cross section in plane under consideration.

Search on Telegram @apna_pdf

(a) $\frac{100b}{D}$ (b) $\frac{100b^2}{D}$

(c) $\frac{100D}{b}$ (d) $\frac{100D^2}{b}$

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (b) : If, in any given plane, one end of the column if unstrained, its unsupported length *l* shall not exceed $\frac{100\ b^2}{D}$

Where b = width
D = depth

357. For high yield strength deformed bars of grade Fe 500, the permissible stress in direct tension and flexure tension shall be ..... used in working stress method.

(a) $0.87 f_y$ (b) $0.67 f_y$

(c) $0.55 f_y$ (d) $0.48 f_y$

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (c) : The permissible stress is direct tension and flexure tension shall be 0.55 f_y used in working stress method.

358. Analysis of cracks in various structural elements in a building is as follows :
Crack 1 : Cracks on RCC components, due to non-consideration of loads acting on the element on design
Crack 2 : Formation of the crack due to the use of poor quality materials.
Crack 3 : Crack in the foundation due to overloading of structure not considered in design.
Crack 4 : Diagonal crack in a masonry wall due to temperature/moisture variations.
Identify the cracks as structural cracks (SC) and non-structural cracks (NSC).

(a) SC : Crack 4;
NSC : Crack1, Crack2, Crack3

(b) SC : Crack1, Crack4;
NSC : crack2, Crack3

(c) SC : Crack1, Crack2, Crack3;
NSC : Crack 4

(d) SC : Crack1;
NSC : Crack2, Crack3, Crack4

BHEL ET 2019

Ans. (c) : Structural cracks :
- Cracks on RCC components, due to non-consideration of loads acting on elements on design
- Formation of the crack due to the use of poor quality material.
- Cracks in the foundation due to overloading of structure not considered in design.
- Vertical cracks that are wider at the top or bottom.

Non-structural cracks :
- Vertical to diagonal cracks.
- Cracks in plaster.
- Cracks at the corners of doors and windows.

359. The modulus of elasticity of concrete 'E_c (N/mm^2) can be assumed as follows :

(a) $E_C = 5700 (f_{ck})^{1/2}$ (b) $E_C = 0.7 (f_{ck})^{1/2}$

(c) $E_C = 1.85 (f_{ck})^{1/2}$ (d) $E_C = 5000 (f_{ck})^{1/2}$

Where, f_{ck} is characteristic cube compressive strength in N/mm^2

GPSC Assistant Prof. 2016

Ans. (d) : As per codel provision, [IS 456 - 2000]
$E_C = 5000 \sqrt{f_{ck}}$
As per IS 456-1978, $E_C = 5700 \sqrt{f_{ck}}$

360. The modulus of elasticity of structural steel is taken as

(a) 2.0×10^5 kg/m^2 (b) 2.0×10^5 N/mm^2

(c) 2.0×10^5 kN/m^2 (d) 2.0×10^5 N/m^2

GPSC Assistant Prof. 2016

Ans. (b) : As per IS 800 : 2007
$E_s = 2.0 \times 10^5$ N/mm^2
$E_s \rightarrow$ modulus of elasticity of structural steel
- Modulus of rigidity, $G = 0.76 \times 10^5$ N/mm^2 (MPa)
- Coefficient of thermal expansion, $\alpha = 12 \times 10^{-6}$/°C

361. Along the neutral axis of a simply supported beam in pure bending

(a) fibres do not undergo any strain
(b) fibres undergo some minimum strain
(c) fibres undergo maximum strain
(d) fibres undergo maximum stress

GPSC Assistant Prof. 2016

Ans. (a) : For a beam subjected to a pure bending moment the stresses generated on the neutral layer is zero. Neutral axis is the line of intersection of neutral layer with the transverse section.

362. In case of simply supported RCC beam the maximum value of $\frac{\text{Span}}{\text{Depth}}$ ratio is:

(a) 5 (b) 20

(c) 10 (d) None of the above

PTCUL AE 2016

Ans. (b) : As per IS 456 : 2000 the maximum value of $\frac{\text{Span}}{\text{Depth}}$ = 20 for simply supported beam
= 26 for continuous beam
= 7 for cantilever beam

363. Minimum grade of reinforced concrete in sea water:

(a) M15 (b) M20

(c) M30 (d) M40

PTCUL AE 2016

Ans. (c) : Minimum grade for PCC is M20 and the minimum grade for RCC is M30 for concreting in sea water.

364. The modular ratio 'm' of a concrete whose permissible compressive stress is 'C', may be given by:-

(a) m = 700/3C (b) m = 2800/3C

(c) m = 3500/3C (d) m = 1400/3C

UPPCL AE 2014

Ans. (*) : Modular ratio $= (m) = \frac{280}{3\sigma_{cbc}} = \frac{280}{3C}$

Options are incorrect.

Search on Telegram @apna_pdf

365. The section in which concrete is not fully stressed to its maximum permissible value while stress in steel reaches its maximum value, is called

(a) Under reinforced section
(b) Critical section
(c) Over reinforced section
(d) Balanced section

APPSC AEE 2016

Ans. (a) : Under reinforced beam- Reinforced concrete beam sections in which the steel reaches yield strain at loads lower than the load at which the concrete reaches failure strain are called under reinforced sections.

366. Modular ratio (m) for concrete can be calculated as .....

(a) $250/\sigma_{cbc}$ (b) $280/3\sigma_{cbc}$
(c) $280/\sigma_{cbc}$ (d) $250/3\sigma_{cbc}$

GPSC AE January 2018

Ans. (b) : Modular ratio (m) $= \frac{280}{3\sigma_{cbc}} = \frac{E_s}{E_c}$

$= \frac{\text{Young's modulus of elasticity of steel}}{\text{Young's modulus of elasticity of concrete}}$

367. In the context of provisions given in IS 456:2000, consider the following statements:

Statement–1: The modulus of concrete E_c may be estimated using the equation $E_c = 500\ (f_{ck})^{0.5}$ where f_{ck} is the characteristic strength of the concrete.

Statement–2: The minimum grade of concrete that can be used in reinforced concrete construction is M15.

Which of the following is CORRECT?

(a) Statement-1 is TRUE and Statement -2 FALSE
(b) Both statements are FALSE
(c) Statement-1 is FALSE and Statement–2 is TRUE
(d) Both statements are TRUE

UPPCL AE 2018

Ans. (b) : Statement (I) :

The modulus of concrete $f_c = 5000\sqrt{f_{ck}}$

Statement (II) :

The minimum grade of concrete that can be used in reinforced concrete construction is M20.

368. Under-reinforced concrete beams fail due to _____.

(a) crushing of concrete
(b) ductile failure of reinforcing bars
(c) tensile failure of concrete
(d) brittle failure of reinforcing bars

UPPCL AE 2018

Ans. (b) : Under-reinforced concrete beams fail due to ductile failure of reinforcing bars.

369. Working stress method is based on _____ .

(a) Maximum shear stress theory
(b) Linear elastic theory
(c) Maximum distortion theory
(d) Material failure theory

UPPCL AE 2019

Ans. (b) This method is based on the elastic theory which assumes that concrete and steel are elastic and the stress strain curve is linear for both.

- In this method the factor of safety are applied to the yield stresses to get permissible stresses.

370. According to IS 456, simply supported beam of effective depth, d and breadth, b shall be so proportioned that the clear distance between the lateral restraints does not exceed

(a) 60b or $\frac{250b^2}{d}$, which is less
(b) 25b or $\frac{100b^2}{d}$, which is less
(c) 60b or $\frac{100b^2}{d}$, which is less
(d) 25b or $\frac{250b^2}{d}$, which is less

LMRC AM 2015

Ans (a) According to the IS code 456 : 2000 clause 23.3. A simply supported or continuous beam shall be so proportioned that clear distance between the lateral restraints does not exceed 60 b or 250 b^2/d whichever is less

Where, d = effective depth of the beam

b = breath of the compression face midway between the lateral restraints.

$$\left.\begin{aligned} L &\nless 60\ b \\ &\nless 250\frac{b^2}{d} \end{aligned}\right\} \text{whichever is less}$$

For cantilever beam : Clear distance between the free end of cantilever and lateral restrain shall not exceed.

$$25\ b \text{ or } \frac{100b^2}{d}, \text{ whichever is less.}$$

371. The maximum stress to which any member is designed is much less than the ultimate stress. This stress is called as:

(a) Limit stress (b) Working stress
(c) Nominal stress (d) True stress

LMRC AM 2018

Ans. (b) : The maximum stress to which any member is designed is much less than the ultimate stress. This stress is called as Working stress.

372. A reinforced concrete beam is subjected to the following bending moments :

Moment due to Dead load = 40 kNm;
Moment due to live load = 60 kNm;
Moment due to Seismic load = 20 kNm.

The design bending moment for limit state of collapse is:

(a) 180 kNm (b) 150 kNm
(c) 120 kNm (d) 144 kNm

CIL MT 2020

Ans. (b) : Design moment is maximum of,

Total load = 1.5 (D.L. + L.L) = 1.5 (40+60)=150 kNm
Total load = 1.5 (D.L. + W.L) = 1.5 (40+20)=90 kNm
Total load = 1.2 (D.L. + L.L+WL)
= 1.2 (40+60+20)=144 kNm
Hence 150 kNm is design bending moment.

Search on Telegram @apna_pdf

373. The limiting value of neutral axis for Fe 415 grade steel is

(a) 0.43 d (b) 0.46 d
(c) 0.48 d (d) 0.53 d

Haryana PSC AE 2010

Ans. (c) : Maximum depth of neutral axis

f_y (N/mm^2)	x_u
Fe 250	0.53d
Fe 415	0.48d
Fe 500	0.46 d

374. If the modular ratio is 'm', steel ratio is 'r' the critical neutral axis constant "K" is given by

(a) $\frac{m}{m-r}$ (b) $\frac{m}{m+r}$
(c) $\frac{m+r}{m}$ (d) $\frac{m^2}{r}$

Haryana PSC AE 2010

Ans. (b) : Critical neutral axis = $\frac{m}{m+r}$

m = modular ratio

375. The permissible stress to which a structural member can be subjected, is known as:

(a) Working stress (b) Bearing stress
(c) Tensile stress (d) Compressive stress
(e) Shear stress

Haryana PSC AE 2018 Paper–I

Ans. (a) : It is desirable to keep the stress lower than the maximum or ultimate stress at which failure of the material takes place. This stress is known as the working stress or design stress.
F.O.S. of steel = 1.78, concrete = 3

376. The flexural cracking strength of concrete having cube compressive strength of 25 MPa is:

(a) 3.5 MPa (b) 4.5 MPa
(c) 5 MPa (d) 17.5 MPa
(e) 22.5 MPa

Haryana PSC AE 2018 Paper–I

Ans. (a) : Flexural cracking strength of concrete is


$= 0.7\sqrt{f_{ck}}$ $= 0.7\sqrt{25} = 3.5\,MPa$

377. The failure strain in (i) axial and (ii) bending compression are respectively taken as:

(a) 0.02 and 0.035 (b) 0.002 and 0.0035
(c) 0.002 and 0.003 (d) 0.035 and 0.02
(e) 0.0035 and 0.002

Haryana PSC AE 2018 Paper–I

Ans. (b) : As per code 456-2000



strain diagram

Axial compression strain of concrete 0.002
In Bending maximum normal compression strain is 0.0035

378. In a reinforced concrete (RC) liquid storage tank, the permissible compressive stress due to bending in concrete is given as 8.5 N/mm^2. What long-term modular ratio should be taken in the design of the tank?

(a) 9.8 (b) 10.98
(c) 13.33 (d) 18.67
(e) None of the above options

Haryana PSC AE 2018 Paper–I

Ans. (b) Modular Ratio (m) $= \frac{280}{3\sigma_{cbc}} = \frac{280}{3\times 8.5} = 10.98$

379. As compared to working stress method of design, limit state method takes concrete to:

(a) A higher stress level
(b) A lower stress level
(c) The stress level
(d) Sometimes higher but generally lower stress level

Haryana PSC AE 2017

Ans. (a) :

Working stress method	Limit state method
• In this design method, members are designed to never go beyond their elastic range	• The stress in material is allowed to go beyond the yield limit and enter into the plastic zone to reach ultimate strength.
• WSM is a elastic design method	• LSM is a plastic design method
• WSM is stress based method	• LSM is strain based method

380. In a singly Reinforced Beam, if the permissible stress in concrete reaches earlier than the permissible stress in steel, the Beam section is called:

(a) Under Reinforced Section
(b) Economic Section
(c) Critical Section
(d) Over Reinforced Section

RRB SSE Bilaspur : 21.12.2014

Ans : (d) Reinforced concrete beam sections in which the failure stain in concrete is reached earlier than the yield strain of steel is reached, are called over-reinforced beam sections.

381. If the characteristic strength of concrete is 30 MPa, then the short-term static modulus of elasticity in MPa is :

(a) 27386 (b) 16431
(c) 2738 (d) 21908

HPPSC Poly. Lect. 2016

Ans : (a) $E_c = 5000\sqrt{f_{ck}}$
For, M30 f_{ck} = 30 MPa
$E_c = 5000\sqrt{30}$
E_c = 27386 MPa

382. Which of the following characterizes the typical failure of an over-reinforced ratio higher than the balanced ratio?

(a) The steel yields and large deflections and tensile cracks will be observed prior to failue

Search on Telegram @apna_pdf

(b) The concrete crushes and large deflections and tensile cracks will be observed prior to failure.
(c) The steel yields and the beam fails suddenly without warning
(d) The concrete crushes and the beam fails suddenly without warning

HPPSC Poly. Lect. 2016

Ans : (d) Reinforced concrete beam sections in which the failure strain in concrete is reached earlier than the yield strain of steel, are called over reinforced beam sections. The failure in over reinforced section is sudden.

383. The moment of resistance of a RCC balanced section is given by :

(a) $\frac{1}{3}\sigma_{cbc} b_n \left(d - \frac{n}{2}\right)$ (b) $\frac{1}{2}\sigma_{cbc} b_n \left(d - \frac{n}{3}\right)$

(c) $\frac{1}{3}\sigma_{cbc} b_n \left(d - \frac{n}{3}\right)$ (d) $\frac{1}{2}\sigma_{cbc} b_n \left(d - \frac{n}{2}\right)$

GPHC AE 2018

Ans : (b) The moment of resistance of a RCC balanced-Section is :

$$\Rightarrow \frac{1}{2}\sigma_{cbc} b_n \left[d - \frac{n}{3}\right]$$

$\sigma_{cbc} \rightarrow$ Permissible stress in concrete.
$n \rightarrow$ Distance of Neutral axis below the top of beam.
$d \rightarrow$ Depth of the beam.

384. Ductility of a flexural member (Reinforced concrete) can be increased by

(a) increasing percentage of tensile reinforcement
(b) decreasing percentage of tensile reinforcement
(c) decreasing percentage of compressive reinforcement
(d) decreasing the shear reinforcement

WBPSC AE 2016

Ans. (b) : Ductility of a flexural member (Reinforced concrete) can be increased by decreasing percentage of tensile reinforcement.

385. For a single reinforced beam if concrete reaches it maximum allowable stress earlier than steel, the beam is known as

(a) under reinforced (b) over reinforced
(c) critical section (d) economic section

WBPSC AE 2014

Ans. (b) : Over reinforced section–If the area of steel provided is more than that required for a balanced section it is known as over reinforced section.

386. The all evable tensile stress in mild steel stirrups in E.C. structure (working stress method) is

(a) 140 N/mm^2 (b) 190 N/mm^2
(c) 230 N/mm^2 (d) 250 N/mm^2

WBPSC AE (PHE) 1998

Ans. (a) :

387. In the working stress method of R.C. design, permissible bending compressive stress in concrete is approximately equal to

(a) 0.40 fcn (b) 0.33 fcn
(c) 0.25 fcn (d) 0.20 fcn

WBPSC AE (PHE) 1998

Ans. (b) : The working stress method is based upon the concept of permissible stresses permissible stresses are obtained by dividing the ultimate strength of concrete or yield strength of steel (0.2% proof stress) by appropriate factors of safety.

388. The limiting value of depth of neutral axis for concrete beam of overall depth 300 mm and Fe 415 grade steel with effective cover 50 mm is:

(a) 144 mm (b) 132 mm
(c) 115 mm (d) 120 mm

TSPSC AEE 2017

Ans. (d) : Limiting depth of neutral axis =

$$X_u, \lim = \frac{700}{0.87 f_y + 1100} \times d$$

$$X_u, \lim = \frac{700}{0.87 \times 415 + 1100} \times (300 - 50)$$

$X_u, \lim = 119.776 \simeq 120$ mm

389. What will be the compressive strength of concrete if the flexural tensile strength of concrete is 3.5 MPa?

(a) 25 MPa (b) 12.5 MPa
(c) 5 MPa (d) 2.5 MPa

TSPSC AEE 2017

Ans. (a) : Flexural tensile strength = $f_{cr} = 0.7\sqrt{f_{ck}}$

$$3.5 = 0.7\sqrt{f_{ck}}$$

$$f_{ck} = \frac{(3.5)^2}{(0.7)^2} = 25 \text{ MPa}$$

390. The short term static modulus of elasticity for concrete of grade M 25 is

(a) 25 GPa (b) 2500 MPa
(c) 2.5 GPa (d) 250 MPa

TSPSC AEE 2017

Ans. (a) : The short term static modulus of elasticity

$= E_c = 5000\sqrt{f_{ck}}$

$E_c = 5000\sqrt{25} = 25000$ N/mm^2 = 25 GPa

391. The target mean strength of concrete mix for characteristic compressive strength of 40 MPa is

(a) 45.8 MPa (b) 48.3 MPa
(c) 46.6 MPa (d) 49.9 MPa

TSPSC AEE 2017

Ans. (b) : Target mean strength = $f_{cm} = f_{ck} + 1.65 \times \sigma$
for M40 grade of concrete –
$\sigma = 5$ (by referring table 1 of IS 10262:2009
$f_{cm} = 40 + 1.65 \times 5$
$f_{cm} = 48.25$

Search on Telegram @apna_pdf

3. Shear and Bond Strengths of Reinforced Concrete Section

392. In limit state design, permissible bond stress in the case of deformed bars is more than in the plain bars by what percentage?
(a) 25 (b) 35
(c) 40 (d) 50
(e) 60

CGPSC AE 2014 Shift–I

Ans. (e) : Permissible bond stress as per IS 456-2000

	M15	M20	M25	M30	M35	M40
WSM	0.6	0.8	0.9	1.0	1.1	1.2
LSM	-	1.2	1.4	1.5	1.7	1.9

- These value of bond stress is for plain bar in tension.
- For deformed bar the above value should be increased by 60% (tension).
- For bar in compression on the above value should be increased by 25%.

393. If the estimated modulus of elasticity is 30 GPa, then the probable variation (according to IS 456) of the actual values (in GPa) could be between
(a) 27-33 (b) 24-36
(c) 25.5-34.5 (d) 28.5-31.5
(e) 25-35


CGPSC AE 2014 Shift–I

Ans. (b) : As per IS 456-2000,
E_S = 30 GPa
probable variation = ± 6

394. Shear failure at sections of simply supported beams and cantilever beam without shear reinforcement will normally occur on plane inclined at an angle
(a) 30 degree to the horizontal
(b) 30 degree to the vertical
(c) 45 degree to the horizontal
(d) 45 degree to the vertical
(e) 25 degree to the vertical

CGPSC AE 2014 Shift–I

Ans. (a) :



Above figure show that, the shear failure of simply supported & cantilever beam without shear reinforcement the failure plane is normally inclined at an angle of 30^0 to the horizontal.

395. As per IS 1343, at the time of initial tensioning, the maximum tensile stress immediately behind the anchorages shall be limited to p percent of the ultimate tensile strength of the wire, where in p is
(a) 85 (b) 67
(c) 50 (d) 80
(e) 72

CGPSC AE 2014 Shift–I

Ans. (d) : As per IS 1343 : 1980, (Cl 18.5.1) - at the time of initial tensioning, the maximum tensile stress immediately behind the anchorages shall not exceed 80% of ultimate tensile strength of the wire or bar or stand.

396. According to IS 3414, the recommended spacing of expansion joints for thin unprotected slabs is
(a) 30 m (b) 45 m
(c) 6 m (d) 12 m

CGPSC AE 2014 Shift–I

Ans. (a) : According to IS 456-2000, structure exceeding 45 m in length are designed with one or more expansion joint.
As per IS 3414, which is a specific code for joints, it is mentioned as 30 m.

397. A Ready-mix concrete supplier supplied 101 cum of concrete for a slab. As per the minimum sampling frequency, the number of cube samples required are
(a) 5 (b) 4
(c) 7 (d) 6
(e) 3

CGPSC AE 2014 Shift–I

Ans. (a) : As per IS 456 : 2000
Frequency of sampling
Minimum sample of cube per m^3 concrete quantity.
for 1-5 m^3 concrete – 1 sample – 3 cube
for 6-15 m^3 concrete – 2 sample – 6 cube
for 16-30 m^3 concrete – 3 sample – 9 cube
for 31-50 m^3 concrete – 4 sample – 12 cube
for greater than 51 m^3 concrete – (4+1) sample
i.e. for every 50 m^3 1 sample additional.

398. The minimum period before striking the props to a beam spanning 7.5 m is
(a) 3 days (b) 16 - 24 h
(c) 7 days (d) 14 days
(e) 21 days

CGPSC AE 2014 Shift–I

Ans. (e) : If span of beam is upto 6m, it is propped for 14 days & above 6m is propped for 21 days.

399. As per IS 456, the minimum cement content for the respective durability classes can be reduced by R kg/cum while changing the maximum size of aggregate from 20 mm to 40 mm, where in R is
(a) 10 (b) 15
(c) 20 (d) 25
(e) 30

CGPSC AE 2014 Shift–I

Ans. (e) : As per IS 456, the minimum cement content, while changing the maximum size of aggregate from 20 mm to 40 mm is 30 kg/m^3.

Search on Telegram @apna_pdf

400. Lap splices shall not be used without additional precautions beyond bar diameter of

(a) 28 mm (b) 30 mm
(c) 32 mm (d) 36 mm
(e) 40 mm

CGPSC AE 2014 Shift–I

Ans. (d) : Splice at point of maximum tensile stress shall be avoided wherever possible, splices where used shall be welded, lapped or otherwise fully developed. Lapped splices in tension shall not be used for bars of sizes larger than 36 mm diameter and such splices shall preferably be welded.
Note: after the latest amendment the bar beyond the 32mm diameter shall not be lapped. It should be welded.

401. For vertical stirrups, the maximum spacing of shear reinforcement measured along the axis of the member shall not exceed :

(a) 0.75 d (b) 0.40 d
(c) 0.15 d (d) 0.12 d

TNPSC AE 2015

Ans. (a) Maximum spacing of shear reinforcement measured along the axis of the member shall not be more than 0.75d for vertical stirrups and 'd' for inclined stirrups at 45°, where 'd' is effective depth of the section.

402. In a rectangular beam of section b × d, subjected to ultimate torsional moment Tu, equivalent ultimate shear can be given as

(a) $V_u + 1.6\frac{T_u}{b}$ (b) $V_u + 1.6\frac{T_u}{bd}$

(c) $V_u + 2\frac{T_u}{b}$ (d) $V_u + \frac{T_u}{2b}$

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (a) The combined shear effects on a reinforced concrete beam, subject to flexural shear and torsional shear :

$$\left[V_e = V_u + \frac{1.6T_u}{b}\right] \quad \text{– Equivalent Shear}$$

The equivalent nominal shear stress τ_{ve} –

$$\left[\tau_{ve} = \frac{V_u + 1.6T_u / b}{bd}\right]$$

403. Generally, which of the following sections is most economical and preferred for resisting bending moments ?

(a) I-section (b) Circular
(c) Triangular (d) Rectangular

Rajasthan AE (Nagar Nigam) 2016

Ans. (a) :
■ I–Section is most economical and preferred for resisting bending moment.
ISJB – IS Junior Beam
ISLB – IS Light Beam
ISMB – IS Medium Beam
ISHB – IS Heavy Beam
ISWB – IS Wide Beam

404. A certain RCC structure has to be constructed along sea coast and will be exposed to sea water spray. What is the exposure condition according IS 456–2000 ?

(a) Very Severe (b) Mild
(c) Extreme (d) Moderate

Rajasthan AE (Nagar Nigam) 2016

Ans. (a) :

S.No.	Environment	Exposure Conditions
(i)	Mild	Concrete surfaces protected against weather or aggressive conditions, except those situated in costal area.
(ii)	Moderate	Concrete surfaces sheltered from severe rain or freezing whilst wet. Concrete exposed to condensation and rain. Concrete continuously under water. Concrete in contact or buried under non-aggressive soil/Ground water. Concrete surface sheltered from saturated salt air in coastal area.
(iii)	Severe	Concrete surface exposed to severe rain, alternate wetting and drying or occasional freezing whilst wet or severe condensation. Concrete completely immersed in sea water. Concrete exposed to coastal environment.
(iv)	Very severe	Concrete surfaces exposed to sea water spray, corrosive fumes or severe freezing conditions whilst wet concrete in contact with or buried under aggressive sub soil/ground water
(v)	Extreme	Surface of members in tidal zone, members in direct contact with liquid/solid aggressive chemicals.

405. Development length of bars is inversely proportional to _____.

(a) Shear stress (b) Bond stress
(c) Tensile stress (d) Compressive stress

LMRC AM 2019

Ans. (b) Development length of bars is inversely proportional to bond stress

The Development length $\left(L_d\right) = \frac{\phi\sigma_s}{4\tau_{bd}}$

ϕ = Nominal dia. of the bar.
σ_s = stress in bar at the section considered at design load
τ_{bd} = Design bond stress

Search on Telegram @apna_pdf

406. The percentage of steel as per IS recommendation in compression should not exceed :

(a) 0.15% (b) 1.5%
(c) 2.5% (d) 4%

Nagaland PSC CTSE 2017 Paper–I

Ans. (d) : As per IS 456-2000, Cl 26.5.1.2, the maximum area of compression or tension reinforcement shall not exceed 0.04bD i.e 4%

407. The permissible value of local bond stress for M15 (1:2:4) cement concrete is :

(a) 5 Kg/cm^2 (b) 10 Kg/cm^2
(c) 20 Kg/cm^2 (d) 50 Kg/cm^2

Nagaland PSC CTSE 2017 Paper–I

Ans. (b) : As per IS 456 Cl 26.2.1.1, Design Bond stress for M20 is 1.2 N/mm^2, So Design bond stress for M15 grade will be definitely less than 1.2 N/mm^2, around 10 kg/cm^2

Grade of concrete	Permissible stress in compression (N/mm^2)	Permissible stress in bond (average) (N/mm^2)
M15	5.0	0.96
M20	7.0	1.28
M25	8.5	1.44
M30	10.0	1.6

408. The maximum permissible shear stress given in IS : 456-1978 is based on :

(a) Diagonal tension failure
(b) Diagonal compression failure
(c) Flexural tension failure
(d) Uniaxial compression

GOA PSC Assistant Prof. 2020
Nagaland PSC CTSE 2017 Paper–I
ESE 2001, 2016

Ans. (b) : The maximum permissible shear stress, τ_{max} is based on diagonal compression failure Because If the total x-sectional area A_{sv} of bent up bar exceed a certain Limit, it is likely that the section become stronger in diagonal tension compare to diagonal compression.
Hence, a shear-compression failure may occur even before the shear reinforcement has fielded (And thus realised its full potential), Such a situation is undesirable due to brittle nature of the failure, more over, it turns out to be uneconomical, in much the same way as over reinforced Beam.

409. Diagonal tension reinforcement is provided in a beam as

(a) longitudinal bars
(b) bent up bars and vertical stirrups
(c) helical reinforcement
(d) 90^0 bend at the bend of main bar

(UKPSC AE 2012 Paper–I)
ESE 2004

Ans : (b) Bent up bars and vertical stirrups are provided to resist diagonal tension in member.

410. If a R.C. beam is likely to fail in bond, then its bond strength can be increased most economically by

(a) increasing the depth of beam
(b) using thinner bars but more in numbers
(c) using thicker bars but less in numbers
(d) providing vertical stirrups

(Uttrakhand AE 2013/
UKPSC AE 2012 Paper–I)
WBPSC AE 2012

Ans : (b) If an RC beam is likely to fail in bond, then we can use thinner bars having the same area of steel as required for the section. Using thinner bars increases the area of contact of bars with concrete, therefore increasing its bond strength.

411. The shear strength can be ensured in a beam by providing :

(a) binding wire on main bar
(b) high strength deformed bars
(c) rounded aggregates
(d) stirrups

(UKPSC AE (Paper-I) 2007)


Ans : (d) Shear stirrups are provided to ensure the shear strength of beam. Vertical or inclined stirrups provide shear resistance to members. Bent up bars are also used to provide shear resistance upto certain limit.

412. In a reinforced concrete beam the distribution of shear stress is

(a) Parabolic over and below the neutral axis
(b) Parabolic over neutral axis and rectangular below neutral axis
(c) Rectangular over neutral axis and parabolic below neutral axis
(d) Rectangular over and below neutral axis

RPSC AE 2013

Ans : (b) In a RC beam the distribution of shear stress is parabolic over neutral axis and rectangular below neutral axis.



413. Which one of the following pairs is not correctly matched in context of IS 456 provisions for reinforced concrete

(a) Footing Design – Punching shear generally considered
(b) Concrete Cover– Essential for durability
(c) Beams are mostly – without shear reinforcement
(d) Roof slab design may be-without shear reinforcement

RPSC VPITI - 2012

Ans : (c) Without shear reinforcement beams cannot retain its tension reinforcement in place. To hold tension members few rings are provided.

414. The live load to be considered for an inaccessible reinforced concrete roof, is

(a) 0 (b) 75 kg/m^2
(c) 150 kg/m^2 (d) 200 kg/m^2

UPPSC AE 12.04.2016 Paper–I
[UPPSC State Eng. A.E.2013, 2007(I), 2004 (I)]

Search on Telegram @apna_pdf

Ans : (b) The live load to be considered for an inaccessible reinforced concrete roof, is 75 kg/m^2.

415. For bar in compression, the values of bond stress for M20 grade shall be increased by

(a) 15% (b) 25%
(c) 60% (d) None of above

RPSC POLY. TECH. LECT. 2014

Ans : (b)

Concrete	M 20	M 25	M 30	M 35	M 40
Bond stress τ_{bd} N/mm^2	1.2	1.5	1.5	1.7	1.9

The code requires that τ_{bd} values may be increased 60% for deformed bars in tension, they may be further increased by 25% for bar in compression.

416. The longitudinal shearing stresses acting on the surface between the steel and concrete are called

(a) Bond stresses
(b) Tensile stresses
(c) Compression stresses
(d) None of these

RPSC POLY. TECH. LECT. 2014

Ans : (a) The longitudinal shearing stresses acting on the surface between the steel and concrete are called bond stresses. Bond strength of steel can be increased by using of smaller diameter and more number of bars so the area of steel is same.

417. If nominal shear stress τ_v exceeds the design shear strength of concrete τ_c the nominal shear reinforcement as per IS : 456 - 2000 shall be provided for a shear stress equal to

(a) τ_v (b) τ_c
(c) $\tau_v - \tau_c$ (d) $\tau_v + \tau_c$

Utrrakhand A.E. - 2013
RPSC ACF - 2011

Ans : (c) Design shear stress $\tau_{vs} = \tau_v - \tau_c$
Conditions for providing shear reinforcement
(i) If $\tau_v < \tau_c / 2$ Then no shear reinforcement
(ii) If $\tau_c / 2 < \tau_v \le \tau_c$ Minimum shear reinforcement
(iii) $\tau_c < \tau_v < \tau_{c(max)}$ then $(\tau_v - \tau_c)$ for this reinforcement is provided.
(iv) $\tau_v > \tau_{c(max)}$ Redesign the section

418. For vertical stirrups, the maximum spacing of shear reinforcement measured along the axis of the members shall not exceed

(a) 0.70 d (b) 0.75 d
(c) 0.80 d (d) 0.90 d

OPSC AEE 2015 PAPER–I
RPSC ACF - 2011

Ans : (b) Maximum spacing of shear reinforcement measured along the axis of member for vertical shear shall not exceed the lesser of 0.75 d and 300 mm, where d is effective depth of beam. Spacing of shear reinforcement can be increased towards the centre of the beam.

419. Lap length including anchorage value of hooks for bars in flexural tension shall be

(a) L_d or 20ϕ, whichever is greater
(b) $2L_d$ or 20ϕ, whichever is greater
(c) L_d or 30ϕ, whichever is greater
(d) $3L_d$ or 30ϕ, whichever is greater

[UPPSC State Eng. A.E. 2011]

Ans : (c) The lap length including anchorage value of hooks for bars in flexural tension shall be L_d or 30ϕ, whichever is greater.

420. A rectangular beam of width 200 mm and depth 300 mm is subjected to a shear force of 200kN. The maximum shear stress produced in the beam is

(a) 10.0 N/mm^2 (b) 7.5N/mm^2
(c) 5.0 N/mm^2 (d) 3.33 N/mm^2

(UPPSC State Eng. A.E. 2003)

Ans : (c) Average shear stress $Z_{av} = \dfrac{V}{bd}$

$$= \frac{200 \times 10^3}{200 \times 300} = \frac{10}{3} \text{N/mm}^2$$

We know that,
Maximum shear stress = 1.5 × average shear stress

$$\tau_{max} = 1.5\tau_{av}$$

$$\tau_{max} = 1.5 \times \frac{10}{3} = 5\text{N/mm}^2$$

421. In reinforced concrete members, the best way to ensure adequate bond is

(a) To provide minimum number of large diameter bars
(b) To provide more number of small diameter bars
(c) To increase the cover for the reinforcement
(d) To provide additional stirrups

GPSC AE (CLASS 1 & 2) 2019
[UPPSC State Eng. A.E. 2011]
ESE 2004

Ans : (b) : More small diameter results more (τ_{bd}) Bond strength

$$\tau_{bd} = \frac{V}{\Sigma Pjd}$$

Sum of perimeter of all reinforcement $\Sigma P_i = n \times (\pi\phi)$
V = Shear force at any section
d = effective depth of section

422. The bond between steel and concrete is mainly due to

(a) adhesive resistance
(b) frictional resistance
(c) mechanical resistance
(d) all of these

[UPPSC State Eng. A.E. 2008]

Ans : (d) The bond between steel and concrete depends mainly on frictional resistance, adhesive resistance between concrete and steel and on some extent mechanical resistance.

423. The limiting shear stress in reinforced section of width b and effective depth d carrying shear force V is

(a) $\dfrac{V}{bjd}$ (b) $\dfrac{V}{bd}$

Search on Telegram @apna_pdf

(c) $\frac{Vb}{d}$ (d) $\frac{Vd}{b}$

[UPPSC State Eng. A.E. 2008]

Ans : (b) limiting shear stress $= \frac{V}{bd}$

where, V = shear force
b = width of beam
d = depth of beam

424. The equivalent development length of a 90^0 bend in a reinforcement bar of diameter f is

(a) 4f (b) 8f
(c) 12f (d) 16f

[UPPSC State Eng. A.E. 2008]

Ans : (b) f = diameter of bar
- for 45^0 bend = 4f
- for 90^0 bend = $2 \times 4f = 8f$
- for 180° bend = 16f

425. The maximum shear stress for M-20 grade concrete is

(a) $2.8N/mm^2$ (b) $3.1N/mm^2$
(c) $3.5N/mm^2$ (d) $3.7N/mm^2$

[UPPSC State Eng. A.E. 2007(I)]
[UPPSC State Eng. A.E. 2003]

Ans : (a)
Using LSM
- The value of $\tau_{c\,max}$ depends on the grade of concrete

Concrete Grade	M15	M20	M25	M30	M35	M40 and above
$\tau_{c\,max}$ **N/mm²**	2.5	2.8	3.1	3.5	3.7	4.0

- $\tau_{c\,max}$ is the maximum shear strength of concrete in beam.

Using WSM
- The value of $\tau_{c\,max}$ depends on the grade of concrete.

Concrete Grade	M15	M20	M25	M30	M35	M40 and above
$\tau_{c\,max}$ **N/mm²**	1.6	1.8	1.9	2.2	2.3	2.5

- $\tau_{c\,max}$ is the maximum shear strength of concrete in beam.

426. In an RCC beam the shear force is carried by

(a) concrete alone
(b) vertical stirrups
(c) vertical stirrups and inclined bars
(d) concrete, vertical stirrups and inclined bars

[UPPSC State Eng. A.E. 2004 (I)]

Ans : (d) In a RCC beam, the shear force is carried by
(i) concrete
(ii) vertical stirrups
(iii) inclined bars

427. Diagonal tension is RCC beam is due to

(a) Vertical shear stress
(b) Horizontal shear stress
(c) Vertical shear stress and horizontal shear stress
(d) Neither vertical shear stress nor horizontal shear stress

[UPPSC State Eng. A.E. 2004 (I)]

Ans : (c) As the concrete is very weak in tension it split along the diagonal (at 45°) and develops crack. This tension which is caused in the tensile zone of the beam due to shear, at near the supports is called as diagonal tension which is caused by shear and it cannot be resisted by concrete alone.

428. Spacing of shear stirrups in a R.C. rectangular beam is

(a) kept constant throughout the span
(b) decreased towards the centre of beam
(c) increased at ends
(d) increased towards the centre of the span

[UPPSC State Eng. A.E. 2004(I), 2013(I)]

Ans : (d) As shear force decrease towards centre and become zero at centre so shear stress induced in section also reduced towards centre. So the spacing of shear stirrups increased towards the centre of the span.

429. Lap length of reinforcement in compression shall not be less than

(a) 30ϕ (b) 24ϕ
(c) 20ϕ (d) 15ϕ

Where ϕ = diameter of bar.

[UPPSC State Eng. A.E. 2003]
ESE 2011

Ans : (b)
- Lap length in compression shall not be less than 24 ϕ.
- Lap length in flexible tension shall be greater of L_d or 30 ϕ.
- Lap length in direct tension shall be greater of $2L_d$ or 30 ϕ.
- where L_d is the development length.

430. The shear strength of concrete depends upon :

(a) Grade of concrete
(b) Percentage of longitudinal tensile reinforcement
(c) Shear reinforcement provided
(d) All of the above

[UPPSC State Eng. A.E. 2003, 2007 (I)]

Ans : (d) τ_c value depends upon;
(i) % tensile reinforcement
(ii) Grade of concrete

$$P_t = \frac{A_{st}}{B \times d} \times 100$$

A_{st} = Area of tensile reinforcement
Shear strength of concrete (τ_c) (LSM)

431. The development length of bars of diameter ϕ, as per IS : 456-2000 is given by

(a) $\frac{4\phi\sigma_s}{\tau_{bd}}$ (b) $\frac{\phi\sigma_s}{4\tau_{bd}}$
(c) $\frac{2\phi\sigma_s}{3\tau_{bd}}$ (d) $\frac{\phi\sigma_s}{3\tau_{bd}}$

OPSC AEE 2019 Paper–I
Rajasthan AE (Nagar Nigam) 2016
Nagaland PSC CTSE 2017 Paper–I
UPPSC Civil Eng. A.E. 2013(I)
ESE 2012
WBPSC AE 2007

Search on Telegram @apna_pdf

Ans. (b)

Development length = $\frac{\phi \sigma_S}{4\,\tau_{bd}}$

ϕ = nominal diameter of the bar.

σ_s = stress in bar at the section considered at design load.

τ_{bd} = design bond stress given in clause 26.2.1.1 of IS 456 : 2000

432. If diameter of reinforcement bar is d, the anchorage value of the hook alone will be

(a) 4d (b) 3d

(c) 12d (d) 16d

BPSC AE 2012 Paper–V

Ans : (d) If diameter of reinforcement bar is d, the anchorage value of the hook is taken 16 d. This is for U type hook bend at 180°.

At 135° anchorage value is taken as 12d, at 90° it is taken 8d, and it is taken as 45° for 4d.

433. Maximum spacing of shear reinforcement measured along the axis of the member for vertical shear shall not exceed the lesser of :

(a) 0.85d and 200m.

(b) 0.50d and 300mm

(c) 0.75d and 300mm

(d) 0.75d and 450 mm

(BPSC AE Paper V 2006)

Ans : (c) Maximum spacing of shear reinforcement measured along the axis of member for vertical shear shall not exceed the lesser of 0.75 d and 300 mm, where d is effective depth of beam. Spacing of shear reinforcement can be increased towards the centre of the beam.


434. A steel hook of 10 mm diameter is embedded in concrete for a distance 70 mm. If permissible stress in steel is 343 N/mm^2, and the bond then the maximum load that can be suspended on the hook is-

(a) 55N (b) 1540N

(c) 26950N (d) 74300N

(JPSC Combined AE Paper V 2013)

Ans : (c)



D=10 mm

L_d=70mm

$$L_d = \frac{\sigma_{st}\,\phi}{4\,\tau_{bd}}$$

$$\tau_{bd} = \frac{343 \times 10}{4 \times 70} = 12.25\,\text{N/mm}^2$$

$$\text{Load (P)} = \tau_{bd} \times \pi \times \phi \times L_d$$

$$= 12.25 \times \pi \times 10 \times 70$$

$$= 12.25 \times \frac{22}{7} \times 10 \times 70 = 26950\ \text{N}$$

435. Which statement is correct if splices are provided in the reinforcing bars?

(a) Lap splices shall not be used for bars larger than 30 mm diameter

(b) For flexure tension; Lap length = L_d or 30 ϕ whichever is greater

(c) For direct tension; Lap length = 2 L_d or 24 ϕ whichever is greater

(d) For compression members; Lap length = L_d or 30 ϕ whichever is greater

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (b) :

⇒ **Lap length –** During placing the steel in RC structure if the required length of bar is not sufficiently available to make a design length then lapping is done.

⇒ Lap length is the minimum length that must be provided if two bars are joined together such that forces can be transferred safely.

Lap length in tension

1. For flexural tension – L_d or 30ϕ whichever is greater.
2. For direct tension – 2L_d or 30ϕ whichever is greater.

   Lap length in compression,
3. The lap length in compression shall be equivalent to the development length in compression but not less than 24ϕ.

⇒ Clause 26.2.5.1 of IS 456 : 2000.

436. The usual practice of bending of a bar near a support is at an angle of-

(a) 30° (b) 45°

(c) 60° (d) 15°

MPSC (Mains) 2017 Paper–II

Ans. (b) : Bending of a bar near a support is 45°. Bending of bar is done to resist shear cracks.

437. To avoid sudden collapse just after a shear crack, minimum shear reinforcement is provided in prestressed concrete member in the form of stirrups. IS 1343 suggested the relation as-

(a) $\frac{A_{SV}}{b.S_V} = \frac{0.4d}{0.87 f_y}$ (b) $\frac{A_{SV}}{bd.S_V} = \frac{0.4}{0.87} \times f_y$

(c) $\frac{A_{SV}}{b.S_V} = \frac{0.4}{0.87 f_y}$ (d) $\frac{A_{SV}}{b.S_V} = \frac{0.4 f_{ck}}{0.87 f_y}$

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (c) : According to IS 456 : 2000, minimum value of shear R/F to be provided is given as :

$$\frac{A_{SV}}{b.S_V} = \frac{0.4}{0.87 f_y}$$

438. The maximum spacing of shear reinforcement measured along the axis of the member shall *not* exceed _____ for the vertical stirrups, where '*d*' is the effective depth of the section-

(a) 0.5 *d* (b) 0.7 *d*

(c) 0.75 *d* (d) 0.65 *d*

Maharashtra PSC (Mains) 2017 Paper–I

Search on Telegram @apna_pdf

Ans. (c) : Maximum spacing of vertical stirrups is limited to 0.75 times the effective depth and the crack which originates at an angle 45^0.

439. If nominal shear stress τ_v exceeds the design shear strength of concrete $\tau_{c'}$ the nominal shear reinforcement as per IS : 456-2000 shall be provided for a shear stress equal to-

(a) τ_v (b) τ_c
(c) $\tau_v - \tau_c$ (d) $\tau_v + \tau_c$

OPSC AEE 2015 PAPER–I

Ans. (c) : Nominal shear reinforcement is provided for nominal shear stress minus the design shear strength of concrete.

440. When width b, effective depth *d*, overall depth *D*, the maximum area of reinforcement in RCC beam shall not exceed-

(a) 0.04 *bd* (b) 0.04 *bD*
(c) 0.05 *bd* (d) 0.05 *bD*

OPSC AEE 2015 PAPER–I

Ans. (b) : According to IS code the maximum reinforcement in an RCC beam is 4% of gross cross sectional area or 0.04 bD.
b = width of beam
D = overall depth

441. The shear stress on a beam section is maximum-

(a) On the extreme bottom surface fibres
(b) On the extreme top surface fibres
(c) At the free edges
(d) At the neutral axis of the section

OPSC AEE 2015 PAPER–I

Ans. (d) : Shearing stress in a beam is maximum at the neutral axis. Shearing stress is defined as the resistance offered by the internal stress to the shear force.

442. The section in which concrete is not fully stressed to its maximum permissible value while stress in steel reaches its maximum value, is called

(a) Under reinforced section
(b) Critical section
(c) Over reinforced section
(d) Balanced section

APPSC AEE (Mains) 2016

Ans. (a) : In under reinforced section, the quantity of steel provided is less than that required at balanced condition, hence stress in steel reaches first causing a ductile failure, and every singly reinforced beam should be designed as under-reinforced section because this section gives enough warning before failure.

443. If the diameter of a reinforcement bar is "d", the anchorage value U-type of hook is

(a) 4d (b) 8d
(c) 12d (d) 16d

TNPSC AE 2018
Rajasthan JEN (Degree) Shift - II 2016


Ans. (d) : If diameter of reinforcement bar is d, the anchorage value of the hook is taken 16d. This is for U hook bend at 180º.
At 135º anchorage value is taken 12d, at 90º it is taken 8 d, at 45º it is taken as 4d.

444. Shear failure at sections of beams without shear reinforcement normally occur on plane inclined at an angle _____ to the horizontal.


(a) 30° (b) 45°
(c) 60° (d) 20°

[HPPSC AE 2016]

Ans. (b) : Types of shear failure:-
(i) Diagonal tension failure: It occurs under large shear force and small bending moment. Such cracks occur normally at 45º with horizontal.



(ii) Flexural shear failure: It occurs under large bending moment and small shear force. It occurs nearly at 90% to the horizontal



(iii) Diagonal compression failure: It occurs due to large shear force and is characterized by crushing of concrete. Generally, it occurs in beam which are reinforced against heavy shear.

445. If a bar is cranked at both ends at an angle of 30^0, then extra length required when compared to a straight bar is (D = centre to centre distance between the top and bottom steel).

(a) 2×0.72 D (b) 2×0.27 D
(c) 2×0.42 D (d) 2×0.24 D

Karnataka PSC AE 2017 Paper - II

Ans. (b) : For 30° bends–

Length of crank = $\frac{d}{\sin 30^o}$ = 2d, Length covered by crank $\frac{d}{\tan 30^o}$ = 1.73d.

Therefore, extra length required for only one bend
= 2d – 1.73 d = 0.27d.
Thus if a bar is cranked at both ends at 30° then total length of bar = L + 2 × 0.27 d.

446. When HYSD bars are used in place of mild steel bars in a beam, the bond strength

Rajasthan AE Nagar Nigam Shift-3, 2016

OR


When HYSD bars are used in place of mild steel bars in a beam,

(a) Both bond strength and ductility increase
(b) Both bond strength and ductility decrease
(c) Bond strength increases and ductility decreases
(d) Bond strength decreases and ductility increases

GPSC AE (CLASS 1 & 2) 2019
ESE 2008

Search on Telegram @apna_pdf

Ans : (c) : In HYSD bars yield strength is removed out by cold working which results more yield stress as compare to mild steel but the ductility value decrease.



447. Torsion resisting capacity of a Reinforced Concrete section
(a) Decreases with increase in stirrups spacing
(b) Decreases with increase in longitudinal bars
(c) Does not depend upon stirrup and longitudinal steel
(d) Increases with the increase in stirrup and longitudinal steel

GPSC AE (CLASS 1 & 2) 2019
ESE 1995

Ans : (d) : Torsion resisting capacity increases more by shear reinforcement & longitudinal reinforcement.

448. Statement (I): In a RC beam, bond stress developed is due to pure adhesion, and frictional and mechanical resistance.
Statement (II): Inadequacy of bond strength can be compensated by providing end anchorage in the reinforcing bars.


ESE 2018

Ans. (b) Mechanism of Bond in RCC
1. **Pure adhesion:** due to chemical gum in concrete
2. **Frictional resistance:** It is due to shrinkage of concrete
3. **Mechanical resistance:** it is due to ribs (or) lugs present over surface of the bar If mild steel is embedded in concrete at the end of bar bend (or) hook is provided because over the surface it is smooth hence bond resistance is less. The statement II related to frictional resistance only.

449. A rectangular beam is of size 230 mm×350 mm (effective depth). The factored shear force acting at a section is 80 kN. If the permissible shear stress in concrete is 0.25 MPa, the design shear force is nearly
(a) 100 kN (b) 80 kN
(c) 60 kN (d) 20 kN

ESE 2017

Ans. (c) : Size of beam = 230mm × 350mm.
Permissible shear stress in concrete 'τ_c' = 0.25MPa.
Factored shear force, V_u = 80 kN.



Shear force resisted by concrete section only
$F_c = 230 \times 350 \times 0.25 \times 10^{-3}$
$[F_c = 20.125kN]$
Design shear force (that will be resisted by shear stirrups).
F_d = Factored shear force – F_c
$F_d = 80 - 20.125$
$F_d = 59.875$ kN
$\boxed{F_d \simeq 60kN}$

450. As per BIS 456-2000, deformed bars may be used without end anchorage provided:
(a) Minimum spacing between the adjacent rod is ensured
(b) Sufficient cover is provided to the reinforcement bars
(c) Development length required is satisfied
(d) None of the above

ISRO Scientist/Engineer 2020

Ans. (c) Anchoring bars in tension : Deformed bars may be used without end anchorages, provided development length requirement satisfied. Hooks are normally provided for plain bars. Maximum anchorage length obtained by the provision of hooks and bends.

451. The average shear stress for structural steel rolled beams is calculated by dividing the shear force at the cross section by the
(a) Gross sectional area of the beam
(b) Depth of beam
(c) Gross sectional area of web
(d) Width of flange

ISRO Scientist/Engineer 2019

Ans : (a) :
- The average shear stress for rolled beams or channels calculated by dividing the shear force at the cross section by the gross section of the web.
  The gross-cross-section of the web is defined as the depth of the beam or channel multiplied by its web thickness.
- Average shear stress for rectangular beam is - $\left[T_V = \frac{F}{b \times d}\right]$
- Average shear stress for I-beam is - $\left[T_V = \frac{F}{h \times t_w}\right]$

For rolled steel beams and channels, it is assumed that shear force is resisted by web only.

452. As per IS : 456–2000, for the design of reinforced concrete beams, the maximum allowable shear stress (τ_{cmax}) depends on the
(a) grade of concrete and grade of steel
(b) grade of steel only
(c) grade of concrete and percentage of reinforcement
(d) grade of concrete only

APTRANSCO 2017

Ans : (d) As per IS 456:2000, Table 20

Concrete Grade	**τ_{cmax} (N/mm^2)**
M15	2.5
M20	2.8
M25	3.1
M30	3.5
M35	3.7
M40 & above	4.0

Search on Telegram @apna_pdf

453. The target mean strength f_{cm} for concrete mix design obtained from the characteristic strength f_{ck} and standard deviation σ, as defined in IS : 456–2000, is

(a) $f_{ck} + 1.35\sigma$ (b) $f_{ck} + 1.45\sigma$

(c) $f_{ck} + 1.55\sigma$ (d) $f_{ck} + 1.65\sigma$

APTRANSCO 2017

Ans : (d) : As per IS : 456–2000 A concrete mix designed for a target mean tension strength given by following expression.

$$\boxed{f_{cm} = f_{ck} + 1.65\sigma}$$

where, f_{ck} = Characteristic strength

σ = Standard deviation.

454. A column of size 450 mm × 600 mm has unsupported length of 3.0 m and is braced against side sway in both directions. According to IS : 456–2000, the minimum eccentricities (in mm) with respect to major and minor principal axis are

(a) 20.0 and 20.0 (b) 26.0 and 21.0

(c) 26.0 and 20.0 (d) 21.0 and 15.0

APTRANSCO 2017

Ans : (b) :

The eccentricities of major axis

$$(e) = \frac{\ell}{500} + \frac{D}{30} \text{ or } 20 \text{ mm}$$

$$e = \frac{3000}{500} + \frac{600}{30}$$

$$\boxed{e = 26\,mm}$$

The eccentricities of minor axis $(e) = \frac{3000}{500} + \frac{450}{30}$

$$\boxed{e = 21\,mm}$$


455. A simply supported beam having 200 mm width and 450 mm effective depth supports a total uniformly distributed load of 2,00,000 N. The nominal shear stress will be nearly.

(a) 0.8 N/mm^2 (b) 1.1 N/mm^2

(c) 1.8 N/mm^2 (d) 2.2 N/mm^2

ESE 2020

Ans. (b)



Beam is symmetrically loaded hence support reactions are equal and half of the total load. It is equal to shear force (V_u).

$$R_A = R_B = V_u = \frac{200}{2}\,kN$$

$$\boxed{V_u = 100\,kN}$$

Nominal shear stress $(\tau_u) = \frac{V_u}{bd}$

$$= \frac{100 \times 10^3}{200 \times 450}$$

$$\boxed{\tau_u = 1.1\ N/mm^2}$$

456. As per IS–456 : 2000, cracking of concrete in tension zone cannot be avoided but can be limited by :

1. **Adhering to the codal requirements of minimum steel area**
2. **Proper and prolonged curing of concrete**
3. **Increasing water cement ratio to increase workability**

(a) 1 and 2 only (b) 1 and 3 only

(c) 2 and 3 only (d) 1, 2 and 3

ESE 2020

Ans. (a) : Cracking of concrete in tension can be limited by

(i) following codal requirements of minimum steel area and maximum spacing of bars.

(ii) proper and prolonged curing, which will increase the tensile stress and delay the loading

Increase in water-cement ratio will increase crack-width due to higher shrinkage and creep (though it increases workability)

457. At limit state of collapse in shear, in case of web shear cracks, it is assumed that the concrete cracks when the maximum principal tensile stress exceeds a value of f_t equal to :

(a) $0.24\sqrt{f_{ck}}$ (b) $0.20\sqrt{f_{ck}}$

(c) $0.16\sqrt{f_{ck}}$ (d) $0.30\sqrt{f_{ck}}$

OPSC AEE 2019 Paper–I

Ans. (a) : The maximum principal tensile stress should not exceed $0.24\sqrt{f_{ck}}$

- flexural strength $(f_{cr}) = 0.7\sqrt{f_{ck}}$

458. In the design of reinforced concrete beam the requirement of bond is not getting satisfied. The economical option of satisfy the requirement for bond is by :

(a) Bundling of bars

(b) providing smaller diameter bars more in number

(c) providing larger diameter bars less in number

(d) providing same diameter bars more in number

PSPCL AE 2012

Ans. (b) : In design of RCC beam economically provides large number of bar in of small diameters because large diameter are difficult to hand and erect more over making hook's and adequate bond & beam is not good enough by small diameter bar provide/ large bond area and hence large bond strength and avoid congestion also.

459. In case of simply supported beam subjected to uniformly distributed load 'W', throughout the span which develops maximum bending moment at the mid span, the cracks formed during the failure of the beam at mid span are


(a) Inclined at 45° (b) Inclined at 60°

(c) Horizontal (d) Vertical

GPSC Poly. Tech. Lect. 2016

Search on Telegram @apna_pdf

Ans. (d) :



• Maximum BM occurs at the mid span, the cracks formed during the failure of the beam at mid span are vertical.

460. In limit state design, permissible bond stress in case of deformed bars is more than that in plain bars by :

(a) 60% (b) 50%
(c) 40% (d) 25%

KPTCL AE 2016
Punjab MCP SDO 2015
ESE 1995

Ans. (a) : For deformed bars, the bond stress shall be increased by 60% of the value for plain bar in tension. For bars in compression, the value of bond stress for bars in tension shall be increased by 25%.

461. The maximum spacing of shear reinforcement should not exceed 0.75 d subject to a minimum of :

(a) 300 mm (b) 350 mm
(c) 400 mm (d) 450 mm

KPTCL AE 2016

Ans. (a) : According IS 456 : 2000
The maximum spacing of shear reinforcement measured along the axis of the member shall not exceed 0.75d for vertical stirrups where 'd' is the effective depth of the section under consideration in no case the spacing exceed 300 mm.

462. Shear reinforcement in beams is not provided in the form of

(a) hanger bars (b) inclined stirrups
(c) vertical stirrups (d) bent up bars

Rajasthan Nagar Nigam AE Shift-2, 2016

Ans. (a) : Shear reinforcement in beams is not provided in the form of hanger bars.
• Shear reinforcement shall be provided in any of the following forms
(A) vertical stirrups
(B) Bend-up bar along with stirrups, and
(C) inclined stirrups.

463. What is the maximum shear stress in rectangular section?

(a) 1.5 times the average shear stress
(b) 2 times the average shear stress
(c) 2.5 times the average shear stress
(d) 4 times the average shear stress

Rajasthan Nagar Nigam AE Shift-2, 2016

Ans. (a) : The maximum shear stress in rectangular section is 1.5 times the average shear stress.
The maximum shear stress in circular section '1.33' times the average shear stress.

464. Cracks at bottom face of a simply supported beam are observed. The cracks are along the span and are concentrated near the mid span of the beam. The reason of the cracks may be

(a) Area of main reinforcement in beam is less than required area of main reinforcement
(b) Area of main reinforcement in beam is more than required area of main reinforcement
(c) Shear stirrups dia of spacing is less than the required dia or spacing of shear stirrups
(d) Shear stirrups dia of spacing is more than the required dia or spacing of shear stirrups

Sikkim PSC AE 2017

Ans. (a) : Cracks at bottom face of a simply supported beam are observed. The cracks are along the span of the beam, the reason of the crack may be, Area of main reinforcement in beam is less than required area of main reinforcement.

465. A RCC beam is 300 mm wide and 450 mm deep. It is designated for the load acting on it and 20 mm dia main reinforcement and 10 mm dia stirrups are to be used. However, it is later found that the beam is failing in bond. Which of the following is the most economical solution to save the beam from failing in bond?

(a) Use 12 mm dia stirupps instead of 10 mm bars
(b) Use 12/16 mm bars instead of 25 mm bars
(c) Use 8 mm dia stirupps instead of 10 mm bars
(d) Use 25/28 mm bars instead of 25 mm bars

Sikkim PSC AE 2017

Ans. (b) : For ensuring adequate bond in RCC member, provide large number of smaller diameter bars.

466. Critical section for shear in a fixed beam is considered at

(a) Center of the span of the beam
(b) Center of the supports of the beam
(c) Center of gravity of the applied loads
(d) None of the above

Sikkim PSC AE 2017

Ans. (d) : IS 456-2000, clause (22.6.2.1),
The critical section for computing design shear force in an RC beam where the support exerts a compressive reaction is at a distance of effective depth from the face of support.

467. A RCC beam is carrying a large point load that results in high shear force which results in exceeding maximum permissible shear stress. Which of the following is correct

(a) Increasing depth of beam is more suitable
(b) Increasing width of beam is more suitable
(c) Increasing depth or width will have almost similar effect
(d) Increasing shear reinforcement is more suitable

Sikkim PSC AE 2017

Search on Telegram @apna_pdf

Ans. (a) : If $\tau_v > \tau_{max}$, redesign the section, so for condition given in question, increasing depth of beam is more suitable for shear.

468. Total length of a simply supported RCC beam is 6m. 8mm dia stirrups have been provided at center to center spacing of 120 mm. Total number of stirrups in the beam shall be

(a) 50 (b) 51
(c) 49 (d) 720

Sikkim PSC AE 2017


Ans. (b) : L = 6m, ϕ = 8mm, c/c spacing = 120 mm

Total no. of spacing $= \frac{Beam\,length}{spacing\,b/w\,bar} = \frac{6000mm}{120mm}$

= 50

Assume if beam length is 1 meter and spacing b/w bars is 250 mm, then no. of spacing = 1000/250 = 4

So no. of bars = 4 + 1 = 5



So total stirrups above will be = 50 + 1 = 51.

469. An R.C.C. beam not provided with shear reinforcement may leads to failure in its bottom inclined roughly to :

(a) 60^0 to the horizontal
(b) 30^0 to the horizontal
(c) 45^0 to the horizontal
(d) 25^0 to the horizontal

TRB Poly. Lect. Tech. 2017

Ans. (b) : An RCC beam not provided with shear reinforcement may leads to failure in its bottom inclined roughly to 30^0 to the horizontal.

470. A Rectangular beam has b = 250 mm, d = 500 mm, A_{st} = 3 @ 20 mm, f_{ck} = 20 N/mm^2 and Fe - 415 steel are used. The limit moment capacity of the beam is :

(a) 4.433×10^8 N.mm
(b) 3.433×10^8 N.mm
(c) 1.433×10^8 N.mm
(d) 2.433×10^8 N.mm

TRB Poly. Lect. Tech. 2017

Ans. (c) : C = T

$0.36 \times f_{ck} \times b \times x_u = 0.87 \times f_y \times A_{st}$

$0.36 \times 20 \times 250 \times x_u = 0.87 \times 415 \times 3 \times \frac{\pi}{4} \times 20^2$

$x_u = 189.04$ mm

$m = 0.36 \times f_{ck} \times b \times x_u (d - 0.42\, x_u)$

$= 0.36 \times 20 \times 250 \times 189.04 \times (500 - 0.42 \times 189.04)$

$m = 1.43 \times 10^8$ N-mm

471. The maximum bending stress in tension or in compression in extreme fibre is

(a) 0.6 f_y (b) 0.45 f_y
(c) 0.66 f_y (d) 0.75 f_y

BPSC Poly. Tech. Lect. 2016

Ans. (c) : The maximum bending stress in tension or in compression in extreme fibre is 0.66 f_y.
In axial tension and compression is = 0.60 f_y.
In shear
= 0.40 f_y (avg. maximum permissible)
= 0.45 f_y (max_m permissible)

472. For bars in compression, the values of bond stress for bars in tension shall be increased by

(a) 30% (b) 50%
(c) 35% (d) 25%

BPSC AE Aug. 2019 Paper-V

Ans. (d) : For bars- bond stress in compression = 1.25 × bond stress in tension.
• For bar in compression, the values of bond stress for bar in tension shall be increased by additional 25%.

473. The design bending strength of laterally supported beam can be calculated for low shear case when the shear force in the member is ..... times that of design shear strength V_d of the member

(a) 0.4 (b) 0.6
(c) 0.8 (d) 1.0

GPSC AE Dec 2018

Ans. (b) : For low shear, $V \le 0.6\, V_d$
where V_d = design shear strength.

474. The maximum spacing of shear reinforcement in beams, in the form of inclined stirrups at 45^0 measured along the axis of the member shall not exceed (d) is effective depth.

(a) 0.75d subject to a maximum of 300 mm
(b) 0.75 d subject to maximum of 200 mm
(c) d subject to maximum of 200 mm
(d) d subject to maximum of 300 mm

GPSC Assistant Prof. 2016

Ans. (d) : As per IS code 456-2000 spacing of shear reinforcement :
Maximum spacing is minimum of (i) (ii) & (iii)

(i) $S_V = \frac{2.175\, f_y\, A_{sv}}{b}$

(ii) 300 mm
(iii) 0.75 d → for vertical stirrups
d → for inclined stirrups
where d → effective depth of the section.

475. Min shear reinforcement in the form of stirrups shall be provided such that ..... . Where A_{SV} = total cross-sectional area of stirrups let
S_V = Stirrups spacing along the length of member
b = Width of beam
f_y = Characteristic strength of steel

(a) $\frac{A_{SV}}{bS_V} \ge \frac{0.4}{0.87fy}$ (b) $\frac{A_{SV}}{bS_V} \ge \frac{0.87fy}{0.4}$

(c) $\frac{A_{SV}}{bS_V} < \frac{0.4}{0.87fy}$ (d) $\frac{A_{SV}}{bS_V} \ge \frac{0.45}{fy}$

PTCUL AE 2016

Search on Telegram @apna_pdf

Ans. (a) : As per IS 456 : 2000 the minimum shear reinforcement in the form of vertical stirrups shall be provided such that $\frac{A_{SV}}{bS_V} \geq \frac{0.4}{0.87 f_y}$

where, A_{SV} = total cross-sectional area of stirrups leg.
S_V = stirrups spacing
b = width of beam
f_y = characteristic strength of steel.

476. The centre to centre spacing of vertical stirrups, in a rectangular reinforced concrete beam is

(a) increased towards the centre of the span of the beam.
(b) decreased towards the centre of the span of the beam.
(c) increased at the ends
(d) maintained non-uniformly.

APPSC AEE 2016

Ans. (a) : In rectangular concrete beam centre to centre spacing of vertical stirrups increased towards the centre of the span of the beam because shear force is reducing towards centre of span and maximum at ends.

477. According to IS456:2000, the flexural tensile strength of concrete is _____:

(a) directly proportional to characteristic compressive strength
(b) inversely proportional to the square root of characteristic compressive strength
(c) directly proportional to the square root of characteristic compressive strength
(d) inversely proportional to characteristic compressive strength

UPPCL AE 2018

Ans. (c) According to IS 456:2000, the flexural tensile strength of concrete is directly proportional to the square root of characteristic compressive strength.

Flexural tensile strength : Tensile strength of concrete in flexure is called flexural tensile strength

$f_{cr} = 0.7\sqrt{f_{ck}}$

f_{cr} = flexural tensile strength is N/mm^2

f_{ck} = characteristics compressive strength of cube in N/mm^2.

478. In the context of provisions for design of mixes and acceptance of concrete in Indian Standards, consider the following statements:

Statement – 1: For a M25 grade concrete, if it is expected that the standard deviation in strength will be 4 MPa, the target mean strength for the design of the mix should be taken as 31.5 MPa

Statement – 2: The sample of three specimens should be rejected if the difference between the maximum and the minimum strength obtained (from the three specimens) is more than 3.5 MPa

Which of the following is CORRECT?

(a) Both statements are False
(b) Statement– 1 is TRUE and Statement– 2 is FALSE
(c) Both statements are TRUE
(d) Statement– 1 is FALSE and statement– 2 is TRUE

UPPCL AE 2018

Ans. (b) : Statement I :

$\delta_m = f_{ck} + 1.64\sigma$

δ_m = target mean strength

f_{ck} = characteristic strength of concrete

σ = standard deviation in strength

$\delta_m = 25 + 1.64 \times 4 = 31.56$ MPa

Statement II :

The average value of set of three cubes (one sample) should have strength with in the limit of IS 15% of the average value otherwise the result of that sample will be invalid.

479. As per IS 456-2000 the target strength for M40 mix proportion having standard deviation 5 N/mm^2 is:

(a) 47.5 N/mm^2 (b) 45 N/mm^2
(c) 35 N/mm^2 (d) 48.25 N/mm^2

UPPCL AE 2019

Ans. (d) : Target mean strength

$f_m = f_{ck} + 1.65\sigma$

Standard deviation = 5 N/mm^2

$f_{ck} = 40$ N/mm^2

$f_m = 40 + 1.65 \times 5$

$f_m = 48.25$ N/mm^2

480. Ultimate load method is also called as :

(a) Nonlinear stress strain method
(b) Load factor method
(c) Failure load method
(d) Approximate load method

UPPCL AE 2019

Ans. (b) The ultimate load method is also called as the load factor method or the ultimate strength method. In this method, the non-linear stress-strain behavior of steel and concrete are accounted for and stresses induced in the structure at the verge of failure at ultimate loads are considered.

481. For solid slabs the permissible shear stress in concrete shall be k× Shear stress in concrete. The least value of k as per IS 456-2000 is _____.

(a) 0 (b) 1.0
(c) 1.30 (d) 0.5

UPPCL AE 2019

Ans. (b) : For solid slabs the permissible shear stress in concrete K × Shear stress in concrete, then the least value of K as per IS 456-2000 is 1.

thickness of slab (mm)	less than 150	175	200	225	250	275	300
value of k	1.3	1.25	1.20	1.15	1.10	1.05	1.0

482. Tetrapods are to be designed to kept on the shores of Arabian sea. It is expected that these structures would face high tides for 70% of the time and low tides for the remaining 30% of the time. The exposure class to be considered for these structures as per IS 456 would be:

(a) Severe (b) Very Severe
(c) Extreme (d) Moderate

LMRC AM 2015

Ans (c)

Search on Telegram @apna_pdf

483. A concrete mix of grade M40 is to be used for pavements using paver machine. The recommended slump range as per IS:456-2000 is:

(a) 25-75 mm (b) 50-100 mm
(c) 75-100 mm (d) 100-150 mm

LMRC AM 2015

Ans (a) Recommended slumps (I.S. 456–2000)

Type of construction Work	Slump (mm)
Road pavement	25-75
Underwater construction, pumpcreating	50-100
Over reinforced concrete beam	50–100
Massive concrete	25–50
Bridge & deck	25–75
Pier and foundation	25–75

A concrete mix of grade M40 is to be used for pavements using paver machine. The recommended slump range as per IS:456-2000 is 25-75 mm.

484. As per IS 456-2000 standard, the average permissible bond stress (τ_{bd}) for plain bars in M25 grade of concrete is :

(a) 0.8 (b) 0.9
(c) 1.0 (d) 1.1

LMRC AM 2018

Ans. (b) : Permissible stresses in concrete (Refer to table 21, IS 456)–

Grade of concrete	Permissible stress in compression	Permissible stress in bond (average)
M 20	7.0	0.8
M 25	8.5	0.9
M 30	10.0	1.0
M 35	11.5	1.1

485. As per IS 456, the maximum free water cement ratio for M25 concrete in RCC work is:

(a) 0.55 (b) 0.45
(c) 0.5 (d) 0.6

LMRC AM 2018

Ans. (c) : According to IS 456, the maximum free water content ratio for M25 Concrete in RCC work is 0.5. Increasing the water cement ratio decrease strength of concrete.

486. The percentage increase in the design bond stress in limit state, for deformed bars in tension (conforming to IS 1786), with respect to plain bars in tension is:

(a) 20 (b) 50
(c) 60 (d) 35

CIL MT 2020

Ans. (c) : The value of bond stress for deformed bars (conforming to IS 1786) may be increased by 60% of the values for plain mild steel bars in tension.
These values may be further increased by 25% for bars in compression.

487. For beams the maximum area of tension reinforcement with HYSD bars shall not exceed :

(a) 0.04 bD (b) 0.12 bD
(c) 0.06 bD (d) 0.015 bD
(e) 0.22 bD

CGPSC AE 2017

Ans. (a) The maximum area of tension reinforcement with HYSB bars shall not 0.04 bD. i.e. 4% of the total area.

- The minimum area of tensile reinforcement shall not be less than that given by the following

$$\frac{A_s}{bd} = \frac{0.85}{f_y}$$

where A_s = Area of tensile reinforcement
b = Breadth of beam or the breadth of the web of T beam
d = Effective depth of beam
f_y = characteristic strength of reinforcement in N/mm^2

488. As per IS 456 : 2000, the maximum shear stress for M20 grade of concrete is :

(a) 1.0 N/mm^2 (b) 2.8 N/mm^2
(c) 1.8 N/mm^2 (d) 3.8 N/mm^2
(e) 3.3 N/mm^2

CGPSC AE 2017

Ans. (b) As per IS 456 : 2000, the maximum shear stress for M20 grade of concrete is 2.8 N/mm^2

- The value of maximum shear stress $\tau_{c\ max}$ depends on the grade of concrete.

489. What is the anchorage value of a standard hook of a reinforcement in compression that shall not be less than:

(a) 30 ϕ (b) 24 ϕ
(c) 20 ϕ (d) 15 ϕ

Where ϕ = diameter of bar

Haryana PSC AE 2017

Ans. (b) : Anchorage value of a standard hook of a reinforcement in compression that shall not be less than 24 ϕ.

490. If a beam fails in bond, then its bond strength can be increased most economically by -

(a) Increasing the depth of beam
(b) Using thinner bars but more in number
(c) Using thicker bars but less in number
(d) Providing vertical stirrups

Rajasthan VP ITI 2018

Ans. (b) : If a beam fails in bond, then its bond strength can be increased by using thinner bars but more in number.

491. As per IS:456-2000, the flexural tensile strength of M-25 grade of concrete is -

(a) 7.5 MPa (b) 5.5 MPa
(c) 4.5 MPa (d) 3.5 MPa

Rajasthan VP ITI 2018

Ans. (d) : $f_{cr} = 0.7\sqrt{f_{ck}}$

Where f_{ck} = Characteristic strength of concrete
Form M 25 grade of concrete -

$f_{cr} = 0.7\sqrt{25}$

$f_{cr} = 3.5$ N/mm^2

Search on Telegram @apna_pdf

492. Match List-I (Beam Variable) with List-II (Design Provision)

List-I (Beam Variable)	List-II (Design Provision)
A. Flexure	1. Minimum depth of section
B. Shear	2. Longitudinal steel reinforcement
C. Bond	3. Stirrups
D. Deflection	4. Anchorage in support

(a) A-3, B-2, C-1, D-4 (b) A-2, B-3, C-1, D-4
(c) A-3, B-2, C-4, D-1 (d) A-2, B-3, C-4, D-1

UPRVUNL AE 2014

Ans. (d) :

(Beam Variable)	(Design Provision)
A. Flexure	Longitudinal steel reinforcement
B. Shear	stirrups
C. Bond	Anchorage in support
D. Deflection	Minimum depth of section

493. Which of the following correctly defines the reason of providing minimum shear reinforcement in beams in the form of stirrups?

(a) To resist extra shear force due to live load
(b) To resist the effect of shrinkage of concrete
(c) To resist principal tension
(d) To resist shear cracks at the bottom of beam

UPRVUNL AE 2014

Ans. (c) : The minimum shear reinforcement is provided :
(i) To control the propagation of diagonal crack and thus avoid abrupt failure.
(ii) Prevent sudden failure of beam if concrete cover bursts and bond between concrete and fusion reinforcement is lost.
(iii) Prevent tension failure due to shrinkage, thermal stresses and internal cracking in beam.
(iv) Holding reinforcement in place when concrete is being casted.

494. The anchorage value for a standard U-type hook as per IS code shall be taken as, how many times the diameter (ϕ) of the bar?

(a) 12 (b) 16
(c) 8 (d) 10

JUVNL AE 2016

Ans. (b) : IS code has specified that plain bars when used, standard U-shaped hook value as 16 ϕ (ϕ = diameter of bar used) is provided.

495. The length of hook provided in a beam or column ring shall be ..... times the diameter of ring bar :

(a) SD (b) 6D
(c) 10D (d) 3D

GPHC AE 2018

Ans : (c) The length of hook provided will be 10 times the diameter of ring bar either in beam or coloumn.

496. The anchorage value of 90º hook is :

(a) 6ϕ (b) 8ϕ
(c) 10ϕ (d) 12ϕ

GPHC AE 2018

Ans : (b) The anchorage value of 90º hook is 8ϕ
$\Rightarrow$ The anchorage value of a bend shall be taken as 4 times the diameter of the bar for each 45º bend subjected to a maximum of 4 times the diameter of bar, the anchorage value of a standard U-type hook is equal 16 times the diameter of bar, the anchorage value of the standard 90º bend is 8 times the diameter.

497. The spacing of nominal shear reinforcement in given by :

(a) $\frac{0.87 A_{sv} f_y}{0.4b}$ (b) $\frac{0.77 A_{sv} f_y}{0.3b} j$
(c) $\frac{0.87 f_y}{0.2b} j$ (d) $\frac{0.97 A_{sv} f_y}{0.5b} j$

GPHC AE 2018

Ans : (a) The Spacing of nominal shear reinforcement is :

$$\Rightarrow \frac{0.87 A_{SV} f_y}{0.4b}$$

$A_{SV} \rightarrow$ Area of shear Reinforcement.
$f_y \rightarrow$ Characteristics Strength
$b \rightarrow$ Width of the Beam

498. For a 90º bend in reinforcement, anchorage value in tension, is kd where d = diameter of reinforcement and the value of k is

(a) 4 (b) 8
(c) 16 (d) 12

WBPSC AE (PHE) 1998

Ans. (b) : The anchorage value of 90º hook is 8ϕ
$\Rightarrow$ The anchorage value of a bend shall be taken as 4 times the diameter of the bar far each 45º bend subjected to a maximum of is times the diameter of bar, the anchorage value of a standard U-type hook is equal is times the diameter of bar, the anchorage value of the standard 90º bend is 8 times the diameter.

499. A decrease in stress at constant strain in called

(a) shrinkage stress (b) creep stress
(c) relaxation of stress (d) transfer stress

WBPSC AE (PHE) 1998

Ans. (c) : A decrease in stress at constant strain in called relaxation of stress.

500. Development length of a reinforcing bar

(a) includes anchorage value of hooks in compression
(b) is less for compression than for tension
(c) is less for tension than for compression
(d) excludes anchorage value of hooks in tension

WBPSC AE (PHE) 1998

Ans. (b) : Development length of a reinforcing bar is less for compression than for tension.

501. The development length is

(a) $\frac{T_s}{\tau_{bd}}$ (b) $\frac{T_s}{3\tau_{bd}}$
(c) $\frac{T_s}{4\tau_{bd}}$ (d) $\frac{T_s}{5\tau_{bd}}$

WBPSC AE (Common) 1998

Ans. (c) : development length is given as $\frac{\phi\sigma_s}{4\tau_{bd}}$

Search on Telegram @apna_pdf


4. Singly and Doubly Reinforced Concrete Beams

502. The main reinforcement in R.C.C. cantilever members is placed at

(a) top fibre (b) side fibres
(c) bottom fibre (d) top and bottom fibres

TNPSC AE 2012

Ans. (a)




503. Minimum spacing of vertical stirrups is ..... in a beam.

(a) 100 mm (b) 150 mm
(c) 60 mm (d) 120 mm

PTCUL AE 2016

Ans. (a) : Minimum spacing of vertical stirrups is 100 mm in a beam



504. The maximum area of tension steel in a beam shall *not* exceed-

(a) 0.15 bD (b) 0.12 bD
(c) 0.04 bD (d) 1.00 bD

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (c) : According to IS 456 – 2000, maximum tension steel that can be provided in a beam is 4% of the gross sectional area.

Max tension steel

$$= \frac{4}{100} \times bD = 0.04bD$$

505. The spacing of vertical stirrups in a rectangular beam is

(a) maximum near the support
(b) minimum near the support
(c) minimum near the centre
(d) none of these

TNPSC AE 2012

Ans. (b) : The spacing of vertical stirrups in a rectangular beam is minimum near the support due to maximum shear force at the supports

- Maximum spacing of vertical stirrups in a rectangular beam is at its midspan. It is because the shear force at the midspan is very less and use vertical stirrups to counter shear force.

506. If d is the effective depth, b is the width and D is the overall depth, then the maximum area of compression reinforcement in a beam is given by :

(a) 0.04 bd (b) 0.04 bD
(c) 0.12 bd (d) 0.12 bD

CGPSC AE 2014 Shift–I
WBPSC AE 2014


Ans. (b) : As per IS 456-2000 maximum compression or tension reinforcement = 0.04 bD

507. In a doubly reinforced beam, steel reinforcement is provided in a

(a) tension zone (b) compression zone
(c) either (a) or (b) (d) both (a) and (b)

TNPSC AE 2012

Ans. (d)



508. If the given bending moment is greater than moment of resistance of balanced section, then the section is :

(a) Balanced section
(b) Under-reinforced section
(c) Over-reinforced section
(d) Critical section

TNPSC AE 2015

Ans. (b) An under reinforcement section has lesser amount of tensile reinforcement as compared to balanced section and so will have lesser moment of resistance.

- Similarly an over reinforced section will have greater moment of resistance than balanced section.

509. The size of the rectangular section is fixed and the moment of resistance of a singly reinforced section is less than design moment. the beam shall be designed as :

(a) Under-reinforced (b) Over-reinforced
(c) Doubly reinforced (d) Compressive failure

TNPSC AE 2015

Ans. (c) Sections reinforced with steel in compression and tension are known as doubly reinforced section.
Doubly reinforced section is designed when the size of rectangular, section is fixed and the moment of resistance of singly reinforced section is less than design moment.

510. In case of simply supported beam subjected to U.D.L.w throughout the span which develops maximum B.M. at the mid-span, the cracks formed during the failure of beam at mid-span are

(a) horizontal (b) inclined at 45°
(c) inclined at 60° (d) vertical

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (d) Flexural cracks (Vertical cracks) – The region normally occurs adjacent to midspan where B.M. is large and shear force is either zero or very small. The

Search on Telegram @apna_pdf

principal planes are perpendicular to the beam axis, when the principal tensile stress reaches the tensile strength of concrete (which is quite low) tensile cracks develop vertically.

511. A singly reinforced rectangular section, b × d is effective c/s, f_{ck} and f_y are the characteristic strengths of concrete and steel respectively. The depth of neutral axis is calculated as

(a) $\frac{0.85 f_{ck} bd}{f_y}$ (b) $\frac{0.87 f_y A_{st}}{0.36 f_{ck} bd}$

(c) $\frac{0.87 f_y A_{st}}{0.36 f_{ck} bd^2}$ (d) $\frac{0.87 f_y A_{st}}{0.36 f_{ck} b}$

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (d) Singly reinforced Beam–

- Depth of Neutral axis $X_u = \frac{0.87 f_y A_{st}}{0.36 f_{ck}.b}$
- $X_{umax} = \frac{0.0035}{0.0055 + \frac{0.87 f_y}{Es}}$
- $C = 0.36 f_{ck} b. X_u$ – Compression area
- $T = 0.87 f_y A_{st}$ – Tension area.

512. Area of torsional reinforcement provided in a two-way slab at corners where both adjacent edges are continuous is

(a) $\frac{3}{4} A_{st} x^+$ (b) $\frac{3}{4} A_{st} y^+$

(c) $\frac{3}{8} A_{st} x^+$ (d) 0

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (d) There is no (zero) need of torsion reinforcement if the edges are continuous.
Torsion reinforcement provided will be half of the torsion reinforcement described above, if one of edge is continuous.
Area of torsion reinforcement required shall be $\frac{3}{4}$ of area required for the maximum mid-span moment in the slab. [When both edges are discontinuous]

513. A simply supported reinforced cement concrete beam shall be deemed to be deep beam, if its effective span to depth ratio is less than :

(a) 3.00 (b) 2.50
(c) 2.00 (d) 1.50

CIL MT 2017

Ans. (c) : A simply supported reinforced cement concrete beam shall be deemed to be deep beam, if its effective span to depth ratio is less than 2.00.
For continuous beam it is 2.5.

514. In case of a continuous beam, the shear force coefficients at the support next to the end support and inner side of mid span (Where w_d = Dead load and imposed load (fixed), W_L=live load:

(a) $(0.40w_d + 0.4w_L)L_C$
(b) $(0.60w_d + 0.60w_L)L_C$
(c) $(0.50w_d + 0.60w_L)L_C$
(d) $(0.55w_d + 0.60w_L)L_C$

APPSC Poly. Tech. Lect. 2020

Ans. (d) : In case of a continuous beam, the shear force coefficients at the support next to the end support and inner side of mid span is $(0.55w_d + 0.60w_L)L_C$

515. The deflection of beams and one-way slabs can be controlled by using the appropriate:

(a) modular ratio (b) water cement ratio
(c) aspect ratio (d) span/depth ratio

APPSC Poly. Tech. Lect. 2020

Ans. (d) : The deflection of beams and one-way slabs can be controlled by using the appropriate span/depth ratio.

516. Minimum shear reinforcement in beams is provided in the form of stirrups-

(a) to resist the extra shear force due to live load
(b) to resist the effect of shrinkage of concrete
(c) to resist the principal tension
(d) to resist the shear cracks at the bottom of beam

Gujarat PSC AE (N.W.R.) 2020
ESE 2004

Ans. (c) : Minimum shear reinforcement in beams is provided in the form of stirrups to resist the principal tension.

517. In design practice of beams the span to overall depth ratio are generally taken in the range:

(a) 10 to 16 (b) 25 to 30
(c) 1 to 2 (d) 30 to 45

KPSC AE 2020

Ans. (a) : In design practice of beams the span to overall depth ratio are generally taken in the range 10 to 16.

518. Basic value of span to effective depth ratio for span up to 10 m of a continuous beam as per IS 456-2000:

(a) 7 (b) 20
(c) 24 (d) 26

KPSC AE 2020
UPPSC State Eng. A.E. 2011

Ans. (d) : Basic value of span to effective depth ratio for span up to 10 m of continuous beam as per IS 456-2000 is basic values of span to depth ratio.

Span type	*l*/d
Cantilever	7
Simply supported	20
Continuous	26

For span greater than 10 m above values are multiplied by $\left(\frac{10}{\text{span}}\right)$ except for cantilever in which case exact deflection calculation should be made.

519. The design of a beam as deep beam takes into account

(a) Lateral buckling
(b) Temperature stresses
(c) Non-linear distribution of stresses

Search on Telegram @apna_pdf

(d) All of the above

Nagaland PSC CTSE 2017 Paper–I

Ans. (d) : The Design of a beam as a deep beam takes into account
(1) Lateral Buckling
(2) temperature stresses
(3) Non-linear distribution of stresses.
$\Rightarrow$ Deep beam is a beam having large depth / thickness ratio and shear depth ratio less than 2.5 for concentrated load and less than 5.0 for distributed load. Because the geometry of deep beams there behavior is different with slender beam or intermediate beam.

520. When a beam section spans over several supports continuously then the beam at supports should be designed as :
(a) Simply reinforced beam
(b) Prestressed beam
(c) Doubly reinforced beam
(d) Pre-cast beam

Nagaland PSC CTSE 2017 Paper–I

Ans. (c) : When a Beam section spans several support continuously then the beam at supports should be designed as Doubly reinforced beam.

521. The maximum deflection due to load in RCC beams in buildings in limited to :
(a) $\frac{\text{Span}}{100}$ (b) $\frac{\text{Span}}{250}$
(c) $\frac{\text{Span}}{350}$ (d) $\frac{\text{Span}}{500}$

Nagaland PSC CTSE 2017 Paper–I

Ans. (b) : As per IS 456-2000, The final deflection due to all loads including the effect of temp; creep & shrinkage and measured from as cast level of the support of floors, roofs and other horizontal member should not normally exceed $\frac{\text{span}}{250}$

522. The shear reinforcement in a RCC beam is provided to resist :
(a) Diagonal tension (b) Flexural shear
(c) Shear in concrete (d) Punching shear

Nagaland PSC CTSE 2017 Paper–I

Ans. (a) : The shear reinforcement in RCC is provided to resist Diagonal tension.

523. The maximum value of span/depth ratio permissible in case of simply supported RCC beam is :
(a) 5 (b) 10
(c) 15 (d) 20

Nagaland PSC CTSE 2017 Paper–I

Ans. (d) : As per IS 456–2000 (cl 23.2.1), for simply supported Beam, Basic value of $\left(\frac{\text{Span}}{\text{Depth}}\right) = 20$ (upto span 10m)
$\rightarrow$ Above value will be multiplied by $\left(\frac{10}{\text{Depth}}\right)$ in case span > 10 m

524. If a beam fails in bond, it would be best to
(a) Increase the depth of beam
(b) Use thinner but more number of bars
(c) Use thicker but less number of bars
(d) Providing vertical stirrups

Nagaland PSC CTSE 2017 Paper–I

Ans. (b) : For ensuring Adequate bond in RCC member, provide large number of smaller diameters bars.

525. According to the recommendations of IS : 456 the compressive reinforcement in rectangular beams should not exceed :
(a) 0.4% to the total cross-sectional area
(b) 1% to the total cross-sectional area
(c) 4% to the total cross-sectional area
(d) 10% to the total cross-sectional area

Nagaland PSC CTSE 2017 Paper–I

Ans. (c) : As per IS 456–2000, (Cl 26.5.1.2), the maximum area of compression reinforcement shall not exceed 0.04 bD or 4%

526. As per Indian standard the spacing of stirrups in a RCC beam shall not exceed by a distance equal to :
(a) Effective depth of the beam
(b) Width of the beam
(c) Total depth of the beam
(d) Lever arm of the resisting moment

Nagaland PSC CTSE 2017 Paper–I

Ans. (a) : As per IS 456-2000, cl 26.5.1.5, maximum spacing is minimum of (i), (ii) & (iii)
(i) $S_V = \frac{0.87 f_y A_{sv}}{0.4 b}$
(ii) 300 mm
(iii) 0.75 d $\rightarrow$ for vertical stirrups
d $\rightarrow$ for inclined stirrups
d is effective Depth of the section

527. When R.C.C. beam is subjected to bending, and the top most layer elongates and the bottom one shortens, then that beam is called :
(a) Fixed beam
(b) Cantilever beam
(c) Simply supported beam
(d) Doubly reinforced beam

Nagaland PSC CTSE 2017 Paper–I

Ans. (b) When RCC cantilever Beam is subjected to Bending, then the top most layer elongate and bottom one shortens.


528. Side face reinforcement shall be provided in the beam when depth of web in beam exceeds :
(a) 50 cm (b) 75 cm
(c) 100 cm (d) 120 cm

Nagaland PSC CTSE 2017 Paper–I

Ans. (b) : According to IS 456–2000, when a Beam is subjected to torsion, If depth of the Beam is more than 450 mm or for Beam not subjected to torsion, If the Depth of web exceed 750 mm then side face reinforcement equal to 0.1% of x-sectional area is provided and is equally distributed on the both faces of the Beam.

Search on Telegram @apna_pdf


529. A simply supported RC beam having clear span of 5 m and support width 300 mm has the cross section as shown in Fig. What is the effective span of beam as per IS – 456?



(a) 5300 mm (b) 5400 mm
(c) 5200 mm (d) 5150 mm

UKPSC AE 2012 Paper–I
ESE 2009

Ans : (a)



effective length (ℓ_e) = ℓ+d or $\ell+\frac{A}{2}+\frac{B}{2}$ (Whichever is less), where A and B are width of support.

$$\ell_e \cdot 5000+\frac{300}{2}+\frac{300}{2} \text{ or } 5000+400$$
$$= 5300\text{mm or } 5400\text{mm}$$

$\therefore$ Effective length (ℓ_e) · 5300 mm

530. A singly reinforced concrete beam of 300 mm width and 750 mm effective depth is provided with 2000 mm^2 steel. If the modular ratio is 15, the depth of neutral axis will be–

(a) 200 mm (b) 350 mm
(c) 300 mm (d) 400 mm

UKPSC AE 2013 Paper–I

Ans : (c) Given $A_{st} = 2000\ mm^2$
m = 15
d = 750 mm
b = 300 mm
Depth of neutral axis is given as

$$\frac{bx^2}{2} = mA_{st}(d-x)$$

Putting the values

$$\frac{300x^2}{2} = 15\times 2000(750-x)$$
$$150x^2 + 30000x - 22500000 = 0$$
$$\boxed{x = 300\text{mm}}$$

531. Span to effective depth ratio for a continuous beam with steel grade of Fe 415 should not be more than–

(a) 7 (b) 20
(c) 26 (d) 48

UKPSC AE 2013 Paper–I

Ans : (c) maximum effective depth ratio of beam (is to 10 m span).

(i) Simple support beam	20
(ii) Continuous beam	26
(iii) Cantilever beam	7

532. In a reinforced concrete beam, if the amount of reinforcement increases, then the

(a) depth of neutral axis decreases
(b) depth of neutral axis increases
(c) depth of neutral axis remains constant
(d) none of the above

(UKPSC AE 2012 Paper–I)

Ans : (b) Depth of neutral axis

$$x = \frac{0.87\sigma_y A_t}{0.36\sigma_{ck} b}$$

If percentage of reinforcement in tension increased, then depth of neutral axis also increases.

533. When width b, effective depth d, overall depth D, the maximum area of reinforcement in RCC beam shall not exceed

(a) 0.04 bd (b) 0.04 bD
(c) 0.05 bd (d) 0.05 bD

RPSC GWD A. En. – 2014
RPSC ACF 2011

Ans : (b) Maximum reinforcement is taken 4% of the gross area of beam i.e. 0.04bD.
$A_{st\ max}$ = 0.04 bD

534. Deep beams are designed for :

(a) Shear force only
(b) Bending moment only
(c) Both shear force and bending moment
(d) Bearing

Nagaland PSC CTSE 2017 Paper–I
Chandigarh AE 2017
RPSC GWD A. En. - 2014

Ans : (b) Deep beam is a beam having large depth/thickness ratio and shear depth ratio less than 2.5 for a simply supported beam and 2.5 for a continuous beam.

535. Side face reinforcement is required when the depth of beam is

(a) Greater than 750 mm
(b) Greater than 1000 mm
(c) Greater than 300 mm
(d) Greater than 500 mm

RPSC LECTURE - 2011
RPSC VPITI - 2012

OR

Side face reinforcement is provided in a beam when the depth of web exceeds:

(a) 750mm (b) 450mm
(c) 500mm (d) 300mm

[UPPSC State Eng. A.E. 2003, 2004 (I)]

Ans : (a) Requirement of side face reinforcement :
(i) when depth of beam is greater than 750 mm and beam is not subjected to torsion.
(ii) when beam is subjected to torsion and depth of beam is greater than 450 mm
side face reinforcement shall be provided 0.1% of web area and distributed on both faces.

$$A_{st} = \frac{0.1}{100} \times B\ D$$

536. In a singly reinforced beam, steel reinforcement is placed in :


(a) Tension zone

Search on Telegram @apna_pdf

(b) Compression zone
(c) Both Tension and Compression zone
(d) At neutral zone

[UPPSC State Eng. A.E. 2008]

Ans : (a) In singly reinforced beam, steel reinforcement is placed in tension zone only.



537. The torsional longitudinal reinforcement in RCC beams should be placed at:
(a) Each corner of the beam
(b) Middle of each face
(c) Middle of the beam
(d) Core of the beam

[UPPSC State Eng. A.E. 2007(I)]
[UPPSC State Eng. A.E. 2003]

Ans : (a) Torsional longitudinal reinforcement shall be placed as close as is practicable to the corners of the cross-section and in all cases, these shall be at least one longitudinal bar in each corner of the ties. When the cross-sectional dimension of the member exceeds 450 mm, additional longitudinal bars shall be provided to satisfy the requirements of minimum reinforcement and spacing.

538. The maximum area of tension reinforcement in beams shall not exceed;
(a) 0.15% (b) 1.0%
(c) 1.5% (d) 4.0%

[TNPSC AE 2012]
[UPPSC State Eng. A.E. 2004 (I)]

OR

Given that d = effective depth, b = width and D = overall depth, the maximum area of compression reinforcement in a beam is
(a) 0.01 bd (b) 0. 10bD
(c) 0.12 bd (d) 0. 04bD

UPPSC State Eng. A.E. 2003
UKPSC AE (Paper-I) 2007

Ans : (d) As per IS 456:2000 maximum area of compression or tension reinforcement shall not exceed 0.04 bD.

539. A RC beam curved in plan is designed for
(a) bending moment and shear
(b) bending moment and torsion
(c) shear and torsion
(d) bending moment, shear and torsion

UPPSC State Eng. A.E. 2003, 2004(I)

Ans : (d) Reinforcement concrete beam curved in plane is designed for :
(i) Bending moment
(ii) Shear force
(iii) Torsion.

540. In case of cantilever beam the vertical deflection limits may generally be assumed to be satisfied provided that the span to depth ratio are not greater than:
(a) 7 (b) 20
(c) 26 (d) 30

UPPSC AE 12.04.2016 Paper–I

Ans : (a) In case of cantilever beam span to depth ratio should not be greater than 7.

For simply supported beam $\frac{\text{Span}}{\text{Depth}} < 20$

For continuous beam $\frac{\text{Span}}{\text{Depth}} < 26$

541. Area of the side face reinforcement of a beam where the depth of web exceeds 750 mm shall not be less than :
(a) 0.25% of web area (b) 0.15% of web area
(c) 0.10% of web area (d) 0.08% of web area

(BPSC AE Paper V 2006)

Ans : (c) When depth of web of a beam is greater than 750 mm then we provide side face reinforcement. Its area is taken 0.10% of the area of web. Side reinforcement are provided at spacing of 300 mm or depth of beam whichever is less.

542. The minimum tension reinforcement required in the concrete beam should not be less than (here, width of the beam = b; depth of the beam = d; and yield strength of steel = f_y)
(a) 0.04 b.d (b) $\frac{0.12}{100}$ b.d
(c) $\frac{0.85\,b.d}{f_y}$ (d) $\frac{0.87\,b.d}{f_y}$


MPPSC AE 2016
[BPSC A.E. Paper (V) 2006]

Ans : (c) According to IS– 456:2000 minimum reinforcement of beam should be $\frac{0.85\,b.d}{f_y}$.

543. Maximum depth of neutral axis for singly reinforced beam with Fe500 is (here, depth of the beam = *d*)
(a) 0.44 *d* (b) 0.46 *d*
(c) 0.48 *d* (d) 0.53 *d*

MPPSC AE 2017
OPSC AEE 2015 PAPER–I

Ans. (b) : From strain diagram :
IS 456 : 2000



Search on Telegram @apna_pdf

$$\frac{x}{0.0035} = \frac{d-x}{\left(0.002+\frac{0.87f_y}{E_S}\right)}$$

$$\left[\frac{x_m}{d} = \frac{0.0035}{0.87\frac{f_y}{E_S}+0.002}\right]$$

putting, $f_y = 500$ MPa
and $E_S = 2\times10^5$ MPa
then $x = 0.456\,d = 0.46\,d$

544. For a simply supported beam of span 12 m, the basic value of span to effective depth ratio is-

(a) 20 (b) 26

(c) $\frac{65}{3}$ (d) $\frac{50}{3}$

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (d) :

Effective depth ratio $\frac{l}{d} = \text{basic}\frac{l}{d}\times\left(\frac{10}{\text{span}}\right)$

$$= 20\times\frac{10}{12} = \frac{200}{12} = \frac{50}{3}$$

545. In a singly reinforced balanced section, if M 30 concrete and Fe 415 steel is used, then the value of neutral axis factor (ku_{max}) in L.S.M. is-

(a) 0.42 (b) 0.46

(c) 0.48 (d) 0.52

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (c) : Neutral axis factor is L.S.M. is given as

$$K = \frac{0.0035}{0.0035+\left(0.002+\frac{0.87f_y}{E_S}\right)}$$

Where, $f_y = 415$ MPa

$E = 2\times10^5$ MPa

$$K = \frac{0.0035}{0.0035+\left(0.002+\frac{0.87\times415}{2\times10^5}\right)}$$

$$K = \frac{0.0035}{7.30525\times10^{-3}} = 0.479$$

$K = 0.48$

546. A beam AB is simply supported and has flexural rigidity *EI*. The flexural strain energy of the beam having span 6 m and carrying a central point load of 10 kN is-

(a) $\frac{142.38}{EI}$ (b) $\frac{775}{EI}$

(c) $\frac{225}{EI}$

(d) None of the above

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (c) :

$M_1 = 5x \quad [0 < x < 3]$

$M_2 = (30–5x) \quad [3 < x < 6]$

$$u = \int\frac{M^2dx}{2EI}$$

$$= \int_0^3\frac{(5x^2)dx}{2EI}+\int_3^6\frac{(30-5x)^2dx}{2EI}$$

$$= \frac{225}{EI}$$

547. In a fixed beam of span '*L*' subjected to a central concentrated load '*W*', the fixed end moment and moment at midspan are respectively-

(a) $\frac{WL}{12}$ and $\frac{WL}{6}$ (b) $\frac{WL}{8}$ and $\frac{WL}{8}$


(c) $\frac{WL}{6}$ and $\frac{WL}{12}$ (d) None of the above

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (b) : Moment at mid span -

$$M_{AB} = \frac{1}{2}\times\frac{W}{2}\times\frac{L}{2} = \frac{WL}{8}$$

$$M_{BA} = -\frac{WL}{8}$$



548. Due to shrinkage stresses, simply supported beam having reinforcement only at the bottom tends to deflect

(a) downward
(b) upward
(c) downward or upward
(d) None of the above

BPSC AE 2019 Paper (V) Section-I

Ans. (a) : Due to shrinkage stresses, simply supported beam having reinforcement only at the bottom tends to deflect downward.

549. A simply supported RC beam carries UDL and is referred as beam A. A similar beam is prestressed and carries the same UDL as the beam A This beam is referred as beam B. The mid-span deflection of beam A will be

(a) more than that of beam B
(b) less than that of beam B
(c) the same as that of beam B
(d) generally less but sometimes more depending upon the magnitude of UDL

APPSC AEE (Mains) 2016

Ans. (a) : The deflection in PSC beam as compared to RCC beam will be less because a moment due to prestressed cable produces deflection in direction opposite to that of live loads.

Search on Telegram @apna_pdf

550. The neutral axis of the reinforced beam passes through

(a) centre of gravity of the concrete section
(b) meta-centre of the concrete section
(c) centroid of the transformed section
(d) centroid of the concrete section

APPSC AEE (Mains) 2016

Ans. (c) : Neutral axis is the axis where the strain in the section is zero. It passes through centroid of the transformed section.

551. In a singly reinforced beam if the failure strain of concrete in bending compression reaches earlier than yield strain in steel, the beam section is called

(a) balanced section
(b) critical section
(c) under-reinforced section
(d) over-reinforced section

TNPSC AE 2018

Ans. (d) : In over reinforced member failure is due to compression failure of concrete and in under reinforced member failure is due to tension failure in steel.

552. A beam shall be deemed to be a deep beam when the ratio of effective span to overall depth is less than _____ and _____ for simply supported beam and cantilever beam, respectively.

(a) 7.26 (b) 2.5, 2.0
(c) 2.0, 2.5 (d) 26, 7.0

[HPPSC AE 2016]

Ans. (c) : A beam with effective span to overall depth ratio less than 2 for simply supported and less than 2.5 for cantilever is termed as deep beam.

553. Maximum allowed deflection in a simply supported RC beam (span, L) under uniformly distributed load including long term elastic and shrinkage effect is :

(a) $\frac{L}{350}$ (b) $\frac{L}{250}$
(c) $\frac{L}{200}$ (d) $\frac{L}{175}$

Rajasthan JEN (Degree) Shift - II 2016

Ans. (b)

Category	Max allowable deflection
Simply supported beam (UDL)	L/250
Railway bridges	L/800
Roadway bridges	L/600
Structural buildings	L/300
Crane track girders	L/800

554. The load carrying capacity of a helically reinforced column as compared to that of a tied column is about -

(a) 5% less (b) 10% less
(c) 5% more (d) 10% more

RPSC AE 2018

Ans. (c) Helical Reinforcement–

- The diameter of helical bars should not be less than $1/4^{th}$ the diameter of largest longitudinal bar and not less than 6 mm.
- The pitch should not exceed (if helical reinforcement is allowed)

$\Rightarrow$ 75 mm
$\Rightarrow$ 1/6 time of core diameter of the column.

555. The maximum deflection due to load in RCC beams in buildings is limited to :

(a) Span/100 (b) Span/250
(c) Span/350 (d) Span/500

GPSC AE Class (1&2) Paper - 2 2017

Ans. (b) : The maximum deflection due to load in RC beam in building span/250.

556. Which of the following cracks are the first cracks to be formed in an overloading scenario of an Over-reinforced RCC beam?

(a) Web shear cracks
(b) Flexural shear cracks
(c) Flexural cracks
(d) Concrete crushing

GPSC AE (CLASS 1 & 2) 2019

Ans : (d) : Over reinforcement fails in crushing because in over reinforcement concrete fail first (i.e., primary failure) and flexural failure comes in secondary failure.

557. The minimum area of tension reinforcement required in a rectangular beam section 200 mm × 400 mm if Fe415 steel is used at 25 mm effective cover:

(a) 154 mm^2 (b) 180 mm^2
(c) 164 mm^2 (d) 193 mm^2

Kerala PSC AE 2015

Ans. (a) : Minimum tension reinforcement in a beam is given as

$$\frac{0.85}{f_y} = \frac{A_{st}}{bd}$$

Minimum area of steel required

$$= \frac{0.85}{415} \times 200 \times 375$$

A_{st} = 154 mm^2

558. In which of the following types of concrete beam section, failure will occur all on a sudden?

(a) singly reinforced beam
(b) under reinforced beam
(c) balanced section
(d) over reinforced section

Kerala PSC AE 2015

Ans. (d) : In over reinforced section, concrete fails prior to failure of steel. Since concrete is a brittle material, the failure is sudden. $x_{actual} > x_{critical}$

559. Effective span of a simply supported beam is:

(a) Face to face distance of supports
(b) Clear span + effective depth
(c) Clear span – effective depth


Search on Telegram @apna_pdf

(d) Clear span + effective depth/2

Kerala PSC AE 2015

Ans. (b) : Effective span of a simply supported beam or slab

$$l_{\text{eff}} = \text{minimum}\begin{cases} l_0 + d \\ l_0 + \frac{w}{2} + \frac{w}{2} \end{cases}$$



Effective span for cantilever beam/slab

$l_{\text{eff}} = l_0 + d/2$

or

$l_{\text{eff}} = l_0 + b/2$

d = Effective depth

w = width of support

l_0 = Clear span

l_{eff} = Effective span

560. The ultimate moment of resistance by LSM for a beam with b = 300 mm, d = 550 mm, M20 concrete, reinforced with 4 bar of 25 mm dia Fe250 bars :

(a) 146 kNm (b) 194 kNm

(c) 200 kNm (d) 210 kNm

Kerala PSC AE 2015

Ans. (c) : Given that ;

Fe250, M20

$\Rightarrow$ $f_y = 250$ N/mm^2

$f_{ck} = 20$ N/mm^2

For Fe250

Limiting depth of neutral axis:

$x_{u,\,lim} = 0.530\,d$

$= 0.53 \times 550 = 291.5$ mm

Actual depth of neutral axis:

$C = T$

$0.36\, f_{ck}\, x_u\, b = 0.87\, f_y\, A_{st}$

$$x_u = \frac{0.87 \times 250 \times 4 \times \frac{\pi}{4} \times (25)^2}{0.36 \times 20 \times 300}$$

$= 197.71$ mm

$x_u < x_{u,\,lim} \Rightarrow$ (section is under reinforced)

$\therefore$ Ultimate moment of resistance,

MOR $= 0.36\, f_{ck}\, x_u\, b(d - 0.42\, x_u)$

$= 0.36 \times 20 \times 197.71 \times 300$

$(550 - 0.42 \times 197.71)$

$= 199417717.8$ N-mm

$= 199.417$ kNm $= 200$ kNm

561. Two simply supported beams A and B of same width have identical loading. What is the ratio $\left(\frac{\text{strength of beam A}}{\text{strength of beam B}}\right)$ if beam A has depth double that of beam B?

(a) 2 (b) 4

(c) $\frac{1}{2}$ (d) $\frac{1}{4}$

Kerala PSC AE 2015

Ans. (b) : Strength of beam can be determined by the section modulus (Z) = I/y, $d_a = 2d_B$

$$\frac{Z_A}{Z_B} = \frac{\frac{bd_A^2}{6} \times 6}{\frac{bd_B^2}{6} \times 6} = \frac{d_A^2}{d_B^2} = \left(\frac{2d_B}{d_B}\right)^2 = (2)^2 = 4$$

$$\frac{Z_A}{Z_B} = 4$$

562. In which condition a doubly reinforced beam is used?

(a) when extra safety is needed

(b) when depth and breadth of beam have to be restricted in size

(c) when large moment is expected

(d) when depth is more than 1 m

Kerala PSC AE 2015

RPSC AE 2013

Ans. (b) : Designing condition for doubly reinforced beam.

(i) When depth and breadth of beam have to be restricted in size.

(ii) When the beam section is continuous over several supports.

(iii) When member are subjected to shock impact or accidental lateral load.

(iv) $(MOR)_{required} > (MOR)_{Design}$

563. In a cantilever beam tensile reinforcement is provided:

(a) On top beam

(b) On bottom of beam


(c) At middle of beam

(d) On top and bottom of beam

KPSC AE 2016

Ans. (a) : In simply supported beam compression occurs at top and tension in bottom. That's why we generally provide reinforcement in bottom.

While in case of cantilever beam tension occurs at top. That's why we provide reinforcement on top in order to give strength the structure in tension.



564. In a singly reinforced beam, the effective depth is measured from is compression edge to


(a) tensile edge

Search on Telegram @apna_pdf

(b) tensile reinforcement
(c) neutral axis of the beam
(d) longitudinal central axis

TNPSC AE 2018

Ans. (b) In a singly reinforced beam, the effective depth is measured from is compression edge to tensile reinforcement.



Here,
B = width of beam
D = overall depth
d = Effective depth
σ_{cbc} = c = permissible stress in concrete
σ_{st} = t = permissible stress in steel
the concrete below NA is not taken into consideration the efficient depth is only upto tensile reinforcement.

565. The overall depth for a two way simply supported two way slab is 300mm. Find the span length.
(a) 14120 mm (b) 13250 mm
(c) 7035 mm (d) 10500 mm

DSSSB AE 2019

Ans. (d)

$$\text{Effective depth of two way slab} = \frac{\text{span length}}{35}$$

$$300 = \frac{\text{span length}}{35}$$

span length = 10500 mm

566. The area of tensile steel reinforcement in a singly reinforced beam section is 1075 mm^2. The breadth and depth of the beam section is 250 mm × 250 mm. Find out percentage of tensile steel.
(a) 2.25 percent (b) 3.55 percent
(c) 4.38 percent (d) 1.72 percent

DSSSB AE 2019

Ans. (d)

$$\% \text{ of Tensile steel} = \frac{\text{Area of tensile steel reinforcement}}{\text{Area of beam section}}$$


$$= \frac{1075}{250 \times 250} \times 100$$

$$= 1.72\%$$

567. Two planks each of 50 mm × 50 mm section are glued together along the length to form a section 50 mm × 100 mm and used as a beam. If the shear force at a section is 1000 N, what is the maximum shear stress on the glue?
(a) 0.15 MPa (b) 0.3 MPa
(c) 0.6 MPa (d) 2.4 MPa

ISRO Scientist/Engineer 2020

Ans. (b) :



$$\text{Shear stress at glue} = \frac{3}{2}\tau_{avg}$$

$$= \frac{3}{2} \times \frac{1000}{50 \times 100}$$

$$= 0.3 \text{ MPa}$$

568. If d and n are the effective depth and depth of the neutral axis respectively of a singly reinforced beam, the lever arm of the beam is:
(a) d (b) n
(c) d + n/3 (d) d –n/3

ISRO Scientist/Engineer 2020

Ans. (d) : Lever arm = distance between the compressive and tensile force

$$= d - \frac{x_u}{3}$$

d = Effective depth of beam
x_u = depth of neutral axis

569. In the case of a continuous beam, if the width of the support is less than 1/12th of the clear span, then the effective span shall be calculated as
(a) Centre to centre of support
(b) Clear span plus effective depth
(c) Clear span plus effective depth or centre to centre of support whichever is less
(d) Clear span plus effective depth or centre to centre of support whichever is more

ISRO Scientist/Engineer 2019


Ans : (c) :
- According to IS : 456-200 code clause 22.2 for a continuous beam having a support width less than $\frac{1}{12}^{th}$ clear span, the effective span shall be as per freely supported beam, i.e. clear span plus the effective depth or centre to centre of supports whichever is less.
- If the supports are wider than $\frac{1}{12}^{th}$ the clear span or 600mm whichever is less, the effective span for end span with one free and the other end continuous the effective span shall be equal to the clear span plus half the effective depth of beam or the clear span plus half the width of discontinuous support whichever is less.

570. In an under reinforced R.C.C. beam section, the actual neutral axis falls _____ the critical neutral axis of balanced section.
(a) Below (b) Above
(c) At (d) None of the above

ISRO Scientist/Engineer 2019

Search on Telegram @apna_pdf

Ans : (b) Under-Reinforced Beam - The sections in which the steel reaches yield strain at loads lower than the load at which the concrete reaches failure strain. The actual neutral axis of such a section will fall above the critical neutral axis of a balanced section.
The under-reinforced section in which the actual neutral axis is above the critical N.A.



- In a under reinforced concrete, the concrete is not fully stressed to its permissible value when stress in steel reaches it maximum value of $\tau = \sigma_{st}$.

571. The effective depth of a singly reinforced rectangular beam is 400 mm. The section is over reinforced and the neutral axis is 180 mm below the top. If the maximum stress attained by concrete is 5N/mm^2 and the modular ratio is 18, then the stress developed in the steel will be
(a) 110 N/mm^2 (b) 135 N/mm^2
(c) 160 N/mm^2 (d) 180 N/mm^2

ISRO Scientist/Engineer 2017

Ans : (a) : Given,
M = 18
d = 400 mm
n = 180 mm
c = 5 N/mm^2

By using formula $\frac{M \times c}{t} = \frac{n}{d-n}$

$$\frac{18 \times 5}{t} = \frac{180}{400-180}$$

$$\frac{90}{t} = \frac{180}{220}$$

$$t = \frac{90 \times 220}{180} = 110 \text{ N/mm}^2$$

572. If the bond stress developed in a reinforced concrete beam is more than permissible value, it can be brought down by
(a) Decreasing the depth of the beam
(b) Decreasing the number of bars
(c) Decreasing the diameter of the bars
(d) Increasing the diameter of the bars

ISRO Scientist/Engineer 2017

Ans : (c) : According to Indian Standard specification (IS : 456-1978) the permissible value of bond stress for M15 grade of concrete limited to 1 N/mm^2 in case the bond stress developed in a reinforced concrete beam is more than the permissible value then it can be brought down by (a) increasing the depth of beam (b) decreasing the diameter of the bars, and (c) inclosing the number of bars.

573. A T-beam behaves like a rectangular beam of width equal to its flange, if neutral axis
(a) Remains outside the flange
(b) Remains within the flange
(c) Remains below the slab
(d) Remains anywhere in the web


ISRO Scientist/Engineer 2017

Ans : (b) T-beam having neutral axis which the flange the formula derived for rectangular beam can be used.

574. A cantilever beam 'A' with rectangular cross section is subjected to a concentrated load at its free end. If the width and depth of another cantilever beam 'B' are twice those of beam 'A' and subjected to the same load, then the deflection at the free end of beam 'B' as compared to that of 'A' will be
(a) 6.25% (b) 14.0%
(c) 23.6% (d) 28.0%

ISRO Scientist/Engineer 2018

Ans : (a) :
- Deflection is inversely proportional to moment of inertia. By doubling the width and depth moment of inertia will become 16 times that of original.



$$\delta_A = \frac{PL^3}{3EI_A} \text{(at free end)} \quad \delta_B = \frac{PL_3}{3EI_B} \text{(at free end)}$$

$$\frac{\delta_B = \frac{PL^3}{3EI_B} = \frac{1}{I_B}}{\delta_A = \frac{PL^3}{3EI_A} = \frac{1}{I_A}}$$

$$\frac{\delta_B}{\delta_A} = \frac{I_A}{I_B} = \frac{\frac{bd^3}{12}}{\frac{2b(2d^3)}{12}} \quad \therefore \text{(B are twice of beam A)}$$


$$\frac{\delta_B}{\delta_A} = \frac{1}{16}$$

$\delta_B = 6.25\% \, \delta_A$

575. In a singly reinforced beam, the effective depth is measured from its compression edge to
(a) Tensile edge
(b) Longitudinal central axis
(c) Neutral axis of the beam
(d) Centre of tensile reinforcement

ISRO Scientist/Engineer 2018

Ans : (d) : In a singly reinfroced beam, the effective depth is measured from its compression edge to centre of tensile reinforcement.



Search on Telegram @apna_pdf

576. The permissible value of span/depth ratio will be the highest in the case of
(a) a simply supported beam
(b) a cantilever beam
(c) a continuous beam
(d) it will be same for all cases

ISRO Scientist/Engineer 2014

Ans : (c) Permissible value of span/depth ratio:
$\Rightarrow$ simply supported slab = 20
$\Rightarrow$ continuous slab = 26
$\Rightarrow$ cantilever slab = 7

577. A doubly Reinforced section is used,
(a) When the members are subjected to alternate external loads and bending moment in the section reverses
(b) When the members are subjected to loading eccentric on either side of the axis
(c) When the members are subjected to accidental lateral loads
(d) All the above

ISRO Scientist/Engineer 2013

Ans : (d)
- Loads are altering and reversing and may cause tension on both faces.
- Loads are eccentric.
- Accidental and sudden lateral loads.
- Dimensions are restricted.
- Continuous beam and slab.

578. Permissible deviation from specified dimensions of cross-section of Column & Beams as per IS Standards is ------ mm
(a) +10 mm -4 mm (b) +12 mm -6 mm
(c) +14 mm -8 mm (d) None

ISRO Scientist/Engineer 2013

Ans : (b)
- Deviation from specified dimensions of cross-section of columns and beams are +12mm, –6mm.
- Deviation from dimension of footing in plan +50mm, –12mm.

579. A simply supported beam has an effective span of 16m. What shall be the limiting ratio of span to effective depth as per IS 456-2000?
(a) 26 (b) 20
(c) 12.5 (d) 15

ISRO Scientist/Engineer 2013
ESE 2012

Ans : (c)
- The span to depth ratio limit is specified in IS : 456–2000 for reinforced concrete beams in order to ensure that the deflection of beam is below a limiting value.
- $\frac{L}{d} < 20$ upto 10m (Length)
- Above 10m length

$$\frac{L}{d} = 20 \times \frac{10}{16} = 12.5$$

$$\left[\begin{array}{l}\text{The limiting ratio of span to effective depth} \\ \text{as per IS } 456 - 2000 = 12.5\end{array}\right]$$

580. A simply supported beam is considered as a deep beam if the ratio of effective span to overall depth is less than
(a) 1 (b) 2
(c) 3 (d) 4

Nagaland PSC CTSE 2017 Paper–I
UPPSC State Eng. A.E. 2011
ISRO Scientist/Engineer 2013
ESE 2012

Ans : (b) According to IS 456 : 2000,
Deep beam defined as when ratio of effective span to overall depth $\frac{'\ell'}{D}$ is less than–
$\Rightarrow$ 2.0 for simply supported beam.
$\Rightarrow$ 2.5 for a continuous beam.
R.C. deep have usefull applications in tall buildings, offshore structures and foundations.

581. If the span to effective depth ratio of a simply supported beam, for span upto 10m, does not exceed ----------, the vertical deflection limits may generally be satisfied.
(a) 30 (b) 35
(c) 20 (d) 26

ISRO Scientist/Engineer 2018

Ans : (c) : • The vertical deflection limit may generally be satisfied if.
(i) Basic span to effective depth ratio for span upto 10m is $\frac{\text{Span}}{\text{Effective depth}}$
- For simply supported $\rightarrow 20$
- For cantilever $\rightarrow 7$
- For continuous $\rightarrow 26$

Support Condition	Span/Overall depth	
	Fe 250	Fe 415/ Fe500
Simply supported	35	28
Continuous	40	32

582. Tension failure occurs in a singly reinforced beam in
(a) Balanced reinforced beam
(b) Under reinforced beam
(c) Over reinforced
(d) None of these

ISRO Scientist/Engineer 2018

Ans : (b) :
- Tension failure occur in a singly reinforced beam in under reinforced beam.
- Tension steel reaches the maximum permissible value prior to concrete.
- Area of tension steel is less then that in the balanced section ($A_{st} < A_{st\ bal}$)
- Failure is ductile.

583. The short term deflection of a two way reinforced concrete slab depends on
(a) the long span
(b) the short span
(c) the aspect ratio
(d) coefficient of orthotropy

APTRASCO 2017

Search on Telegram @apna_pdf

Ans : (b) Short term or instantaneous deflection caused by the service loads may be calculated by using the elastic theory using short-term modulus of elasticity and effective moment of inertia ($I_{eff.}$)

$$\left[\delta = \frac{PL^3}{48EI}\right]$$


584. The effective depth in a singly reinforced concrete beam is defined as the distance between the compression edge.

(a) To the centre of compression steel
(b) To the centre of tension steel
(c) To the bottom edge of the beam
(d) To the neutral axis of the beam

APTRASCO 2017

Ans : (b) Effective depth is the distance between extreme compression fiber to the centroid of tension reinforcement in a section under flexure.

585. Consider the singly reinforced beam shown in figure below :



At the cross-section XX, which of the following statement is TRUE at the limit state?

(a) The variation of stress is linear and that of strain is non-linear.
(b) The variation of strain is linear and that of stress is non-linear.
(c) The variation of both stress and strain is linear.
(d) The variation of both stress and strain is non-linear.

APTRANSCO 2017

Ans : (b) According to IS 456 : 2000 in a RCC beam in flexure (bending) has linear strain and parabolic variation of stress in the compression side and point stress in the tension side hence stress is non-linear.

586. Flexural collapse in over reinforced beams is due to :

(a) Primary compression failure
(b) Secondary compression failure
(c) Primary tension failure
(d) Bond failure

OPSC AEE 2019 Paper–I
ESE 1997

Ans. (a) : Secondary compression failure of concrete occurs in under reinforcement section in which steel fails first and finally failure occur due to gradual increase of strain in concrete when steel states yielding and finally concrete getting crashed (called secondary compression failure).

587. In limit state of design, the maximum limit imposed by IS:456-1978 on the redistribution of moments in statically indeterminate beams is

(a) 10% (b) 15%
(c) 20% (d) 30%

OPSC AEE 2019 Paper–I

Ans. (d) : The maximum limit imposed on the redistribution of moment in statically indeterminate beams is 30%.

588. Shrinkage deflection in case of rectangular beams and slabs can be eliminated by putting :

(a) Compression steel equal to tensile steel
(b) Compression steel more than tensile steel
(c) Compression steel less than tensile steel
(d) Compression steel 25% more than tensile steel

OPSC AEE 2019 Paper–I

Ans. (a) : Shrinkage deflection can be eliminated by putting tension steel is equal to compression steel.

589. For the deflection of simply supported beam to be within permissible limits the ratio of its span to effective depth as per IS : 456 : 1978 should not exceed :

(a) 7 (b) 20
(c) 26 (d) 35

OPSC AEE 2019 Paper–I

Ans. (b) : Span to effective depth ratio for simply supported beam to satisfy vertical deflection limit is

$$\frac{L}{d} = 20$$

590. Which of the following are correct for cover to reinforcement ?

1. The reinforcement shall have a minimum clear cover of 20 mm or diameter of such bar whichever is more.
2. At each end of reinforcing bar not less than 25 mm nor less than twice the diameter of such bar.
3. Increased cover thickness may be provided when surface of concrete is exposed to the action of harmful chemical.

(a) 1, 2 and 3 (b) 1 and 2 only
(c) 1 and 3 only (d) 2 and 3 only

ESE 2020

Ans. (a) : Reinforcement shall have concrete cover (nominal) and the thickness of such cover shall be as follows as per SP-34.

(i) The reinforcement shall have a minimum clear cover of 20 mm or diameter of such bar whichever is more.
(ii) At each end of reinforcing bar not less than 25 mm, or twice the diameter of such bar whichever is greater.
(iii) Minimum cover for reinforcing bar in
  (a) Column is 40 mm or diameter of bar whichever is greater.
  (b) In beam is 25 mm or diameter of bar whichever is greater.
(iv) Increased cover thickness may be provided when the surfaces of concrete members are exposed to the action of harmful chemicals.

- However, in no case cover should exceed 75 mm.

Search on Telegram @apna_pdf

591. A rectangular beam with b = 200 mm and effective depth d = 300 mm is subjected to limit state shear of 80 kN and torsional moment of 6 kNm. The equivalent value of shear will be :

(a) 128 kN (b) 116 kN
(c) 104 kN (d) 92 kN

ESE 2020

Ans. (a) : Given,

$b = 200$ mm, $d = 300$ mm, $V_u = 80$ kN

$T_u = 6$ kN/m

Equivalent shear force,

$$V_e = V_u + \frac{1.6T_u}{b}$$

$$V_e = 80 + \frac{1.6 \times 6}{0.2}$$

$$\boxed{V_e = 128\text{kN}}$$

592. Which of the following types of failures occur in the beam-column connections ?

1. **Failure by lateral - torsional buckling**
2. **Failure by combined instability in both the principal directions**
3. **Failure by combined twisting and bending on the torsionally weak sections**
4. **Failure by combined twisting and bending when plane of bending does not contain the shear centre.**

(a) 1, 2 and 3 only (b) 1, 3 and 4 only
(c) 1, 2 and 4 only (d) 2, 3 and 4 only

ESE 2020

Ans. (b) : Beam-column is a structural member subjected to both axial compression and bending moment with likely mode of failures may exist, which are :


(1) Failure by instability in plane of bending without twisting under axial compression and bending about one axis.
(2) Failure by lateral torsional buckling under axial compression and bending about the major axis.
(3) Failure by instability in one of the principal direction due to axial compression and biaxial bending (torsionally stiff section)
(4) Failure by combined twisting and bending on torsionally weak section (thin walled section).
(5) Failure by combined twisting and bending when plane of bending does not contain the shear centre under axial compression, biaxial bending and torsion.

593. A T-Beam behaves as a rectangular beam of width equal to its flange if its neutral axis is :

(a) coincides with centroid of reinforcement
(b) coincides with centroid of T-section
(c) remains within the flange
(d) remains in the web

JPSC AE (Pre) 2019
ESE 2006

Ans. (c) :



When neutral axis lies in the flange and concrete below the neutral axis is assumed to have cracked, the beam is as good as a rectangular section having width 8_f i.e., effective width of flange and effective depth 'd' with only the depth above the natural axis utilized in resisting flexure.

594. For a simply supported cantilever beam, the ratio of the effective span to effective depth of the beam should be less than to satisfy the deflection criterion is :

(a) 10 (b) 26
(c) 20 (d) 7

PSPCL AE 2012

Ans. (d) :

For simple supported slenderness ratio (λ) i.e

$$\lambda = \frac{l}{r} \quad \frac{\text{effective span}}{\text{effective span}}$$

$\gamma \leq 20$

Cantilever = 7

Continuous beam = 26

In two way slab	**mild**	**Fe 45/500**
SSB	35	28
continuous	40	30

595. The maximum permissible final deflection of a beam should not exceed

(a) span/350 (b) span/250
(c) span/480 (d) span/500

Maharashtra PSC Mains 2018 Paper-1

Ans. (a) : As per IS 456 :

The deflection including the effects of temperature, creep and shrinkage occurring after erection of partitions and the application of finishes should not normally exceed span/350 or 20 mm whichever is less.

596. Span effective depth ratio for cantilever for span upto 10 m is

(a) 7 (b) 20
(c) 26 (d) 35

Maharashtra PSC Mains 2018 Paper-1

Ans. (a) : • span effective depth ratio for cantilever for span upto 10 m is '7'.

• Span effective depth ratio for continuous slab for span upto 10 m is '26'.

• Span effective depth ratio for simply support for span upto 10 m is '20'.

Search on Telegram @apna_pdf

597. A simply supported beam shall be deemed to be a deep beam when the ratio of the effective span (L) to the overall depth (D) is

(a) less than 2.0 (b) more than 2.0
(c) less than 2.5 (d) more than 2.5

GPSC AE March 2018

Ans. (a) : Beam is classified as deep

For simply supported beam = $\frac{L}{d} < 2$

For continuous beam = $\frac{L}{d} < 2.5$

598. The minimum vertical space of the main reinforcement in R.C.C. beam is

(a) the diameter of the larger bar or 5 mm more than the nominal maximum size of the coarse aggregate
(b) the diameter of the larger bar or two-thirds the nominal maximum size of the coarse aggregate
(c) 5 mm more than the diameter of the bar
(d) 15 mm

GPSC AE March 2018

Ans. (b) :

The minimum vertical space of main reinforcement in RCC beam = $\begin{cases} \text{(i) } 15\text{mm} \\ \text{(ii) } 2/3 \text{ of nominal size of coarse aggregate} \\ \text{(iii) maximum size of bar} \end{cases}$

599. The lap length of a direct tension reinforcement bar in a R.C.C. beams should be more than

(a) 16 times the diameter of the bar
(b) 48 times the diameter of the bar
(c) thrice the development length or 24 times the diameter of the bar
(d) twice the development length or 30 times the diameter of the bar

GPSC AE March 2018

Ans. (d) : Lap length of direct tension reinforcement bar in a RCC beams $\geq 2 \times$ development length.
$\geq 30 \times$ diameter of bar.

600. The maximum diameter of the reinforcement bars in R.C.C. beam is limited to

(a) 28 mm
(b) 40 mm
(c) one-eighth of the least dimension of the beams
(d) one-tenth of the depth of beams

GPSC AE March 2018

Ans. (c) : According to IS:456-2000.

Diameter for reinforcement bar $\leq \frac{1}{8}$ (least dimension of beam)

601. The minimum percentage of tension reinforcement in R.C.C. beams is

(a) $\not< \frac{0.85}{f_y}$ (b) $\not< 6$
(c) $\not< 4$ (d) $\not< \frac{0.4 b_s}{0.87 f_y}$

GPSC AE March 2018

Ans. (a) : $\frac{A_s}{bd} = \frac{0.85}{f_y}$

A_s = minimum area of tension reinforcement
b = breadth of beam or the breadth of the web of T-beam
f_y =characteristic strength of reinforcement in (N/mm^2)
$\Rightarrow$ Maximum tension reinforcement = 0.04 bD

602. Limiting value of moment of resistance for a rectangular beam reinforced with Fe 415 is

(a) 0.148 fck bd^2 (b) 0.133 fck bd^2
(c) 0.141 fck bd^2 (d) 0.138 fck bd^2

GPSC Poly. Tech. Lect. 2016

Ans. (d) : Limiting value of moment of resistance value N.mm–

Grade of steel	Moment of resistance
Fe 250	0.148 f_{ck} bd^2
Fe 415	0.138 f_{ck} bd^2
Fe 500	0.133 f_{ck} bd^2

603. Basic value of span to effective depth ratio of a continuous beam of span up to 10 m, according to IS 456 : 2000 is,

(a) 7 (b) 20
(c) 23 (d) 26

GPSC Poly. Tech. Lect. 2016

Ans. (d) : The vertical deflection of beam is ensured within limit by providing following depth ratio.
$\Rightarrow$ Basic values of span upto 10 m.

cantilever	7
simply supported	20
continuous	26

604. In a doubly reinforced rectangular beam, the allowable stress in compression steel is :

(a) equal to the permissible stress in tension in steel
(b) more than to the permissible stress in tension in steel
(c) less than to the permissible stress in tension in steel
(d) not relted to the permissible stress in tension in steel

Punjab MCP SDO 2015

Ans. (c) : In a doubly reinforced rectangular beam, the allowable stress in compression steel is less than to the permissible stress in tension in steel.

605. The vertical deflection limit upto 10 meter span for cantilever beam, span to effective depth ratio is .....

(a) 7 (b) 20
(c) 26 (d) 14

GPSC R&B AE 2016

Ans. (a) : For vertical deflection limit

For cantilever beam	$\rightarrow l/d = 7$
For simply supported beam	$\rightarrow l/d = 20$
for continuous beam	$\rightarrow l/d = 26$

upto 10 m of span.

Search on Telegram @apna_pdf

606. For a cantilever of effective span 0.5m, the maximum span to satisfy vertical deflection limit is :

(a) 3.5 m (b) 4.0 m
(c) 4.5 m (d) 5.0 m

Punjab MCP SDO 2015

Ans. (a) : Basic value of span to depth effective ratio for span upto 10 m.
1. Cantilever = 7
2. Simply supported = 20
3. Continuous = 26

For cantilever

$$\Rightarrow \quad \frac{l_e}{d} = 7 \Rightarrow l_e = 7 \times 0.5$$

$L_e = 3.5$ m

607. Basic value of span to effective depth ratio for span upto 10 m in case of continuous beam for deflection control is

(a) 7 (b) 20
(c) 26 (d) 24

GOA PSC Assistant Prof. 2020

Ans. (c) : Basic value to effective depth ratio for span upto 10 m
For continuous = 26
For cantilever = 7
For S.S. Beam = 20

608. A reinforced concrete (RC) beam with width of 250 mm and effective depth of 400 mm is reinforced with Fe415 steel. As per the provisions of IS 456-2000, the minimum and maximum amount of tensile reinforcement (expressed in mm^2) for the section are, respectively :

(a) 205and 4000 (b) 250 and 3000
(c) 432 and 4500 (d) 210and 3100

KPTCL AE 2016

Ans. (a) Width of beam (b) = 250 mm
effective depth (d) = 400 mm
minimum tension reinforcement

$$\frac{A_s}{bd} = \frac{0.85}{f_y}, \quad A_s = \frac{0.85\ bd}{f_{\rightarrow}} = \frac{0.85 \times 250 \times 400}{4.15}$$

$= 204.819 \approx 205\ mm^2$
maximum tension reinforcement = 0.04 bd
$= 0.04 \times 250 \times 400 = 4000\ mm^2$

609. In case of beams, the ratio of breadth to depth is usually taken as

(a) 0.5 to 0.7 (b) 0.9 to 1.0
(c) 1.2 to 1.4 (d) 1.8 to 2.0

Maharashtra PSC Mains 2012 Paper -2

Ans. (a) : In case of beams, the ratio of breadth to depth is usually taken as 0.5 to 0.7.

610. In which of the following ways is the splicing of bars done in a RCC beam?

(a) By the use of mesh reinforcement
(b) By Lapping of bars
(c) By the use of bolts
(d) By the use of riveted joints

Rajasthan AE Nagar Nigam Shift-3, 2016

Ans. (b) : Concrete at point of splicing is subjected to high shear and splitting stress causing cracks.
Splicing is basically done in three methods-
1. Lapping
2. Weld
3. Mechanical

611. The deflection in a RCC beam is reduced by (as per IS 456 2000) / RCC

(a) moderating water cement ratio
(b) controlling span/depth ratio
(c) using large aspect ratio
(d) using small modular ratio

Rajasthan AE Nagar Nigam Shift-3, 2016

Ans. (b) : By controlling span/depth ratio the reduction of span/depth ratio from 20 to (15, 12.5 and 10) will reduce maximum deflection by 21%, 30.3% and 41.6% respectively.

612. The behavior of an over reinforced beam is more ductile than that of under reinforced beam because over reinforced beam contains

(a) more steel and steel is more ductile than concrete
(b) concrete is brittle
(c) both concrete and steel stressed simultaneously
(d) statement is wrong

TRB Poly. Tech. Lect. 2012

Ans. (d) : The behavior of an over reinforced bean is less ductile than that under Reinforced Beam.

613. The doubly reinforced beam is less economical than singly reinforced beam because

(a) Tensile steel required is more than balanced section
(b) Shear reinforcement is more
(c) Concrete remains under utilized
(d) Compressive steel remains under utilized

TSGENCO_2015

Ans. (d) : The doubly reinforced beam is less economical than singly reinforced beam because Compressive steel remains under utilized in doubly reinforced beam.

614. The maximum tension reinforcement in RC beams is given by

(a) 0.85 bd/fy (b) 0.85 fy/bd
(c) 0.04 bD (d) 0.08 bD

where the symbols have their usual meanings.

UKPSC(Urban engineering)-2011

Ans. (c) : Maximum percentage of reinforcement (both compression and tension steel) should be 4% of cross–sectional area of beam i.e.
$A_{st} = 0.04$ bD

615. Side face reinforcements is provided when the depth of web of the beam exceeds

(a) 500 mm (b) 650 mm
(c) 750 mm (d) 1000 mm

Gujarat PSC AE (N.W.R.) 2020
BPSC AE Aug. 2019 Paper-V
UJVNL AE 2016
TRB Poly. Tech. Lect. 2012
ESE 2013

Search on Telegram @apna_pdf

Ans. (c) : As per IS 456-2000 (Cl 26.5.1.3)
Side face reinforcement, Where the Depth of the web in a beam exceeds 750 mm, side face reinforcement shall be provided along the two faces.

616. In a doubly reinforced rectangular beam, the allowable stress in compression steel is
(a) equal to the permissible stress in the tension steel
(b) more than permissible stress in the tension steel
(c) less than permissible stress in the tension steel
(d) None of these

APPSC AEE 2012

Ans. (c) : In doubly reinforced rectangular beam, the allowable stress in compression steel is less than permissible stress in the tension steel

617. In case of deep beams, ratio of effective span to overall depth for simply supported and continuous edge conditions respectively are limited to
(a) 3 & 5 (b) 2 & 2.5
(c) 2 & 2 (d) 2 & 3

BPSC AE Aug. 2019 Paper-V

Ans. (c) : As per **IS 456 : 2000, (Cl - 29.1)**- A beam is considered as a deep beam when effective plan (l) to overall depth (D) ratio is < 2 for simply supported beam & for continuous beam, $\frac{l}{d} < 2.5$

618. The maximum value of span/effective depth ratio permissible in case of simply supported RCC beam is
(a) 5 (b) 20
(c) 10 (d) 40

BPSC AE Aug. 2019 Paper-V

Ans. (b) : As per IS 456 : 2000 (Cl-23.2.1)– Basic value of span (l) to effective depth (d) ratio for span upto 10 m.
For cantilever beam $l/d \le 7$
for simply supported beam $l/d \le 20$
for continuous beam $l/d \le 26$

619. As per IS 456, the ordinary portland cement (kg/cum) should be restricted to what value without a special consideration in design to avoid thermal cracking?
(a) 380 (b) 450
(c) 540 (d) 600

UPRVUNL AE 2016

Ans.: (b) Maximum cement content as per IS 456 : 2000 is limited to 450 Kg/m^3.

620. Reinforced concrete beam sections in which the steel reaches yield strain at loads lower than the load at which the concrete reaches failure strain are called
(a) Under-reinforced sections
(b) Balanced sections
(c) Over-reinforced sections
(d) Prestressed sections

UPRVUNL AE 2016

Ans.: (a) Reinforced concrete beam section in which the steel reaches yield strain at loads lower than the load at which the concrete reaches failure strain are called under reinforced section.

621. A continuous member beam is referred as deep beam when the ratio of effective span to overall depth is:
(a) <2 (b) >2
(c) <2.5 (d) >2.5

UPRVUNL AE 2016

Ans.: (c) A beam shall be deep if span to overall depth is as follows .
$\frac{L}{D} < 2$ for a simply supported beam
$\frac{L}{D} < 2.5$ for a continuous beams.

622. An under - reinforced section means
(a) Steel is provided at under side only
(b) Steel provided is insufficient
(c) Steel is provided on one face only
(d) Steel will yield first

GPSC AE June 2019

Ans. (d) : An under reinforced section means the percentage of steel provided is less than that provided in balanced section so the actual neutral axis will shift upwards i.e. $n_c > n$.
→ Steel is fully stressed while concrete not but $\sigma_c < \sigma_{cbc}$.
→ Ductile failure because steel fails first & sufficient warning is given before collapse.

623. The minimum transverse reinforcement in prestressed concrete beam is given by formula:
(a) $\frac{bS_V}{A_{S_V}} = \frac{0.87 f_y}{0.4}$ (b) $\frac{A_{S_V}}{bS_v} = \frac{0.4}{0.87 f_y}$
(c) $\frac{A_{S_V}}{0.87 f_y} = \frac{0.4}{bS_v}$ (d) $\frac{bS_V}{0.87 f_y} = \frac{A_{S_V}}{0.4}$

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (b) : The minimum transverse reinforcement in prestressed concrete beam is,
$\frac{AS_v}{bS_v} = \frac{0.4}{0.87 f_y}$

624. The minimum area of tension reinforcement shall not be less than ..... for design of beam.
(a) $\frac{0.87}{f_y} bD$ (b) $\frac{0.85}{f_y} bD$
(c) $\frac{0.67}{f_y} bD$ (d) $\frac{0.76}{f_y} bD$

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (b) : The minimum area of tension reinforcement shall be not less than $\frac{0.85}{f_y} bd$ for design of beam.

Search on Telegram @apna_pdf

625. A doubly reinforced beam is considered as less economical as compared to a singly reinforced beam because

(a) The depth of section is small
(b) Concrete is under-stressed
(c) Compressive steel is under-stressed
(d) Tensile steel is under-stressed

GPSC AE Dec 2018
ESE 1999

Ans. (c) : A doubly reinforced beam is considered as less economical as compared to a singly reinforced beam because compressive steel is under stressed.

626. A continuous beam is called Deep beam when the ratio of effective span to overall depth, *l*/d ratio is

(a) less than 2 (b) more than 2.5
(c) less than 2.5 (d) more than 2

GPSC Assistant Prof. 2016

Ans. (c) A continuous beam is called deep beam when the ratio of effective span to overall depth (*l*/d) ratio is less than 2.5

627. For a given grade of steel, the limiting reinforcement index for a singly reinforced beam is proportional to

(a) f_{ck} (b) f_y
(c) f_y/f_{ck} (d) f_{ck}/f_y

UJVNL AE 2016

Ans. (d) : The limiting reinforcement index f_{ck}/f_y

628. The maximum percent of moment redistribution allowed in RCC beams is

(a) 10 % (b) 20 %
(c) 30 % (d) 40 %

AP TRANSCO AEE 2017
ESE 2010

Ans. (c) : As per IS 456 : 2000, The maximum percent of moment distribution allowed in RCC beam is 30%

629. As per IS 456-2000, for the design of reinforced concrete beams, the maximum allowable shear stress (τ_{max}) depends on the

(a) grade of concrete and grade of steel
(b) grade of steel only
(c) grade of concrete and percentage of reinforcement
(d) grade of concrete only

AP TRANSCO AEE 2017

Ans. (d) As per IS 456-2000, for the design of reinforced concrete beams, the maximum allowable shear stress (τ_{max}) depends on the grade of concrete only.

630. IS 456 : 2000 recommends to provide certain minimum steel in RCC beam :-

(a) to avoid rupture of steel in case a flexural failure occurs
(b) to ensure compression failure
(c) to hold the stirrups in position
(d) to provide enough ductility to the beam

UPPCL AE 2014

Ans. (a) : IS 456 : 2000 recommends to provide certain minimum steel in RCC beam to avoid rupture of steel in case a flexural failure occurs.

631. In doubly reinforced beams, the percentage of the maximum compression reinforcement of the gross cross sectional area of beam should not exceed:-

(a) 2% (b) 4%
(c) 5% (d) 3%

UPPCL AE 2014

Ans. (a) : In doubly reinforced beams, the percentage of the maximum compression reinforcement of the gross cross sectional area of beam should not exceed 2%.

632. Minimum area of tension reinforcement in a beam shall be greater than:-

(a) 0.85 bd/f_y (b) 0.87 f_y/bd
(c) 0.4bd f_y (d) 0.04 bd

UPPCL AE 2014

Ans. (a) : Minimum area of tension reinforcement in a beam shall be greater than 0.85 $\frac{bd}{f_y}$

633. The ratio of the depth of the parabolic and rectangular portion block at the limiting state of collapse of a singly reinforced section is :-

(a) 4:5 (b) 4:3
(c) 3:4 (d) 2:1

UPPCL AE 2014

Ans. (b) : depth of parabolic portion $= \frac{2h}{3}$

depth of rectangular portion $= \frac{h}{2}$

Ratio of depth of parabolic and rectangular portion

$$= \frac{\frac{2h}{3}}{\frac{h}{3}} = \frac{4}{3}$$

634. Unfactored maximum bending moments at a section of a reinforced concrete beam are 50, 80, 120 and 180kNm under dead, live, wind and earthquake load respectively. The design moment as per IS : 456-2000 for limit state of collapse (flexure) is :-

(a) 250 kNm (b) 372 kNm
(c) 195 kNm (d) 315 kNm

UPPCL AE 2014

Ans. (b) :

$$\text{Design moment} = \max\begin{cases}1.5DL+1.5LL\\1.2(DL+LL\pm WL/EQ)\\0.9DL-1.5EQ\end{cases}$$

$$\max\begin{cases}1.5\times50+15\times80=195\\1.2(50+80+180)=372\end{cases}$$

$\therefore$ Design momemt = 372 kNm

635. Maximum reinforcement in an RCC beam of dimension b x D shall not exceed

(a) 0.06 bD (b) 0.04 bD
(c) 0.02 bD (d) 0.08 bD

APPSC AEE 2016

Search on Telegram @apna_pdf

Ans. (b) :
- Maximum reinforced in an RCC beam is 4%.
- Minimum reinforced in an RCC beam is $\frac{0.85}{f_y}bd$

636. Maximum spacing of vertical stirrups permitted in RC beam having depth D is .....
(a) 0.75 D (b) 2.0 D
(c) 0.5 D (d) 0.25 D

GPSC AE January 2018

Ans. (a) : Maximum spacing of shear reinforcement → (beam) 0.75 d (vertical stirrups)

$$\left.\begin{array}{c} 0.75d \text{ (vertical stirrups)} \\ \text{d (inclined stirrups)} \\ 300 \text{ mm} \end{array}\right\} \text{minimum}$$

637. The maximum percentage of tension reinforcement in beam shall not exceed ..... of cross sectional area as per IS:456.
(a) 0.15% (b) 2.00%
(c) 4.00% (d) 0.12%


GPSC AE January 2018

Ans. (c) : Tension reinforcement in beam ≤ 4% of cross sectional area.
Tension reinforcement in column ≤ 6% of cross section area.

638. A concrete beam of rectangular cross-section of 250 mm (width) by 500 mm (depth) is pre-stressed so that at a section the effective force is 250 kN at an eccentricity (along depth) of 50 mm. What is the maximum compressive stress in concrete in this section of the beam?
(a) 3.2 N/mm^2 (b) 0.8 N/mm^2
(c) 2.0 N/mm^2 (d) 4.5 N/mm^2

UPPCL AE 2018

Ans. (a)



Maximum compression force

$$= \frac{250\times10^3}{250\times500} + \frac{250\times10^3\times50}{\frac{1}{6}\times250\times500^2}$$

$= 3.2$ N/mm^2.

639. Calculate the maximum factored bending moment of rectangular beam for an effective span of 6m. The superimposed load is 84 kN/m. The dimensions of the beam are limited to 35.5 cm × 75 cm overall. Use M-20 and Fe415 grade density of concrete is 25kN/m^3.
(a) 612 kN-m (b) 620 kN-m
(c) 630 kN-m (d) 600 kN-m

LMRC AM 2018

Ans. (a) : Self weight of beam = 0.355 × 0.75 × 1 × 25
= 6.65 kN/m
∴ Total weight = 6.65 + 84
= 90.65 kN/m
Factored load = 1.5 × 90.65
= 135.975 kN/m

Maximum factored bending moment (M_u) = $\frac{w\ell^2}{8}$

$$= \frac{135.975\times6^2}{8}$$

= 612 kN-m

640. The length of the straight portion of a bar beyond the end of the hook should be at least:
(a) Twice the diameter
(b) Thrice the diameter
(c) Four times the diameter
(d) Five times the diameter
(e) Seven times the diameter

Haryana PSC AE 2018 Paper–I

Ans. (c) :
When the bar is bent at
an angle of at least 90^0 - 8d
When the bar is bent at
an angle of at least 135^0 - 12d
When the bar is bent at
an angle of at least 180^0 - 16d

641. In a singly-reinforced beam, if the permissible stress in concrete reaches earlier than that in steel, the beam section is called:
(a) Economic section
(b) Over-reinforced section
(c) Critical section
(d) Under-reinforced section
(e) None of these options

Haryana PSC AE 2018 Paper–I

Ans. (b) : Balanced section:-The max, stresses in the steel and concrete reach their permissible value of stresses at same time.
Under Reinforced section:-If permissible stresses in steel reaches earlier than concrete.
Over Reinforced section:-If permissible stresses in concrete reaches earlier than steel.

642. For normal cases, serviceability requirements of a simply-supported beam is satisfied if the ratio of its span to its overall depth does not exceed:
(a) 10 (b) 20
(c) 30 (d) 40
(e) 50

Haryana PSC AE 2018 Paper–I

Ans. (b) : Basic values of span to effective depth ratio for span upto 10 meter.

• Cantilever	7
• Simply supported	20
• Continuous	26

For spans above 10 meter, the values may be multiplied by 10/span in meters, except for cantilever in which case deflection calculations should be made.

Search on Telegram @apna_pdf

643. The maximum spacing of stirrups in a reinforced concrete (RC) beam of effective depth 400 mm is:

(a) 150 mm (b) 200 mm
(c) 300 mm (d) 400 mm
(e) 450 mm

Haryana PSC AE 2018 Paper–I

Ans. (c) : Maximum spacing of stirrups should not exceed
(a) 0.75 d
(b) 300 mm
(c) Calculated spacing (S_v)

644. The chances of diagonal tension cracks in RCC member reduce when:

(a) Axial compression and shear force
(b) Axial tension and shear force act
(c) Only shear force act
(d) Flexural and shear force act

Haryana PSC AE 2017

Ans. (a) : Chances of diagonal tension cracks in RCC member reduce when axial compression and shear force act.

645. What is the adoptable maximum spacing between vertical stirrups in an RCC beam of rectangular cross-section having an effective depth of 300 mm?

(a) 300 mm (b) 275 mm
(c) 250 mm (d) 225 mm

Haryana PSC AE 2017
ESE 2009


Ans. (d) Spacing of vertical stirrups
$> .75\ d = .75 \times 300 = 225\ mm > 300\ mm$
So $= 225\ mm$

646. A simply supported concrete beam is designed by load balancing concept for an effective span of 20 m and to carry a total load of 30 kN/m. If the beam is prestressed with a force of 2500 kN, determine the central dip of the cable profile.

(a) 200 mm (b) 400 mm
(c) 600 mm (d) 800 mm

UPRVUNL AE 2014

Ans. (c) :



$$w_p = \frac{8(p\cos\theta)e}{l2}$$

The above figure shows the load balancing beam for complete load balancing

$w_p = W$ $\quad P\cos\theta = P$

$\because \theta$ is very small

$$\frac{8Pe}{l^2} = 30$$

$$\frac{8\times 2500\times e}{(20)^2} = 30$$

$e = 0.6\ m$

$e = 600\ mm$

647. Where is main reinforcement provided in a cantilever beam carrying gravity load?

(a) Above the neutral axis
(b) As vertical stirrups
(c) As a helical reinforcement
(d) Below the neutral axis

UPRVUNL AE 2014
ESE 2004

Ans. (a) : The main reinforcement in a cantilever beam carrying gravity load is provided in above the neutral axis.

648. In a beam diagonal, tension reinforcement is provided :

(a) as longitudinal bars
(b) as bent up bars
(c) as helical reinforcement
(d) as 90^0 bend at the bends of main bars

UPRVUNL AE 2014

Ans. (b) Diagonal tension cracks occurs due to diagonal tension which occurs at 45^0 from horizontal for diagonal tension bent-up bars inclined stirrups, vertical stirrups are used.

649. Doubly reinforced beams are recommended when :

(a) the depth of the beam is restricted
(b) the breadth of the beam is restricted
(c) both depth and breadth are restricted
(d) the shear is high

UPRVUNL AE 2014
ESE 2004

Ans. (a) : If load condition is such that depth of singly reinforced beam becomes very large, instead of designing singly reinforced beam we go for doubly reinforced beam.

650. Which of the following is the result of unequal top and bottom reinforcement in a reinforced concrete section?

(a) Shrinkage deflection
(b) Large deflection
(c) Long-term deflection
(d) Creep deflection

UPRVUNL AE 2014

Ans. (a) : Shrinkage deflection is the result of unequal top and bottom reinforcement in a reinforced concrete section.

651. The moment and shear coefficients mentioned in IS : 456-2000 can be used for the analysis of continuous beams with three or more spans only if the spans do not differ by more than ..... percent with respect to the longest span.

Search on Telegram @apna_pdf

(a) 20 (b) 15
(c) 10 (d) 30

HPPSC Poly. Lect. 2016

Ans : (b) In IS : 456-2000 can be used for the analysis of continuous beams with 3 and more spans only if the spans do not differ by more than 15% with respect to longest span.

652. As per IS : 456-2000, the basic span to effective depth ratio for cantilever beam is :

(a) 20 (b) 26
(c) 7 (d) 35

HPPSC Poly. Lect. 2016

Ans : (c) In case of limit state of serviceability excessive deflection of structural elements are contained in IS 456 : 2000 by limiting the 'L/d' ratios is prescribed a limiting value (L/d) = 7 for cantilever beams up to 10 m

653. As per IS : 456-2000 the beam is considered a deep beam when the effective span to overall depth ratio is less than ..... for simply supported beam.

(a) 2.5 (b) 2.0
(c) 3.0 (d) 4.0

HPPSC Poly. Lect. 2016

Ans : (b) Beams with large depth in relation to spans are called deep beams as per IS 456-2000 clause 29, a simply supported beam is classifieds deep when the ratio of it's effective span L to over all depth D is less then 2. Continuous beams considered as deep when L/D is less then 2.5.

654. In order to ensure the lateral stability of simply supported beams, the beam shall be so proportioned that the clear distance between the lateral restraints does not exceed ..... whichever is less.

(a) 60 b or $\frac{250\ b^2}{d}$ (b) 60 b or $\frac{100\ b^2}{d}$

(c) 25 b or $\frac{250\ b^2}{d}$ (d) 25 b or $\frac{250\ b^2}{b}$

HPPSC Poly. Lect. 2016

Ans : (a) To ensure lateral stability for simply supported or continuous beam the clear distance between lateral sustain should not exceed 60 b or $\frac{250\ b^2}{d}$, whichever is less.

655. Number of redundancy in a propped cantilever beam subjected to point load:

(a) 1 (b) 0
(c) 2 (d) 3

IRCON AE 2017

Ans. (a) : Propped cantilever beam

No. of unknowns in propped cantilever beam = 4
(3 reaction and 1 moment)
No. of redundancy = No. of unknowns – No. of equilibrium equation.
= 4 – 3
= 1

656. The simply supported deep beam is one whose L/D ratio is:

(a) less than 3.0 (b) less than 2.0
(c) equal to 2.0 (d) equal to 3.0

IRCON AE 2017

Ans. (b) : As per IS-456 : 2000 (clause-29)
For simply supported beam
ratio of effective span

$$\boxed{\frac{l_{eff}}{D} \le 2}$$

For continuous beam

$$\boxed{\frac{l_{eff}}{D} \ge 2.5}$$

657. Side face reinforcement in a reinforced concrete beam is to be provided for

(a) Total depth of beam > 750 mm
(b) Depth of web of the beam > 750 mm
(c) Total depth of beam > 1000 mm
(d) Depth of web of the beam > 1000 mm

WBPSC AE 2016

Ans. (a) :
As per IS 456: 2000, side face reinforcement is provided when.

- Depth of beam (web) is more than 750 mm (when beam is not subjected to torsion)
- Depth of beam (web) is more than 450 mm (when beam is subjected to torsion)

Side face reinforcement is provided 0.1% of web area equally distributed on both face.
* Maximum spacing of side face reinforcement = 300 mm or width of beam which ever is less.

658. Torsion resisting capacity of a given reinforced concrete section

(a) decreases with decrease in stirrup spacing
(b) decreases with increase in longitudinal bars
(c) does not depend upon stirrup and longitudinal steels
(d) increases with the increase in stirrup and longitudinal steel

WBPSC AE 2007

Ans. (d) : Torsion resisting capacity of a given reinforced concrete section increases with the increase in stirrup and longitudinal steel.

659. As per IS specification the spacing of stirrups in a RCC beam shall not exceed a distance equal to

(a) Effective depth of the beam
(b) Width of the beam
(c) Total depth of the beam
(d) Lever arm of the resisting moment

WBPSC AE (MCD) 1998

Ans. (d) : As per IS specification the spacing of stirrups in a RCC beam shall not exceed a distance equal to lever arm of the resisting moment.

660. A reinforced concrete beam of 25 cm width and 50 cm effective depth as a clear span of 6 m and carries a U.D.L. of 3000 kg/m inclusive of its self weight. If the lever arm constant of the section is 0.865 maximum intensity of shear stress is

Search on Telegram @apna_pdf

(a) 8.3 kg/cm^2 (b) 7.6 kg/cm^2
(c) 10.0 kg/cm^2 (d) 11.4 kg/cm^2

WBPSC AE (MCD) 1998

Ans. (a) : Maximum intensity of shear stress = $\frac{\text{shear force}}{\text{lever arm} \times \text{width of beam}}$

given,

$$V = \frac{wl}{2} = \frac{3000 \times 6}{2} = 9000 \text{ kg}$$

b = 25 cm

d = 50 cm

lever arm = 0.85 × d = 0.85 × 50 = 43.25

maximum intensity of shear stress = $\frac{9000}{43.25 \times 25}$

= 8.323 Kg/cm^2

661. Limiting moment of resistance for singly reinforced rectangular beams using Fe 415 steel is (usual notation being used)

(a) 0.133 f_{ck}/bd^2 (b) 0.138 f_{ck}/bd^2
(c) 0.149 f_{ck}/bd^2 (d) 0.150 f_{ck}/bd^2

WBPSC AE (PHE) 1998

Ans. (*) : For Fe - 415

X_{ulim} = 0.48d

Now, MOR limiting from compression side–

MR = 0.36 f_{ck}. B.X_{ulim} (d-0.42 X_{ulim})

Putting value of X_{ulim}–

MR = 0.36 f_{ck} B.(0.48d) (d–0.42×0.48d)

MR = 0.36×0.48(1–0.72×0.48) ×f_{ck}.B.d^2.

MR = 0.138 f_{ck} ×Bd^2.

No option is correct.

662. Critical section for shear in case of R.C.C. beams in frame buildings is taken at a distance

(a) d from edge of support
(b) at the face or support
(c) $\frac{d}{2}$ from face of support
(d) 0.75 d from face of support where d = effective depth of beam

WBPSC AE (PHE) 1998

Ans. (a) : Critical section for shear in case of R.C.C. beams in frame buildings is taken at a distance d from edge of support.

663. To take care of reversible shear in a R.C.C. beam, it is advisable to use

(a) only vertical stirrups
(b) vertical stirrups in association with cranked reinforcement
(c) only cranked reinforcement
(d) a combination of vertical and inclined stirrups

WBPSC AE (PHE) 1998

Ans. (d) : To take care of reversible shear in a R.C.C. beam, it is advisable to use a combination of vertical and inclined stirrups.

664. The maximum spacing for vertical stirrups of shear reinforcements shall not exceed

(a) 0.75 d (b) 0.45 d
(c) d (d) 0.6 d

WBPSC AE (Common) 1998

Ans. (a) : IS 456 stipulates that the maximum spacing of shear reinforcement measured along the axis of the member shall not be more that 0.75 d for vertical stirrups and d for inclined stirrups at 45º.

665. When the depth of the web of beam is more than _____mm, side face reinforcement of _____% of the web area is needed to be provided according to IS: 456-2000.

(a) 600, 0.1% (b) 750, 0.15%
(c) 600, 0.15% (d) 750, 0.1%

TSPSC Deputy Engineer 2015

Ans. (d) : When the depth of the web of beam is more than 600 mm, side face reinforcement of 0.1% of the web area is needed to be provided according to IS: 456-2000

666. Maximum spacing of vertical shear reinforcement measured along the axis of the RCC beam shall not exceed _____, whichever is lowest.

(a) 0.75d or 300 mm (b) 0.75d or 400 mm
(c) 0.50d or 250 mm (d) 0.5d or 300 mm

TSPSC Deputy Engineer 2015

Ans. (a) : Maximum spacing of shear reinforcement

(i)	For vertical stirrups	0.75 d or 300 mm whichever is less
(ii)	For inclined stirrups at 45º	d or 300 mm whichever is less

667. What is the minimum area of tension reinforcement required for a concrete beam of width 200 mm, effective depth 500 mm and with Fe 250 grade steel?

(a) 340 sq.mm (b) 170 sq.mm
(c) 3400 sq.mm (d) 1700 sq.mm

TSPSC AEE 2017

Ans. (a) : Given,

width of beam = 200 mm

effective depth = 500 mm

$$A_{st_{min}} = \frac{0.85bd}{f_y}$$

$$A_{st_{min}} = \frac{0.85 \times 200 \times 500}{25} = 340 \text{ mm}^2$$

668. The problem of lateral buckling can arise only in those steel beams which has

(a) Moment of inertia about the bending axis larger than the other
(b) Moment of inertia about the bending axis smaller than the other
(c) Fully supported compression flange
(d) None of these

Chandigarh AE 2017

Ans. (b) : The problem of lateral buckling can arise only in those steel beams which has moment of inertia about the bending axis smaller than the other.

Search on Telegram @apna_pdf

5. Reinforced Concrete Slabs

669. Among the different ways of providing reinforcement in reinforced cement concrete beam, identify the one that does not contribute to improve the shear resistance of the beam section.

(a) Reinforcement provided in tension zone which extend into the support
(b) Reinforcement provided in compression zone which extend into the support
(c) Bent-up reinforcement
(d) Vertical or inclined stirrups

CIL MT 2020

Ans. (b) : Reinforcements which are contributed the shear resistances of the beam :
Reinforcement provided in tension zone which extend
- Into the support.
- Bent-up reinforcement
- Vertical or inclined stirrups.

670. One of the criteria for the effective width of flange of T – beam is $b_f = \frac{l_o}{6} + b_w + 6D_f$ In the above formula, l_0 signifies

(a) Effective span of T – beam
(b) distance between points of zero moments in the beam
(c) Clear span of the beam
(d) Distance between points of maximum moments in the beam

APPSC AEE 2012

Ans. (b) : $b_f = \frac{l_o}{6} + b_w + 6D_f$ (effective width of flange of T beam)
This effective width is calculated on the basic of distance between points of zero moment in the beam.

671. In case of 2-way slab, the limiting deflection of the slab is

(a) Primarily a function of the long span
(b) Primarily a function of the short span
(c) Independent of long or short span
(d) Dependent on both long and short spans

UPRVUNL AE 2015

Ans. (b) : The strip of a two way slab may be checked against shorter-span to effective depth ratio.
Span to effective depth ratio

Type of slab	Type of reinforcement	
	for Mild steel	for HYSD
S.S.B.	35	28
Continuous	40	32

672. For design purposes, the width of one way slab is always taken as

(a) 1 mm (b) 100 mm
(c) 1000 mm (d) 2000 mm

TNPSC AE 2012

Ans. (c) The analysis of slab spanning in one direction is done by assuming it to be a beam of 1m (1000 mm) width.

673. Minimum reinforcement required in either direction in slabs reinforced with high strength deformed bars is:

(a) 0.11 (b) 0.12
(c) 0.15 (d) 0.17

Kerala PSC AE 2015

Ans. (b) : Minimum percentage of reinforcement in slab.
For **Fe – 415** → 0.12 × total Area of cross section
Fe – 250 → 0.15 × total Area of cross section

674. The L/d ratio for one-way cantilevered slab specified in IS 456-2000 is

(a) 8 (b) 26
(c) 20 (d) 7

TNPSC AE 2019

Ans. (d) l/d = 7 (Slenderness Ratio = λ) (Cantilever)
l/d = 20 (Simple Support Beam)
l/d = 26 (Continuous Beam)

675. A RCC slab under mild exposure condition having main longitudinal tensile reinforcement of diameter 12 mm, then minimum allowable nominal cover to satisfy durability requirement is

(a) 10 mm (b) 15 mm
(c) 20 mm (d) 25 mm

Gujarat PSC AE 2017

Ans : (b) For main reinforcement upto 12 mm diameter bar and for mild exposure the nominal cover is 15 mm.

676. In case of a non-cellular, non-ribbed flat slab, the spacing of the steel reinforcing bars shall not exceed m times the thickness of the slab, where in m is

(a) 1.5 (b) 1.2
(c) 1.9 (d) 2.0
(e) 3.0

CGPSC AE 2014 Shift–I

Ans. (d) : In case of a non-cellular, non-ribbed flat slab, the spacing of the steel reinforcing bars shall not be exceed 2 times the thickness of slab.

677. The maximum theoretical diameter (in mm) of steel reinforcement in slab 180 mm thick shall be

(a) 30.0 (b) 36.0
(c) 22.5 (d) 45.0
(e) 18.0

CGPSC AE 2014 Shift–I

Ans. (c) : Maximum size of reinforcement for slab/beam is (1/8) of the total thickness of the member
$\frac{180}{8} = 22.5$

678. According to IS 456, when high strength deformed bars are used, the reinforcement shall not be less than p percent of the total cross sectional area of the slab where p is

(a) 0.12 (b) 0.15
(c) 0.10 (d) 0.09
(e) 0.16

CGPSC AE 2014 Shift–I

Ans. (a) : According to IS 456-2000
Maximum reinforcement :
= 0.12% of gross area (deformed bar)
= 0.15% of gross area (in mild steel bar)

Search on Telegram @apna_pdf

679. In a slab cast monolithically with cantilever beam, the beam is above the slab so as to give plain soffit. Then the beam is designed as
(a) Rectangular section
(b) Flanged section
(c) Doubly reinforced section
(d) None of the above

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (b) A slab cast monolithically with cantilever beam, the beam is above the slab so as to give plain soffit. Then the beam is designed as flanged section.

680. The clear spans of a two-way slab are 4.6m×6.20 m, and it is subjected to the factored load of 16kN/m^2 (including dead loads also). The shear force along the longer edge will be–
(a) 15.5kN (b) 25.7 kN
(c) 29.13 kN (d) 35.06 kN

APPSC Poly. Tech. Lect. 2020

Ans. (d) : 35.06 kN

681. In case of a two-way slab for positive moment reinforcement, 100% reinforcement must be provided upto a distance of .....from the simply-supported edge.
(a) 0.10L (b) 0.15L
(c) 0.20L (d) 0.25L

APPSC Poly. Tech. Lect. 2020

Ans. (b) : In case of a two-way slab for positive moment reinforcement, 100% reinforcement must be provided upto a distance of 0.15L from the simply-supported edge.

682. What is the ratio of the diameter of reinforcing bars to the slab thickness?
(a) 1/2 (b) 1/4
(c) 1/8 (d) 1/16

GESCOM (KARNATAKA) AE 2011

Ans : (c) The diameter of reinforcing bars shall not exceed one eight of the total thickness of the slab.

683. One way slabs are those in which most of the load is carried on the _____ span :
(a) longest (b) shortest
(c) middle (d) quarter

KPSC AE 2020

Ans. (b) : One way slabs are those in which most of the load is carried on the shortest span.

684. The distance between main bars in a simply supported slab should not exceed by:
(a) Three time of effective depth
(b) Four time of effective depth
(c) Five time of effective depth
(d) Six time of effective depth


[UPPSC State Eng. A.E. 2004 (I)]

Ans : (a) As per IS 456 : 2000
Spacing of reinforcement in slab–
(i) 3d or 300 mm for main bar (should be less)
(ii) 5d or 450 mm for distribution bar,
where d = effective depth of slab in mm.

685. Thickened part of a flat slab over the supporting column is called
(a) drop panel (b) capital
(c) column head (d) All of the above

(UKPSC AE 2012 Paper–I)

Ans : (a) Thickened part of flat slab over the supporting column is called drop panel.



686. The spacing of main bars in a RCC slab shall not be more than :
(a) three times the effective depth of the slab or 300 mm whichever is less
(b) four times the effective depth of the slab or 450 mm which ever is less
(c) three times the total depth of the slab or 300 mm whichever is less
(d) 300 mm

UKPSC AE (Paper-I) 2007

Ans : (a) In case of slabs spacing of main bars is taken 3d or 300 whichever is less.
Spacing of shear stirrups is limited to 0.75d or 300 mm whichever is less.

687. In RCC slabs spacing of shrinkage and temperature bars should not be more than :
(a) three times the effective depth of slab or 300 mm whichever
(b) four times the effective depth of the slab or 300 mm whichever is less
(c) five times the effective depth of the slab or 450 mm whichever is less
(d) 450 mm


UKPSC AE (Paper-I) 2007

Ans : (c) In RCC slabs spacing of shrinkage and temperature bars should not be more than five times the effective depth or 450 mm whichever is less.

688. In case of one way slab, the main reinforcement is provided–
(a) Along longer span
(b) Both along shorter and longer span
(c) Along shorter span
(d) 50% on the shorter span and 50% on longer span

UKPSC AE 2013 Paper–I

Ans : (c) When length is greater than twice the width of slab, then it is known as one way slab. In this slab main reinforcement is provided along the shorter span.



689. For slabs spanning in two directions the ratio of span to depth should not exceed :
(a) 15 (b) 25
(c) 35 (d) 50

UKPSC AE (Paper-I) 2007

Search on Telegram @apna_pdf

Ans : (c) For two way slab, $\frac{\ell}{d} < 35$

for one way slab $\frac{\ell}{d} < 30$

for continuous slab $\frac{\ell}{d} < 40$

690. In a simply supported slab, alternate bars are curtailed at :

(a) $\frac{\text{span}}{5}$ (b) $\frac{\text{span}}{6}$

(c) $\frac{\text{span}}{7}$ (d) $\frac{\text{span}}{8}$

UKPSC AE (Paper-I) 2007

Ans : (c) In simply supported slab, alternate bars are curtailed at one-seventh of span length.

691. In case of two way slab, the deflection of the slab is :

(a) primarily a function of long span
(b) primarily a function of short span
(c) independent of the spans
(d) none of the above

(UKPSC AE (Paper-I) 2007)

(ESE 1995, 2003)

Ans : (b) In two way slab ratio of length of longer side to the shorter side is less than 2. In this maximum load is on shorter side. Slenderness ratio is found for the shorter span and deflection is function of shorter span.

692. The slab is designed as one way if the ratio of long span to short span is

(a) Less than 1 (b) Greater than 2
(c) Between 1 and 1.5 (d) Between 1.5 and 2

(UPRVUNL AE 2015)

Ans : (b) A slab is an one way slab if ratio of long span to short span is greater than 2.

693. Distribution reinforcement in a simply supported RC slab is provided to distribute:

(a) load (b) temperature stresses
(c) shrinkage stresses (d) All of these

UPPSC AE 12.04.2016 Paper–I

Ans : (b) Distribution reinforcement in a simply supported RC Slab is provided to distribute temperature stresses.

694. In case of flat slab, the minimum thickness of slab shall be

(a) 100 mm (b) 115 mm
(c) 125 mm (d) 130 mm

[UPPSC State Eng. A.E. 2011]
[UPPSC State Eng. A.E. 2007(I)]

Ans : (c) Flat slab is a reinforced concrete slab supported directly by concrete column without the use of beam. As per IS 456 : 2000, the minimum thickness of flat shall be 125 mm.

695. The minimum HYSD reinforcement in slab is:

(a) 0.10% (b) 0.12%
(c) 0.15% (d) 0.18%

[UPPSC State Eng. A.E. 2007(I)]
[UPPSC State Eng. A.E. 2011]

Ans : (b) Both for one way and two way slab, the amount of minimum reinforcement in either direction shall not be less than 0.15% and 0.12% of the total cross-sectional area for mild steel (Fe 250) and high strength deformed bars (Fe 415 and Fe 500) welded wire fabric, respectively.


696. In two way slab panel, the width of edge strip, where 'L' is the width of the panel, is

(a) $\frac{L}{3}$ (b) $\frac{L}{4}$

(c) $\frac{L}{6}$ (d) $\frac{L}{8}$

[UPPSC State Eng. A.E. 2008]

Ans : (d) In two way slab panel, the width of edge strip is taken as $\frac{l}{8}$.



697. The diameter of main reinforcing bars in a reinforced concrete slab shall not exceed x-times the total thickness of slab. Where x is equal to

(a) $\frac{1}{4}$ (b) $\frac{1}{8}$

(c) $\frac{1}{12}$ (d) $\frac{1}{16}$

UPPSC State Eng. A.E. 2008, 2003

OR

The maximum diameter of reinforcing bars in a slab shall not exceed.

(a) 1/4 of the total slab thickness
(b) 1/8 th of total slab thickness
(c) 1/4th of effective slab thickness
(d) 1/8th of effective slab thickness

(BPSC AE Paper V 2006)

Ans : (b) Maximum dia of main bar in RCC concrete slab = $\frac{1}{8} \times$ Total thickness

$$\phi = \frac{1}{8} D$$

698. In a reinforced concrete slab of 100 mm thickness, the maximum size of reinforcing bars is

(a) 10mm (b) 12mm
(c) 16mm (d) 20mm

[UPPSC State Eng. A.E. 2007(I)]
[UPPSC State Eng. A.E. 2003]

Ans : (b) As per IS 456 : 2000
maximum dia of main bar in concrete slab

$$\phi_{main} = \frac{1}{8} \times \text{thickness}$$

$$\phi_{main} = \frac{1}{8} \times 100$$

$$\phi_{main} = 12.3 \approx 12\text{mm}$$

Search on Telegram @apna_pdf

699. The pitch of the main bars in a simply supported slab should not exceed the effective depth by

(a) three times (b) four times
(c) five times (d) six times

[UPPSC State Eng. A.E. 2007(I)]
[UPPSC State Eng. A.E. 2004]


Ans : (a) As per IS 456:2000
spacing of reinforcement in slab.
(i) 3d or 300 mm for main bars.
(ii) 5d or 450 mm for distribution bars.

700. Enlarged head of a supporting column of an RC flat slab is called:

(a) capital (b) drop panel
(c) column head (d) None of these

UPPSC AE 12.04.2016 Paper–I
ESE 2014

Ans : (a)



Flat slab with column capital and drop panel.

701. The one–way simply–supported slab for a room of plan dimensions 9m × 4m carries ultimate working load of 9 kN/m. The design moment for the slab should be


(a) 12.00 kN.m (b) 18.00 kN.m
(c) 9.00 kN.m (d) 27.00 kN.m

MPPSC AE 2016

Ans : (b) For one way slab

$$\frac{\ell_y}{\ell_x} > 2$$

Ultimate working load (W_u) = 9 kN/m
effective length (l_{eff}) = 4 m



$$\text{maximum bending moment} = \frac{W_u \ell^2_{eff}}{8} = \frac{9\times 4^2}{8}$$
$$= 18\text{kN} - \text{m}$$

702. It is usual not to provide thickness of floor slabs in buildings less than

(a) 7.5 cm (b) 10 cm
(c) 12.5 cm (d) 15 cm

RPSC AE 2013

Ans : (a) Minimum thickness of floor slabs in buildings is 7.5 cm.

703. For design of slabs, IS 456 specifies effective span to overall depth ratio, this is to safeguard mainly

(a) Strength Criterion
(b) Deflection Criterion
(c) Crack widths
(d) Temperature stresses

RPSC VPITI - 2012

Ans : (b) Effective span to overall depth ratio to control deflection criteria is as follows–

Cantilever beam	7
simply supported beam	20
continuous beam	26
one way slab	30
two way slab	35
continuous slab	40

704. Drops are provided in flat slabs to resist :

(a) Shear (b) Bending moment
(c) Thrust (d) Torsion

RPSC LECTURE - 2011
(ESE 1997)

Ans : (a) Flat slab is without beam or girders and is two way slab. In flat slabs, column are provided with column capital then above it drop panel and then flat slab is provided. Drop are provided to resist punching shear from column in the flat slab. Shear section is taken at distance $\frac{d}{2}$ from the column. Minimum thickness of flat slab should be 125 mm.

705. In a slab, the minimum mild steel reinforcement provided, is

(a) 0.12% of its gross sectional area
(b) 0.15 % of its gross sectional area
(c) 0.10 % of its gross sectional area
(d) None of the above

RPSC ACF - 2011

Ans : (b) In a slab main reinforcement is calculated by following formula ; $A_{st} = \frac{M}{\sigma_{st} \times Z}$

Minimum mild steel reinforcement is taken 0.15% of gross sectional area of slab. If deformation bars are used then minimum reinforcement is taken 0.12% of gross-sectional area.

706. In a two-way spanning slab, if corner of the slab are not allowed to lift, torsion reinforcement is provided at corners in the form of a mesh. The size of mesh should be equal to-

(a) $0.125\ell_x \times 0.125\ell_y$ (b) $0.125\ell_x \times 0.25\ell_y$
(c) $0.25\ell_x \times 0.25\ell_y$ (d) $0.25\ell_x \times 0.20\ell_y$

BPSC AE 2012 Paper–V

Ans : (c) In two way slab, if corner of slab is not allowed to lift, torsion reinforcement is provided at corners in the form of mesh. The size of mesh is taken equal to $0.25l_x \times 0.25l_y$.

707. In an RCC slab, having effective depth equal to 100 mm, maximum spacing of main reinforcement should not be greater than

(a) 100mm (b) 200mm
(c) 300 mm (d) 400mm

BPSC AE 2012 Paper–V

Search on Telegram @apna_pdf

Ans : **(c)** If effective depth of an RCC is 100 mm then maximum spacing of main reinforcement is taken
(i) 3d = 3× 100 = 300mm
(ii) 300mm
Whichever is less. therefore spacing of main bars is taken 300 mm.

708. In two-way slabs the main reinforcement is provided along
(a) In short span direction
(b) In long span direction
(c) both short and long span direction
(d) In corners

(BPSC AE Paper V 2001)

Ans : **(c)** In two way slab main reinforcement is provided along both short and long span because load distribution is assumed along both the spans. In one way slab main reinforcement is provided along shorter span only. Spacing of main bars is taken 3d or 300 mm whichever is less.

709. In flat slab design, the critical section for shear shall be considered from the periphery of the column/capital/drop panel, perpendicular to the plane of the slab at distance
(a) d (b) 2d
(c) d/2 (d) 1.5d
Where d = Effective Depth of Slab Section

(BPSC AE Paper V 2006)

Ans : **(c)** Flat slab is without beam or girders and is two way slab. In flat slabs, column are provided with column capital then above it drop panel and then flat slab is provided. Drop are provided to resist punching shear from column in the flat slab. Shear section is taken at distance $\frac{d}{2}$ from the column. Minimum thickness of flat slab should be 125 mm.

710. The main reinforcement in an RC slab consists of 10 mm bars 100mm spacing centre to centre. If it is desired to replace the 10 mm bars by 12 mm bars, then the spacing of the 12 mm bars will be
(a) 100mm (b) 120mm
(c) 144mm (d) 240mm

(JPSC Combined AE Paper V 2013)

Ans : **(c)** Given spacing S = 100 mm c/c; ϕ = 10 mm

Total steel $A_{st} = \frac{1000 \times a_t}{S}$

$$= \frac{1000 \times \frac{\pi}{4} \times 10^2}{100}$$

$$= 785 mm^2$$

changing 10 mm bars to 12 mm bars

$$S = \frac{1000 \times a_t}{A_{st}}$$

$$= \frac{1000 \times \left(\frac{\pi}{4}\right) \times 12^2}{785}$$

= 144mm C/C

711. The minimum area of steel required per meter length of a slab with overall depth of 100 mm consisting of steel grade Fe500 is-
(a) 96 mm^2 (b) 150 mm^2
(c) 120 mm^2 (d) Insufficient data

MPPSC AE 2017

Ans. (c) : As per IS 456 : 2000, minimum reinforcement should be 0.12% of total cross-sectional area of slab.

minimum $A_{st} = \frac{0.12}{100} \times 1000 \times 100 = 120 mm^2$

712. If '*L*' is the length of cantilever slab measured parallel to the fixed edge, the effective width of the cantilever slab shall not exceed- (For slabs carrying concentrated load)
(a) $\frac{L}{3}$ (b) $\frac{2L}{3}$
(c) $\frac{L}{2}$ (d) $\frac{3L}{2}$

Maharashtra PSC (Mains) 2015 Paper–I


Ans. (a) :

713. A continuous beam shall be deemed to be deep beam when, the ratio of effective span to overall depth is less than-
(a) 2.0 (b) 2.5
(c) 1.5 (d) 1.0

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (b) : For deep beam, ratio of effective span to overall depth must be less than,
1. For continuous deep beam L/D is less than 2.5
2. For simply supported deep beam L/D is less than 2.0

714. Match the end conditions for restrained slab panels-



A.	**S1**	**I.**	**Four edges continuous**
B.	**S2**	**II.**	**One long edge continuous**
C.	**S3**	**III.**	**Two adjacent edges discontinuous**
D.	**S4**	**IV.**	**Four edges discontinuous**
		V.	**One short edge continuous**


Select the correct response-

	A	**B**	**C**	**D**
(a)	IV	II	V	I
(b)	II	V	I	IV
(c)	III	V	II	IV
(d)	III	IV	II	V

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (c) : S_1 : Two adjacent edges discontinuous
S_2 : One short edge continuous
S_3 : One long edge continuous
S_4 : Four edge discontinuous

Search on Telegram @apna_pdf



715. Span to effective depth ratio for a two way continuous slab (upto span 3.5m) with steel of grade Fe 415 should not be more than-

(a) 7 (b) 40
(c) 26 (d) 32

OPSC AEE 2015 PAPER–I

Ans. (d) : According to IS : 456 : 2000
For slabs spanning in two directions, the shorter of the two spans should be used for calculating the span to effective depth ratio.

- For two way slabs of shorter spans (up to 3.5 m) with mild steel reinforcement, the span to overall depth ratio given below may generally be assumed to satisfy vertical deflection limits for loading class upto 3 kN/m^2

Continuous slab $\rightarrow$ 40

For grade Fe415, the values given above should be multiplied by 0.8
Span to effective depth ratio for a continuous slab = 40 × 0.8 = 32

716. In a slab, the minimum reinforcement for Fe 250 provided, is-

(a) 0.10% of its gross sectional area
(b) 0.12% of its gross sectional area
(c) 0.15% of its gross sectional area
(d) None of these

OPSC AEE 2015 PAPER–I

Ans. (c) : Minimum R/F in slab for
Fe 250 = 0.15% (mild steel) of its gross sectional area
Fe 415 = 0.12% (HYSD) of its gross sectional area

717. A steel beam supporting loads from the floor slabs as well as from wall is termed as

(a) stringer beam (b) lintel beam
(c) spandrel beam (d) header beam

BPSC AE 2019 Paper (V) Section-I

Ans. (a) : • **Stringer beam**–Main steel member along the longitudinal direction is called stringer beam.
The load may be a floor or roof as well as wall in a building.
• **Lintel beam**–A lintel beam is a beam that goes horizontally over a door or a window. It can be decorative, load-bearing or a combined ornamental structural beam.
• **Spandrel beam**–The exterior beam in a steel or concrete construction that marks the floor level between stories.
• **Header beam**–Header refers to a beam-like support in wood-frame construction.

718. The main reinforcement of an RC slab consists of 10 mm bars at 10 cm spacing. If it is desired to replace 10 mm bars by 12 mm bars. then the spacing of 12 mm bars should be

(a) 12.0 cm (b) 14.0 cm
(c) 14.4 cm (d) 16.0 cm

BPSC AE 2019 Paper (V) Section-I
CGPSC AE 2014 Shift–I
ESE 2011

Ans. (c) : Given,
S_{V_1} = 10 cm, d_1 = 10 mm, S_{V_2} = ?, d_2 = 12 mm
We know that,

$$S_V \propto d^2$$

Now, $$\frac{S_{V_1}}{S_{V_2}} = \frac{d_1^2}{d_2^2}$$

$$\frac{10}{S_{V_2}} = \frac{(10)^2}{(12)^2}$$

$$\boxed{S_{V_2} = 14.4 \text{ cm}}$$

719. Drops are provided in flat slab to resist primarily

(a) bending moment (b) thrust
(c) shear (d) torsion

TNPSC AE 2018
RPSC AE 2018
APPSC AEE (Mains) 2016


Ans. (c) : This provision will gives more depth to resist shear. Since, there won't be any beams in flat slab arrangement, the vertical load will be transferred through shear from slab drops to column capitals to column gradually. Drop panels are used to increase punching shear capacity at the column-slab joint.

720. In a slab, the transverse reinforcement is provided at _____ to the span of the slab.

(a) 45 degrees (b) 60 degrees
(c) 75 degrees (d) Right angle

APPSC AEE (Mains) 2016

Ans. (d) : In a slab, transverse reinforcement are provided at right angle to the span of the slab. The transverse reinforcement is provided to take care of temperature stresses.



721. As the span of a bridge increases, the impact factor

(a) decreases
(b) increases
(c) decreases up to a critical value of span and then increases
(d) increases up to a critical value of span and then decreases

APPSC AEE (Mains) 2016


Ans. (a) : Impact factor is just a function of span length or the first vibration frequency of the bridge. Impact factor decrease as bridge span increase.

Search on Telegram @apna_pdf

722. Tie bars are designed to withstand
(a) tensile stresses (b) compressive stresses
(c) bending stresses (d) combined stresses

TNPSC AE 2018

Ans. (a) : Tie bars are designed to withstand tensile stresses. These are provided at longitudinal joints.



723. In an interior span of flat slab, the negative design moment is taken as ..... times the total design moment.
(a) 0.35 (b) 0.70
(c) 0.65 (d) 0.50

[HPPSC 2016-II]

Ans. (c) : According to IS : 456:2000
In an interior span, the total design moment No shall be divided in the following proportions:-
Negative design moment : 0.65
Positive design moment : 0.35

724. In an under-reinforced one way slab with effective depth 100 mm, the main steel is provided as 10mm bars at 200 mm centre to centre. The moment of resistance of the slab for M-20 grade concrete and Fe-415 steel will be :
(a) 10 kNm/m (b) 13 kNm/m
(c) 27.6 kNm/m (d) 29.8 kNm/m

[HPPSC 2016-II]

Ans. (b) : Given data:-
M20, Fe 415: d= 100 mm; c/c spacing between bar = 200 mm
depth of neutral axis

$$x_a = \frac{0.87\sigma_y A_{st}}{0.36\sigma_{ck} b}$$

$$= \frac{0.87 \times 415 \times 392.7}{0.36 \times 20 \times 1000} = 19.7 \text{ mm}$$

$$\text{spacing} = \frac{1000 \times \text{area of one bar}}{\text{total area of bars}} = \frac{1000 \times a_s}{A_{st}}$$

$$A_{st} = \frac{1000}{200} \times \frac{\pi}{4} \times (10)^2 = 392.7 \text{ mm}^2$$

depth of neutral axis
Moment of resistance = $0.87 \times \sigma_y A_{st} (d - 0.42x_a)$

$$= 0.87 \times 415 \times 392.7 (100 - 0.42 \times 19.7)$$

$$= 13 \text{ kNm/m}$$

725. In two-way slabs, the torsional reinforcement is provided at :
(a) mid-depth only
(b) top face only
(c) bottom face only
(d) top and bottom face both

[HPPSC 2016-II]

Ans. (d) : Torsion or corner reinforcement must be provided at corners of slab. They consist of top and bottom mesh with bars parallel to the sides of the slab and extending for one fifth of shorter span.

726. The Reinforcement in either direction in slabs shall not be less than :
(a) 0.12% of cross-sectional area
(b) 0.15% of cross-sectional area
(c) 0.2% of cross-sectional area
(d) 0.25% of cross-sectional area

Karnataka PSC AE 2015 Paper - II

Ans. (a) : Minimum reinforcement criteria for slabs as per Is 456 – 2000
For Fe 415 – 0.12% of cross sectional area
For Fe 250 – 0.15% of cross sectional area

727. As per IS : 456-2000, the final deflection due to all loads including the effects of temperature, creep and shrinkage and measured from the as-cast level of the supports of floors, roofs and all other horizontal members, should not normally exceed-
(a) span/250 (b) span/350
(c) 20 mm (d) Both (b) and (c)

RPSC AE 2018

Ans. (a) The maximum final deflection should not normally exceed span/250 due to all loads including the effects of temperatures, creep and shrinkage and measured from the as cast level of the supports of floors, roof and all other horizontal members.

728. In case of two way slab, the limiting deflection of the slab is -
(a) Primarily a function of the long span
(b) Primarily a function of the short span
(c) Independent of long or short spans
(d) Dependent on both long and short spans

RPSC AE 2018
ESE 1995

Ans. (b) The two way slab may be checked against shorter span to effective depth ratios.
for simply supported slab, span to depth ratio in mild steel = 35 and for Fe415 = 28.

729. Where the tension steel is provided in a two way slab?
(a) only at top
(b) only at bottom
(c) at top and bottom
(d) at corners

Kerala PSC AE 2015

Ans. (c) :

$\frac{L}{B} < 2$ Two way slab

$\frac{L}{B} > 2$ One way slab

→ Tension reinforcements in slabs are provided both at top and bottom.
→ In two way slab the limiting deflection of the slab is primarily function of short span.
→ In the centre portion where the moment is sagging in nature, reinforcements are provided at bottom and at supports reinforcements are provided at top.
→ For two-way slab – $\frac{\ell}{d} \not> 35$

Search on Telegram @apna_pdf

730. In a monolithic slab-beam RC constructions transverse reinforcement to be provided in the slab shall be :

(a) 40% of main reinforcement at mid span
(b) 25% of main reinforcement at mid span
(c) 60% of main reinforcement at mid span
(d) 50% of main reinforcement at mid span

Rajasthan JEn (Degree) 2016

Ans. (c) Slab must be provided with the transverse reinforcement of at least 60% of main reinforcement at mid span of the slab if the main reinforcement of the slab is parallel to transverse beam.

731. In limit state method, the failure criterion for reinforced concrete beam and column is based on

(a) Maximum principle stress theory
(b) Maximum principle strain theory
(c) Maximum shear stress theory
(d) Maximum normal stress theory

GPSC AE (CLASS 1 & 2) 2019

Ans : (b) : Maximum principle strain theory is good for brittle material hence for concrete it gave good result in beam & Column.


732. On which of the following, the support for flat slab is provide?

(a) beams built monolithically above walls
(b) columns built monolithically with slab
(c) beams
(d) walls

Kerala PSC AE 2015

Ans. (b) : Flat slab is a typical type of construction in which reinforced slab is built monolithically with the supporting column and reinforced in two or more direction without any provision of beam.

- For one way slab $\frac{L}{B} > 2$ – Long span
- For two way slab $\frac{L}{B} < 2$ – Short span



733. Consider the following statements in the light of IS:456-2000:

(a) There is an upper limit on the nominal shear stress in beams (even with shear reinforcement) due to the possibility of crushing of concrete in diagonal compression.
(b) A rectangular concrete slab whose length is equal to its width may not be a two-way slab for certain definable supports conditions.

Which of the above statements is/are *correct?*

(a) 1 only (b) 2 only
(c) Both 1 and 2 (d) Neither 1 nor 2

ESE 2017

Ans. (c)

- Generally concrete is strong in compression but under shear there is a chance of crushing of concrete due to diagonal compression hence an upper limit τ_{max} is defined for nominal shear stress in diagonal compression.
- A rectangular concrete slab whose length is equal to its width may not be a two way slab when there is absence of supports in two parallel edges. In this case it would be one way slab.

734. Consider the following statements:

1. The minimum steel requirements of slabs are based on considerations of shrinkage and temperature effects alone, and not on strength.
2. Providing excessive reinforcement in beams can result in congestion, there by adversely affecting the proper placement and compaction of concrete.

Which of the above statements is/are *correct?*

(a) 1 only (b) 2 only
(c) Both 1 and 2 (d) Neither 1 nor 2

ESE 2017

Ans. (c)

The functions of minimum steel in slabs are.

- To keep the main reinforcement in positions.
- To take care of secondary effects like shrinkage, creep, temperature change.
- To receive the load from concrete and distributed to main steel safely.

The limitation of maximum tension steel in beams as per IS 456–2000 is 4% of gross cross sectional area. It is because of avoiding the practical difficulty i.e. placing of reinforcement and compaction of concrete.

735. As per IRC specification, the maximum spacing of contraction joints in unreinforced Cement Concrete slab is

(a) 5.5m (b) 7m
(c) 4.5m (d) 3m

DSSSB AE 2019

Ans. (c) As per IRC specification, the maximum spacing of contraction joints in unreinforced cement concrete slab is 4.5 m.

736. When the ratio of the long to short dimension of the slab is greater than X, the slab shall be designed as one-way slab, where X is

(a) 1.1 (b) 1.5
(c) 1.8 (d) 2.0

ISRO Scientist/Engineer 2020

Ans. (d) : In general slabs are divided into two categories depending upon the ratio of long span to short span when the ratio of long span to short span is greater than or equal to 2, then the slab is known as a slab spanning in one direction or one-way slab when the ratio of long span to short span is less than 2, then the slab is known as a two-way slab.

737. The analysis of slab spanning in one direction is done by assuming it to be a beam of

(a) 1 m length (b) 1 m^2 area
(c) 1 m width (d) Least thickness

ISRO Scientist/Engineer 2017

Search on Telegram @apna_pdf

Ans : (c) The analysis of slab spanning in one direction is done by assuming it to be a beam of 1 m width.

738. A reinforced concrete slab is 75 mm thick. The maximum size of reinforcement bar that can be used is

(a) 6 mm dia (b) 8 mm dia
(c) 10 mm dia (d) 12 mm dia

ISRO Scientist/Engineer 2017
APPSC AEE 2012
ESE 1997, 2011

Ans : (b) : $\phi = \frac{1}{8} \times \text{thickness}$

$= \frac{1}{8} \times 75 = 9.3\,\text{mm} \approx 8\ \text{mm}$

739. Slenderness ratio of a compression member is

(a) Moment of inertia/Radius of gyration
(b) Effective length/Area of cross-section
(c) Effective length/Radius of gyration
(d) Radius of gyration/Area of cross-section

ISRO Scientist/Engineer 2015

Ans : (c) : Slenderness ratio = $(\lambda) = \frac{l}{r}$

l = effective length
r = radius of gyration

740. The horizontal distance between parallel main reinforcement bars shall not be more than ------ the effective depth of solid slab.

(a) Two times (b) Three times
(c) Four times (d) Five times

ISRO Scientist/Engineer 2018

Ans : (b) : Spacing of bars - The horizontal distance between parallel main reinforcement bar shall not be more than three times the effective depth of solid slab or 450mm, whichever is smaller. The horizontal distance between parallel reinforcement bars provided against shrinkage and temperature shall not be more than five times the effective depth of the slab or 45mm whichever is smaller.

741. A concrete floor slab of 140 mm thick is reinforced by 16mm dia steel rods placed 38mm above the lower face of the slab and spaced 150mm on center. The distance from the upper face of slab to steel is 100mm. The modulus of elasticity is 25 MPa for concrete and 200 MPa for steel. Knowing that bending moment of 4.5KN-M is applied to each 0.30 m width of slab, determine the maximum stress in the concrete and steel respectively

(a) 12.9 Mpa & 177.8 Mpa
(b) 1.29 Mpa & 1.778 Mpa
(c) 129 Mpa & 17.78 Mpa
(d) 0.129 Mpa & 0.177 Mpa

ISRO Scientist/Engineer 2014

Ans : (a)

742. The minimum reinforcement in slabs should not be less than.....% of the total cross-sectional area when HYSD bars are used in the either direction

(a) 0.10 (b) 0.12
(c) 0.15 (d) 0.18

ISRO Scientist/Engineer 2013

Ans : (b)

- Minimum reinforcement is 0.12% for HYSD bars and 0.15% for mild steel bars. The diameter of bar generally used in slabs are 6mm, 8mm, 10mm, 12mm and 16mm.
- 15mm to 20mm cover is provided for the main reinforcement.

743. Consider the following statements for prediction of yield lines in a reinforced concrete slab :

(i) They represent the axis of rotation.
(ii) They will propagate outward from a point load.
(iii) They are straight lines between two intersection planes.
(iv) They end at the boundary of the slab or at another yield line.

(a) i, ii, iii and iv (b) i, ii and iii only
(c) i, ii and iv only (d) ii, iii and iv only

APTRANSCO 2017

Ans : (a) yield lines in a reinforced concrete slab represent–
(i) They represent the axis of rotation.
(ii) They will propagate outward from a point load.
(iii) They are straight lines between two intersection planes
(iv) They end at the boundary of the slab or at another yield line.

744. Minimum cover in a slab shall neither be less than the diameter of the bar, nor less than

(a) 10 mm (b) 15 mm
(c) 20 mm (d) 25 mm

WBPSC Poly Lect. 2019


Ans. (b) : Minimum cover in a slab shall neither be less than the diameter of the bar, nor less than 15 mm.

745. A beam ABC is simply supported at A and B, BC is overhanging. Span AB = 8 m, BC = 2 m. Point 'D' is situated at 3 m from A. Using an influence line diagram or otherwise, find the maximum ordinates at 'D' of the influence line diagram for shear at 'D'-

(a) –0.375 (b) –0.625
(c) +0.625 (d) +1.875

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (c) :



influence line diagram at D

$x + y = 1$ ..... (i)

$\frac{x}{3} = \frac{y}{5}$

$y = \frac{5}{3}x$ put in equation (1)

$y = \frac{5}{8}(+\text{ve})$

$x = \frac{3}{8}(-\text{ve})$

Search on Telegram @apna_pdf

746. In a two way slab with corners held down, the torsion is provided at corners in :

(a) middle (b) bottom
(c) top (d) both 'b' and 'c'

PSPCL AE 2012


Ans. (d) : In a two way slab with corners held in position, the torsion is provide at bottom and top both so that to prevent the corner Slab from lifting and percent crack because torsional moment are high near the corner that is why torsional reinforcement are provided at corner of two way slab.

747. According to IS 456, two-way slabs with corners held down are assumed to be divided in each direction into middle strips and edge strips such that the width of middle strip is,

(a) half of the width of the slab
(b) two-third of the width of the slab
(c) three-fourth of the width of the slab
(d) four-fifth of the width of the slab

Maharashtra PSC Mains 2018 Paper-1

Ans. (c) :



As per Annex D, clause D-1.2 : IS 456, slops are considered as divided in each direction, into middle strips end strips such that

width of middle strip = $\frac{3}{4}$ (width of slab)

width of end strip at each end = $\frac{1}{8}$ (width of slab)


748. In the design of slab, the diameter of reinforcing bars shall not exceed

(a) one-eighth of overall thickness of slab
(b) one-fourth of overall thickness of slab
(c) one-half of overall thickness of slab
(d) one-third overall thickness of slab

Maharashtra PSC Mains 2018 Paper-1

Ans. (a) : Diameter of reinforce in bar in slab = one-eight of overall thickness of slab
= 1/8


749. Determine the slab area of which load is acting on supporting beams A and B



(a) 5.5 m^2 and 7.0 m^2 (b) 4.0 m^2 and 5.5 m^2
(c) 7.0 m^2 and 4.0 m^2 (d) 4.0 m^2 and 7.0 m^2

Maharashtra PSC Mains 2018 Paper-1

Ans. (d) :



Slab area for A = area of region (2)

$$= 2 \times \left[\frac{1}{2} \times 2 \times 2\right] = 4.0 \text{ m}^3$$

Slab area for B = area of region (1)

$$= \frac{1}{2} \times 2[5.5 + 1.5] = 7.0$$

750. If W is the load per unit area on a circular slab of radius R, then the maximum radial moment at the centre of a simply supported slab is equal to

(a) $\frac{WR^2}{16}$ (b) $\frac{2WR^2}{16}$
(c) $\frac{3WR^2}{16}$ (d) $\frac{5WR^2}{16}$

GPSC AE March 2018
WBPSC AE 2003

Ans. (c) : W: load/area on circular slab of R radius.

Radial or circumferential moment $= \frac{3W(R^2 - r^2)}{16}$

at centre, so, r = 0 (max. at centre)

Maximum radial moment = $\boxed{\frac{3}{16}WR^2}$

751. Minimum reinforcement for mild steel reinforcement in either direction in slabs shall not be less than …….. % of total cross sectional area.

(a) 0.12% (b) 0.20%
(c) 0.15% (d) 0.10%

GPSC Poly. Tech. Lect. 2016

Ans. (c) : As per IS 456-2000, the minimum reinforcement in either direction of slabs shall not be less than 0.15% of total cross-section area in case of mild steel and 0.12% of total cross-section in case of high strength deformed bars.

752. As per IS 456 : 2000, Bending moment (M_y) for two way R.C.C. slab can be calculated using equation .....

(a) $\alpha_x.w.l_x^2$ (b) $\alpha_y.w.l_x^2$
(c) $\alpha_x.w.l_y^2$ (d) $\alpha_y.w.l_y^2$

GPSC R&B AE 2016

Ans. (b) : For Two way RCC slab → (As per IS code 456 : 2000 Annex D clause D-1.1)

Bending moment $\boxed{(m_y = \alpha_y w l_x^2)}$

l_x : length of slab in xx axis, α_y = table coefficient (Table 26).

Search on Telegram @apna_pdf

753. The diameter of the column head support a flat slab, is generally kept :
(a) 0.25 times the span length
(b) 0.25 times the diameter of the column
(c) 4.0cm larger than the diameter of the column
(d) 5.0 cm larger than the diameter of the column

KPTCL AE 2016

Ans. (a) The diameter of the column head support a flat slab, is generally kept 0.25 times the span length.

754. The minimum thickness of a flat slab is taken
(a) 13 cm
(b) L/32 for end panels without drops
(c) L/36 for end panels without
(d) 13 cm and L/32 for end panels with drops and L/36 for end panels without drops

KPTCL AE 2016

Ans. (d) :

755. If the beams in slabs are restricted as per the architect's plan then, what type of slab will be recommended?
(a) T-beam and slab (b) Framed structure
(c) Flat slab (d) Two way slab

Rajasthan Nagar Nigam AE Shift-2, 2016

Ans. (c) : Flat slab a reinforced concrete slab supported directly by concrete columns without the use of beams flat slabs are highly versatile elements widely used in construction, providing minimum depth fast construction and allowing flexible column grids.

756. In case of two way slab the ratio of the long span to the short span is
(a) more than two (b) zero
(c) five (d) less than two

Rajasthan Nagar Nigam AE Shift-2, 2016

Ans. (d) : A slab or panel is said to be two way slab if the ratio of longer span to the shorter span is less than two.

757. According to IS 456 : 2000, the maximum diameter of reinforcing bars shall not exceed
(a) One - fourth of total thickness of slab
(b) One-sixth of total thickness of slab
(c) One-eighth of total thickness of slab
(d) One-tenth of total thickness of slab

TANGEDCO AE 2018

Ans. (c) : According to IS 456 : 2000, the maximum diameter of reinforcing bars shall not exceed one-eighth of total thickness of slab.

$$d \le \frac{t}{8}$$

758. Anchor bolts to resist over-turning moment are used in slab base :
(a) When the column carries only moments
(b) When the column carries axial load only
(c) When the column carries axial load and moment
(d) When the column carries no load

TRB Poly. Lect. Tech. 2017

Ans. (c) : Anchor bolts to resist over turning moment are used in slab base when the column carries axial load and moment.

759. The effective span of a simply supported slab is :
(a) Distance between the centre of the bearings
(b) Clear distance between the inner faces of the walls plus twice the thickness of the wall
(c) Clear span plus effective depth of the slab
(d) Distance between outer faces

TRB Poly. Lect. Tech. 2017

Ans. (a/c)
• The effective span of a simply supported slab is distance between the centre of the bearing
• The effective span of a simply supported slab clear span plus effective depth of the slab

760. The torsional reinforcements for corners held down in the slabs are provided at
(a) continuous edges (b) discontinuous edges
(c) fixed boundaries (d) for all boundaries

TRB Poly. Tech. Lect. 2012

Ans. (b) : The torsional reinforcements for corner held down in the slab are provided at discontinuous edge.

761. As per I.S. 456 recommendation the total thickness of a flat slab should not be less than:
(a) 8.5 cm (b) 10 cm
(c) 12.5 cm (d) 15 cm

UJVNL AE 2012

Ans. (c) : The minimum thickness of flat slab:
1. 12.5 cm
2. L/32 for end panels with drop
3. L/36 for end panels without drop.

762. In a continuous slab the bending moment near middle of end span due to dead load will be:
(a) $\frac{Wl^2}{8}$ (b) $\frac{Wl^2}{10}$
(c) $\frac{Wl^2}{12}$ (d) $\frac{Wl^2}{24}$

UJVNL AE 2012

Ans. (c) : In a continuous slab the bending moment near middle of end span due to dead load will be $\frac{Wl^2}{12}$

763. In the design of two way slab restrained at all edges, torsional reinforcement required is
(a) 0.75 times the area of steel provided at mid span in the same direction
(b) 0.375 times the area of steel provided at mid span in the same direction
(c) 0.375 times the area of steel provided in the shorter span
(d) None of these

APPSC AEE 2012

Ans. (a) : Torsional reinforcement should be 0.75 times area of steel provided at mid span as per annex D clause D-1.8, of IS 456 : 2000.

764. Yield line theory results in
(a) elastic solution
(b) upper bound solution
(c) lower bound solution
(d) unique solution

APPSC AEE 2012

Search on Telegram @apna_pdf

Ans. (b) : The yield line analysis is an upper bound method in which the predicted failure load of slab for given moment of resistance may be higher than true values.

765. For a slab supported on its four edges with corners held down and loaded uniformly, the Marcus correction factor to the moments obtained by Grashoff Rankine's theory

(a) is always less than 1
(b) is always greater than 1
(c) is equal to 1
(d) None of the above

APPSC AEE 2012

Ans. (a) : Marcus correction factor

$$C = \left[1 - \frac{5}{6}\frac{r^2}{1+r^4}\right] \qquad r = \frac{l_y}{l_x}$$

C is always less than 1

766. For simply supported slab, what is the minimum thickness of solid one-way slab taking vertical deflection criteria in consideration?

(a) L/8 (b) L/24
(c) L/20 (d) L/10

SJVNL ET 2019

Ans. (c) : For simply supported slab, L/20 minimum thickness of solid one-way slab taking vertical deflection criteria in consideration.

767. The diameter of reinforcing bars used in slabs shall not exceed x times the total thickness of the slab. What is the value of x?

(a) 1/6 (b) 1/3
(c) 1/4 (d) 1/8

UPPCL AE 2015

Ans. (d) : According to IS 456-2000, the maximum diameter of reinforcing bars shall not exceed one-eight of total thickness of slab

$$d \le \frac{t}{8}$$

where d diameter of reinforcement bar
t : thickness of slab.

768. As per IS- 456:2000, span to overall depth ratio for two-way simply supported slabs (with HYSD bars) satisfying vertical deflection limits is

(a) 28 (b) 32
(c) 30 (d) 35

BPSC AE Aug. 2019 Paper-V

Ans. (a) As per IS 456 : 2000, (Cl - 24.1),
For two-way slabs of shorter span (upto 3.5 m) with mild steel reinforcement (for loading class upto 3 kN/m^2)–

Beam	Span / overall depth
Simply supported slab	35
Continuous slabs	40

For HYSD bars the values given above is multiplied by 0.8

Beam (for HYSD)	Span / overall depth
Simply supported slab	35×0.8 = 28
Continuous slabs	40 × 0.8 = 32

769. Which of the following properties is not required for concrete mix design, as per the guidelines given by the Indian Standard?

(a) Specific gravity of cement
(b) Density of aggregate
(c) Maximum size of aggregate
(d) Characteristic strength of concrete

UPRVUNL AE 2016

Ans.: (b) Mix design can be defined as the process of selecting suitable ingredients of concrete and determining their relative proportions with the object of producing concrete of certain minimum strength and durability as economical as possible.

770. A 125 mm flat, non- cellular, non- ribbed slab can have a reinforcement spacing limited to a maximum of

(a) 65 mm (b) 125 mm
(c) 190 mm (d) 250 mm

UPRVUNL AE 2016

Ans.: (d) A 125 mm flat, non- cellular, non- ribbed slab can have a reinforcement spacing limited to a maximum of 250 mm

771. What is the maximum diameter of main reinforcement used in the slab of overall thickness 160 mm as per IS 456-2000?

(a) 10 mm (b) 12 mm
(c) 16 mm (d) 20 mm

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (d) : Overall thickness of slab = 160 mm
effective thickness = 160 – 30 = 130 mm

$$d \le \frac{t}{8}$$

$$d = \frac{160}{8}$$

$$\boxed{d = 20 \text{ mm}}$$

772. In design of slab, as per IS-456, what should be minimum percent of distribution steel if Fe 415 reinforcement is used?

(a) 0.12% of total cross section
(b) 0.15% of total cross section
(c) 0.50% of total cross section
(d) 1% of total cross section

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (a) In design of slab, as per IS-456, the minimum percent of distribution steel should be used if Fe 415 reinforcement is 0.12% of total cross-section.

773. The horizontal distance between parallel reinforcement bars provided against shrinkage and temperature shall not be more than

(a) 3 times the effective depth of solid slab or 300 mm whichever is less
(b) 3 times the effective depth of solid slab or 450 mm whichever is less
(c) 5 times the effective depth of solid slab or 300 mm whichever is less
(d) 5 times the effective depth of solid slab or 450 mm whichever is less

GPSC AE Dec 2018

Search on Telegram @apna_pdf

Ans. (d) : The horizontal distance between parallel reinforcement bars provided against shrinkage and temperature shall not be more than 5 times the effective depth of solid slab or 450 mm whichever is smaller.

774. According to IS 456:2000, the HYSD reinforcement in either direction of the slab shall not be less than
(a) 0.10% of the total cross-sectional area
(b) 0.12% of the total cross-sectional area
(c) 0.15% of the total cross-sectional area
(d) 0.20% of the total cross-sectional area

GPSC AE Dec 2018

Ans. (b) : According to IS 456:2000,
1. Vertical reinforcement to gross concrete area shall be: 0.12% for HYSD bar.
2. Horizontal reinforcement to gross concrete area shall be 0.20% for HYSD bar.
In either direction, it should not be less than 0.12% of gross area for HYSD bar.

775. According to IS 456:2000, the maximum diameter of reinforcing bars shall not exceed
(a) One-fourth of the total thickness of the slab
(b) One-sixth of the total thickness of the slab
(c) One-eighth of the total thickness of the slab
(d) One-tenth of the total thickness of the slab

GPSC AE Dec 2018

Ans. (c) : According to IS 456:2000, the maximum diameter of reinforcing bars shall not exceed One-eighth of the total thickness of the slab.

776. For two-way slabs, with shorter span (less than 3.5m) and imposed load less than 3 kN/m^2, the span to overall depth ratio of continuous slabs, with mild steel reinforcement is :
(a) 28 (b) 40
(c) 35 (d) 32

BHEL ET 2019

Ans. (b) : For a two-way slabs, with shorter span (less than 3.5m) and imposed load less than 3 kN/m^2, the span to overall depth ratio of continuous slabs, with mild steel reinforcement is 40.

777. Read the following statements made for RCC slabs
(i) The maximum horizontal distance between parallel main reinforcement bars shall not be more than three times the effective depth of solid slab or 300 mm whichever is small.
(ii) The horizontal distance between parallel reinforcement bars provided against shrinkage and temperature shall not be more than five times the effective depth of a solid slab or 450 mm whichever is small
Select the correct answer from the following :
(a) Both (i) and (ii) are correct
(b) Both (i) and (ii) are wrong
(c) Only (i) is correct
(d) Only (ii) is correct

GPSC Assistant Prof. 2016

Ans. (a) : For RCC slab –
(1) The maximum horizontal distance between parallel main reinforcement bars shall not be more than three times the effective depth of solid slab or 300 mm which ever is small.
(2) The horizontal distance between parallel reinforcement bars provided against shrinkage and temperature shall not be more than five times the effective depth of solid slab or 450 mm whichever is small.

778. The minimum mild steel reinforcement in either direction in slabs, in percent of total cross-sectional area, shall not be less than
(a) 0.15% (b) 0.12%
(c) 0.10% (d) 0.20%

GPSC Assistant Prof. 2016

Ans. (a) : As per codel provision (IS 456 : 2000)
The minimum mild steel reinforcement in either direction is slabs, in percent of total cross-sectional area shall not be less than 0.15%

779. The total thickness of flat slab should not be less than (as per IS 456):
(a) 85 mm (b) 125 mm
(c) 150 mm (d) 65 mm

PTCUL AE 2016

Ans. (b) : Total thickness of flat slab should not be less than 125 mm as per IS 456 : 2000.

780. For design purpose the width of one way slab is always taken as:
(a) 0.001 meter (b) 0.01
(c) 1.00 meter (d) None of the above

PTCUL AE 2016

Ans. (c) : For design purpose the width of one way slab is always taken as 1.0 meters.

781. Consider the following statements for prediction of yield lines in a reinforced concrete slab :
i. They represent the axis of rotation.
ii. They will propagate outward from a point load.
iii. They are straight lines between two intersecting planes.
iv. They end at the boundary of the slab or at another yield line.
Which of the following are correct ?
(a) i, ii, iii and iv
(b) i, ii and iii only
(c) i, ii and iv only
(d) ii, iii and iv only

AP TRANSCO AEE 2017

Ans. (a) : Prediction of yield lines in a reinforced concrete slab –
- They represent the axis of rotation.
- They will propagate outward from a point load.
- They are straight lines between two intersecting planes.
- They end at the boundary of the slab or at another yield line.

782. The minimum percentage of steel reinforcement to be provided in design of reinforced concrete slab in terms of cross sectional area is
(a) 0.20% (b) 0.15%
(c) 0.12% (d) 0.25%

GPSC AE January 2018

Search on Telegram @apna_pdf

Ans. (c) : Minimum tension reinforcement in RC slab = 0.12% of cross sectional area.

$$A_{st} \geq \frac{0.12}{100} \times BD \text{ for HYSD bars}$$

$$A_{st} \geq \frac{0.15}{100} \times BD \text{ for mild steel}$$

783. If a beam of cross section 350 mm × 600 mm is subjected to torsional moment of 50 kNm then equivalent shear will be

(a) 129 kN (b) 229 kN
(c) 329 kN (d) Zero

UPRVUNL AE 2015

Ans. (b) : b = 350 mm, d = 600 mm
Torsional moment = 50 kN-M

$$\text{equivalent shear stress} = V_u + 1.6\frac{T_u}{b}$$

$$= 0 + 1.6 \times 50/0.35 = 228.57 \simeq 229 \text{ kN}$$


784. The slab is designed as one way if the ratio of long span to short span is

(a) Less than 1 (b) Greater than 2
(c) Between 1 and 1.5 (d) Between 1.5 and 2

UPRVUNL AE 2015

Ans. (b) : One way slab

$$\Rightarrow \frac{\ell}{b} > 2$$



• In one way slab 95% of total load bear by shorter span and 5% of total load come on longer span.

785. Drops in flat slabs are provided to resist

(a) Bending moment (b) Thrust
(c) Shear (d) torsion

Chandigarh AE 2017
MPPSC AE 2014

Ans. (c) : Drops in flat slabs are provided to resist shear.

786. The maximum diameter of steel bar that can be used in a RCC slab of thickness 200 mm as per IS 456 is :

(a) 20 mm (b) 16 mm
(c) 25 mm (d) 32 mm

UPPCL AE 2019

Ans. (c) :
As per IS 456 : 2000 the maximum diameter of steel bar that can be used in a RCC $\frac{1}{8}$ of thickness of slab.

Thickness of slab = 200 mm

Maximum diameter of steel bar $= \frac{200}{8}$

$\boxed{\phi = 25\text{mm}}$

787. A flat slab of span length of 6.45 m was cast today afternoon. As per the recommendation of IS 456, the minimum time after which the props should be removed is:

(a) 7 days (b) 10 days
(c) 14 days (d) 21 days

LMRC AM 2015

Ans (c) A flat slab of span length 6.45 m was cast today afternoon. As per the recommendations of IS 456, the minimum time after which the props should be removed is 14 days.

	Type of form work	form work removal time
1	Side of wall, column and vertical faces of structural member	24 to 48 hours
2	slabs (prop left under)	3 days
3	beam soffits (prop left under)	7 days
4	Removal of props of slab-	
	(i) slab spanning upto 4.5 m	7 days
	(ii) slabs spanning over 4.5 m	14 days
5	Removal of props for beam and arches	
	(i) span upto 6 m	14 days
	(ii) span over 6 m	21 days

788. For a continuous slab of 3 m × 5 m size, the minimum overall depth of slab to satisfy vertical deflection limits, with mild steel reinforcement is :

(a) 108 mm (b) 86 mm
(c) 94 mm (d) 75 mm

CIL MT 2020

Ans. (d) : Deflection limit for :
slab with mild steel

$$\frac{l}{d} \leq 40 \qquad (l = \text{shorter span})$$

$$\frac{3000}{d} \leq 40$$

$$d \geq \frac{3000}{40}$$

$d_{min} = 75$ mm

789. What is the $\left(\frac{\text{span}}{\text{depth}}\right)$ ratio (as per IS 456 : 2000) for the slab that is continuous and of uniform thickness and that spans upto 10m?

(a) 20 (b) 7
(c) 26 (d) 30

DMRC AM 2020

Ans. (c) : $\left(\frac{\text{span}}{\text{depth}} = 26\right)$, for the slab that is continuous span ≤ 10m.

790. A bulkhead may also serve as a :

(a) beam (b) slab
(c) pier (d) footing
(e) wall

CGPSC AE 2017

Ans. (c) A bulkhead may also serve as a pier

Search on Telegram @apna_pdf

791. For a two-way simply supported slab of shorter span (upto 3.5 m) with mild steel reinforcement, the span to overall depth is generally taken as :

(a) 35 (b) 45
(c) 40 (d) 20
(e) 25

CGPSC AE 2017

Ans. (a) For two-way slab of shorter span (upto 3.5 m) with mild steel reinforcement, the span to overall depth ratio as given below may generally to be assumed to satisfy vertical deflection.

	mild	HYSD 415
Simply supported slab	35	28
Continuous slab	40	32

792. The effective width of a column strip of a flat slab is taken as

(a) One-fourth the width of the panel
(b) Half the width of the panel
(c) Half the diameter of the column
(d) One-third the diameter of the column

Haryana PSC AE 2010

Ans. (b) : The effective width of a column strip of a flat slab is taken as half the width of the panel.

793. Design of a two-way slab simply-supported on edges and having no provision to prevent the corners from lifting is made by:

(a) Marcus formula
(b) Rankine-Grashoff formula
(c) Grashoff formula
(d) Rankine formula
(e) None of these options

Haryana PSC AE 2018 Paper–I

Ans. (b) : Marcus's Method:-It is the method by which maximum bending moment in a slab with corners held down can be determined.
Grashoff-Rankine Method:-It is used to design of a two-way slab simply-supported on edges and having no provision to prevent the corners from lifting.

794. For a circular slab carrying a uniformly distributed load, the ratio of the maximum negative to maximum positive radial moment is:

(a) 1 (b) 2
(c) 3 (d) 4
(e) 5

Haryana PSC AE 2018 Paper–I

Ans. (b) : Maximum negative radial moment $= \frac{2wr^2}{16}$

Maximum positive radial moment $= \frac{wr^2}{16}$

Ratio $= \frac{2wr^2}{16} \times \frac{16}{wr^2} = 2$

795. Distribution reinforcement in a simply-supported slab is provided to distribute:

(a) Load
(b) Shrinkage stress
(c) Temperature stress
(d) All of the above options
(e) None of these options

Haryana PSC AE 2018 Paper–I

Ans. (d) : Distribution bars are laid in longer span. Distribution bar take care of following.
1. Temperature stresses
2. Creep stresses
3. Shrinkage stresses

The distribution bars also assist in keeping the main bars in exact position at the time of concreting.

796. The minimum reinforcement using mild steel in slab should not be less than-

(a) 0.10% (b) 0.12%
(c) 0.15% (d) 0.20%

Rajasthan VP ITI 2018

Ans. (c) : The minimum reinforcement using mild steel in slab should not be less than 0.15%.

797. The basic span to effective depth ratio of a simply supported slab spanning in one direction is -

(a) 40 (b) 20
(c) 25 (d) 30

Rajasthan VP ITI 2018

Ans. (b) :

Slab	Maximum ratio of span effective depth
(1) One way simply supported slab	30
(2) Two way simply supported slab	35
(3) Continuous slab	40
(4) Cantilever Slab	12

798. The maximum diameter of reinforcing bars used in slabs shall not exceed ..... of the total thickness of the slab.

(a) $1/8^{th}$ (b) $1/10^{th}$
(c) $1/12^{th}$ (d) $1/15^{th}$

HPPSC Poly. Lect. 2016

Ans : (a) Minimum reinforcement is 0.12% for HYSD bars and 0.15% for mild steel bars, the diameter of bar generally used in slabs are : 6 mm, 8 mm, 10 mm, 12 mm and 16 mm. The max. diameter of bars used in slab should not exceed $1/8^{th}$ of the total thickness of slab.

799. In a two way slab corner steel is provided to counter :

(a) Bending moment (b) Shear force
(c) uplift of corner edges (d) None of these

GPHC AE 2018

Ans : (c) Two way slab :
(a) It is used for corners not held down position.
(b) It is purely simply supported case.

800. The props of RCC slab spanning up to 4.5 meters shall be removed after minimum ..... days.

(a) 28 days (b) 7 days
(c) 14 days (d) 3 days

GPHC AE 2018

Ans : (b) The props of RCC slab spanning up to 4.5 meters shall be removed after minimum 7 days

801. In a simply supported slab bent-up steel reinforcement is provided at ..... (L is the span of the slab).

(a) L/5 (b) L/4

Search on Telegram @apna_pdf

(c) L/7 (d) L/3

GPHC AE 2018

Ans : (c) The simply supported slab bent-up is provided at length of span of slab by $= \frac{L}{7}$

802. The slab without any beam is called as

(a) Ribbed slab (b) One-way slab
(c) Two-way slab (d) Flat slab

WBPSC AE 2016

Ans. (d) : Flat slab is a reinforced concrete slab supported directly by concrete column without the use of beam.

803. For two-way R.C. slab, the deflection is guided by

(a) shorter span (b) longer span
(c) diagonal distance (d) None of the above

WBPSC AE 2016

Ans. (a) : For two-way R.C. slab, the deflection is guided by shorter span.

804. The percentage of HYSD bars in one-way slabs to cater for shrinkage or temperature, as per IS:456 is

(a) 1.2% (b) 1.0%
(c) 0.2% (d) 0.12%

WBPSC AE 2016
WBPSC AE (Common) 1998

Ans. (d) : Minimum reinforcement criteria for slabs as per Is 456 – 2000
For fe 415 – 0.12% of cross sectional area
For fe 250 – 0.15% of cross sectional area

805. The maximum permissible value of ratio of span to depth of a two way simply supported RCC slab is

(a) 20 (b) 30
(c) 35 (d) 40

WBPSC AE (MCD) 1998

Ans. (c) : Effective span to overall depth ratio to control deflection criteria is as follows–
one way slab → 30
two way slab → 35
continuous slab → 40

806. Corner steel is provided in slab

(a) to resist the bending moment at the corner
(b) to make the slab sufficiency rigid
(c) to resist torsional moment
(d) to prevent displacement of corners

WBPSC AE (Common) 1998

Ans. (c) : Corner steel is provided in slab to resist torsional moment.

807. Minimum amount of high strength deformed bar reinforcement used in solid slabs shall not be less than _____ of the total cross sectional area of the slab according to IS: 456-2000.

(a) 0.15% (b) 0.12%
(c) 0.20% (d) 0.25%

TSPSC Deputy Engineer 2015
WBPSC AE (PHE) 1998

Ans. (b) : Minimum reinforcement criteria for slabs as per Is 456 – 2000
For Fe 415 – 0.12% of cross sectional area
For Fe 250 – 0.15% of cross sectional area

808. A reinforced concrete slab is 100 mm thick. The maximum diameter of reinforcement bar that can be used is:

(a) 6 mm (b) 8 mm
(c) 12 mm (d) 14 mm

TSPSC AEE 2017

Ans. (c) : Thickness of slab = 100
thickness of bar = $\frac{100}{8} = 12\,\text{mm}$

6. T-Beams

809. The section of the beam having greater width at the top in comparison to the width below neutral axis is known as

(a) Critical section (b) T-section
(c) L-section (d) none of these

TNPSC AE 2012


Ans. (b) The section of the beam should be such that it has greater width at the top (compression side) in comparison to the width below the neutral axis such section is known as T-section.

810. The breadth of rib in a T-beam should at least be equal to.....the depth of rib.

(a) one-half (b) one-third
(c) one-fourth (d) one-sixth

TNPSC AE 2012

Ans. (b) :



where, b_w = width of rib
d_r = depth of rib
d = effective depth

$$b_w = \frac{d_r}{3}$$

811. As per IS 456 : 2000, maximum bending moment at a support next to end support of a three span continuous beam having each span 'L' subjected to U.D.L. in the form of dead load (W_d) and live load (W_L) is given by

(a) $\frac{1}{10}W_dL^2 + \frac{1}{9}W_LL^2$ (b) $\frac{1}{9}W_dL^2 + \frac{1}{10}W_LL^2$

(c) $\frac{1}{10}W_dL^2 + \frac{1}{16}W_LL^2$ (d) $\frac{1}{12}W_dL^2 + \frac{1}{16}W_LL^2$

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (a) In case of beams and slabs continuous over three or more approximately equal spans and loaded with uniformly distributed load, the bending moment at support next of the end support are–

$$\frac{1}{10}W_dL^2 + \frac{1}{9}W_LL^2$$

Search on Telegram @apna_pdf


812. A T-beam behaves as a rectangular beam of width equal to its flange if its neutral axis-

(a) Coincides with centroid of reinforcement
(b) Coincides with centroid of T section
(c) Remains within the flange
(d) Remains in the web

Gujarat PSC AE (N.W.R.) 2020

Ans. (c) : A T-beam behaves as a rectangular beam of width equal to its flange if its neutral axis remains within the flange.


813. A cast iron beam is a T-section as shown. It is supported and carrying a uniformly distributed load. Which of the following is the correct bending stress distribution diagram if the element is stressed perfectly within plastic limit?



(a) A (b) B
(c) C (d) D

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (c)



814. What is the change in layer length of beam at level of neutral axis, if beam bends due to UDL?

(a) No change in length
(b) Depends on stress developed at that level
(c) Depends on shear stress
(d) Depends on intensity of load

Rajasthan AE (Nagar Nigam) 2016

Ans. (a) : A neutral surface must exist that is parallel to upper and lower surfaces and for which the length does not change.

Stresses in beam–


- Internal bending moment causes beam to deform.
- Top fibers in compression bottom in tension.
- Neutral surface has no change in length
- Neutral axis line of intersection of neutral surface with the transverse section.

815. A T-beam roof section has the following particulars :
Thickness of slab = 100mm
Width of rib = 300 mm
Depth of beam = 500 mm
C/c distance of beams = 3.0m
Effective span of beam = 6.0 m
Distance between points of contraflexure is 3.6m.
The effective width of flange of the beam is :

(a) 1600 mm (b) 1900 mm
(c) 1500 mm (d) 3000 mm

UKPSC AE (Paper-I) 2007
ESE 2006

Ans : (c)



$$b_f = \frac{\ell_0}{6} + b_w + 6D_f$$

or $b_f = b_w + \left(\frac{A}{2} + \frac{B}{2}\right)$

Whichever is less

$$b_f = \frac{3600}{6} + 300 + 6 \times 100$$

$$b_f = 600 + 300 + 600$$

$$b_f = 1500\text{mm}$$

or $b_f = 300 + \left(\frac{3000}{2} + \frac{3000}{2}\right)$

$$b_f = 3300\text{mm}$$

Therefore, effective width of flange is 1500 mm.

816. The side face reinforcement, if required in a T–beam will be .....

(a) 0.1% of the web area
(b) 0.15% of the web area
(c) 0.02% to 0.3% of the web area depending upon the breadth of the web
(d) Half of the longitudinal reinforcement

BPSC AE 2019 Paper (V) Section-I
(RPSC LECTURE - 2011)

Ans : (a) In a T-beam minimum side face reinforcement is taken as 0.1% of the web area. It should be equally distributed on each of the two faces. In T-beam thickness of web to the depth of beam should be $\frac{1}{3}$ to $\frac{2}{3}$. Minimum steel reinforcement should be $\frac{0.85 b_w \times d}{f_y}$ and maximum steel is limited to 4% of gross area of beam.

817. The neutral axis of a T-beam

(a) Always passes through the flange area
(b) Always passes through the rib area
(c) Always at the junction of the rib and the flange
(d) Can exist anywhere in the section of beam

RPSC AE 2013

Ans : (d) In a floor system consisting of several beams cast monolithically with the slab, the intermediate beams act as T-beams, and the end beams and beams round the staircase act as L-beams.
In such a construction, the slabs between any two beams is designed as one way slab or a two way slab depending upon its aspect ratio and boundary condition along its all the four edges. Neutral axis can exist anywhere in the section.

Search on Telegram @apna_pdf

818. Effective width of flange for T-beam is taken as

(a) $b_f = \frac{l_0}{6} + 3b_w + 6D_f$ (b) $b_f = \frac{l_0}{6} + b_w + 6D_f$

(c) $b_f = \frac{l_0}{6} + 6b_w + 3D_f$ (d) $b_f = \frac{l_0}{6} + b_w + 3D_f$

[UPPSC State Eng. A.E. 2011]

Ans : (b) The effective width b_f of the flange may be taken as the least of the following:

(i) $b_f = \frac{l_0}{6} + b_w + 6D_f$

(ii) $b_f = b_w + \frac{1}{2}$ (sum of clear distance to the adjacent beams on either side).

819. The most economical type of RCC beam is

(a) singly reinforced rectangular beam
(b) singly reinforced T-beam
(c) doubly reinforced rectangular beam
(d) doubly reinforced T-beam

[UPPSC State Eng. A.E. 2004 (I)]

Ans : (d) Tensile strength of concrete is assumed to be zero so the concrete below NA is neglected i.e. it does not contribute in moment resistance.
Thus there is saving of concrete in T-beam. so most economical type of RCC beam is doubly reinforcement T-beam.

820. Effective flange width of a continuous T-beam is-

(a) $b_f = \frac{l_0}{6} + b_W + 6D_f$ (b) $b_f = \frac{l_0}{12} + b_W + 3D_f$

(c) $b_f = \frac{l_0}{\frac{l_0}{b} + 4} + b_W$ (d) $b_f = \frac{0.5l_0}{\frac{l_0}{b} + 4} + b_W$

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (a) : Effective flange width of a continuous T-beam

$$\frac{l_0}{6} + b_w + 6D_f$$


Type of T-beam or L beam	Effective flange width
1. Isolated L beam	$\frac{0.5l_0}{\frac{l_0}{b} + 4} + b_W$
2. Isolated T beam	$\frac{l_0}{\frac{l_0}{b} + 4} + b_W$
3. Continuous L beam	$\frac{l_0}{12} + b_W + 3D_f$
4. Continuous T beam	$\frac{l_0}{6} + b_W + 6D_f$

821. In T-shaped RCC retaining walls, the main reinforcement in the stem is provided on-

(a) The front face in one direction
(b) The front face in both direction
(c) The inner face in one direction
(d) The inner face in both direction

OPSC AEE 2015 PAPER–I

Ans. (c) :



822. Among which of the following conditions a T-beam becomes identical to a rectangular beam with width equal to that of flange?

(a) neutral axis remains within web
(b) neutral axis remains within flange
(c) neutral axis coincides with geometrical centre of beam
(d) none of these


Kerala PSC AE 2015

Ans. (b) : Generally 2 case of neutral axis generates in T-Beam.
(1) When neutral axis lies within flange–

$$B_f \times x_a\left(\frac{x_a}{2}\right) = M\,A_{st}\left(d - x_a\right)$$

T–Beam considered as a rectangular section
(2) When the neutral axis lies in the web or rib

$$B_f \times D_f\left(x_a - \frac{D_f}{2}\right) = M\,A_{st}\left(d - x_a\right)$$




823. A T-beam becomes identical to a rectangular beam with width equal to its flange width when the neutral axis is

(a) Through the geometrical centre of the beam
(b) At the junction of the rib and the flange
(c) Below the slab
(d) Within the flange

ESE 2017

Ans. (d)

- When neutral axis lies within the flange, the section is treated like rectangular. The analysis and design is similar to rectangular section.



Above N.A like rectangle below the N.A. concrete area is not consider because steel will alone take care of tensile stresses.

Search on Telegram @apna_pdf

824. The minimum beam width for 1 hour fire exposure is:

(a) 200 mm (b) 150 mm
(c) 300 mm (d) 280 mm

DSSSB AE 2019

Ans. (a) The minimum beam width for 1 hour fire exposure is 200 mm.

825. When the depth of web in a R.C.C. T-beam exceeds _____, side face reinforcement shall be provided.

(a) 750 mm (b) 600 mm
(c) 500 mm (d) 350 mm

ISRO Scientist/Engineer 2019

Ans : (a) :

- As per IS 456: 2000, side face reinforcement is provided when.
- Depth of beam (web) is more than 750 mm (when beam is not subjected to torsion)
- Depth of beam (web) is more than 450 mm (when beam is subjected to torsion)

Side reinforcement is provided 0.1% of web area equally distributed on both face.


* Maximum spacing of side face reinforcement = 300 mm or width of beam which ever less.

826. A Tee-beam behaves as a rectangular beam of a width equal to its neutral axis

(a) remains within the flange
(b) remains below the slab
(c) coincides with the geometrical centre of the beam
(d) None of the above

Maharashtra PSC Mains 2018 Paper-1

Ans. (a) : When the neutral axis lies within flange, the T-beam behaves a rectangular beam with width equal to that of flange width.



827. A soft storey is characterised by vertical discontinuity in

(a) strength (b) stiffness
(c) infill wall (d) size of shear wall

GPSC AE March 2018

Ans. (b) : A soft story is characterized by vertical discontinuity in stiffness. A soft or weak story exists if the height of that story is atleast 15% greater than storey above or below

828. As per IS : 456 - 2000, for R.C.C. T - Beam, effective width of flange "b_f" is calculated using equation .....


(a) $\frac{l_0}{6} + b_w + 12D_f$ (b) $\frac{l_0}{6} + b_w + 6D_f$
(c) $\frac{l_0}{3} + b_w + 6D_f$ (d) $\frac{l_0}{12} + b_w + 3D_f$

GPSC R&B AE 2016

Ans. (b) : In R.C.C. T-beam, the effective width of the flange is adopted or minimum of centre to centre distance of nearby ribs or beams.

effective width of flange (b_f) = $\frac{l_0}{6} + b_w + 6D_f$

l_0 = length of T-beam.



829. The main reinforcement in case of cantilever beam carrying gravity load is provided

(a) below the neutral axis
(b) As a helical reinforcement
(c) As vertical stirrups
(d) Above the neutral axis

Rajasthan Nagar Nigam AE Shift-2, 2016


Ans. (d) : A cantilever beam carrying gravity load main reinforced is provided above the neutral axis.

830. The flexural stresses at top and bottom of a T-section of 30 cm depth are 50 N/mm^2 and 150 N/mm^2. The neutral axis from the top will be.

(a) 7.5 cm (b) 22.5 cm
(c) 15.5 cm (d) 25.5 cm

UJVNL AE 2016

Ans. (a) :



for similar triangle,

$$\frac{50}{x} = \frac{150}{30-x}$$

30-x = 3x

30 = 4x

$$x = \frac{30}{4}$$

x = 7.5 cm

So, Neutral axis from the top will be 7.5 cm.

Search on Telegram @apna_pdf

831. For a continuous slab of 3m × 3.5m size, the minimum overall depth of slab to satisfy vertical deflection limits is :

(a) 50 mm (b) 75 mm

(c) 100 mm (d) 120 mm

TRB Poly. Lect. Tech. 2017

ESE 2011

Ans. (b) : $\frac{l}{D}$ Ratio for continuous slabs = 40

$$\frac{3000 \text{ mm}}{D} = 40$$

$$D = \frac{3000}{40} = 75 \text{ mm}$$

832. In the design of RCC beams, the basic value of span to effective depth ratio for spans upto 10 m, in case of simply supported beams should not be greater than

(a) 20 (b) 7


(c) 26 (d) 10

GPSC Assistant Prof. 2016

Ans. (a) : As per IS 456-2000 basic span to effective depth ratio for span upto 10 m is

Types of Beam	Span / effective
For cantilever	7
For simply supported	20
For continuous	26

833. A simply supported isolated 'T' beam of 6m span shown below is used as a walkway. The effective width of the flange is:-



(a) 1000 mm (b) 900 mm

(c) 2200 mm (d) 1259 mm

UPPCL AE 2014

Ans. (b) : Effective width of flange for isolated T-beam, $B_f = \frac{l_o}{\left(\frac{l_o}{B}\right)} + b_w + 4$

$$B_f = \frac{6000}{\left(\frac{6000}{1000}\right)} + 300 + 4$$

$B_f = 600 + 300 = 900$ mm

834. The side face reinforcement, if required, in a T-beam will be

(a) 0.1% of the web area

(b) 0.15% of the web area

(c) 0.2% to 0.3% of the web area depending upon the breadth of the web

(d) 0.1% of the total longitudinal reinforcement

Rajasthan VP ITI 2018

MPPSC AE 2014

Ans. (a) : As per IS 456-2000 (Cl - 26.5.1.3)
The side face reinforcement, if required, in T-beam will be–0.1% of the web area.

835. A T-beam roof section has the following particulars: depth of slab 10 cm width of rib 30 cm, depth of rib 50 cm, center to center distance of beam 3m. effective span of beams of 5 m. The effective flange width of the beam is

(a) 200 cm (b) 300 cm

(c) 150 cm (d) 100 cm

WBPSC AE 2003

Ans. (a) :

836. The effective depth of a T beam for heavy loads is taken as

(a) $\frac{1}{10}$ of the span

(b) $\frac{1}{12}$ of the span

(c) $\frac{1}{15}$ of the span

(d) $\frac{1}{18}$ of the span

WBPSC AE 2001

Ans. (a) :

837. The overall depth of a simply supported T-Beam is usually assumed as:

(a) 1/2 to 1/4 of span

(b) 1/12 to 1/15 of span

(c) 1/2 to 1/4 of width of flange

(d) 2 to 3 times of width of flange

JUVNL AE 2016

Ans. (b) : For T-beam overall depth:

(i) In case Simply supported beam = $\frac{1}{12}$ to $\frac{1}{15}$ of span beam.

(ii) In case of continuous beam = $\frac{1}{10}$ to $\frac{1}{12}$ of span beam.

Search on Telegram @apna_pdf

7. R.C.C. Columns and Column-footings

838. A short square column with side 200 mm is subjected to a design load of 300 kN, If the grade of concrete is M-20 and the grade of steel Fe-415, then the area of longitudinal steel required for the section in the limit state design will be

(a) 0 (b) 320 mm^2
(c) 300 mm^2 (d) 160mm^2

(JPSC Combined AE Paper V 2013)

Ans : (b) Design load on column = 300kN
M-20 Fe-415, $f_{ck} = 20\ N/mm^2$ $f_y = 415\ N/mm^2$

$$\boxed{P_u = 0.4 f_{ck} A_c + 0.67 f_y A_{sc}}$$

$300 \times 10^3 N = [\{0.4 \times 20\ (200 \times 200 - A_{sc})\} + \{0.67 \times 415\ A_{sc}\}]$

$A_{sc} = -74.06\ mm^2$

Hence, No need of compressive steel
But minimum reinforcement steel provided is 0.8%.

$$A_{sc} = \frac{0.8 \times b \times b}{100} = \frac{0.8 \times 200 \times 200}{100} = 320 mm^2$$

839. In case of columns area of longitudinal reinforcement shall be not less than

Gujarat PSC AE 2017
WBPSC AE (common) 1998
Or

As per IS : 456, the main reinforcement in a column should not be less than:

(a) 0.6 % (b) 0.70 %
(c) 0.8 % (d) 1.00 %

UPPSC AE 12.04.2016 Paper–I
[UPPSC State Eng. A.E. 2007(I)]

Ans : (c) According to code IS 456-2000, the cross-sectional area of longitudinal reinforcement shall be not less than 0.8% and not more than 6% of the gross cross-sectional area of the column.

840. Calculate the pitch of lateral ties for a column of 300 mm square with 20 mm dia longitudinal bar and 8 mm ϕ lateral tie.

(a) 384 mm (b) 320 mm
(c) 300 mm (d) 280 mm

TNPSC AE 2015

Ans. (c) : Pitch of lateral ties (min)

$$= \begin{cases} \text{least lateral dimension} \\ 16\phi \\ 300\ mm \end{cases}$$

$$= \begin{cases} 300\ mm\ (\text{Given}) \\ 16 \times 20 = 320\ m \\ 300\ mm \end{cases}$$

$= 300\ mm$

841. In the design of columns, the diameter of longitudinal reinforcement shall

(a) Not be less than 12 mm
(b) Be less than 16 mm
(c) Be more than 20 mm
(d) Not be less than 10 mm

TNPSC AE 2019

Ans. (a) Minimum dia of bar in column = 12 mm minimum number of bar in circular = 6 & rectangular column =4.

842. Spacing of longitudinal bars measured along the periphery of the column shall not exceed

(a) 200 mm (b) 250 mm
(c) 300 mm (d) 350 mm

GUJRAT PSC AE - II 2017

Ans : (c) The spacing of longitudinal bars measured along the periphery of the column shall not exceed 300 mm in a pedestal of a column the area of the longitudinal reinforcement shall not be less than 0.8% of the gross area.
Pedestal is a compression number, the effective length of which does not exceed three times the least lateral dimension.

843. Subject to a maximum of 450 mm, the maximum vertical reinforcement used in reinforced walls shall not exceed X time the wall thickness, where in X is

(a) 10 (b) 1.5
(c) 2.0 (d) 3.0
(e) 4.5

CGPSC AE 2014 Shift–I

Ans. (d) : As per IS 456-2000 (clause 32.5) (b) the vertical reinforcement shall be spaced not further than 3 times the wall thickness nor 450 mm.

844. Effective length of the column whose one end fixed and the other end free is

(a) equal to overall length
(b) less than overall length
(c) greater than overall length
(d) less than or equal to overall length

TNPSC AE 2012

Ans. (c) : When the one end is fixed and the other end is free in a column the effective length is equal to-

$[L = 2 \times \ell]$

845. The foundation which consists of a thick reinforced cement slab covering whole area to support heavy concentrated structural loads, is known as

(a) combined footing (b) strap footing
(c) raft footing (d) none of these

TNPSC AE 2012

Ans. (c) Raft foundations (sometimes referred to as raft footings or mat foundation) are formed by reinforced concrete slab of uniform thickness (typically 150 mm to 300 mm) that cover a wide area, often the entire footprint of a building.

846. In an RCC column, if A_s = 1000 mm^2, A_c = 10000 mm^2, σ_c = 5N/m^2 and m = 20, then load on the column is :

(a) 75 kN (b) 145 kN
(c) 150 kN (d) 10005 kN

TNPSC AE 2015

Search on Telegram @apna_pdf

Ans. (c) : $A_s = 1000\ mm^2$ $A_c = 10000\ mm^2$
$\sigma_c = 5\ N/mm^2$ $m = 20$

$$\sigma_s = m.\sigma_c = 5 \times 20 = 100\ N/mm^2$$

$$p = \sigma_c.A_c + \sigma_s.A_s$$
$$= 5 \times 10000 + 100 \times 1000$$
$$= 50000 + 100000$$
$$= 150000\ N$$

$$\boxed{p = 150\ kN}$$

847. The load carrying capacity of a circular column with helical reinforcement is how much % more than that of column with lateral ties?
(a) 5% (b) 10%
(c) 15% (d) 20%

UKPSC AE 2013 Paper–I
Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (a) Strength of compression member is increased by 5% when we use helical reinforcement in replacement of lateral ties.

848. A compression member has a centre-to-centre length of 5m. It fixed at one end & hinged at other end. The recommended effective length of the column is–
(a) 4.0m (b) 2.8m
(c) 3.2m (d) 2.6m

APPSC Poly. Tech. Lect. 2020

Ans. (a) : A compression member has a centre-to-centre length of 5m. It fixed at one end & hinged at other end. The recommended effective length of the column is 0.8L
Then, effective length = 0.8L
= 0.8×5
= 4m

849. An axially loaded column is of 450×450 mm size. The effective length of the column is 5m. What is the minimum eccentricity of the axial load for the column?
(a) 25mm (b) 16mm
(c) 20mm (d) 30mm

APPSC Poly. Tech. Lect. 2020

Ans. (a) : e_{min} (Minimum eccentricity)

$$= \max. \begin{matrix} \frac{l}{500} + \frac{'B'or'D'}{30} \\ 20mm \end{matrix}$$

$$= \max. \begin{matrix} \frac{5000}{500} + \frac{450}{30} = 25mm \\ 20mm \end{matrix}$$

$$e_{min} = 25mm$$

850. Which of the following statements is correct?
(a) Column bases transmit the column load to the column foundation
(b) Column load is spread over a large area of concrete
(c) Loaded columns are supported on column bases
(d) All of the above

GESCOM (KARNATAKA) AE 2011

Ans : (d) The columns are supported on the column bases. The column bases transmit the column load to the column foundation. The intensity of bearing pressure on concrete is kept with the maximum allowable bearing pressure.

851. Generally in a column base the shear resistance at the proper contact surface between steel base and the concrete may be calculated using a friction coefficient of :
(a) 0.45 (b) 0.85
(c) 1.5 (d) 0.95

Rajasthan AE (Nagar Nigam) 2016

Ans. (a) : The tangential behaviour of the contact interaction was defined as friction using contact properties with friction coefficient equal to 0.45.
The slip factor or the coefficient of friction between the base plate and grout layer C_j, d may be taken to be 0.20 for sand-cement mortar and 0.30 for special grouts.

852. The minimum area of steel in mm2 has to be provided in a column of size 250 mm×600 mm is:
(a) 1200 (b) 1500
(c) 1800 (d) 2400

KPSC AE 2020

Ans. (a) : According to IS 456-2000 minimum longitudinal reinforcement is 0.8% of gross sectional area of column.
Minimum area of steel to be provided

$$= 250 \times 600 \times \frac{0.8}{100}$$
$$= 1200\ mm^2$$

853. In a reinforced concrete footing, the thickness at the edge shall not be less than 150 mm for footing on soils for less than _____ mm above the top of piles for footing on piles:
(a) 250 mm (b) 300 mm
(c) 350 mm (d) 200 mm

KPSC AE 2020

Ans. (b) : In a reinforced concrete footing, the thickness at the edge shall not be less than 150mm for footing on soils for less than 300 mm above the top of piles for footing on piles.

854. According to IS 456, minimum slenderness ratio for a short concrete column is :
(a) Less than 12 (b) Between 12 and 18
(c) Between 18 and 24 (d) More than 24

Nagaland PSC CTSE 2017 Paper–I
UKPSC AE 2012 Paper–I
ESE 2011

Ans. (a) : According to IS – 456–2000,
Slenderness ratio

$$(\gamma) = \frac{\text{effective length}}{\text{Least Lateral dimension}}$$

$\rightarrow \lambda < 12 \rightarrow$ For short concrete column.

855. The minimum spacing of stirrups is:
(a) 6 cm (b) 10 cm
(c) 12 cm (d) 15 cm

RPSC AE 2013

Search on Telegram @apna_pdf

Ans : (a) Important points about stirrups–
(i) diameter of stirrups

$$\phi_t \geq \begin{cases} \frac{\phi_{main}}{4} \\ 6mm. \end{cases}$$

(ii) maximum spacing of stirrups

$$S_t \leq \begin{cases} D \\ 16\phi_{main} \\ 300\ mm. \end{cases}$$

(iii) minimum spacing of stirrups is 6 cm.

856. Which one of the following set of values gives the minimum clear, cover (in mm) for the main reinforcements in the slab, beam column and footing respectively according to IS 456 : 1978?
(a) 20, 25, 30, 75 (b) 5, 15, 25, 50
(c) 15, 25, 40, 75 (d) 25, 15, 20, 75
(RPSC LECTURE- 2014)

Ans. (c) Type of structure		Clear cover (mm)
slab	–	15
beam	–	25
column	–	40
footing	–	75

857. The diameter of main reinforcement in a reinforced concrete column should not be less than:
Haryana PSC AE 2018 Paper–I
RPSC A. En. - 2013
UPPSC State Eng. A.E. 2007(I)
UPPSC AE 12.04.2016 Paper–I
RPSC POLY. TECH. LECT. 2014
Or
The minimum size of the reinforcement bar in RCC column is
(a) 6mm (b) 8mm
(c) 10mm (d) 12mm
WBPSC Poly Lect. 2019
Rajasthan VP ITI 2018
APPSC AEE (Mains) 2016
WBPSC AE (PHE) 1998

Ans : (d) As per IS 456 : 2000
The minimum diameter of bar used in column should not be less than 12 mm

$$\phi_{min} = 12\ mm$$

858. The minimum longitudinal reinforcement in a column is provided as a percentage of gross cross–sectional area of the column. This percentage is
(a) 0.6 (b) 0.8
(c) 1.0 (d) None of these
RPSC GWD A. En.–2014
RPSC ACF 2011
RPSC POLY. TECH. LECT. 2011

Ans : (b) Longitudinal reinforcement in columns should be between 0.8% to 6% of gross cross sectional area. Taking in consideration the ease of casting columns only 4% maximum is taken. Diameter of bars should be minimum 12 mm to maximum 50 mm. Minimum reinforcement is column is provided to resist tensile stress in it.

859. The diameter of lateral ties in a column is taken as
(a) 1/4 diameter of the largest longitudinal bar
(b) 6 mm
(c) Greater of 1/4 diameter of the largest longitudinal bar or 6 mm
(d) None of these
RPSC GWD A. En. - 2011

Ans : (c) Lateral reinforcement in column is provided by two methods (i) By lateral ties (ii) Spiral bars.
Important point about lateral ties-
(i) Diameter of ties

$$\phi_t \geq \begin{cases} \phi\ long.max./4 \\ 6mm. \end{cases}$$

(ii) maximum spacing of bars

$$S_t \leq \begin{cases} D \\ 16\phi\ long.min \\ 300\ mm. \end{cases}$$

(iii) minimum spacing of bars = 6 cm.

860. For a short column, the ratio of effective length of the column to its least lateral dimension should not exceed.
(a) 11 (b) 12
(c) 15 (d) 18
RPSC GWD A. En - 2014
RPSC ACF 2011
WBPSC AE (common) 1998

Ans : (b) For short column ratio of effective length to least lateral dimension is 12 or less than 12.
Reduction factor for calculation of strength of long columns:

$$R = 1.25 - \frac{l_{eff}}{48B} \quad OR \quad R = 1.25 - \frac{l_{eff}}{160 i_{min}}$$

and $i_{min} = \sqrt{\frac{I}{A}}$

Where, B = least lateral dimension
l_{eff} = Effective length of column
i_{min} = Least radius of gyration
I = Moment of inertia
A = Cross sectional area

861. The minimum thickness of the RCC footing resting on soil is given by
(a) 150 mm (b) 200 mm
(c) 250 mm (d) 300 mm
[UK Combined AE Paper Ist 2012]
[UPPSC State Eng. A.E. 2004 (I), 2007 (I)]
[UPPSC State Eng. A.E. 2003]

Ans : (a) The minimum thickness of the RCC footing resting on.
(i) Soil = 150 mm (ii) pile = 900 mm
Due to the weight, the piller tries to sink inside the foundation at the periphery of its faces, but the thickness of the foundation block prevents this subsidence when the thickness of the foundation block is insufficient, the foundation fails due to subsidence or shearing block is determined based on both the bending moment and shearing.

Search on Telegram @apna_pdf

862. Minimum clear cover (in mm) to the main steel bars in slab, beam, column and footing respectively are.

(a) 10,15,20,25 (b) 20,25,30,40
(c) 15,25,40,75 (d) 20,35,40,75

UJVNL AE 2016
ESE 1995, 2011

Ans. (c) : Minimum clear cover (in mm) to the main steel bars in
slab = 15 mm
beam = 25 mm
column = 40 mm
footing = 75 mm

863. The minimum clear cover in R.C. columns shall be:

(a) greater of 40mm or diameter of reinforcement
(b) smaller of 40 mm or diameter of reinforcement
(c) greater of 25 mm or diameter of reinforcement
(d) smaller of 25 mm or diameter of reinforcement

[UPPSC State Eng. A.E. 2007(I), 2003, 2004(I)]

Ans : (a) According to IS 456 : 2000 : Longitudinal reinforcing bar in a column nominal cover shall in any case not be less than 40 mm, or less than the diameter of such bars.
In case of columns of minimum dimension of 200 mm or under, whose reinforcing bars not exceed 12 mm, a nominal cover of 25 mm may be used.
Note : For footing minimum cover shall be 50 mm.
Nominal cover : The design depth of concrete cover provided at all type of steel reinforcement including links is called "nominal cover."

864. A 300 × 300 mm RC column is reinforced with eight bars. Four bars are of 12 mmϕ and four of 10 mmϕ. The diameter of lateral ties is 6 mm. The pitch of lateral ties shall be kept as:

(a) 300 mm (b) 192 mm
(c) 160 mm (d) 288 mm

[UPPSC State Eng. A.E. 2007(I)]

Ans : (c) Pitch of transverse reinforcement (lateral ties)
P small not more than
1. Least Lateral dimension
2. 16 × smallest dia in longitudinal bar
3. $48 \times \phi_{(Lateral)}$
4. 300 mm

$$p < \text{minimum} \begin{cases} (i)\ 300\text{mm} \\ (ii)\ 16\times 10 = 160\text{mm} \\ (iii)\ 48\times 6 = 288\text{mm} \\ (iv)\ 300\text{mm} \end{cases}$$

865. A helically reinforced column of 300 mm diameter has 6 bars of 24 mm diameter as longitudinal reinforcement provided at an effective cover of 60 mm and spiral of 8 mm diameter provided at clear cover of 40 mm. The core diameter of the this column is

(a) 212 mm (b) 220 mm
(c) 180 mm (d) 204 mm

RPSC VPITI - 2012

Ans : (b) Core diameter of column = diameter of column – 2 × clear cover
= 300– 2 × 40 = 220 mm

866. Specify the percentage increase in load carrying capacity (specified in IS 456) for a column having longitudinal reinforcement tied with spirals as compared to the allowable load for it with lateral ties

(a) 10% (b) 20%
(c) 25% (d) 5%

RPSC VPITI - 2012

Ans : (d) When we use longitudinal reinforcement tied with spirals then load carrying capacity increases by 5%. Spiral bars should satisfy the following equation.


$$\frac{\text{volume of spiral bars}}{\text{volume of core}} \geq 0.36\left[\frac{A_g}{A_k}-1\right]\times\frac{f_{ck}}{f_y}\leq\frac{V_h}{V_c}$$

867. In reinforced concrete pedestal is defined as compression member whose effective length does not exceed its least lateral dimension by

(a) 12 times (b) 3 times
(c) 16 times (d) 8 times

RPSC ACF - 2011
ESE 2002

Ans : (b) A compression member having ratio of effective length to least lateral dimension greater than 3 are known as column and ratio less than or equal to 3 are known as pedestal. Important points regarding pedestal, column and wall.



868. The thickness of edge of reinforced concrete and plain concrete footings on piles shall not be less than :

(a) 200mm (b) 250mm
(c) 150mm (d) 300mm

(BPSC AE Paper V 2006)

Ans : (d) According to Indian standards the thickness of edge of reinforced concrete and plain concrete footing on piles shall not be less than 300 mm.

869. The spacing of transverse reinforcement of column is decided by the following considerations:

(a) The least lateral dimension of the column
(b) sixteen times the diameter of the smallest longitudinal bar in the column

Search on Telegram @apna_pdf

(c) Forty eight times the diameter of the transverse reinforcement
(d) All of the above

[UPPSC State Eng. A.E. 2007(I)]

Ans : (d) Spacing of transverse reinforcement.
(i) Least Lateral dimension (B or D)
(ii) 16 × smallest dia used in longitudinal reinforcement
(iii) 48 × diameter of transverse reinforcement
(iv) 300 mm.

870. The minimum eccentricity for design of reinforced concrete column as per IS:456 is

(a) maximum of $\frac{\ell_{eff}}{300}+\frac{D}{30}$ and 20mm

(b) maximum of $\frac{\ell_{eff}}{500}+\frac{D}{30}$ and 20mm

(c) maximum of $\frac{\ell_{eff}}{300}+\frac{D}{500}$ and 20mm

(d) maximum of $\frac{\ell_{eff}}{500}+\frac{D}{200}$ and 20mm

[UPPSC Civil Eng. A.E. 2004 (I)]

Ans : (b) As per IS 456 : 2000 all column should be designed for minimum eccentricity of $\frac{\ell_{eff}}{500}+\frac{D}{30}$ or 20 mm.

871. An RC column is reported as long column if the ratio of its effective length and least lateral dimension exceeds:

(a) 10 (b) 12
(c) 15 (d) 20

UPPSC AE 12.04.2016 Paper–I

Ans : (b)

$$\frac{\text{Effective length}}{\text{Least lateral dimension}} \geq 12 \text{ (for long column)}$$

872. The strength of compression member with helical reinforcement shall be taken as the no. of times the strength of similar member with lateral ties:

(a) 1.03 (b) 1.05
(c) 1.10 (d) 1.15

UPPSC AE 12.04.2016 Paper–I

Ans : (b) Strength of compression member is increased by 5% when we use helical reinforcement in replacement of lateral ties.

873. The critical section for computing maximum bending moment for the design of isolated footing supporting a concrete column is (considering d as distance between the column face and the footing edge)

(a) at the face of the column
(b) at a distance d from the column face
(c) at the center of the column
(d) at a distance d/2 from the column face

MPPSC AE 2016
[UK Combined A.E. (I) 2012]

Ans : (a) The critical section for computing maximum bending moment for the design of isolated footing supporting a concrete column is at the face of the column.
It is taken halfway between the centre line and the edge of the wall for footing under masonary walls. i.e. at t/4 from wall face.
Halfway between the face of the column or pedestal and the edge of the gusseted base for footings under gusseted bases.

874. For the purpose of the design of a reinforced concrete footing

(a) a flexible base and linear pressure distribution is assumed
(b) a rigid base and linear pressure distribution is assumed
(c) a flexible base and parabolic pressure distribution is assumed
(d) a rigid base and parabolic pressure distribution is assumed

UKPSC AE 2012 Paper–I

Ans : (a) For the purpose of the design of a reinforced concrete footing a flexible base and linear pressure distribution is assumed.

875. Which of the following statement is correct?

(a) "Degrees of freedom of a rigid block foundation are 6."
(b) "A foundation is considered as shallow if its depth exceeds the width."
(c) Both (a) & (b)
(d) None of the above

UKPSC AE 2012 Paper–I

Ans : (a) Degree of freedom for rigid block foundation is 6. A foundation is considered shallow if depth is equal or less than the width of foundation.

876. Spacing between longitudinal bars measured along the periphery of RCC columns should not exceed :

(a) 150 mm (b) 250 mm
(c) 300 mm (d) 500 mm

[UPPSC State Eng. A.E. 2004 (I)]
UKPSC AE (Paper-I) 2007/2013

Ans : (c) Maximum spacing of longitudinal bars measured along the periphery of RC column shall not exceed 300 mm.

877. Degrees of freedom of a rigid block foundation are :

(a) 2 (b) 3
(c) 4 (d) 6

(UKPSC AE (Paper-I) 2007)

Ans : (d) Degree of freedom for rigid block foundation are 6.

878. What is the minimum number of longitudinal bars provided in a reinforced concrete column of circular cross section?

UPPCL AE 2015
ESE 2005

OR

The number of longitudinal bars in a circular reinforced concrete column should not be less than

Search on Telegram @apna_pdf

(a) 2 (b) 4
(c) 6 (d) 8

CIL MT 2017
CGPSC AE 2014 Shift–I
UPPSC State Eng. A.E. 2008
UKPSC AE (Paper-I) 2007
UPPSC State Eng. A.E. 2007(I)
BPSC AE Paper (V) 2006

Ans. (c) : There will be 6 minimum no. of longitudinal bars provided in a reinforced concrete columns of circular section and having 0.8% area (cross sectional) of column's area or reinforced.
For rectangular column, minimum no. of bars is 4.

879. In a axially loaded spirally reinforced short column, the concrete inside the core is subjected to :
(a) bending and compression
(b) biaxial compression
(c) triaxial compression
(d) none of the above

UKPSC AE (Paper-I) 2007
ESE 2001, 2016

Ans : (c) The spiral reinforcement has confining effect of concrete in the core. Thus core is subjected triaxial compression.
Spirally reinforced column have the bars and the core concrete wrapped with closely spaced helix.

880. The pitch of lateral ties in RCC columns should not exceed :
(a) the least lateral dimension
(b) 16 times the diameter of longitudinal bars
(c) 300 mm
(d) all of the above


UKPSC AE (Paper-I) 2007

Ans : (d) Pitch of lateral ties in RCC column not exceed
1. Least lateral dimension
2. 48 ϕ (ϕ = diameter of spiral bars)
3. 300
4. 16ϕ (d = diameter of longitudinal main bars)

881. For the purpose of the design of reinforced concrete footing, pressure distribution is assumed to be :
(a) linear (b) parabolic
(c) hyperbolic (d) none of the above

(UKPSC AE (Paper-I) 2007/ Uttrakhand AE 2013)

Ans : (a) For purpose of design of footing, pressure distribution is assumed to be linear.



882. Lateral ties in RCC columns are provided to resist :
(a) bending moment
(b) shear
(c) buckling of longitudinal bars
(d) both bending moment and shear

UKPSC AE (Paper-I) 2007

Ans : (c) Lateral ties in RCC columns are provided to resist buckling of longitudinal bars.

1. 16 ϕ
2. 300 mm
3. Least lateral dimension

} which is less

883. In the case of columns of minimum dimension of 200 mm or under, whose reinforcing bars do not exceed 12 mm, a nominal cover may be provided–
(a) 40 mm (b) 25 mm
(c) 20 mm (d) 50 mm

UKPSC AE 2013 Paper–I
(ESE 2005)

Ans : (b) Clear cover–
(i) Clear cover in column is taken 40 mm or equal to diameter of longitudinal bar whichever is greater.
(ii) For columns of diameter less than or equal to 200 mm in which main bars of diameter 12 mm are used, clear cover is kept 25 mm.
(iii) Column in contact with fire or water have clear cover 50 mm.

884. A square column section of 350 mm × 350 mm is reinforced with four bars of 25 mm diameter and four bars of 16 mm diameter. The transverse reinforcement will be–
(a) 5 mm dia @ 240 mm c/c
(b) 8 mm dia @ 300 mm c/c
(c) 6 mm dia @ 350 mm c/c
(d) 8 mm dia @ 500 mm c/c

UKPSC AE 2013 Paper–I
ESE 2005

Ans : (b) As per IS 456-2000, the design of transverse reinforcement is as:
The diameter of transverse reinforcement:
(i) $\frac{1}{4}\phi_{main} = \frac{1}{4} \times 25 = 6.25\,mm$
(ii) 6 mm
whichever is maximum,
Let us take 8 mm diameter bar as transverse reinforcement.
The spacing of transverse reinforcement:
(i) least lateral dimension = 350 mm
(ii) 16 times diameter of main reinforcement bar = 16 × 25 = 400 mm.
(iii) 300 mm
whichever is minimum.
So, spacing will be 300 mm.
Hence overall use 8 mm ϕ @ 300 mm c/c.

885. Minimum reinforcement in a circular concrete column as per IS–456-2000 is–
(a) 4 bars of 12 mm

Search on Telegram @apna_pdf

(b) Greater 0.80% of cross–sectional area 4 bars of 12 mm
(c) 6 bars of 12 mm
(d) Greater of 0.80% of cross–sectional area and 6 bars of 12 mm

UKPSC AE 2013 Paper–I

Ans : (d) According to I.S. 456-2000 for circular concrete column–
Diameter of reinforcement = 12 mm to 50 mm
Area of steel = 0.8% to 6% of gross area.
minimum number of bars = 6.

886. As per IS 456-2000, the minimum nominal cover specified for footings is:
(a) 25 mm (b) 40 mm
(c) 50 mm (d) 75 mm

(LMRC AE 2017 I–Shift)
TSPSC AEE 2017
TSPSC Deputy Engineer 2015

Ans : (c) As per I.S : 456-2000, the minimum nominal cover specified for footings is 50 mm. Total load on the column is transmitted to ground via footing. To transfer load safely in ground soil footing are made below columns.

887. The minimum & maximum percentage of reinforcement in RCC columns should be respectively
(a) 2 and 5 (b) 3 and 6
(c) 0.5 to 5 (d) 0.8 to 6

UKPSC AE 2012 Paper–I

Ans : (d) According to I.S. 456 of circular concrete column–
Diameter of reinforcement = 12 mm to 50 mm
Area of steel = 0.8% to 6% of gross area.
minimum number of bars = 6.

888. A reinforced concrete (RC) column with slenderness ratio greater than 12 is classified as
(a) short column (b) long column
(c) axially loaded column (d) stub column

MPPSC AE 2016

Ans : (b) As per IS Code 456:2000 Slenderness ratio for RC column

$$\lambda = \frac{\text{effective length}}{\text{least lateral dimension}}$$

$\lambda \geq 12 \Rightarrow$ long columns
$\lambda < 12 \Rightarrow$ short columns

Stub column– A stub column is a column whose length is sufficiently small to prevent failure as a column, but long enough to contain the residual stress pattern that exists in the column its self.

889. For a square reinforced concrete (RC) column with cross-section of 300 mm × 300 mm having an effective length of 2500 mm, determine the minimum eccentricity-
(a) 15 mm (b) 30 mm
(c) 20 mm (d) None of these

MPPSC AE 2017

Ans. (c) : Minimum eccentricity of column is given as $\frac{L}{500}+\frac{LLD}{30}$, subject to a minimum of 20 mm (clause 25.4 of IS 456 : 2000). [LLD = least lateral dimension]

$$\frac{2500}{500}+\frac{300}{30}=15$$

Hence minimum eccentricity = 20 mm
(Which is greater)

890. Determine the plain area of a footing carrying load of 1500 kN from 300 mm square column containing 20 mm diameter bars as longitudinal steel. The safe bearing capacity of the soil is 120 kN/m^2.
(a) 12.5 m^2 (b) 8.33 m^2
(c) 12.63 m^2 (d) 14.38 m^3

MPPSC AE 2017

Ans. (a) :

$$\text{Plain area of footing} = \frac{\text{Total load}}{\text{Safe bearing capacity}}$$

$$= \frac{1500kN}{120kN/m^2}$$

$$= 12.5m^2$$

891. Match the minimum number of longitudinal steel bars required in columns as per cross section of column-

A.	**Rectangular column**	**(i)**	**4**
B.	**Circular column**	**(ii)**	**5**
C.	**Octagonal column**	**(iii)**	**6**
		(iv)	**8**

	A	**B**	**C**
(a)	(i)	(ii)	(iii)
(b)	(i)	(iii)	(iv)
(c)	(iv)	(iii)	(i)
(d)	(iii)	(i)	(iv)

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (b) : Minimum number of longitudinal steel bars as per IS 456 : 2000 is given as
A. Rectangular column – 4
B. Circular column – 6
C. Octagonal column – 8

892. Match the conditions under which the given type of footing is used-

A.	**Combined footing**
B.	**Mat foundation**
C.	**Pile foundation**
D.	**Isolated footing**
I.	**For two or more columns**
II.	**For isolated or group of columns**
III.	**For individual column**
IV.	**For supporting all columns of structure/**

Select the correct response-

	A	**B**	**C**	**D**
(a)	II	III	IV	I
(b)	I	IV	II	III
(c)	II	I	III	IV
(d)	II	IV	I	III

Maharashtra PSC (Mains) 2017 Paper–I

Search on Telegram @apna_pdf

Ans. (b) :
Combined footing : for two or more column
Mat foundation : for supporting all column of structure
Pile foundation : for isolated or group of column
Isolated footing : for individual column

893. Determine the minimum and maximum longitudinal reinforcement for a square column of size 300 mm × 300 mm having a clear cover of 25 mm-
(a) 500 mm^2 and 3750 mm^2
(b) 500 mm^2 and 5400 mm^2
(c) 720 mm^2 and 3750 mm^2
(d) 720 mm^2 and 5400 mm^2

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (d) :
Minimum R/F = $\frac{0.8}{100} \times 300 \times 300 = 720\ mm^2$

Maximum R/F = $\frac{6}{100} \times 300 \times 300 = 5400\ mm^2$

For column members minimum and max longitudinal R/F limits are 0.8% and 6% respectively of gross cross section.

894. The effective slenderness ratio of a battened column, λ_e, is taken as 1.10 times the actual slenderness ratio of the column to account for-
(a) Axial deformation
(b) Bending deformation
(c) Shear deformation
(d) All of the above

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (c) : The effective slenderness ratio, $\left(\frac{KL}{r}\right)$, the actual maximum slenderness ratio, in order to account for shear deformation effects. As an axially loaded column bends, each transverse section rotates through an angle.

895. In reinforced concrete footing on soils, the minimum thickness at the edge should not be less than-
(a) 150 mm (b) 250 mm
(c) 100 mm (d) 200 mm

OPSC AEE 2015 PAPER–I

Ans. (a) : The thickness at edge shall be not less than 150 mm for footing on soils nor less than 300 mm above the tops of piles for footing on Piles.

896. The purpose of lateral ties in short RC columns is to-
(a) Avoid buckling of longitudinal bars
(b) Facilitate construction
(c) Facilitate compaction of concrete
(d) Increase the load carrying capacity of the columns

BPSC AE 2019 Paper (V) Section-I
OPSC AEE 2015 PAPER–I
ESE 2016, 2011
MPPSC AE 2014
WBPSC AE 2012

Ans. (a) : The main function of lateral ties in RC column is to :
- Resist the shear force and hence contributes avoiding shear failure
- Restrains the spliced bars and hence prevents their slip.
- Prevent longitudinal reinforcement bars from buckling.
- Confines the concrete core to provide sufficient ductility or deformability.

897. Deep beams are designed for
(a) shear force only
(b) bending moment only
(c) both shear force and bending moment
(d) bearing

BPSC AE 2019 Paper (V) Section-I

Ans. (b) : A beam, whether deep or conventional, is always designed for bending moment, apart from checks for safety in shear, deflection and cracking.
A beam is said to be deep when the ratio of its effective span to overall depth is less than 2 for simply supported beams, or 2.5 for continuous beams.

898. When the ratio of effective length of the column to its least lateral dimension does not exceed 15, it is termed as a
(a) Long column
(b) Short column
(c) Plain column
(d) None of the given answers

APPSC AEE (Mains) 2016

Ans. (b) Columns are defined by slenderness ratio (L/R) if slenderness ratio is less than 15 is short and if it is greater than 15 then it's long column.

899. Lateral ties in RC columns are provided to resist
(a) bending moment
(b) shear
(c) buckling of longitudinal steel bars
(d) both bending moment and shear

APPSC AEE (Mains) 2016
ESE 2000

Ans. (c) : Lateral ties provided in RCC column binds the longitudinal R/F in the column and ensure lateral stability against buckling. It confines the concrete core to provide sufficient ductility or deformability and it resists the shear force and hence contribute avoiding shear failure.

900. Pedestal columns are
(a) Very short columns with effective length less than three times least lateral dimension
(b) Very long columns with effective length more than four times least lateral dimension
(c) Very short columns with effective length more than three times least lateral dimension
(d) Very short columns with effective length more than the least lateral dimension

TNPSC AE 2018

Search on Telegram @apna_pdf

Ans. (a) : Pedestal columns are very short columns with effective length less than three times least lateral dimension.
Pedestal column $l_{eff} < 3$ LLD
Short columns $3 \text{ LLD} < l_{eff} < 12$ LLD
Long columns $l_{eff} > 12$ LLD
LDD = Least lateral dimension

901. The unsupported length between end restraints shall not exceed..... times the least lateral dimension of a column.
(a) 60 (b) 25
(c) 30 (d) 12

[HPPSC 2016-II]

Ans. (a) : According to is code 456 : 2000, maximum slenderness ratio of concrete column is limited to 60.

902. A concrete member under compressive load is called pedestal when the ratio of effective length and least lateral dimension does not exceeds.
(a) 3 (b) 6
(c) 12 (d) 60

[HPPSC 2016-II]

Ans. (a) : Classification of column according to IS code:-

(i) Long column $60 > \frac{l_{eff}}{\text{LLD}} > 12$

(ii) Short column $12 > \frac{l_{eff}}{\text{LLD}} > 3$

(iii) Pedestal $\frac{l_{eff}}{\text{LLD}} < 3$

$l_{eff} \rightarrow$ effective length
LLD $\rightarrow$ least lateral dimension

903. Minimum number of vertical bars in a circular column is :
(a) 6 (b) 4
(c) 5 (d) 8

JPSC AE (Pre) 2019

Ans. (a) : Refer clause 25.5.3.1 of IS : 456–2000.
minimum number of vertical bars for reinforcement for rectangular column $\Rightarrow$ 4
For circular column $\Rightarrow$ 6

904. In a plain concrete pedestal of M35 grade, the maximum bearing pressure at the base is found to be 40 N/mm^2. Find the depth of footing, if the projection beyond the column is 300 mm.
(a) 3.1 m (b) 2.6 m
(c) 2.4 m (d) 1.9 m

RPSC AE 2018

Ans. (a) : $q = 40$ N/mm^2
$f_{ck} = 35$ N/mm^2
Solution-
$d > 300 \tan \alpha$

$$d > 300 \times 0.9 \sqrt{\frac{100q}{f_{ck}} + 1}$$

$$d > 300 \times 0.9 \sqrt{\frac{100 \times 40}{35} + 1}$$

$d > 2.89$ m
so, $d = 3.1$ m

905. Focusing 'material efficiency', which of the following is the correct sequence?
(a) T-beam > Rectangular beam < Two-way slab
(b) T-beam > Rectangular beam > Two-way slab
(c) Two-way slab > T beam Rectangular beam
(d) Two-way slab < T beam Rectangular beam

GPSC AE (CLASS 1 & 2) 2019

Ans : (b) Material efficiency increase as more ($\not{Z}$ value) i.e., (I/y) value increases, In all section T-section has more $\not{Z}$ value which can resist flexure more as compare to other.
($\not{Z}$ Section modulus)

906. If a square column section of size 400 mm × 400 mm is reinforced with 4 bars of 25 mm and 4 bars of 16 mm diameter, then the transverse steel should be
(a) 6 mm dia @ 250 mm c/c
(b) 6 mm dia @ 300 mm c/c
(c) 8 mm dia @ 250 mm c/c
(d) 8 mm dia @ 300 mm c/c

GPSC AE (CLASS 1 & 2) 2019

Ans : (c) : $\phi_{lateral} = \frac{\phi_{main}}{4}$

$= \frac{25}{4} = 6.25 \approx 8$ mm

P < minimum (I) 400 mm
(II) 16 x 16 = 256 mm
(III) 48 x 8 = 384 mm
(IV) 300 mm

8 mm dia @ 250 mm c/c.

907. The depth of footing in case of an isolated column is governed by
(a) Bending moment and shear force
(b) Shear force and punching shear
(c) Bending moment and punching shear
(d) Bending moment and direct shear

GPSC AE (CLASS 1 & 2) 2019

Ans : (b) : The depth of footing in case of an Isolated column is governed by
(1) Shear force
(2) Punching shear

908. A floor slab supported directly on column is called:
(a) Ribbed slab (b) Flat slab Grid
(c) Flat slab (d) Floor

Kerala PSC AE 2015

Ans. (c) : The flat slab is reinforced concrete slab supported directly by concrete columns without use of the beam. Flat slab is used as a floor for another storey so it is also known as floor slab and it has uniform thickness.

909. The minimum number of bars required in a rectangular column for an earthquake resistant design, is
(a) 4 (b) 6
(c) 8 (d) 10

ESE 2019

Ans. (a) : The minimum number of bars required in a rectangular column for an earthquake resist design is at least 4 bars of 12mm diameter should be provided at tie-columns.

Search on Telegram @apna_pdf

910. A 230 mm brick masonry wall is to be provided with a reinforced concrete footing on site having soil with safe bearing capacity of 125 kN/m^2, unit weight of 17.5 kN/m^3 and angle of shearing resistance of 30^0. The depth of footing will be nearly

(a) 0.8 m (b) 0.7 m
(c) 0.6 m (d) 0.5 m

ESE 2019

Ans. (a) : Rankine's formula provides the guidance on minimum depth of foundation based on bearing capacity of soil.

$$\left[D = \frac{P}{\gamma}\left[\frac{1-\sin\theta}{1+\sin\theta}\right]^2\right]$$

P = Gross bearing capacity = 125kN/m^2
γ = Density of soil = 17.5kN/m^3
ϕ = Internal friction angle of soil = 30^0
So,

$$D = \frac{125}{17.5}\left[\frac{1-\sin 30^0}{1+\sin 30^0}\right]^2$$

$$D = \frac{125}{17.5}\times\left[\frac{1}{3}\right]^2$$

$$D = \frac{125}{157.5}$$

$\boxed{D = 0.793 \simeq 0.8m}$ Depth of footing

911. A circular column is subjected to an un-factored load of 1600 kN. The effective length of the column is 3.5 m, the concrete is M 25, and the value of $\rho_g = \frac{A_{SC}}{A_g} = 2\%$ for Fe 415 steel. The design diameter of the column will be nearly

(a) 446 mm (b) 432 mm
(c) 424 mm (d) 410 mm

ESE 2019

Ans. (a)
Un-factored load = 1600 kN
Factored Load 'P_u' = 1.5P

$$P_u = 1.5\times 1600$$

$$P_u = 2400kN$$

Load carrying capacity of a circular column with lateral ties.

$$P_u = 0.4\, f_{ck}\, A_c + 0.67\, f_y A_{sc}$$

$$2400\times10^3 = 0.4\times25\times(A_g - A_{sc}) + 0.67\times415\times A_{sc}$$

$$2400\times10^3 = 0.4\times25\times\left(A_g - \frac{2}{100}A_g\right) + 0.67\times415\times\frac{2}{100}A_g$$

$$2400\times10^3 = 9.8A_g + 5.6A_g$$

$$15.4A_g = 2400\times10^3$$

$$\left[A_g = 155844.16mm^2\right]$$

$$A_g = \frac{\pi}{4}D^2 = 155844.16$$

$$D^2 = \frac{155844.16\times4}{\pi},\quad D = 445.45mm$$


$\boxed{D = 446mm}$

912. A strut is made of a circular bar, 5 m long and pin-jointed at both ends. When freely supported the bar gives a mid-span deflection of 10 mm under a load of 80 N at the centre. The critical load will be

(a) 8485 N (b) 8340 N
(c) 8225 N (d) 8110 N

ESE 2019

Ans. (c)



Load 'P' = 80N
Deflection '' = 10mm

$$\left[\delta = \frac{w\ell^3}{48EI}\right]$$

$$10mm = \frac{80\times(5000)^3}{48EI}$$

$$EI = \frac{10\times10^{12}}{480}$$

[EI = 20833 × 10^6 N-mm^2]
Buckling load (with pin ends)

$$P_e = \frac{\pi^2}{\ell^2}EI \qquad \text{---------- } (l_{eff} = \ell)$$

$$P_e = \frac{\pi^2}{(5000)^2}(20833\times10^6)$$

$$P_e = \frac{\pi^2}{25\times10^6}(20833\times10^6)$$

$$P_e = \frac{205016.38}{25}$$

$\boxed{P_e = 8224.67N \simeq 8225N}$

913. Design strength for M 25 concrete in direct compression, bending compression and flexural tension are, respectively

(a) 10 MPa, 11.15 MPa and 3.5 MPa
(b) 25 MPa, 11.15 MPa and 3 MPa
(c) 10 MPa, 12.5 MPa and 3.5 MPa
(d) 25 MPa, 11.15 MPa and 2.57 MPa

ESE 2018

Ans. (a) : For M25 = f_{ck} = 25 MPa

- As per IS 456–2000 in limit state method.
- Direct compression, $\sigma_{cc} = 0.4\, f_{ck}$
  [$\sigma_{cc} = 0.4 \times 25 = 10$MPa]
- Bending compression, $\sigma_{cbc} = 0.45\, f_{ck}$
  [$\sigma_{cc} = 0.45 \times 25 = 11.25$MPa]
- Flexural tensile strength, for = $0.7\sqrt{f_{ck}}$
  Clause 6.22

$\left[\text{Flexural tensile strength} = 0.7\times\sqrt{25} = 3.5MPa\right]$

914. The ultimate load carrying capacity of a short circular column of 300 mm diameter with 1% helical reinforcement of Fe 415 grade steel and concrete of M 20 grade, is nearly

(a) 451 kN (b) 500 kN
(c) 756 kN (d) 794 kN

ESE 2018

Search on Telegram @apna_pdf

Ans. (d) : Ultimate load carrying capacity of circular column with helical reinforcement.

By using formula

$\left[P_{u-helical} = 1.05(0.4f_{ck}A_c + 0.67f_yA_{sc}\right]$

Given,

$\Rightarrow f_{ck} = 20N/mm^2, \quad f_y = 415N/mm^2$

$\Rightarrow A_c = 0.99\times\frac{\pi}{4}\times300^2 = 69978.97mm^2$

$\Rightarrow A_{sc} = 0.01\times\frac{\pi}{4}\times300^2 = 706.85mm^2$

$P_{u-helical} = 1.05(0.4\times20\times69978.97 + 0.67\times415\times706.85)$

$P_{u-helical} = 1.05(559831.81 + 196539.6425)$


$\boxed{P_{u-helical} = 794.1kN \simeq 794kN}$

915. In a combined footing for two columns carrying unequal load, the maximum hogging moment occurs at

(a) The inside face of the heavier column
(b) A section equidistant from both the columns
(c) A section subjected to maximum shear force
(d) A section subjected to zero shear force

ESE 2017, 2004

Ans. (d) : Combined Footing



The maximum hogging moment occurs at a section subjected to zero shear force.

(i.e. change in shear force.)

where,

W = Column load

P_o = Net soil upward pressure.

916. A certain R.C. short column with 300 mm square cross-section is made of M20 grade concrete and has 4 numbers, 20 mm diameter, longitudinal bars of Fe 415 grade steel. It is under the action of a concentric axial compressive load. Ignoring the reduction in the area of concrete due to the steel bars, the ultimate axial load carrying capacity of the column as by the relevant code is

(a) 1069 kN (b) 1198 kN
(c) 1548 kN (d) 1659 kN

ESE 2017

Ans. (a) : Size of column = 300mm × 300mm

M20, Fe 415

Longitudinal bars having 4 bar and 20mm diameter.

A_{SC} = 4–20mm ϕ

So, ultimate axial load carrying capacity for short column.

$\left[P_u = 0.4f_{ck}A_c + 0.67f_yA_{sc}\right]$

$P_u = 0.4\times20\times300\times300 + 0.67\times415\times4\times\frac{\pi}{4}\times20^2$

$P_u = 720000 + 349407.93$

$P_u = 1069407.93$

$\boxed{P_u = 1069kN}$

917. In an isolated reinforced concrete footing of effective depth d, the stress in punching shear is checked:

(a) at the centre of the column
(b) at the face of the column
(c) at a distance d/2 away from the face of the column
(d) at a distance d/2 away from the centre of the column

ISRO Scientist/Engineer 2020

Ans. (c) : In an isolated reinforced concrete column footing of effective depth d,

⇒ One way shear is checked at distance d from the face of column

⇒ Punching shear is checked at distance d/2 from face of column.

⇒ Bending moment is checked at face of column.

918. A rectangular column section of 250×400 mm reinforced with 6 steel bars of Fe 500, each of 25mm diameter. Concrete Mix is M30. Axial load on column section with minimum eccentricity as per IS 456-2000 using limit state method can be applied upto :

(a) 1805.3 KN (b) 1707.37 KN
(c) 2150.83 KN (d) 1903.7 KN

ISRO Scientist/Engineer 2014

Ans : (c) Given,

column size = 250 × 400 mm

A_{sc} = 6 bar-25 mmϕ (Fe 500)

concrete (f_{ck}) = M30

$(P_u) = 0.4\ f_{ck}\times A_c + 0.67\ f_y\times A_{sc}$

$= 0.4\times30\times\left[250\times400 - 6\times\frac{\pi}{4}(25)^2\right]$

$+0.67\times500\times6\times\frac{\pi}{4}(25)^2$

$= 12[100{,}000 - 2945.24] + 335\times2945.24$

$= 1164657.12 + 986656.44$

$= 2150831.25\ N = 2150.83\ kN$

919. The effective length of circular electrical pole of length L and constant diameter erected on ground is :

(a) 0.8 L (b) 1.20 L
(c) 1.50 L (d) 2.0 L

ISRO Scientist/Engineer 2014

Ans : (d) Circular electric pole can be considered as a column whose one end fixed and other end free.



$L_{eff} = 2L$

Search on Telegram @apna_pdf

920. A concrete column 200×200 mm in cross-section is reinforced with steel bars of 1200 mm², total cross-sectional area. Calculate the safe load for the column if permissible stress in concrete is 5 N/mm² and E_S is 15 E_C

(a) 264 kN (b) 274 kN
(c) 284 kN (d) 294 kN

ISRO Scientist/Engineer 2013

Ans : (c)
Area of concrete column $A_C = 200 \times 200\ mm = 40000\ sq.mm$
Area of steel bars $A_{SC} = 1200 mm^2$

$$\frac{\text{Permissible stress in steel}}{\text{Permissible stress in concrete}} = \frac{E_S}{E_C} = \frac{5 \times 15 E_C}{E_C} = 75$$

$P = 5 \times (40000 - 1200) + (1200 \times 75)$
$P = 284000\ N$
$\boxed{P = 284\ kN}$

921. In case of reinforced concrete isolated footing the critical for bending moment is at

(a) Zero distance from the face of the column
(b) d/2 from the face of the column
(c) d from the face of the column
(d) 2d from the face of the column

APTRASCO 2017

Ans : (a) In case of reinforced concrete isolated footing the critical for bending moment is at zero distance from the face of the column.
The bending moment at any section shall be determined by passing through the section a vertical plane which extends completely across the footing and computing the moment of the forces acting over the entire area of the footing on the side of the side plane.

922. A reduction factor C_r to load carrying capacity of a long column is given by :

(a) $C_r = \left(1.25 - \frac{L_e}{24b}\right)$ (b) $C_r = \left(1.00 - \frac{L_e}{48b}\right)$

(c) $C_r = \left(1.25 - \frac{L_e}{48b}\right)$ (d) $C_r = \left(1.5 - \frac{L_e}{48b}\right)$

OPSC AEE 2019 Paper–I
Vizag steel MT-2017

Ans. (c) C_r = reduction factor

$$C_r = \left(1.25 - \frac{L_e}{48b}\right) \text{ or}$$


$$C_r = 1.25 - \frac{l_{eff}}{160 i_{min}}$$

923. A reinforced concrete circular section of 50,000 mm² cross-sectional area carries 6 reinforcing bars whose total area is 500 mm². If the concrete is not to be stressed more than 3.5 MPa and modular ratio for steel and concrete is 18, the safe load the column can carry will be nearly :

(a) 225 kN (b) 205 kN
(c) 180 kN (d) 160 kN

ESE 2020

Ans. (b) : Given,
Modular ratio (m) = 18
Cross - sectional area of column (A_g) = 50,000 mm²
Area of reinforcement (A_{sc}) = 500 mm²
Cross-sectional area of concrete (A_c) = $A_g - A_{sc}$
= 50000–500
= 49,500 mm²



Safe load (P) = $\sigma_{cc} \times A_c + \sigma_{sc} \times A_{sc}$
= $\sigma_{cc} \times A_c + m\sigma_{cc} \times A_{sc}$
= $3.5 \times 49{,}500 + 18 \times 3.5 \times 500$
= 204750 N
= 204.75 kN
$\boxed{P \simeq 205\ kN}$

924. An axially loaded column is 300 × 300 mm in size, effective length of column is 3 m. What is the minimum eccentricity of the axial load for column?

(a) 20 mm (b) 16 mm
(c) 10 mm (d) 0

Maharashtra PSC Mains 2018 Paper-1

Ans. (a) :

$$e_{x,min} = \begin{cases} \frac{l_{unsupported}}{500} + \frac{D_x}{30} \\ 20\ mm \end{cases} \quad \text{which ever is greater}$$

$$e_{x,min} = \begin{cases} \frac{3000}{500} + \frac{300}{30} = 16 \\ 20\ mm \end{cases}$$

Greater is 20 mm

925. In reinforced and plain concrete footings on soils, the thickness at the edge shall be not less than

(a) 200 mm (b) 150 mm
(c) 300 mm (d) 250 mm

Maharashtra PSC Mains 2018 Paper-1

Ans. (b) : In reinforced and plain concrete footings, the thickness at the edge shall be not less than 150 mm for footing on soils, nor less than 300 mm above the tops of piles for footings on piles.

926. The maximum compressive strain permitted in RCC columns at failure load is

(a) 0.002 (b) 0.003
(c) 0.035 (d) 0.004

GPSC AE March 2018

Ans. (a) : Compressive stress in the concrete reaches its maximum possible value when the maximum compressive strain in concrete is around 0.002 beyond 0.002 the stress falls gradually. Concrete fails in compression when the strain in concrete reaches at around 0.005.

Search on Telegram @apna_pdf

927. If 'p' is the net upward pressure on a square footing of side 'b' for a square column of side 'a', the maximum bending moment is given by


(a) $\frac{pb^2}{8}$ (b) $\frac{pb(b-a)^2}{8}$

(c) $\frac{p.b.a^2}{8}$ (d) $\frac{p(b-a)^2}{8}$

GPSC AE March 2018

Ans. (b) : p not upward pr.

upward force $= p\left[b\frac{(b-a)}{2}\right]\left(\frac{b-a}{4}\right)$



Maximum bending moment $= p\left[\frac{b(b-a)}{2}\right]\left(\frac{b-a}{4}\right)$

$$M_{max} = p\left[\frac{b(b-a)^2}{8}\right]$$


928. Two way shear in a R.C.C. footing is checked at a distance equal to _____ of the footing from the face of the column.

(a) one-fourth of the effective depth
(b) one-half of the effective depth
(c) three-fourth of the effective depth
(d) the effective depth

GPSC AE March 2018

Ans. (b) : By 800 - 2007

Two way shear (punching shear) in RCC footing is checked at d/2 distance from column face.



929. A column is regarded as long column if the ratio of its effective length to least lateral radius of gyration is more than

(a) 150 (b) 100
(c) 60 (d) 40

GPSC AE March 2018

Ans. (b) : For long column: (Valid for long column)

Slenderness ratio (λ) = 50 to 200.

So, $\frac{l_{eff}}{K_{min}} \geq 60$

K_{min} – radius of gyration.

$$\frac{l_e}{d} > 15$$

l_e = effective length of column

d = least lateral dimension of column

K_{min} = minimum radius of gyration.

930. The minimum percentage of longitudinal reinforcement in R.C.C. column is

(a) 6 (b) 0.8
(c) 1.2 (d) 4

GPSC AE March 2018

Ans. (b) : According to IS 456-2000.

Percentage of longitudinal reinforcement 0.8% $\leq A_{st} \geq$ 6% in RCC column.

931. If 'w' is the weight per unit volume, 'p' the safe bearing capacity, and '□' is the angle of repose of the soil retained by the retaining wall, the minimum depth of foundation to be calculated as

(a) $\frac{p}{w}\left(\frac{1-\sin\varphi}{1+\sin\varphi}\right)^2$ (b) $\frac{p}{w}\left(\frac{1+\sin\varphi}{1-\sin\varphi}\right)^2$

(c) $\frac{p}{w}\left(\frac{1-\sin\varphi}{1+\sin\varphi}\right)$ (d) $\frac{p}{w}\left(\frac{1+\sin\varphi}{1-\sin\varphi}\right)$

GPSC AE March 2018

Ans. (a) : Minimum depth of foundation

$$D_{f_{min}m} = \frac{p}{w}k_a^2$$

w = unit of soil, p = ultimate bearing capacity; ϕ = angle of repose.

$$D_{f_{min}m} = \frac{p}{w}\left(\frac{1-\sin\phi}{1+\sin\phi}\right)^2$$

932. As per IS 456-2000 effective length (l) for compression member having effectively held in position at both ends, restrained against rotation at one end, recommended value of effective length is

(a) 0.8 l (b) 0.7 l
(c) 1.0 l (d) 0.65 l

GPSC Poly. Tech. Lect. 2016

Ans. (a) : As per IS 456-2000, effective length of compression members having effective held in position at both ends and restrained in direction at one end, recommended value of effective length is 0.80 l.

933. Recommended value of effective length (l_e) of long R.C.C. column, as compared to actual length (l), effectively held in position and restrained against rotation in both ends is .....

(a) 0.70 l (b) 0.80 l
(c) 0.50 l (d) 0.65 l

GPSC R&B AE 2016

Search on Telegram @apna_pdf

Ans. (d) : For compression member

End conditions	Recommended value
	0.65 l
	0.8 l
	l
	$2l$

Effectively held in position and restrained against both ends for rotation is condition 1 (Both ends fixed)

$\boxed{l_{eff} = 0.65l}$

934. As per IS 456:2000, the cross sectional area of longitudinal reinforcement shall be not less than ..... of the gross cross sectional area of the column.

(a) 6% (b) 0.5%
(c) 1.5% (d) 0.8%

GPSC R&B AE 2016
WBPSC AE (Common) 1998

Ans. (d) : According to IS 456:2000
for column, minimum steel = 0.8% of c/s of column.
maximum steel = 6% of cross section of column.

935. Clear cover to the main reinforcement in beam, column and slab shall be

(a) 40mm, 25mm, 20mm
(b) 40mm, 20mm, 25mm
(c) 40mm, 40mm, 25mm
(d) 25mm, 40mm, 20mm

Sikkim PSC AE 2017

Ans. (d) : As per IS:456-2000, 26.4.2, min. clear cover is provided in RCC member is to prevent steel from the corrosion. It varies with the environmental condition and type of member.

Slab - 15 mm
Beam - 25 mm
Column - 40 mm
Footing - 75 mm

936. Two circular columns are of same size and main reinforcement. Circular ties have been provided in one column where as helical ties have been provided in other column. Which column has high load carrying capacity?

(a) Circular column
(b) Helical column
(c) Both have same load carrying capacity
(d) Depends on the diameter of the ties

Sikkim PSC AE 2017

Ans. (b) : Column with helical reinforcement strength of the column is increased by 5%.

937. Maximum percentage of steel, as a percentage of gross cross sectional area of column, that can be placed in column is

(a) 4.0% (b) 6.0%
(c) 0.8% (d) 2.0%

Sikkim PSC AE 2017
WBPSC AE 2007

Ans. (b) : As per IS 456-2000, the cross-sectional area of longitudinal reinforcement, shall not be less than 0.8% nor more than 6% of the gross cross-sectional area of column.

938. A column with unsupported length of 3.5 m, cross-section 420 mm × 420 mm subjected to an axial load 1000 kN to be checked for minimum eccentricity is

(a) 11 mm (b) 31 mm
(c) 21 mm (d) 41 mm

TRB Poly. Tech. Lect. 2012

Ans. (c) : Alls column should design for a minimum eccentricity of

$$e_{min} = \max\begin{cases}\dfrac{\ell}{500} + \dfrac{\text{B or D}}{30} \\ 20\,\text{mm}\end{cases}$$

$$e_{min} = \max\begin{cases}\dfrac{3.5\times1000}{500} + \dfrac{420}{30} \\ 20\,\text{mm}\end{cases}$$ (which value is large)

$\boxed{e_{min} = 21\text{mm}}$

939. The load carrying capacity of a column designed by working stress method is 500 kN. The ultimate load of the column is

(a) 500 kN (b) 662.5 kN
(c) 750 kN (d) 1100 kN

AP TRANSCO AEE 2017
PTCUL AE 2016
TRB Poly. Tech. Lect. 2012
ESE 1996, 2010

Ans. (c) : Ultimate load of
the column = working load × FOS
= 500 × 1.5
= 750 kN

940. Spacing of main reinforcing bars measured along the periphery of RC column should not exceed

(a) 150 mm (b) 250 mm
(c) 300 mm (d) 500 mm

UKPSC(Urban engineering)-2011

Ans. (c) : Spacing for longitudinal bars from periphery of the column must not exceed 300 mm. the maximum size of aggregate use in column is 20 mm.

941. Minimum percentage of longitudinal reinforcement in column should not be less than

(a) 1.1% (b) 1.0%
(c) 0.8% (d) 0.6%

UKPSC(Urban engineering)-2011

Search on Telegram @apna_pdf

Ans. (c) : The cross-sectional area of longitudinal reinforcement, shall be not less than **0.8** percent and not more than 6 percent of gross cross–sectional area of the column.

942. The critical section for the shear in isolated square footing is taken at a distance equal to

(a) effective depth of footing from the periphery of the column
(b) half the effective depth of footing from the periphery of the column
(c) at the periphery of the column
(d) at the centre of the footing

UKPSC(Urban engineering)-2011

Ans. (b) : The critical section for a moment in case of isolated footing is found at column face critical section for footing, which support a masonry wall is found at a distance equal to **halfway** between the central line and a face.

943. The minimum number of main reinforcing bars provided in a circular RC column is

(a) 2 (b) 4
(c) 6 (d) 8

UKPSC(Urban engineering)-2011

Ans. (c) : The minimum number of longitudinal base provided in a column small be **4** in rectangular columns and **6** in circular columns.

944. The slenderness ratio of a R.C.C column is generally taken as:

(a) –1/r (b) 1/B
(c) 1/D (d) None of the above

UJVNL AE 2012

Ans. (d) : Slenderness ratio (λ)

$$\lambda = \frac{\text{effective length}}{\text{least lateral dimension}}$$

$[\lambda < 12]$ short column.
$[\lambda > 12]$ long column.

945. The limits of percentage P of longitudinal reinforcement in a column are given by

(a) 0.15 % to 2% (b) 0.8% to 4%
(c) 0.8% to 6% (d) 0.15% to 6%

Haryana PSC AE 2017
APPSC AEE 2012
ESE 1996

Ans. (c) : Minimum steel area = 0.8% of gross section area
Maximum steel Area

$$= \begin{cases} 6\% \text{ of gross Area; in non Lapped} \\ 4\% \text{ of gross Area; in Lapped case} \end{cases}$$

946. The minimum eccentricity for the design of column is

(a) $\frac{l}{600}+\frac{b}{30}$ (b) $\frac{l}{500}+\frac{b}{30}$
(c) $\frac{l}{300}+\frac{b}{50}$ (d) $\frac{l}{300}+\frac{b}{30}$

subjected to a minimum of 20 mm, where *l* is unsupported length of the column and b is least lateral dimension of the column.

BPSC Poly. Tech. Lect. 2016

Ans. (b) : Minimum eccentricity for the design of column is equal to unsupported length of column.

$$e_{min} = \left\{ \begin{matrix} \frac{l}{500}+\frac{b \text{ or } d}{30} \\ 20\ mm \end{matrix} \right\} \text{ maximum of above two we take}$$

→ Where b, d are breadth and depth of cross-section respectively which depend on the MOI i.e., I_{xx} or I_{yy} we are looking.

947. The minimum cover prescribed in the code for flexural reinforcement in all footings?

(a) 75 mm (b) 40 mm
(c) 50 mm (d) 60 mm

GPSC AE June 2019

Ans. (c) : The minimum cover prescribed in the code for flexural reinforcement in all footing is 50 mm.

948. As per IS 456, the minimum cover to be provided for columns is

(a) 50 mm (b) 40 mm
(c) 25mm (d) 30 mm

GPSC AE June 2019

Ans. (b) : As per IS 456 : 2000, the minimum cover to be provided for column is 40 mm.

949. The allowable slenderness ratio of the elements in built-up section is

(a) 180 (b) 250
(c) 145 (d) 50

GPSC AE Dec 2018

Ans. (d) : The allowable slenderness ratio of the elements in built-up section is 50.

950. According to IS 456:2000, a pedestal is a compression member whose

(a) effective length does not exceed 2 times its least lateral dimension
(b) effective length does not exceed 3 times its least lateral dimension
(c) effective length does not exceed 4 times its least lateral dimension
(d) effective length does not exceed 5 times its least lateral dimension

GPSC AE Dec 2018

Ans. (b) : According to IS 456:2000, a pedestal is a compression member whose effective length does not exceed 3 times its least lateral dimension.

951. For which of the following conditions, shear failure happens between the base of a shallow strip footing and the first soil reinforcement layer ? (Take D as the distance between the first layer of reinforcement and base of the footing and B the width of footing).

(a) $\frac{D}{B} > \frac{1}{3}$ (b) $\frac{D}{B} > \frac{1}{2}$
(c) $\frac{D}{B} < \frac{2}{3}$ (d) $\frac{D}{B} > \frac{2}{3}$

BHEL ET 2019

Ans. (d) :

Search on Telegram @apna_pdf

952. In reinforced concrete columns, the minimum and maximum quantity of longitudinal reinforcement, as percentage of the gross cross-sectional area of column, are respectively :

(a) 0.15, 4 (b) 1, 10
(c) 0.8, 6 (d) 0.12, 8

BHEL ET 2019

Ans. (c) : In case of RC column, the minimum and maximum quantity of longitudinal reinforcement, as percentage of the gross cross sectional area of column are 0.8% and 6% respectively.

953. Read the following statements for RCC column/compression members?

(i) A compression member may be considered as short when the maximum slenderness ratio is less than 12.
(ii) For a compressive member, the unsupported length between end restrains shall not exceed 60 times the least lateral dimension.

(a) Only (i) is correct
(b) Only (i) is correct
(c) Both (i) and (ii) are correct
(d) Both (i) and (ii) are incorrect

GPSC Assistant Prof. 2016

Ans. (c) : For RCC column/compression member
(1) A compression members may be considered as short when the maximum slenderness ratio < 12.
(2) For a compression member, the unsupported length between end restrain shall not exceed 60 times the least lateral dimension.

954. Four columns of building are to be located within a plot size of 10 m × 10 m. The expected load on each column is 400 KN. Allowable bearing capacity of soil deposit is 100 KN/m^2. The type of foundation to be used is :

(a) Isolated foundation
(b) Raft foundation
(c) Pile foundation
(d) Combined foundation

PTCUL AE 2016

Ans. (a) : Area of plot = $10 \times 10 = 100\ m^2$

Area of each column = $\dfrac{400\,kN}{100\,kN/m^2} = 4\ m^2$

Area of footing = $4 \times 4 = 16\ m^2$

% of footing wrt plot = $\dfrac{16}{100} \times 100\% = 16\%$

$\because$ Area of footing is smaller than 40% of plot area therefore isolated foundation is provided, otherwise raft foundation.

955. Minimum percentage of reinforcement in RCC short column:

(a) 0.8% (b) 6.0%
(c) 8% (d) 4%

PTCUL AE 2016

Ans. (a) : For column IS 456-2000 longitudinal reinforcement shall not be less than 0.8% and shall not be more than 6%.

956. Dia of lateral ties in column taken as:

(a) $\frac{1}{4}$ dia of largest longitudinal bar
(b) 6 mm
(c) $\frac{1}{4}$ dia of largest longitudinal bar or 6 mm which ever greater
(d) Does not defends on longitudinal bar only depends on size of aggregates in concrete

PTCUL AE 2016

Ans. (c) : Dia of lateral ties in column taken as $\frac{1}{4}$th dia of longitudinal bar or 6 mm which is more.

957. Struts is a ..... member.

(a) tension (b) compression
(c) flexure (d) All of the above

PTCUL AE 2016

Ans. (b) : A strut is defined as a structural member subjected to compression in direction parallel to its longitudinal axis. The term strut is commonly used for compression members.

958. A column of size 450mm × 600mm has unsupported length of 3.0 m and is braced against side sway in both directions. According to IS 456 : 2000, the minimum eccentricities (in mm) with respect to major and minor principal axes are

(a) 20.0 and 20.0 (b) 26.0 and 21.0
(c) 26.0 and 20.0 (d) 21.0 and 15.0

AP TRANSCO AEE 2017

Ans. (b) : Given,
Column size = 450 mm × 600 mm

$l = 3$ m

$$e_{x_{min}} = \begin{cases} \dfrac{l}{500} + \dfrac{D}{30} \\ 20\,mm \end{cases}$$ which is greater

$$= \frac{3000}{500} + \frac{600}{30}$$

$e_{x_{min}} = 26$ mm

$$e_{y_{min}} = \begin{cases} \dfrac{l}{500} + \dfrac{B}{30} \\ 20\,mm \end{cases}$$ which is greater

$$= \frac{3000}{500} + \frac{450}{30}$$

$e_{y_{min}} = 21$ mm

959. The critical section for maximum bending moment in the footing under masonry wall is located at

(a) The middle of wall
(b) The face of the wall
(c) Mid-way between the face and the middle of the wall
(d) A distance equal to the effective depth of footing

AP TRANSCO AEE 2017
ESE 2014

Search on Telegram @apna_pdf

Ans. (c) : The critical section for maximum bending moment in the footing under masonry wall is located at mid-way between the face and the middle of the wall.

960. If the diameter of longitudinal bars of a square column is 16mm, the diameter of lateral ties should not be less than

(a) 6 mm (b) 2 mm
(c) 4 mm (d) 8 mm

UPPCL AE 2014

Ans. (c) : Diameter of lateral ties = $\frac{\phi_{main}}{4} = \frac{16}{4} = 4$

- But as per code min. dia to be provided is 6mm.

961. The diameter of longitudinal bars in a column should not be less than

(a) 4 mm (b) 8 mm
(c) 12 mm (d) 16 mm

APPSC AEE 2016

Ans. (c) :
- diameter of longitudinal bar in column should not be less than 12mm
- diameter of vertical stirrups in column should not be less than 8mm.

962. Design of column strip and middle strip is carried out separately for

(a) Waffle slab (b) Ribbed slab
(c) Flat slab (d) Cantilever slab

GPSC AE January 2018

Ans. (c) : Design of column-strip and design strip is carried out separately for flat slab.
A column strip is a design strip with a width on each side of column centre line equal to 0.25 L_1 or 0.25 L_2 whichever is less.
A middle strip is design strip bounded by two column strips.

963. Minimum percentage of cross sectional area to be provided as longitudinal reinforcement for design of RC column is .....

(a) 6% (b) 0.6%
(c) 0.8% (d) 1.0%

GPSC AE January 2018

Ans. (c) : In case of RC column:
Minimum % of longitudinal steel = 0.8% cross section area.
Maximum % of steel =
→ 4% for lapped bars
→ 6% for non-lapped bars

964. As per IS:456 a concrete column may be considered as short when it's slenderness ratio is less than

(a) 18 (b) 15
(c) 12 (d) 20

GPSC AE January 2018

Ans. (c) :

Slenderness ratio $= \frac{\text{effective length}}{\text{radius of gyration}}$

$\lambda = \frac{leff}{r} < 12$ for short column


$\lambda > 12$ for long column.

965. In design of isolated RC footing, the critical section for two way shear is considered at a distance of ..... from the face of column/pedestal.

(a) d/2 (b) d
(c) d/3 (d) 2d

GPSC AE January 2018

Ans. (a) : Critical section for two way shear in the design of isolated reinforced concrete footing (punching stress) is at a distance d/2 in all direction from face of column.



966. In reinforced concrete, pedestal is defined as a compression member, whose effective length does not exceed its least lateral dimension by

(a) 3 times (b) 8 times
(c) 12 times (d) 16 times

MPPSC AE 2014


Ans. (a) : In reinforced concrete pedestal is defined as a compression member, whose effective length not exceed its least lateral dimension by 3 times. (clause 26.5.3.1)

967. Footing of size 4m × 4 m carries a uniformly distributed load of 150 kN/m^2. Compute the vertical pressure at a depth of 6m below the footing using 2:1 method.

(a) 24 kN/m^2 (b) 30 kN/m^2
(c) 32.5 kN/m^2 (d) 36 kN/m^2

UPPCL AE 2018

Ans. (a) :



Total force at base of footing = 150 × 16
= 2400 kN

2V - 1H
6V - 3H
Area at the depth of 6 m
= (4+3+3) (4+3+3)
= 100 m^2

Vertical pressure = $\frac{2400}{100} = 24$ kN/m^2

968. In a continuous beam, the moment coefficient of the innermost support for the dead load is:

(a) $\frac{1}{12}$ (b) $\frac{1}{10}$

Search on Telegram @apna_pdf

(c) $\frac{1}{9}$ (d) $\frac{1}{24}$

LMRC AM 2018

Ans. (a) : Continuous beam, the moment coefficient of the innermost support for the dead load is $\frac{1}{12}$.

969. Calculate the size of the column square in cross-section to carry an axial load of 2100 kN. Use grade of steel Fe415 & grade of concrete of M-20 grade :

(a) 565.4 mm (b) 576.2 mm
(c) 556.8 mm (d) 560.8 mm

LMRC AM 2018

Ans. (c) : $P = A_{cc} \times \sigma_{cc} + A_{sc} \times \sigma_{sc}$
Let,
1% Steel
$A = A_c + A_{st}$
$A_c = (A - 0.01A)$
$P = (A - 0.01A)5 + 0.01A \times 190$
$2100\ kN = 4.95A + 1.9A$
$2100 \times 10^3\ N = 4.95A + 1.9A$
$A = 306569.34\ mm^2$
$\therefore$ One side of square (a) $= 553.68 \approx 556.8mm$
$\boxed{a = 556.8mm}$

970. In the case of reinforced concrete column footings, the minimum value of nominal cover to be provided for meeting the durability requirement is:

(a) 25 mm (b) 60 mm
(c) 50 mm (d) 40 mm

CIL MT 2020

Ans. (c) : Minimum value of nominal cover to provided for meeting the durability requirement is 50 mm.

971. As per IS 456 : 2000, the nominal cover for the exposure condition 'severe' is :

(a) 45 mm (b) 50 mm
(c) 50 mm (d) 30 mm

DMRC AM 2020

Ans. (a) : As per IS 456 : 2000, the nominal cover for the exposure condition 'severe' is 45mm.

972. As per IS code, the K (effective length ratio) value for/ at which one end is fixed and the other is partially fixed for columns unbraced against sideway is :

(a) 1 (b) 1.5
(c) 2 (d) 0.5

DMRC AM 2020

Ans. (b) : The K (effective length ratio) value for/ at which one end is fixed and the other is partially fixed for columns unbraced against sideway is 1.5.

973. For a column member, as per IS : 456 : 2000 the cross-sectional area of longitudinal reinforcement should not be more than :

(a) 8 percent of the gross sectional area
(b) 12 percent of the gross sectional area
(c) 6 percent of the gross sectional area
(d) 10 percent of the gross sectional area
(e) 9 percent of the gross sectional area

CGPSC AE 2017

Ans. (c) For a column member, as per IS : 456 : 2000 the cross-sectional area of longitudinal reinforcement should not be more than 6 percent of the gross sectional area and minimum is 0.8% of gross sectional area.

974. As per IS 456 : 2000, in reinforced and plain concrete footings the thickness at the edge shall NOT be less than.....for footings.

(a) 25 cm (b) 50 cm
(c) 15 cm (d) 35 cm
(e) 55 cm

CGPSC AE 2017

Ans. (c) As per IS 456 : 2000, in reinforced and plain concrete footings the thickness at the edge shall NOT be less than 15 cm for footings.

975. As per IS 456 : 2000, the cross-sectional area of longitudinal reinforcement shall NOT be :

(a) less than 1 per cent and more than 7 percent of the gross sectional area
(b) less than 0.8 per cent and more than 6 percent of the gross sectional area
(c) less than 1.2 per cent and more than 4 percent of the gross sectional area
(d) less than 2 per cent and more than 8 percent of the gross sectional area
(e) less than 4 per cent and more than 10 percent of the gross sectional area

CGPSC AE 2017

Ans. (b) According to IS : 456 - 2000.

Member	Max reinforcement	Min. reinforcement
Beam	4% of gross section area for each compression and tension	$\frac{A_{st\,min}}{bd} = \frac{0.85}{f_y}$
Column	6% of gross cross sectional area	0.8% of gross cross-sectional area

976. The column strip with negative moment at an interior support shall be designed to resist .....percent of the total negative moment in the panel at that support.

(a) 60 (b) 80
(c) 50 (d) 75
(e) 90

CGPSC AE 2017

Ans. (d) The column strip with negative moment at an interior support shall be designed to resist 75 percent of the total negative moment in the panel at that support.

977. If the effective length of a 44 cm diameter reinforced concrete column is 4.4 m, its slenderness ratio is:

(a) 40 (b) 50
(c) 44 (d) 55
(e) 60

Haryana PSC AE 2018 Paper–I

Ans. (a) : Slenderness ratio $(\lambda) = \frac{l_{eff}}{r_{min}}$

l_{eff} = effective length of column.

Search on Telegram @apna_pdf

∴ Given, D = 44 cm, L = 4.4 m

$$r = \sqrt{\frac{I}{A}},\ I = \frac{\pi}{64}D^4 = \frac{\pi}{64}\times(44)^4 = 183984\ \text{cm}^4$$

$$\text{Area} = \frac{\pi}{4}d^2 = \frac{\pi}{4}\times 44^2 = 1520 cm^2$$

$$r_{\min} = \sqrt{\frac{I}{A}} = \sqrt{\frac{183984}{1520}} = 11$$

$$\lambda = \frac{\text{effective length}}{\text{min radius of gyration}}$$

$$\lambda = \frac{440}{11} = 40$$

∴ I = Moment of inertia, r = radius of gyration

978. Thickened part of a flat slab over its supporting column is technically known as:

(a) Capital (b) Drop panel
(c) Column head (d) Cover
(e) None of the options

Haryana PSC AE 2018 Paper–I

Ans. (b) : Capital or column head:-Sometimes, the diameter of supporting column is increased below the slab. This part of column with increased diameter is called column head.
Drop panel:-It is used for resisting high shear at the column, drop panels have thickness more than the slab thickness and they are mostly used when the span is large or shear load is high.

979. In a combined footing if shear stress exceeds 5kg/cm^2, the nominal stirrups provided are:

(a) 6 legged (b) 8 legged
(c) 4 legged (d) 10 legged
(e) 12 legged

Haryana PSC AE 2018 Paper–I

Ans. (e) : In a combined footing if shear stress exceeds 5kg/cm^2, the nominal stirrups provided are 12 legged.

980. Assertion (A): In a helically reinforced concrete column, the concrete core is subjected to triaxial state stress.
Reason (R): Helically reinforced concrete columns are very much suitable for earthquake resistant structures.

(a) Both A and R are true and R is the correct explanation of A
(b) Both A and R are true but R is not a correct explanation of A
(c) A is true but R is false
(d) A is false but R is true

Haryana PSC AE 2017

Ans. (b) :

981. As per IS:45-2000, the minimum eccentricity for design of column should be -

(a) $\frac{L}{300}+\frac{D}{50}$ (b) $\frac{L}{30}+\frac{D}{500}$
(c) $\frac{L}{500}+\frac{D}{30}$ (d) $\frac{L}{50}+\frac{D}{300}$

Subjected to a minimum of 20 mm (where L = unsupported length of column and D = lateral dimension)

Rajasthan VP ITI 2018

Ans. (c) : In limit state method I.S 456-2000, the minimum eccentricity for design of column should be–

$$e_{\min} = \text{maximum}\begin{cases}\frac{l}{500}+\frac{\text{B or D}}{20}\\ 20\ \text{mm}\end{cases}$$

$e_{\min} \le 0.05$ D, then it is a short axially loaded column.

982. The pitch of transverse reinforcement in column shall not be more than the least of the following distance as per IS 456-2000.
(i) The least lateral dimension of the compression members.
(ii) Sixteen times the smallest diameter of the longitudinal reinforcement bar to be tied
(iii) 300 mm
(iv) 48 times of smallest diameter of the transverse reinforcement bar to tied
Which of the above statements is/are correct?

(a) (i) (ii) (iii) (b) (i) (ii) (iv)
(c) (ii) (iii) (iv) (d) (i) (ii) (iii) (iv)

UP Jal Nigam AE 2016


Ans. (d) : The pitch of transverse reinforcement in column shall not be more than :
(i) The least lateral dimension of the compression members.
(ii) 16 times the smallest diameter of the longitudinal reinforcement bar to be tied .
(iii) 300 mm .
(iv) 48 times of smallest diameter of the transverse reinforcement bar to tied

983. T section of a beam subjected to transverse shear force maximum shear stress is developed:

(a) At the centre of the web
(b) At the top edge of top flange
(c) At the bottom edge of top flange
(d) At the junction of flange and web

UP Jal Nigam AE 2016

Ans. (a) : T- section of a beam subjected to transverse shear force maximum shear stress is developed at the centre of the web.



984. If "d" represents the effective depth of footing, which of the following represents the critical section for two way shear of footing?

(a) Face of the column
(b) Distance d from the column face
(c) Distance d/2 from the column face
(d) Distance 2d from the column face

UPRVUNL AE 2014

Ans. (c) : Two way shear shall be checked around the column on the perimeter at the distance of the effective depth of the footing slab away from the face of the column or pedestal.

Search on Telegram @apna_pdf

985. As per IS 456, the minimum nominal cover specified for footings is:
(a) 25 mm (b) 40 mm
(c) 50 mm (d) 75 mm

LMRC AM 2015

Ans (c) As per IS 456, the minimum nominal cover specified for footings is 50 mm.

986. An RCC column of 4 m length is rigidly connected to the slab and to the foundation. Its cross-section is (400 × 400) mm^2. The column will behave as a/an
(a) Long column (b) Short column
(c) Intermediate column (d) Linkage

ESE 2018

Ans. (b) The end connection are rigid both rotation and translation is not allowed at both ends.
- Effective length (L_{eff}) = 0.65L

Slenderness Ratio = $\frac{L_{eff}}{B}$

$$\left[SR = \frac{0.65 \times 4000}{400} = 6.5\right]$$

Now, for short column $\left(3 < \frac{leff}{b} . < 12\right)$

- If slenderness ratio < 3 (Pedestal)

987. An axially loaded column is of 300 mm × 300 mm size. If effective length of column is 3.0 m, what is the minimum eccentricity of the axial load for the column?
(a) No eccentricity (b) 15 mm
(c) 20 mm (d) 25 mm

HPPSC Poly. Lect. 2016

Ans : (c) To design a perfectly axial column (load passing through CG of the column). IS code has provided minimum eccentricity and if load acts within that we can consider the column as axially loaded column.

e_{min} =

$$\left(\frac{\text{unsuppoted length of column}}{500}\right) + \left(\frac{\text{least lateral dimension}}{30}\right)$$

$$= \left(\frac{L}{500} + \frac{D}{30}\right) \text{ or 20 mm whichever maximum}$$

$$= \left(\frac{300}{500} + \frac{300}{30}\right) = 10.6 \text{ cm or 20 mm}$$

e_{min} = 20 mm is maximum

988. How is the depth of footing for an isolated column governed?
1. By maximum bending moment
2. By shear force
3. By punching shear
Select the correct answer using the codes given below:
(a) 2 and 3 only (b) 1 and 2 only
(c) 1 and 3 only (d) 1, 2 and 3

Haryana PSC AE 2017
ESE 2014

Ans. (d)

989. The permissible load for columns with helical reinforcement shall be ..... times the permissible load for similar member with lateral ties or rings.
(a) 1.5 (b) 1.05
(c) 0.7 (d) 1.25

HPPSC Poly. Lect. 2016

Ans : (b) The permissible load for columns with helical reinforcement satisfying 1.05 times the permissible load for similar member with lateral ties or rings.

990. As per IS 456-2000, the cross sectional area of longitudinal reinforcement provided in a column should not exceed ____ of gross cross-sectional area.
(a) 6% (b) 5%
(c) 4% (d) 7%

IRCON AE 2017

Ans. (a) : As per IS 456-2000–
Minimum % of steel in column = 0.8% of c/s of column.
Maximum % of steel in column–
1. If bars are lapped = 4% of column c/s.
2. If bars are not lapped = 6% of column.

991. If, in any given plane, one end of a column is unrestrained, its unsupported length *l*, shall not exceed:
(a) 100 D^2/b (b) 100 b^2/D
(c) 100 b^3/D (d) 100 D^3/b

IRCON AE 2017

Ans. (b) : If in an any given plane, one end of a column is unstained and its unsupported length = *l*.

so, $l \le \frac{100 b^2}{D}$

b = width of c/s area
D = depth of that section

992. In a RCC column, one of the criteria for the maximum pitch of the lateral ties is that it should be:
(a) equal to 7 times the diameter of the ties
(b) equal to 100 mm
(c) equal to 300 mm
(d) less than 200 mm

JUVNL AE 2016

Ans. (c) : For RCC column–Maximum pitch of lateral ties should be equal to 300 mm.
Pitch of lateral ties ≤ 800 mm.

993. In RCC column with spiral reinforcement minimum number of longitudinal bars in contact with the spiral shall be less than
(a) 3 (b) 4
(c) 5 (d) 6

WBPSC AE 2014

Ans. (d) : Column having helical reinforcement shall have minimum 6 longitudinal bars for columns with helical reinforcement, the permissible load satisfying the requirements shall be adopted as 1.05 times permissible load of a similar member of lateral ties..

Search on Telegram @apna_pdf

994. The lateral ties in a reinforced concrete rectangular column under axial compression are used to

(a) avoid the buckling of the longitudinal steel under compression
(b) provide adequate shear capacity
(c) provide adequate confinement to concrete
(d) reduce the axial deformation of the column

WBPSC AE 2007

Ans. (a) : Traverse reinforcement it may be in the form of lateral ties of spirals. The diameter of the lateral ties should not be less than 1/4th of the diameter of the largest longitudinal bar and in no case less than 6mm.

995. In reinforced concrete footing on soil, the minimum thickness at edge of the footing should not be less than

(a) 200 mm (b) 150 mm
(c) 225 mm (d) 100 mm

WBPSC AE 2007

Ans. (b) : Thickness of the edge of footing in reinforced and plain concrete footings, the thickness at edge shall be not less than 150 mm for footings on soils nor less than 300 mm above the tops of fields for footing on piles.

996. Reduction factor of R.C.C. column with $\frac{l}{b} = 24$ is

(a) 1.25 (b) 0.50
(c) 1.00 (d) 0.75

WBPSC AE 2003

Ans. (d) :

$$C_r = 1.25 - \frac{l_{eff}}{48B}$$

$$C_r = 1.25 - \frac{24}{48} = 0.75$$

997. A P.C.C. column can be considered as a short column, if its slenderness ratio is less than

(a) 30 (b) 35
(c) 40 (d) 50

WBPSC AE (PHE) 1998

Ans. (a) : The tendency of column to buckle is usually measured by its slenderness ratio

$$\text{slenderness ratio} = \frac{L}{r}$$

$$\text{where (r)} = \sqrt{\frac{I}{A}} = \text{radius of gyration}$$

• for a short column slenderness ratio should be less than 30.

998. Reinforcement in a R.C.C. column should be as follows

(a) Not less than 0.8% not more than 6%
(b) Not less than 0.5% not more than 6%
(c) Not less than 1% not more than 4%
(d) Not less than 1% not more than 6%

WBPSC AE (PHE) 1998

Ans. (a) : Minimum and maximum percentage of steel–
for columns–
0.8 to 6% but normally 4% provided
for slabs–
HYSD bar 0.12%
Mild steel 0.15%

999. For the design of R.C. columns a column is treated as short one if the ratio of effective length to its least lateral dimension is less than

(a) 20 (b) 16
(c) 12 (d) 8

WBPSC AE (PHE) 1998

Ans. (c) : This column is considered to be short if the ratio of effective length to its least lateral dimension is less than or equal to 12.

1000. The critical section for bending in a footing should be considered at

(a) a distance of d/2 from the face of column
(b) a distance of d from the face of column
(c) the face of column
(d) distance of d/6 from the face of column where d = effective depth

WBPSC AE (Common) 1998

Ans. (c) : The critical section for bending in a footing should be considered at the face of column.

1001 The top reinforcement at the support section of a continuous beam shall be extended from either face of the column up to a distance equal to

(a) effective span/3 (b) effective span/6
(c) effective span/5 (d) effective span/8

WBPSC AE (Common) 1998

Ans. (a) :

1002. The bearing stress check for column footing in limit state design specified that the value _____ subjected to a maximum of 2 multiplied by bearing stress _____ shall be more than the compressive stress at the base of the column. A_1 = supporting area for bearing of footing, which in sloped or stepped footing maybe taken as the area of the lower base of the largest frustum of a pyramid or cone contained wholly within the footing and having for its upper base, the area actually loaded and having side slope of one vertical to two horizontal; and, A_2 = loaded area at the column base.

(a) $\sqrt{(A_1/A_2)}$, 0.30 f_{ck} (b) $\sqrt{(A_1/A_2)}$, 0.45 f_{ck}
(c) $\sqrt{(A_1/A_2)}$, 0.45 f_{ck} (d) $\sqrt{(A_1/A_2)}$, 0.60 f_{ck}

TSPSC Deputy Engineer 2015

Ans. (c) :

1003. If load carrying capacity of a column designed by working stress method is 500 kN, then collapse load of the column is

(a) 500.0 kN (b) 662.5 kN
(c) 750.0 kN (d) 1000 kN

Chandigarh AE 2017

Ans. (c) : Working load = 500 kN
Collapse load = 1.5 × working load
Collapse load = 1.5 × 500 kN = 750 kN

Search on Telegram @apna_pdf

1004. Six columns of building are to be located within the plot size of 15×10m. The expected load on each column is 600 KN. Allowable bearing capacity of soil is 120KN/m^2. The type of foundation to be used is

(a) Isolated foundation
(b) Pile foundation
(c) Combined foundation
(d) Raft foundation

ISRO Scientist/Engineer 2014

Ans : (a)

1005. Which of the following is not an assumption in the limit state theory for designing of reinforced cement concrete (RCC)?

(a) Strains are proportional to distance from the neutral axis
(b) The tensile strength of concrete is neglected as the section is assumed to be cracked up to the neutral axis
(c) Ultimate limit state of bending failure is assumed to have been reached when the strain in the concrete at the extreme bending compression fiber reaches 0.0050
(d) The stress distribution across compression face will correspond to the stress-strain diagram for concrete in compression

UPRVUNL AE 2016

Ans.: (c)

8. Cantilever Retaining Walls

1006. In a reinforced concrete retaining wall, shear key is provided if

(a) shear stress in the vertical component is exceeds
(b) shear force in the toe slab is less than that in the heel slab
(c) Retaining wall is not safe against sliding
(d) shear force in the toe slab is more than that in the heel slab
(e) Retaining wall is not safe against over - turning

CGPSC AE 2014 Shift–I

Ans. (c) : When a shear key is installed at the base of retaining wall, the failure surface is changed from the wall base soil horizontal plane to plane within foundation soil, therefore, the friction angle mobilized and the sliding resistance can be enhanced.

1007. Which of the following assumptions is wrongly stated in regard to the Rankine's theory of earth pressure?

(a) The retaining wall yields about the base
(b) The soil mass is semi-infinite and homogeneous
(c) The back of the wall is not smooth
(d) The ground surface is plane

CIL MT 2017

Ans. (c) : The Rankine's theory assume that there is no wall friction, the ground and failure surfaces are straight planes, and that the resultant force acts parallel to the backfill slope.
The soil mass is homogeneous and semi infinite and retaining wall yields about the base.

1008. The retaining wall is considered to be safe against sliding if which of the following conditions is satisfied?

(a) $(0.9F \times F_{\text{Resisting force}}/F_{\text{Sliding force}}) \geq 1.40$
(b) $(0.9F \times F_{\text{Resisting force}}/F_{\text{Sliding force}}) \geq 1.70$
(c) $(0.9F \times F_{\text{Resisting force}}/F_{\text{Sliding force}}) < 1.40$
(d) $(F_{\text{Resisting force}}/F_{\text{Sliding force}}) > 2$

APPSC Poly. Tech. Lect. 2020

Ans. (a) : The retaining wall is considered to be safe against sliding if
$(0.9 \times F_{\text{Resisting force}}/F_{\text{Sliding force}}) \geq 1.40$ is satisfied.

1009. To avoid shearing, dam has to be placed as far as possible from ____

(a) Joints (b) Folds
(c) Intrusions (d) Faults

Gujarat PSC AE (N.W.R.) 2020

Ans. (d) : To avoid shearing, dam has to be placed as far as possible from Faults.

1010. Counter fort retaining wall is economical for heights above _____ m:

(a) 2 (b) 4
(c) 5 (d) 7

KPSC AE 2020


Ans. (d) : Counter fort retaining wall is economical for height about 7 m.

1011. In a RC retaining wall, a shear key is provided, if the-

(a) Shear stress in the vertical stem is excessive
(b) Shear force in the toe slab is more than that in the heel slab
(c) Retaining wall is not safe against sliding
(d) Retaining wall is not safe against overturning

UPRVUNL AE 2015
ESE 1998

Ans : (c)



In a RC retaining wall, a shear key is provided, if the retaining wall is not safe in sliding. Maximum height of cantilever retaining wall is limited to 6m. To avoid sliding of soil cantilever retaining walls are constructed.

1012. For preliminary calculations the thickness of the base slab of a retaining wall may be taken as _____ percent of the height of wall:

(a) 0.8 (b) .08
(c) 8 (d) 80

KPSC AE 2020

Search on Telegram @apna_pdf

Ans. (c) : The thickness of the vertical wall may be kept about 150 mm to 300 mm depending upon the overall height of the wall. The thickness at the base of vertical wall may be kept about 8 to 15 percent of the height of wall.

1013. In the heel slab in a cantilever retaining wall, main reinforcement is provided at

(a) Top of the slab (b) Bottom of the slab
(c) Centre of the slab (d) Sides of the slab

(RPSC AEn. - 2013)


Ans. (a) Normally the resultant pressure due to downward weight of earth fill and upward bearing pressure is downward which causes tension on the top face of the heel. The main reinforcement is provided at the top of the slab.

1014. In T–Shape RCC retaining wall, the main reinforcement in the stem is provided on

(a) The front face in one direction
(b) The front face in both direction
(c) The inner face in one direction
(d) The inner face in both direction

RPSC ACF - 2011

Ans : (c) In T-shape retaining wall, the main reinforcement in the stem is provided on the inner face in one direction.




1015. In a reinforced concrete, cantilever retaining wall, the maximum base pressure occurs at

(a) Toe of the wall
(b) Heel of the wall
(c) Mid-point of bases slab
(d) Below the stem in base slab

[UPPSC State Eng. A.E. 2008]

Ans : (a) The maximum base pressure will occur below the toe of retaining wall.



1016. The minimum thickness of R.C.C. wall should not be less than:

(a) 100mm (b) 50mm
(c) 75mm (d) 150mm

[UPPSC State Eng. A.E. 2007(I)]
[UPPSC State Eng. A.E. 2003]


Ans : (a) As per IS 456 : 2000
clause 32.1, the minimum thickness of RCC wall shall be 100 mm.

1017. The width of stem in cantilever retaining wall is usually kept as.....mm.

(a) 100 (b) 200
(c) 230 (d) none of these

(BPSC AE Paper V 2001)

Ans : (b)



1018. The height of a retaining wall is 5.5 m. It is to be designed as-

(a) Cantilever type
(b) Counterfort type
(c) Cantilever or counterfort type
(d) None of the above

Maharashtra PSC (Mains) 2017 Paper–I


Ans. (a) : h < 8 m– cantilever beam wall
h > 8 m –counterfort wall

1019. A shear key is provided in a retaining wall to avoid-

(a) Sliding (b) Overturning
(c) Buckling (d) Bending

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (a) : A shear key in retaining walls acts as a restraining force against sliding hence, avoids sliding.




1020. The vertical retaining wall of the RCC Counterfort is designed as a _____.

(a) Cantilever (b) Simply supported slab
(c) Continuous slab (d) None of these

OPSC AEE 2015 PAPER–I
RPSC ACF- 2011

Ans. (c) :



In a retaining wall, vertical wall, toe and base slab all are designed as cantilever.
In counterfort retaining wall the vertical stem is designed as a continuous slab spanning between the counterforts. Counter forts are designed as cantilever beams from the base slab.

1021. The bending moment at the edges of a square *l* due to a lateral pressure *p* per unit is

(a) $\frac{pl^2}{12}$ (b) $\frac{pl^2}{10}$

Search on Telegram @apna_pdf

(c) $\frac{pl^2}{16}$ (d) $\frac{pl^2}{11}$

BPSC AE 2019 Paper (V) Section-I

Ans. (a) : The bending moment at the edges of a square vertical bunker of side length '*l*' subjected to a lateral pressure 'p' per unit area is $\frac{pl^2}{12}$ and bending moment at the centre of a square vertical bunker of side length '*l*' subjected to a lateral pressure 'p' per unit area is $\frac{pl^2}{24}$.

1022. In a counterfort retaining wall, the main reinforcement is provided on the -

(i) Bottom face in front counterfort
(ii) Inclined face in front counterfort
(iii) Bottom face in back counterfort
(iv) Inclined face in back counterfort

The Correct answer is -

(a) (i) and (ii) (b) (ii) and (iii)
(c) (i) and (iv) (d) (iii) and (iv)

RPSC AE 2018
ESE 2005

Ans. (c) In case of front counterforts, the tension develop at the bottom face and it is provided with main reinforcement.
Counterforts are firmly attached to the face slab as well as the base slab. The earth pressure acting the face slab is transferred to the counterforts which deflect as vertical cantilevers. The back of the rear counterforts comes in tension and their front face is under compression. So the inclined face of rear counterforts should be provided with main reinforcement

1023. If the lateral pressure on a retaining wall is high, the following measure are taken while designing:

(a) Wall thickness is increased to resist the moment at base
(b) Slab thickness is increased to resist the moment
(c) Height of the retaining wall to be increased to the moment resisting capacity
(d) Shear key is provided to resist the lateral pressure

GPSC AE (CLASS 1 & 2) 2019

Ans : (d) : Shear key is provided to resist lateral load and provide fixed like interlocking to girder plate.

1024. For no tension developed in a gravity dam, where the resultant of all forces on dam should always lie?

(a) At Toe (b) Near Heel
(c) At Top
(d) Within the middle third of the section


Kerala PSC AE 2015

Ans. (d) : For no tension to develop, e should be less than B/6 or in other worlds, the resultant should always lie with in the middle third.

$$\sigma_{max/min} = \frac{P}{B}\left(1 \pm \frac{6e}{B}\right)$$

For no tension

$$\frac{P}{B}\left(1 - \frac{6e}{B}\right) > 0$$



$$1 - \frac{6e}{B} > 0$$

$$e < \frac{B}{6}$$

→ Limiting height of low concrete gravity dam is 90m.

1025. For a rectangular foundation of width *b*, eccentricity of load should not exceed

(a) $\frac{b}{2}$ (b) $\frac{b}{3}$
(c) $\frac{b}{5}$ (d) $\frac{b}{6}$

Kerala PSC AE 2015

Ans. (d) : Maximum and minimum stresses on the foundation with eccentric load are given as

$$= \frac{P}{b}\left(1 \pm \frac{6e}{b}\right)$$

We have to ensure that no tension is developed anywhere in the foundation. For that $\sigma_{min} > 0$

$$\frac{P}{b}\left(1 - \frac{6e}{b}\right) = 0, \quad 1 - \frac{6e}{b} > 0$$


$$e < \left(\frac{b}{6}\right)$$

1026. A masonry dam 8 m high, 1.5 m wide at the top and 5 m wide at the base retains water to a depth of 7.5 m, the water face of the dam being vertical. If the weight of water is 9.81 kN/m^3, weight of masonry is 22 kN/m^3, the maximum intensity of stress developed at the base will be nearly

(a) 196 kN/m^2 (b) 182 kN/m^2
(c) 160 kN/m^2 (d) 148 kN/m^2

ESE 2019

Ans. (b)



- Total water pressure = $\gamma\frac{H^2}{2}$
- Taking moment about 'B' overturning moment due to water pressure = $\left(\frac{\gamma H^2}{2}\right) \times \frac{H}{3}$

Overturning moment = $\frac{\gamma H^3}{6} = 9.81 \times \frac{(7.53)^3}{6}$
= 689.76 kNm/m

- Resisting moment = $W_1 \times \left(3.5 + \frac{1.5}{2}\right) + W_2\left(2 \times \frac{3.5}{3}\right)$

$W_1 = 22 \times 1.5 \times 8 = 264$ kN/m. length of dam.
$W_2 = 22 \times 0.5 \times 3.5 \times 8 = 308$ kN/m. length of dam

Search on Telegram @apna_pdf

Resisting moment = 264 (4.25) + $\left(308 \times \frac{7}{3}\right)$

= 1122 + 718.67 = 1840.67kNm/m

Net moment = 1840.67 – 689.76 = 1150.91 kNm

Total downward force = $W_1 + W_2 = 264 + 308 = 572$ kN

Point of application of resultant force from 'B'. =

$$\frac{M}{P} = \frac{1150.91}{572} = 2.01\text{m}$$

E_C eccentricity 'e' = $\frac{b}{2} = \bar{x} = \frac{5}{2} - 2.01$

[e = 0.49m]

Maximum pressure occurs at the base

$$= \Sigma \frac{W}{A}\left(1 + \frac{6e}{b}\right) = \frac{572}{5 \times 1}\left(1 + \frac{6 \times 0.49}{5}\right)$$

Stress at to c = 181.66kN/m^2


1027. In a cantilever retaining wall, the main steel reinforcement is provided

(a) On the backfill side, in the vertical direction
(b) On both, inner and outer, faces
(c) In horizontal as well as in vertical directions
(d) To counteract shear stresses

ESE 2018

Ans. (a)

- Main reinforcement is on back fill side where tension is developed.



- Due to lateral pressure of back fills the wall is designed as a cantilever and main reinforcement is provided on the rear side or backfill side in the vertical direction.

1028. The critical section for maximum bending moment in the footing under masonary wall is located at

(a) The middle of wall
(b) The face of the wall
(c) Mid-way between the face and the middle of the wall
(d) A distance equal to the effective depth of footing

APTRANSCO 2017

Ans : (c) : Critical section for maximum B.M. in the footing under masonry wall is located at mid-way between that face the middle of the wall.

1029. In counterfort retaining walls, the upright and heel slab act as:

(a) Cantilever
(b) Continuous slab
(c) Simply supported slab
(d) Slab supported or four sides

WBPSC Poly Lect. 2019

Ans. (b) : In counterfort retaining walls, the upright and heel slab act as Continuous slab.

1030. The minimum percentage of mild steel reinforcement to be provided in any direction in a retaining wall is

(a) 0.12 (b) 0.15
(c) 0.20 (d) 0.22

GPSC AE March 2018

Ans. (b) : Minimum steel requirement is 0.15% for mild steel bars and 0.12% for HYSD bars of the sectional area in each direction.

1031. Normally counterforts in a retaining wall are spaced at an interval of

(a) > 2 m
(b) 1/3 to 1/2 of the height of the wall
(c) 2 times the height of the wall
(d) 4.5 m to 5.5 m

GPSC AE March 2018

Ans. (b) : Counterfort in a retaining walls are usually required to resist a combination of earth and hydrostatic loadings.

Spacing of counterfort


in a retaining wall = 1/3 to 1/2 of height of wall

1032. While designing a RCC retaining wall the lateral earth pressure is

(a) Equal to the mass of soil retained
(b) Proportional to the height of retaining wall
(c) Proportional to the internal friction of soil
(d) Equal to the square of the depth of soil

Sikkim PSC AE 2017

Ans. (b) :



Earth pressure on the stem from backfill varies linearly, A/c to Rankine's theory at depth (h) below the top of wall is given by

$P_a = K_a \gamma H^2$

K_a = coefficient of active earth

$$K_a = \frac{1 - \sin\phi}{1 + \sin\phi}$$

ϕ = angle of internal friction of soil

γ = unit weight of back fill

1033. If H is the overall height of a retaining wall retaining a surcharge, the width of the base of the slab usually provided is

(a) 0.7 H (b) 0.4 H
(c) 1.0 H (d) 0.8 H

GPSC AE June 2019

Ans. (a) : If H is the over all height of a retaining wall retaining a surcharge, the width of the base of the slab usually provided is 0.7H.

1034. If area of steel for maximum mid span moment is 205 mm^2, what would be the area of steel required for the corner?

(a) 153.75 mm^2 (b) 205 mm^2
(c) 102.5 mm^2 (d) 41 mm^2

GPSC AE Dec 2018

Ans. (a) : Area of steel at corner = 75% of area of steel
= 0.75 × 205
= 153.75 mm^2

Search on Telegram @apna_pdf

1035. Thickness of stem at the base of cantilever RC retaining wall of height h should be between .....

(a) h/6 and h/10 (b) h/12 and h/15
(c) h/12 and h/8 (d) h/5 and h/10

GPSC AE January 2018

Ans. (c) : The thickness of the stem at base of RC retaining wall will be $\frac{h}{12}$ to $\frac{h}{8}$.
The stem thickness is gradually decreased towards top to a minimum value of 15 cm to 20 cm for economic design.

1036. In design of heel of cantilever RC retaining wall, the main steel is usually provided at .....

(a) Centre (b) Bottom
(c) Top (d) Both at top and centre

GPSC AE January 2018

Ans. (c) : In the design of heel in RC retaining wall, the main steel occurs on the tension face of the wall and nominal steel (0.15% of the cross-sectional area of wall) is very often included in the opposite face to control shrinkage.
Reason may be, in cantilever portion, upper part is in tension and lower part is in compression and steel should be provided in tension zone, so in the upper or top of cantilever RC retaining wall.

1307. The factor of safety against sliding should be more than

(a) 1.1 (b) 1.4
(c) 2.0 (d) 1.8

GPSC AE January 2018

Ans. (b) : Factor of safety against sliding ≤ 1.5
Factor of safety against overturning ≤ 2.0

1038. As per IS 456-2000, what should be the value of $(x_{u(max)} / d)$ for fe 415 steel?

(a) 0.48 (b) 0.53
(c) 0.46 (d) 0.44

LMRC AM 2018

Ans. (a) :

Grade of steel	f_y (N/mm^2)	Limiting depth of neutral axis $(x_{u\,max})$	Strain (max)
Fe-250	250	0.53d	0.00308
(HYSD)Fe-415	415	0.48d	0.00380
(HYSD)Fe-500	500	0.46d	0.00417

$$\frac{x_{u\lim}}{d} = \frac{700}{1100 + 0.87 f_y}$$

1039. In a cantilever retaining wall, the heel slab acts as :

(a) horizontal cantilever under the action of the resulting soil pressure acting upward
(b) horizontal cantilever under the action of the resulting soil pressure acting upward
(c) vertical cantilever under the action of the weight of retained earth
(d) vertical cantilever under the lateral earth pressure

DMRC AM 2020

Ans. (a) : In a cantilever retaining wall, the heel slab acts as horizontal cantilever under the action of the weight of retained earth.

1040. If p is the net downward pressure per unit area, the maximum negative bending moment near counterforts will be :

(a) $\frac{(pl^2)}{12}$ (b) $\frac{(pl^2)}{24}$
(c) $\frac{(pl^3)}{24}$ (d) $\frac{(pl^4)}{8}$
(e) $\frac{(pl^3)}{48}$

CGPSC AE 2017

Ans. (a) The maximum negative bending moment near counterforts will be $\left(\frac{Pl^2}{12}\right)$
P = net downward pressure per unit area.

1041. The spacing of counterforts depends on

(a) Height of the wall
(b) Relative cost of steel and concrete
(c) Allowable unit pressure of soil
(d) All of the above

WBPSC AE 2001

Ans. (d) : The spacing of counterforts to be fixed depends on several factors such as height of the wall, permissible limit of pressure acting on the soil, cost of concrete, frame work etc.

1042. The functionality of a wall, retaining wall and a shear wall in order is _____.

i. resist predominantly vertical loads
ii. resist lateral loads perpendicular to the plane of wall
iii. resist lateral loads in the plane of wall

(a) ii, iii, i (b) i, i, iii
(c) iii, ii, i (d) ii, i, iii

TSPSC Deputy Engineer 2015

Ans. (b) : The functionally of wall, retaining wall and a shear wall in order is resist predominantly vertical loads. Lateral loads perpendicular to the plane of wall and resist lateral load in the plane of wall.

1043. In counter fort retaining walls, the main reinforcement in the stem at support is

(a) not provided
(b) provided only on inner face
(c) provided only on front face
(d) provided both on inner and front face

Chandigarh SDE 2017

Ans. (b) : In counter fort retaining walls, the main reinforcement in the stem at support is provided only on inner face.

Search on Telegram @apna_pdf

9. Water Storage Tanks

1044. The permissible concrete stress in direct tension of M20 in calculation relating to resistance to cracking as per IS 3370-1965 part II is:

(a) 20kg/cm^2 (b) 12kg/cm^2
(c) 14 kg/cm^2 (d) 17 kg/cm^2

KPSC AE 2020

Ans. (b) : As per IS 3370 (Part II)-1965,
- The permissible concrete stress in direct tension of M20 is 12 kg/cm^2.
- The permissible concrete stress in tension due to bending of M20 is 17 kg/cm^2.

1045. Considering the concept of durability of water tanks, the minimum grade of concrete shall be:

(a) M10 (b) M20
(c) M30 (d) M40

KPSC AE 2020

Ans. (c) : Considering the concept of durability of water tanks, the minimum grade of concrete shall be M30.

1046. Hoop tension in a RCC water tank will be resisted by–

(a) Steel alone
(b) Concrete alone
(c) Partially by concrete and partially by steel
(d) None of the above

UKPSC AE 2013 Paper–I

Ans : (c) Hoop tension in RCC water tank will be resisted partially by concrete and partially by steel.

1047. The circular ring beam to resist thrust from top dome in Intze tank is designed for

(a) Hoop tension
(b) Hoop compression
(c) Bending moment
(d) Bending moment and shear force

[UPPSC State Eng. A.E. 2008, 2003]


Or

Due to water pressure in Intze tank, the walls will develop;

(a) Hoop tension
(b) Hoop compression
(c) Hoop compression and Hoop tension
(d) None of the above

[UPPSC State Eng. A.E. 2008]

Ans : (a) Due to water pressure in Intze tank, the walls will be hoop tension without any bending moment



Circular ring beams in intze tank are design to resist hoop tension.

1048. As per IS 456 : 2000, the minimum grade of concrete shall not be less than the following in structural reinforced concrete work in concrete water tanks:

(a) M15 (b) M20
(c) M25 (d) M30

[UPPSC State Eng. A.E. 2007(I)]

Ans : (d) As per IS 456 : 2000

concrete used in	minimum grade
(i) Reinforced concrete	M-20
(ii) Water tank	M-30
(iii)Pre - tensioning	M-40
(iv) Post-tensioning	M-30

Hence As per IS 456 : 2000, the minimum grade of concrete shall not be less than the M30 in structural reinforced concrete work in concrete water tanks.

1049. As per the Indian Standard (IS) 3370:2009, the minimum grade of concrete to be used in liquid retaining structures should be

(a) M 20 (b) M 25
(c) M 30 (d) M 15

MPPSC AE 2016

Ans : (c) As per IS – 3370:2009, the minimum grade of concrete for liquid retaining structure is M30 and minimum quantity cement used is 400 kg/m^3.

1050. The permissible bending tensile stress in concrete for vertical wall of an RC water tank made of M25 concrete is

(a) 8.5 N/mm^2 (b) 6.0 N/mm^2
(c) 2.5 N/mm^2 (d) 1.8 N/mm^2

RPSC POLY. TECH. LECT. 2014

Ans : (d) Permissible tensile stress in concrete (MPa)

Stress	Grade				
	M 25	M 30	M 35	M 40	M 50
Direct Tension	1.3	1.5	1.6	1.7	2.1
Bending Tension	1.8	2.0	2.2	2.4	2.8

1051. The allowable bending tension in M30 concrete of RCC water tank in water retaining portion is

(a) 1.2N/mm^2 (b) 1.5N/mm^2
(c) 1.7N/mm^2 (d) 2.0N/mm^2

[UPPSC State Eng. A.E. 2007(I)]

Ans : (d) As per IS 456 : 2000

Grade of concrete	Allowable bending tension in water tank (N/mm^2)
M-25	1.8
M-30	2.0
M-35	2.2
M-40	2.4

1052. If a circular water tank resting on the ground has 275 mm thickness then for M-25 grade concrete and Fe 415 steel, the minimum percentage of area of steel (A_{st}) provided is-

(a) (0.12%) bT (b) (0.16%) bT
(c) (0.20%) bT (d) (0.24%) bT

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (d) : Minimum percentage of steel in water tanks is given as
1. For thickness < 100 mm – 0.3%
2. For thickness between 100 – 450 mm – linearly between 0.3% @ 100 mm to 0.2% @ 450 mm

Search on Telegram @apna_pdf

3. For thickness > 450 mm – 0.2%

For thickness = 275 mm

Percentage of steel

$$= 0.2 + \left(\frac{450-275}{450-100}\right) \times (0.3-0.2)$$

$$= 0.25\% = 0.25\% \times bT$$

1053. In a spherical dome subjected to concentrated load at crown or uniformly distributed load, the meridional force is always

(a) zero
(b) tensile
(c) compressive
(d) tensile or compressive

BPSC AE 2019 Paper (V) Section-I

Ans. (c) : The primary stresses induced in the dome are (i) a compressive force acting along the meridian, called the meridional thrust and (ii) a force compressive or tensile in nature, acting along a horizontal circle on the dome called the hoop tension or hoop compression.
Hence, a spherical dome subjected to concentrated load at crown or uniformly distributed load, the meridional force is always compressive.

1054. In case of designing a water tank with Limit State Method, to control the cracking, the maximum stress in HYSD steel bars should not exceed

(a) 115 MPa (b) 125 MPa
(c) 130 MPa (d) 150 MPa

GPSC AE (CLASS 1 & 2) 2019

Ans : (c) : In water tank, the limit state, the maximum stress in HYSD steel bars should not exceed by 130 MPa

1055. Which of the following measures are relevantly considered for earthquake loading and lateral stability of tall buildings?

1. Minimizing gravity loads
2. Adding masses at floor levels
3. Ensuring ductility at the locations of maximum moments
4. Providing shear walls
5. Providing basement

Select the ***correct*** answer using the codes given below:

(a) 1, 2 and 5 only (b) 1, 2 and 4 only
(c) 1, 3 and 4 only (d) 3, 4 and 5 only

ESE 2017

Ans. (c)


- Minimizing the gravity loads will reduce the overall mass and there by reducing the forces. To have earthquake resistance higher ductility is required at maximum bending moment locations.
- Providing shear walls and rigid basement floors will be higher inertia.
- Cross-bracing or shear walls may be used to provide a structural frame with greater lateral rigidity in order to with stand wind stresses.

1056. A reinforced concrete cantilever porch has thickness t. The main reinforcement steel will be placed:

(a) At mid-thickness
(b) At t/3 from the top
(c) Close to the bottom surface
(d) Close to the top surface

ISRO Scientist/Engineer 2020

Ans. (d) : In the case of cantilever beam tension occurs at top. So, provide main reinforcement on the top surface in order to give strength the structure in tension.



1057. Which of the following are the desirable properties for efficient functioning in design for movement joint of water tank ?

1. **The joint should accommodate repeated movement of the structure without loss of water-tightness**
2. **The design should provide for exclusion of grit and debris which would prevent the closing of the joint.**
3. **The material used in the construction of movement joint should not slump unduly in hot weather or become brittle in cold weather.**

(a) 1, 2 and 3 (b) 1 and 2 only
(c) 1 and 3 only (d) 2 and 3 only

ESE 2020

Ans. (a) : Design of a movement joint should aim at following desirable properties for its efficient functioning :

(a) The joint should accommodate repeated movement of the structure without loss of water tightness.
(b) The design should provide for exclusion of grit and debris which would prevent the closing of the joint.
(c) The material used in the construction of movement joints should have the following properties–
  (1) It should not suffer permanent distortion or extrusion and should not be displaced by fluid pressure.
  (2) It should not slump unduly in hot weather or become brittle in cold weather.
  (3) It is should be insoluble and durable and should not be affected by exposure to light or by evaporation of solvent or plasticizers.
  (4) In special cases, the material should be non-toxic, taintless or resistant to chemical and biological action as may be specified.

1058. The allowable tension stress due to bending for M20 concrete in R.C.C. water tanks is (in N/mm^2)

(a) 1.2 (b) 1.5
(c) 1.7 (d) 2.0

GPSC AE March 2018

Search on Telegram @apna_pdf

Ans. (c) :

Grade of concrete	Direct tension stress	Stress due to bending
M15	1.1	1.5
M20	1.2	1.7
M25	1.3	1.8

1059. For sections up to a thickness of 100 mm, the minimum area of mild steel reinforcement to be provided in walls, floors and roofs of water tank in two particular directions should be

(a) 0.2% of the concrete section
(b) 0.3% of the concrete section
(c) 0.5% of the concrete section
(d) 0.8% of the concrete section

GPSC AE March 2018

Ans. (b) : For thickness upto 100 mm, minimum % of reinforcement should be 0.3%.
For thickness of 100 mm to 450 mm, it may be reduced linearly to 0.2%.

1060. As per IS 3370 (part 2) : 2009 concrete structures for storage of liquids (RCC) the permissible stresses in steel reinforcement for strength for high strength deformed bars is

(a) 115 N/mm^2 (b) 130 N/mm^2
(c) 125 N/mm^2 (d) 140 N/mm^2

TRB Poly. Tech. Lect. 2012

Ans. (b) : As per IS 3370 (part 2) : 2009, concrete structure for storage of liquids (RCC) the permissible stresses in steel reinforcement for strength for high strength deformed bar is – 130 N/mm^2

1061. Maximum width of crack in RC water retaining structures is restricted to .....

(a) 0.05 mm (b) 0.30 mm
(c) 0.01 mm (d) 0.20 mm

GPSC AE January 2018

Ans. (d) : For RC structures, crack width are limited to 0.3 mm generally. Lower maximum crack width as 0.2 mm are specified for water retaining structures.

1062. Minimum percentage of steel reinforcement of HYSD bars in walls, slabs and roofs of water retaining concrete structure as specified by Indian Standards is

(a) 0.2% (b) 0.24%
(c) 0.40% (d) 0.12%

GPSC AE January 2018

Ans. (d) : According to IS-456:2000 clause (26.5.2.1). Minimum percentage of steel reinforcement for slab of HYSD bar = 0.12% and for mild steel bar = 0.15%.

1063. The applicable IS code for RCC liquid retaining structure is

(a) IS:456 (b) IS:800
(c) IS:1893 (d) IS:3370

MPPSC AE 2014

Ans. (d) :
IS : 456 –RCC structure design
IS : 800 – Steel structure design
IS : 1893 – Earthquake resistance structure
IS : 3370 – Liquid retaining structure

1064. A water tank has a square plan area of 3m × km and maximum depth of water as 6m. When the tank ½ full, what is the force acting on one of the side wall (in kN)? Assume the density of water as 1000 kg/m^3 and gravitational acceleration as 10 m/sec^2.

(a) 135 (b) 27
(c) 45 (d) 90

UPPCL AE 2018

Ans. (*) :

1065. If the eccentricity of total self - weight W of a masonry dam at its base is equal to the one-fourth of base width B, then the maximum pressure at the base is given by:

(a) 2W/3B (b) 4W/3B
(c) 5W/2B (d) 8W/3B

Haryana PSC AE 2017

Ans. (d) :

$$P_{max} = \frac{2W}{3\left(\frac{B}{2} - e\right)}$$

masonry dam cannot take tension

$$e = \frac{B}{4}$$

$$P_{max} = \frac{2W}{3\left(\frac{B}{2} - \frac{B}{4}\right)} = \frac{8W}{3B}$$

1066. The capacity of a rectangular tank of size 3 mtr × 3 mtr × 1.5 mtr having free board of 0.3 mtr will be :

(a) 1350 ltr. (b) 9000 ltr.
(c) 10800 ltr. (d) 6000 ltr.

GPHC AE 2018

Ans : (c) Dimension of tank = 3 m × 3 m × 1.5 m
Free board = 0.3 m
Actual dimension = 3 × 3 × (1.5 – 0.3)
= 3 m × 3 m × 1.2 m
Volume = 3 m × 3 m × 1.2 m
= 10.8 m^3 (1 m^3 = 1000 l)
= 10800 l

1067. In case of RCC water tank the reinforcement bars provided in domes surrounding an opening an are called

(a) Meridional bars (b) Anchor bars
(c) Trimming bars (d) Distributor bars

WBPSC AE (MCD) 1998

Ans. (a) : RCC water tank the reinforcement bars provided in domes surrounding an opening an are called meridional bars

1068. The permissible stress for Fe 415 steel in tension used near water face for water tanks is

(a) 100 N/mm^2 (b) 125 N/mm^2
(c) 140 N/mm^2 (d) 150 N/mm^2

WBPSC AE (Common) 1998

Ans. (d) : Values of the permissible tension stress of steel (115 N/mm^2 for Fe 250 and 150 N/mm^2 for Fe415).

Search on Telegram @apna_pdf

10. Fundamentals of Limit State Designs

1069. In limit state design, the permissible bond stress in case of the deformed bars is more than that in plain bars by–

(a) 25% (b) 40%
(c) 60% (d) 70%

Gujarat PSC AE (N.W.R.) 2020

Ans. (c) : As per IS 456 : 2000 the value of bond stress for deformed bars may be increased by 60% of the values for plain mild steel bars in tension.
These values may be further increased by 25% for bars in compression.

1070. According to IS 456, when assessing the strength of a structure or structural member for the limit state of collapse, the value of partial safety factor for concrete (material) should be :

(a) 1.15 (b) 2.00
(c) 2.50 (d) 1.50
(e) 3.00

CGPSC AE 2014 Shift–I

Ans. (d) : As per IS 456 - 2000,
γ_{ms} for concrete = 1.5
γ_{ms} → partial safety factor for concrete.

1171. Partial safety factors considered for concrete and steel in the limit state design methods are :

(a) 1.5, 1.15 (b) 1.15, 1.5
(c) 1.5, 1.5 (d) 3.0, 1.5

HPPSC Poly. Lect. 2016

Ans : (a) Partial safety factors for materials. The strength of concrete in structure is take as (0.67 f_{ck})
For ultimate limit state for concrete is 1.5 and that steel is 1.15.

1072. In an unloaded structure, as erected, the tolerance limit of deviation of distance between adjacent columns after erection is

(a) 0.002h, h is the height of the column
(b) 5 mm
(c) 10 mm
(d) 0.0035 h
(e) 0.0025 h_e, h_e is the effective length of the column

CGPSC AE 2014 Shift–I

Ans. (b) :

Criterion deviation	**Permitted**
Deviation of distance between adjacent columns	± 5 mm

1073. As stated in IS 800, the limit state of strength design of steel includes all of the following except

(a) Brittle fracture
(b) Fatigue fracture
(c) Excessive deformation
(d) Repairable damage
(e) Rupture of a component in the structure

CGPSC AE 2014 Shift–I

Ans. (d) : As per IS : 800-2007, Limit state of strength include :
(a) Loss of equilibrium of structure as a whole or any of its part
(b) Loss of stability
(c) Failure by excessive deformation
(d) Fracture due to fatigue
(e) Brittle fracture

1074. While designing the footing according to the limit state method of design, the permissible bearing stress is taken as k times the characteristic strength of concrete, where in, k is :

(a) 0.25 (b) 0.35
(c) 0.45 (d) 0. 55
(e) 0.65

CGPSC AE 2014 Shift–I

Ans. (c) : The permissible bearing stresses on full area of concrete shall be taken as.
As per IS 456-2000 (Cl. 34.3)
$\tau_{br} = 0.45\ f_{ck}$ → in LSM
$\tau_{br} = 0.25\ f_{ck}$ → in WSM

1075. In limit state design approach, the spacing of main reinforcement primarily takes care of :

(a) Durability (b) Corrosion
(c) Deflection (d) Cracking
(e) Spalling

CGPSC AE 2014 Shift–I

Ans. (d) : There are many checks to be performed while designing a concrete member. Checks like stress in steel & crack width are directly dependent on the spacing of the bars.

1076. As per IS 456, using limit state designed method, in members where cracking in tensile zone is harmful because they are continuously exposed to ground water, the limiting crack width suggested is

(a) 0.3 mm (b) 0.15 mm
(c) 0.25 mm (d) 0.2 mm
(e) 0.02 mm

CGPSC AE 2014 Shift–I

Ans. (d) : The surface width of cracks should not in general exceeds 0.3 mm where cracking is not harmful to reinforcing steel, 0.2 mm where structure exposed to moisture weather, soil or ground water, 0.1 mm in aggressive environment.

1077. The redistribution of moments in a statically indeterminate beams is restricted to q percents as per the IS 456 limit state design method, where in, q is

(a) 10% (b) 70%
(c) 30% (d) 50%
(e) 40%

CGPSC AE 2014 Shift–I

Ans. (c) : The ultimate moment of resistance provided at any x-section of member after the redistribution should not be less than 70% of moment at that section.
∴ Maximum redistribution = 30%.

Search on Telegram @apna_pdf

1078. The maximum compressive strain according to limit state design as per IS 456, at the highly compressed extreme fiber in concrete subjected to axial compression and bending and when there is no tension on the section shall be

(a) 0.002
(b) 0.0035
(c) $0.002\text{-}0.75\varepsilon_{ext;}$ is the strain at the least compressed fiber
(d) $0.0035\text{-}0.75\varepsilon_{ext}$
(e) 0.0002

CGPSC AE 2014 Shift–I

Ans. (d) : IS code recommendation :
$\Rightarrow$ Maximum compression strain in column subjected to axial compression & bending.
$\Rightarrow$ 0.0035-0.75 × strain at least compressed fiber. If no tension in section.
$\Rightarrow$ 0.002 otherwise.

1079. The maximum strain in steel at failure in limit state method of design is considered as

(a) $\frac{f_y}{1.15E_s}+0.002$ (b) $\frac{f_y}{1.15E_s}+0.0035$
(c) $\frac{f_y}{1.5E_s}+0.0035$ (d) $\frac{1.5f_y}{E_s}+0.002$

APPSC Poly. Tech. Lect. 2020
Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (a) The maximum strain in tension reinforcement in the section of failure is to be not less than $0.002+\frac{f_y}{1.15E_s}$.

1080. For assessing the strength of a structure for limit state of collapse, the values of partial safety factors for concrete and steel are taken respectively as–

(a) 1.15 and 1.5 (b) 1. 5 and 1.15
(c) 1. 5 and 1.5 (d) 1.15 and 1.15

CIL MT 2017
ISRO Scientist/Engineer 2014
UKPSC AE 2013 Paper–I
ESE 1998

Ans : (b) For assessing the strength of a structure for limit state of collapse, the values of partial safety factor for concrete and steel are taken 1.5 and 1.15 respectively.

1081. In case of footing, the critical section for punching shear is considered at:

(a) The face of the column
(b) 'd' distance from the face of the column
(c) d/2 distance from the face of the column
(d) '2d' distance from the face of the column

APPSC Poly. Tech. Lect. 2020

Ans. (c) : In case of footing, the critical section for punching shear is considered at d/2 distance from the face of the column.

1082. Which of the following criteria is not considered under Limit State of Serviceability?

(a) Fatigue (b) Vibration Limit
(c) Durability consideration
(d) Fire Resistance

Gujarat PSC AE (N.W.R.) 2020

Ans. (a) : Fatigue is not considered under Limit State of Serviceability.

1083. Which one of the following is known as limit state of strength?

(a) Loss of equilibrium of structure
(b) Corrosion
(c) Excessive deflection
(d) Cracks

LMRC AM 2019

Ans. (a) Limit state method refers method which considered the ultimate strength of material at failure so when we talk about limit state of strength then it refers to loss of equilibrium of structure.

1084. The limiting value of the depth of neutral axis ($x_{u,max}$ /d) for Fe 500 grade steel bars as per IS 456-2000 is:

(a) 0.53 (b) 0.48
(c) 0.51 (d) 0.46

KPSC AE 2020

Ans. (d) : The limiting value of the depth of neutral axis ($x_{u,max}$ /d) for Fe 500 grade steel bars as per IS 456-2000 is 0.46

Steel grade	Fe 250	Fe 415	Fe 500
$K=\frac{X_{u\,lim}}{d}$	0.53	0.48	0.46

1085. For M15 grade concrete, shear reinforcement is necessary, if shear stress is more than :

(a) 0.5 N/mm^2 (b) 1 N/mm^2
(c) 1.5 N/mm^2 (d) 2 N/mm^2

Nagaland PSC CTSE 2017 Paper–I

Ans. (d) : As per IS 456–2000
max shear stress τ_{max} with shear reinforcement

	M15	M20	M25	M30	M35	M40 & Above
LSM	2.5	2.8	3.1	3.5	3.7	4.0
WSM	1.6	1.8	1.9	2.2	2.3	2.5

$\tau_v \not> \tau_{max}$

1086. The cube strength of the concrete used for the prestressed member should not be less than :

(a) 10 N/mm^2 (b) 25 N/mm^2
(c) 35 N/mm^2 (d) 50 N/mm^2

Nagaland PSC CTSE 2017 Paper–I

Ans. (c) : According to IS 456-2000,
The Minimum cube strength of concrete used for a prestressed member is, 350 kg/cm^2 or 35 N/mm^2

1087. The approx. ratio of the strength of cement concrete of 7 days to that of 28 days is :

(a) 0.65 (b) 0.85
(c) 1.0 (d) 1.15

Nagaland PSC CTSE 2017 Paper–I

Ans. (a) : The strength of concrete at any Age, can be expressed by the Relation,

$f_t=\frac{T}{a+bT}f_{28}$

The 7–days and 28 days strength are related as.

Search on Telegram @apna_pdf

$f_{28} = k_2 (f_7)^{k_1}$

A/C to IS code, the Ratio $\frac{f_7}{f_{28}}$ is approximately $\frac{2}{3}$

Grade of concrete	7 days strength (N/mm^2)	f_7/f_{28}
M10	7	0.7
M15	10	0.67
M20	13.5	0.675
M25	17.0	0.68
M30	20.0	0.67

1088. The approx. ratio of direct tensile strength to flexural strength is :
(a) 0.25 (b) 0.33
(c) 0.5 (d) 0.90

Nagaland PSC CTSE 2017 Paper–I

Ans. (c) : direct tensile strength $(f_{ct}) = 0.35\sqrt{f_{ck}}$

flexural strength $(f_{cr}) = 0.7\sqrt{f_{ck}}$

$$\frac{f_{ct}}{f_{cr}} = \frac{0.35\sqrt{f_{ck}}}{0.7\sqrt{f_{ck}}} = 0.5$$

1089. The limit state of serviceability of a steel structure includes all of the following except.
(a) Corrosion
(b) Crack due to fatigue
(c) Fire
(d) Fracture due to fatigue

(UP RVNL AE 2016)

Ans.: (d) According to I.S.-456−2000 limit states which must be examined in design are as follows–
(i) **Limit state of collapse**– It includes loss of equilibrium or failure due to flexure, compression, shear and torsion.
(ii) **Limit state of serviceability–** It involves (a) deformations that affect appearance, comfort of users, functioning of the structure.
(b) vibrations that cause discomfort
(c) damage that adversely affect appearance, durability or functioning of the structure.
Failure caused by fatigue is case of limit state of collapse.

1090. The value of limiting moment of resistance of a RC beam for M25 grade of concrete and Fe 500 grade of steel is given by (Notational have their usual meaning) –
(a) $3.33\ bd^2$ (b) $3.38\ bd^2$
(c) $3.35\ bd^2$ (d) $3.44\ bd^2$

UKPSC AE 2013 Paper–I

Ans : (a) For Fe 500, moment of resistance is Mr = $0.133\ \sigma_{ck}\ bd^2$
$\sigma_{ck} = 25$ for M 25
Mr = $0.133 \times 25\ bd^2 = 3.33\ bd^2$

1091. In limit state method of design for RCC flexural members, the centre of gravity of the compressive force acting on the section from the top most fiber of concrete is a distance of–
(a) 0.30 of the depth of neutral axis
(b) 0.57 of the depth of neutral axis
(c) 0.42 of the depth of neutral axis
(d) None of the above

UKPSC AE 2013 Paper–I

Ans : (c) The centre of gravity of compressive force acting on the section from the top most fiber of concrete at a distance of 0.42 of the depth of neutral axis.

1092. In limit state design of RC, the strains in tension reinforcement should not exceed
(a) $0.87\frac{f_y}{E_s}$ (b) 0.002
(c) $0.87\frac{f_y}{E_s} + 0.002$ (d) 0.0035

(UKPSC AE 2012 Paper–I)
(UPPSC State Eng A.E.-2008)

Ans : (c) The maximum strain in tension reinforcement in the section of failure is be not less than

$$\varepsilon_{su} = \left(\frac{f_y}{1.15.E_s}\right) + 0.002$$

$$\varepsilon_{su} = \frac{0.87 f_y}{E_s} + 0.002$$

1093. In limit state design of reinforced concrete, deflection is computed by using :
(a) initial tangent modulus
(b) secant modulus
(c) tangent modulus
(d) short and long term values of Young's modulus

(UKPSC AE (Paper-I) 2007)

Ans : (d) In limit state design of concrete, deflection is computed by using short and long term values of Young's modulus.

1094. The maximum depth of neutral axis in RC beam for Fe 415 grade of steel is–
(a) 0.53d (b) 0.48d
(c) 0.67d (d) 0.46d

(UK Combined AE Paper I 2012
UTTRAKHAND AE 2013)

Ans : (b) As per IS 456:2000 maximum depth of neutral axis is given–


σ_y (N/mm^2)	x_m
250	0.53 d
415	0.48 d
500	0.46 d
550	0.44 d

1095. In limit State Method of design of RCC flexural members, the centre of gravity of the compressive forces acting on the section from the top most fiber of concrete is at a distance of
(a) 0.57 of the depth of neutral axis
(b) 0.36 of the depth of neutral axis
(c) 0.42 of the depth of neutral axis
(d) None of theses

RPSC ACF - 2011

Search on Telegram @apna_pdf

Ans : (c) Centre of gravity for compressive forces from top fiber is at a distance of 0.42 of depth of neutral axis–



1096. As per IS 456 : 2000, the final deflection due to all loads including the effect of temperature, creep and shrinkage should not normally exceed:

(a) $\frac{\text{span}}{250}$ (b) $\frac{\text{span}}{350}$

(c) $\frac{\text{span}}{400}$ (d) $\frac{\text{span}}{450}$

[UPPSC State Eng. A.E. 2007(I)]

Ans : (a) Maximum permissible deflection

(i) Final deflection including all loads, effect of creep, temperature and shrinkage should not be greater than $l/250$.

(ii) Deflection including creep, temperature and shrinkage after construction of partition wall and floor finish should not be greater.

$$\text{than} \begin{cases} \text{span}/350 \text{ mm} \\ 20 \text{ mm} \end{cases} \text{ which ever is less}$$


1097. In an under-reinforced concrete section, the depth of the neutral axis is.....the limiting depth of neutral axis.

(a) less than (b) more than

(c) equal to (d) none of these

[UPPSC State Eng. A.E. 2011]

Ans : (a)



1098. To control the deflection limit state, the basic values of span to effective depth ratio (As per IS 456-2000) for simply supported and continuous beams are kept as :

(a) 20 and 26 respectively

(b) 7 and 20 respectively

(c) 26 and 20 respectively

(d) 20 and 7 respectively

RPSC POLY. TECH. LECT. 2014

Ans : (a) To control deflection limit state, the basic values of span to effective depth ratio is given–

Cantilever beam	7
simply supported beam	20
continuous beam	26
simply supported slab	35
continuous slab	40

1099. In limit state design of reinforced concrete structure the value of limiting neutral axis depth factor (k) depends upon

(a) Grade of concrete only

(b) Grade of steel only

(c) Grade of concrete and steel both

(d) None of the these

RPSC POLY. TECH. LECT. 2014

Ans : (b) Limiting neutral axis depth factor can be found by following formulae–

$$\frac{x_{ulim}}{d} = \frac{700}{1100 + 0.87 f_y}$$

It is clear from formula that limiting neutral axis depth factor depends only upon grade of steel.

1100. In the limit state design of concrete structure, the strain distribution is assumed to be

(a) Linear


(b) Non linear

(c) Parabolic

(d) Parabolic and rectangular

GPSC AE Class (1&2) Paper - 2 2017
RPSC POLY. TECH. LECT. 2014

Ans : (a) In the limit state design of concrete structure the strain distribution is assumed to be linear.



1101. A simply supported beam is required to carry a load of 23 kN/m including self weight over an effective span of 6.0m. This beam shall be designed for a factored bending moment in limit state method of:

(a) 103.500 kN-m (b) 119.025 kN

(c) 155.250 kN-m (d) 187.273 kN-m

[UPPSC State Eng. A.E. 2007(I)]

Ans : (c) Given

$w = 23$ kN/m

$l_{eff} = 6.0$ m

factored load $= 1.5 \times w = 1.5 \times 23$

$= 34.5$ kN/m

$$M_{design} = M_{max} = \frac{w l_{eff}^2}{8}$$

$$M_{design} = \frac{34.5 \times 6^2}{8}$$

$M_{design} = 155.250$ kN-m

1102. In limit state design, permissible bond stress in the case of deformed bars is more than that in plain bars by

(a) 60% (b) 50%

(c) 40% (d) 25%

[UPPSC State Eng. A.E. 2003]

OR

Search on Telegram @apna_pdf

In tension, for deformed bars designed bond stress in limit state method is increased as below for plain bars

(a) 60% (b) 40%
(c) 25% (d) 75%

[UPPSC State Eng. A.E. 2011]

Ans : (a) $\tau_{bd} = \dfrac{V}{\sum P.j}$

$\Sigma P.j$ = sum of perimeter of diameter of reinforcement $(n\pi\phi)$

j = coefficient of lever arm.

Maximum Permissible values

Steel in Tension	WSM (N/mm^2)	LSM (N/mm^2)
M 15	0.6	–
M 20	0.8	1.2
M 25	0.9	1.4
M 30	1.0	1.5
M 35	1.1	1.7
M 40	1.2	1.9

For high yield strength deformed bar (HYSD) and CTD bars, above value in tension is increased by 60%

Note : If bars are in compression, the value should be further increased bond strength by 25%.

Example : τ_{bd} for Fe 415 steel when bars in compression for M 25 concrete in LSM is

$\tau_{bd} = 1.4 \times 1.6$ (due to HYSD) $\times$ 1.25 (due to compression)

$\tau_{bd} = 1.28 N/mm^2$

1103. In the limit state design of concrete section the limiting value of the depth of the neutral axis $X_{u\,(max)}/d$ for steel grade Fe 415 is :

(a) 0.53 (b) 0.48
(c) 0.46 (d) 0.42

(RPSC LECTURE - 2011)

Ans : (b) As per IS 456:2000 maximum depth of neutral axis is given–

σ_y N/mm^2	x_m
250	0.53 d
415	0.48 d
500	0.46 d
550	0.44 d

1104. In the limit state design method of concrete structures, the recommended partial safety factor (V_m) for steel according to IS 456 : 2000 is

(a) 1.5 (b) 1.15
(c) 1.00 (d) 0.87

[UPPSC State Eng. A.E. 2007 (I)]

Ans : (b) According to IS 456-2000–
Partial safety factor for concrete is 1.5
partial safety factor for steel is 1.15

1105. The design stress for mild steel in limit state design is taken as:

(a) $1.5f_y$ (b) $1.15f_y$
(c) f_y (d) $0.87f_y$

[UPPSC State Eng. A.E. 2007(I)]

Ans : (d) For design purpose a partial factor safety of 1.15 shall be used in steel.

If f_y is yield strength of mild steel then

$$\text{design stress} = \frac{f_y}{\text{partial FOS}}$$

$$f_d = \frac{f_y}{1.15} = 0.87\, f_y$$

1106. As per IS 456 :2000, the maximum compressive stress in concrete for design purpose is

(a) $0.37f_{ck}$ (b) $0.416\, f_{ck}$
(c) $0.446\, f_{ck}$ (d) $0.67\, f_{ck}$

[UPPSC Civil Eng. A.E. 2004 (I)]

Ans : (c) For design purpose, compressive strength of concrete shall be assumed to 0.67 times f_{ck} . The partial factor of safety for concrete is 1.5.

$$\therefore \text{ Design stress} = \frac{0.67 f_{ck}}{\text{partial FOS}}$$

$$= \frac{0.67\, f_{ck}}{1.5} = 0.446\, f_{ck}$$

1107. According to IS : 456, the partial safety factor for concrete is taken as

(a) 0.87 (b) 1.15
(c) 1.50 (d) 3.00

[GPSC AE Class (1&2) Paper - 2 2017]
[UPPSC State Eng. A.E. 2003]

Ans : (c) As per IS 456 : 2000, the recommended partial factor of safety are :

For concrete = 1.5
For steel = 1.15

Note : In limit state method of design two factors of safety are used, one to account for uncertainty in material properties and other for uncertainty in loading. Hence the factor are called factor of safety.

1108. Limit state of serviceability for deflection including the effects due to creep, shrinkage and temperature occurring after erection of partitions and application of finishes as applicable to floors and roofs is restricted to

(a) $\dfrac{\text{Span}}{150}$ (b) $\dfrac{\text{Span}}{200}$
(c) $\dfrac{\text{Span}}{250}$ (d) $\dfrac{\text{Span}}{350}$

[UPPSC State Eng. A.E. 2003]
[ESE 1995]

Ans : (d) The deflection shall generally be limited to the following

(i) The final deflection due to all loads including the effects of temperature, creep and shrinkage and measured from the as-cast level of the support of floors, roof and all other horizontal members shall not normally exceed span/250.

The deflection including the effects of temperature, creep and shrinkage occurring after the erection of partitions and the application of finishes should not normally exceed span/350 or 20 mm whichever is less.

Search on Telegram @apna_pdf

1109. The target mean strength of concrete mix should be:

(a) The characteristic strength+1.65 times standard deviation.
(b) The characteristic strength+1.45 times standard deviation.
(c) The ultimate strength+1.65times standard deviation.
(d) The ultimate strength+1.45 times standard deviation.

UPPSC AE 12.04.2016 Paper–I

Ans : **(a)** The target mean strength of concrete mix should be the characteristic strength + 1.65 times standard deviation.
Note: Characteristic strength of material
The strength of material below which not more than 5% of the test results are expected to fail, is known as the characteristic strength of the material and denoted by f_{ck} for concrete.

1110. The limiting compressive strain of concrete in case of bending is:

(a) 0.02 (b) 0.0025
(c) 0.003 (d) 0.0035

APPSC Poly. Tech. Lect. 2020
ESE 2011

Ans. (d) : The Maximum strain in concrete at outer most compression fiber is taken as 0.0035 in bending.

1111. Load factor in plastic design depends upon

(a) nature of loading
(b) support conditions
(c) geometrical shape
(d) All of the above

BPSC AE 2012 Paper–V

Ans : **(b)** Load factor in plastic design depends upon support conditions.

1112. For limit state of collapse : flexure, the maximum strain in concrete at the outermost compression fiber is taken equal to

(a) 0.002 (b) 0.02
(c) 0.0035 (d) 0.035

ISRO Scientist/Engineer 2014
BPSC AE 2012 Paper–V


OR

The maximum strain in concrete in compression in bending is taken as

(a) 0.003 (b) 0.002
(c) 0.0035 (d) $\frac{f_{ck}}{E_C}$

GPSC AE Class (1&2) Paper-2 2017
GPSC R&B AE 2016
GPSC Assistant Prof. 2016
UPPCL AE 2015
TNPSC AE 2015, 2012
APPSC AEE 2012
[UPPSC State Eng. A.E. 2008]
ESE 1996

Ans : **(c)** The maximum strain in concrete in compression in bending is taken as 0.0035 where as maximum strain in tension reinforcement is taken as $\frac{f_y}{1.15E_s}+0.002$.



So, By IS: 456-2000
Maximum strain in concrete = 0.0035 and that of in steel is $0.002+\frac{f_y}{1.15E_s}$

1113. When assessing the strength of structural member for the limit state of collapse, the values of partial safety factor γ_m for material strength should be

(UPPSC CIVIL ENG. (I) 2013)
(BPSC AE Paper V 2006)

Or

In limit state design of reinforced concrete structures the partial safety factors for strength of concrete and steel taken as

(a) 1.5 for concrete and 1.15 for steel
(b) 1.15 for concrete and 1.5 for steel
(c) 1.2 for both concrete and steel
(d) 1.5 for both concrete and steel

RPSC VPITI - 2012
UTRRAKHAND A.E. - 2013

Or

In the limit state design method, the material safety factor for steel and concrete are taken as

(a) 1.15 for steel and 1.5 for concrete
(b) 1.15 for both steel and concrete
(c) 1.5 for both steel and concrete
(d) 1.5 for steel and 1.15 for concrete

Rajasthan JEn (Degree) 2016
(JPSC Combined AE Paper V 2013)

Ans : (a) Partial safety factor for concrete is 1.5
Partial safety factor for steel is 1.15

1114. Maximum strain at the level of compression steel for a doubly reinforced rectangular section having effective depth d, effective cover to compression steel as d' and neutral axis depth from compression face as x_u will be

(a) 0.035 (b) $0.0035\frac{d'}{x_u}$
(c) $0.0035\left(1-\frac{d'}{x_u}\right)$ (d) 0.002

(JPSC Combined AE Paper V 2013)

Search on Telegram @apna_pdf

Ans : **(c)** Maximum strain at the level of compression steel for a doubly reinforced rectangular section is given as $0.0035\left(1-\frac{d'}{x_u}\right)$;
Where d' = is effective depth for compression steel
x_u = is depth of neutral axis.

1115. In singly reinforced sections, when the section is under-reinforced, the relation between depth of neutral axis (x_u) and the limiting value of depth of neutral axis ($x_{u'}$ max) is-
(a) $x_u = x_{u'}$ max
(b) $x_u < x_{u'}$ max
(c) $x_u > x_{u'}$ max
(d) None of the above

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (b) : For under reinforced section,
$$x_u < x_{u\,max}$$
For balanced section,
$$x_u = x_{u\,max}$$
For over reinforced section,
$$x_u > x_{u\,max}$$

1116. The limit state of collapse for prestressed concrete is-
(a) Limit state of collapse : Deflection
(b) Limit state of collapse : Cracking
(c) Limit state of collapse : Maximum compression
(d) None of the above

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (d) Limit state of collapse for prestressed concrete is when tension cracks develop in the concrete.

1117. The designed prestressed concrete element should satisfy the limits specified for permissible stresses at transfer stage as well as service condition. The prestressing force '*P*' and eccentricity '*e*' evaluated from those limits are-
(a) Maximum value of '*P*' and maximum value of e
(b) Maximum value of '*P*' and minimum value of e
(c) Minimum value of '*P*' and maximum value of e
(d) Minimum value of '*P*' and minimum value of e


Maharashtra PSC (Mains) 2017 Paper–I

Ans. (c) : The design of the prestressed member ensures that there is no generation of tension any where in the beam at any stage. For this we analyze the beam at transfer stage as well as service conditions. For most economical design, least value of force is obtained and for that maximum value of 'e' is obtained.

1118. The maximum strain in tension reinforcement (having yield stress f_y and elasticity modulus E_s) in a flexural member shall not be less than :
(a) $\frac{f_y}{1.15E_s}$ (b) $\frac{f_y}{1.5E_s}$
(c) $\frac{f_y}{1.15E_s}+0.002$ (d) $\frac{f_y}{1.5E_s}+0.002$

RPSC AE 2018
Rajasthan JEN (Degree) Shift - II 2016

Ans. (c)



1119. In limit state design, the limiting depth of neutral axis for Fe-500 for beam having effective depth "d" is :
(a) 0.43 d (b) 0.48 d
(c) 0.46 d (d) 0.53 d

JPSC AE (Pre) 2019

Ans. (c) :
For Fe – 250, $X_{u,lim}$ = 0.53d
For Fe – 415, $X_{u,lim}$ = 0.48d
For Fe – 500, $X_{u,lim}$ = 0.46d

1120. The probability of failure implied in the limit state design is of the order of :
(a) 10^{-3} (b) 10^{-2}
(c) 10^{-5} (d) 10^{-7}

JPSC AE (Pre) 2019

Ans. (b) : The structure may fail when
– The load exceeds the design load,
– The strength is less than the characteristic strength, and
– Both the load exceeds the design load and strength is less than the characteristic length.
Since, the probability of load exceeding design load = 5%.
The probability of strength is = 5% the probability of failure is = 0.05 × 0.95 + 0.05 × 0.95 + 0.05 × 0.05 = 0.0975 thus the order of failure is 10^{-2}.

1121. A reinforced concrete beam is subjected to 5 kNm bending moment due to dead load and 25 kNm bending moment due to live load. What should be the design bending moment for limit state of collapse?
(a) 30.0 kN.m (b) 34.5 kN.m
(c) 45.0 kN.m (d) 50.0 kN.m

GPSC AE Class (1&2) Paper - 2 2017

Ans. (c) : In LSM, we go for factored value i.e., maximum loading and bending so that structure strength would be used and safe before ultimate point.
BMD ⇒ B.M. due dead load + B.M. due to LL
= 20 + 10 = 30
form factored BM = 1.5 × B.M.D.
= 1.5×30 = 45 kN-m

1122. In limit state method of design, the value of permissible shear stress in concrete when shear reinforcement is not provided is :
(a) $0.16(f_{ck})^{1/2}$ (b) $0.25(f_{ck})^{1/2}$
(c) $0.34(f_{ck})^{1/2}$ (d) $0.48(f_{ck})^{1/2}$

GPSC AE Class (1&2) Paper - 2 2017

Search on Telegram @apna_pdf

Ans. (b) The limit state design, the value of permissible shear stress in concrete is $0.25\sqrt{f_{ck}}$, when shear reinforcement is not provided.

1123. In limit state approach, the spacing of main reinforcement primarily controls :

(a) Collapse (b) Cracking
(c) Deflection (d) Durability

GPSC AE Class (1&2) Paper - 2 2017
ESE 1996

Ans. (b) : The spacing which we provide in the beam/slab in reinforcement as according to code the gap between two reinforcement bar more than 3×effective depth (d) and/or 300mm to control flexural crack.

1124. For limit state design of RC beam consider following :

(i) $\left[\frac{f_y}{f_{ck}} = 0.36\right]$

(ii) $\left[\frac{A_{st}}{bD} = 4\%\right]$

(iii) $\left[\frac{x_{u\,max}}{d} = 0.48\right]$

Which one of the design criteria shall be applicable ?

(a) Balanced section
(b) Under reinforced section
(c) Over-reinforced section
(d) both balanced and over reinforced sections

Rajasthan JEn (Degree) 2016

Ans. (a) For Fe – 415

$\left[\frac{x_{u\,max}}{d} = 0.48\right]$


Hence balanced section is applicable.

1125. The limiting tensile strain in reinforced concrete is

(a) 0.002 (b) 0.0035
(c) $0.002 + f_y/(1.15\,E_s)$ (d) 0.002 + 0.0035

GPSC AE (CLASS 1 & 2) 2019

Ans : (c) :




1126. Design compressive stress in concrete, for collapse in flexure, is taken as

(a) 0.77 f_{ck} (b) 0.67 f_{ck}
(c) 0.55 f_{ck} (d) 0.45 f_{ck}

GPSC AE (CLASS 1 & 2) 2019

Ans : (d) :



1127. Tensile stresses in concrete arise on account of the following:

(i) Direct tension
(ii) Flexural tension
(iii) Diagonal tension (shear)
(iv) Temperature and shrinkage

(a) (i) only (b) (i) and (ii)
(c) (ii), (iii) and (iv) (d) (i), (ii), (iii) and (iv)

GPSC AE (CLASS 1 & 2) 2019

Ans : (d) : Tensile stress arise from all

- Flexural tension $0.7\sqrt{f_{ck}}$

1128. The partial safety factor for strength of concrete for service ability limit state is:

(a) 1.00 (b) 1.10
(c) 1.15 (d) 1.25

Kerala PSC AE 2015

Ans. (a) : Partial safety factor of concrete for
(i) Serviceability limit state - 1.0
(ii) Ultimate limit state - 1.5

For WSM-
FOS for concrete = 3
FOS for steel = 1.78

For LSM-
Partial FOS for concrete = 1.5
Partial FOS for steel = 1.15

1129. The permissible stress in axial tension in steel member on the net effective area of the section shall not exceed the following value :
(Note : f_y is the yield stress)

(a) 0.80 f_y (b) 0.75 f_y
(c) 0.60 f_y (d) 0.50 f_y

GPSC AE Class (1&2) Paper - 2 2017

Ans. (c) The permissible stress in axial tension in steel member on the net effective area of the section shall not exceed 0.60 f_y.

1130. In limit state method of design approach, spacing of main reinforcement primarily controls:

(a) collapse (b) cracking
(c) deflection (d) Durability

ESE 1996

Ans. (b) : The code specified minimum and maximum limits for the spacing between parallel reinforcing bars in a layer. The minimum limits are necessary to ensure that the concrete can be placed easily in between and ground the bars during the placement of area specified for bars in tension for the purpose of controlling crack-widths and improving bond.

1131. Creep Strain is

(a) caused due to live load only
(b) caused due to cyclic load only

Search on Telegram @apna_pdf

(c) caused due to dead load only
(d) Independent of load

ISRO Scientist/Engineer 2014

Ans : **(c)** A concrete element when kept under sustained load presents progressive strain over time, associated to the creep.

1132. For design of Flexure members, the strain in the reinforcing bars under tension at ultimate state as per IS 456 - 2000 shall not be less than

(a) $f_y/1.15E$ (b) $f_y/1.15E_S + 0.002$
(c) f_y/E_S (d) $f_y/E_S + 0.002$

ISRO Scientist/Engineer 2013

Ans : (b)

- According to IS 456 : 2000 the maximum strain in the tension reinforcement in the section at failure shall not be less than

$$\left[\frac{f_y}{1.15E_S} + 0.002\right]$$

f_y = characteristic strength of steel.
E_S = Modulus of elasticity of steel.

- Minimum strain requirement at collapse ensure that the design stress in tension steel at collapse will always be $f_{yd} = (0.87f_y)$.
Hence there is no sudden collapse.

1133. As per IS 456-2000; in the limit state design of a flexural member, the strain in reinforcing bar under tension at ultimate state should not be less than

(a) $\frac{f_v}{E_x}$ (b) $\frac{f_v}{E_x} + 0.002$
(c) $\frac{f_v}{1.15E_x}$ (d) $\frac{f_v}{1.15E_x} + 0.002$

ISRO Scientist/Engineer 2014

Ans : (d)

1134. According to the concept of Limit State Design as per IS : 456–2000, the probability of failure of a structure is

(a) 0.09 to 0.10 (b) 0.9 to 0.01
(c) 0.10 to 0.20 (d) 0.01 to 0.02

APTRANSCO 2017

Ans : (a)
Probability of not failing under load = 95% = 0.95
probability of not failing under material strength criteria = 95% = 0.95
⇒ Overall probability of not failing is
$= 0.95 \times 0.95 = 0.9025$
Therefore overall probability of failure of a structure as per I.S. 456-2000 = 1 – 0.9025 = 0.0975

1135. Which one of the following statements is correct?

(a) Maximum longitudinal reinforcement in an axially loaded short column is 6% of gross sectional area.
(b) Columns with circular section are provided transverse reinforcement helical type only.
(c) Spacing of lateral ties can not be more than 16 times the diameter of the bar.
(d) Longitudinal reinforcement bar need not be contact with lateral ties.

OPSC AEE 2019 Paper–I

Ans. (a) : Maximum longitudinal reinforcement to an axially loaded short column is 6% of gross cross section area.

1136. In the limit state method of design, the failure criterion for reinforced concrete beams and columns is :

(a) Maximum principal theory
(b) Maximum principal strain theory
(c) Maximum shear theory
(d) Maximum strain energy theory

OPSC AEE 2019 Paper–I

Ans. (b)
⇒ Maximum Principal Strain Theory
Or
Saint Venant's Theory
According to this theory, the maximum principal strain in the complex stress system must be less than the elastic limit in simple tension if there is to be no failure.
⇒ Maximum Shear Stress Theory
The maximum shear stress theory states that failure occurs when the maximum shear stress from a combination of principal stresses equals or exceeds the value obtained for the shear stress at yielding in the uniaxial tensile test
⇒ Maximum strain energy Theory (Beltrami's theory) failure would occur when the total strain energy absorbed at a point per unit volume exceeds the strain energy absorbed per unit volume at the tensile yield point.

1137. In limit state design of concrete for flexure, the area of stress block diagram is taken as where f_{ck} is characteristic compressive strength of concrete and X_u is depth of neutral axis from top of the section :

(a) $0.36\ f_{ck}\ X_u$ (b) $0.42\ f_{ck}\ X_u$
(c) $0.446\ f_{ck}\ X_u$ (d) $0.56\ f_{ck}\ X_u$

OPSC AEE 2019 Paper–I

Ans. (a) : $0.36\ f_{ck}\ X_u$

1138. In limit state method, balanced design of a reinforced concrete beam gives :

(a) Smallest concrete section and maximum area of reinforcement.
(b) Largest concrete section and maximum area of reinforcement.
(c) Smallest concrete section and minimum area of reinforcement.
(d) Largest concrete section and minimum area of reinforcement.

OPSC AEE 2019 Paper–I

Ans. (a) : In limit state method, balanced design of a reinforced concrete beam gives, smallest concrete section and maximum area of reinforcement.

Search on Telegram @apna_pdf

1139. A beam of size 250 mm width and 460 mm effective depth is subjected to limit state moment of 146 kNm. If M 20 grade concrete and Fe 415 steel are used, the area of steel required will be :

(a) 435 mm^2 (b) 935 mm^2
(c) 1100 mm^2 (d) 1235 mm^2

ESE 2020

Ans. (c) : Given,
Width (b) = 250 mm, effective depth (d) = 460 mm
M_u = 146 kN-m
Limiting moment of resistance of singly reinforced beam,

$$M_{u,\,lim} = 0.138\, f_{ck}\, bd^2 \quad \text{..... (for Fe 415)}$$
$$= 0.138 \times 20 \times 250 \times 460^2$$
$$\boxed{M_{u,lim} = 146\ kN-m}$$

$\because\ M_u = M_{u,lim}$

$\therefore$ The section is balanced section.
Now, we know that,

$$A_{st} = \frac{f_{ck}}{2f_y}\left[1-\sqrt{1-\frac{4.6M_u}{f_{ck}bd^2}}\right]bd$$

$$= \frac{20}{2\times 415}\left[1-\sqrt{1-\frac{4.6\times 146\times 10^6}{20\times 250\times 460^2}}\right]\times 250\times 460$$

A_{st} = 1096.43 mm^2
or, $\boxed{A_{st} \simeq 1100 mm^2}$

1140. Which of the following are the general design requirements of retaining wall ?

1. **The factor of safety against sliding should be at least 1.5**
2. **The factor of safety against over-turning should be at least 2.0**
3. **The bearing pressure at toe should be less than the bearing capacity of the soil**
4. **The length of retaining wall to be cast in one go should not exceed 10 m otherwise cracks may develop**

(a) 1, 2 and 3 only (b) 1, 3 and 4 only
(c) 1, 2 and 4 only (d) 2, 3 and 4 only

ESE 2020

Ans. (a) : Retaining walls shall be designed, using following criteria–
(i) Factor of safety against sliding should be atleast 1.5.
(ii) Factor of safety against overturning should be at least 2.0.
(iii) The bearing pressure at toe should be less than the bearing capacity of soil.

1141. As per IS-456 : 2000, the value of maximum compression strain in concrete in axial compression for limit state of collapse is :

(a) 0.001 (b) 0.002
(c) 0.003 (d) 0.004

ESE 2020

Ans. (b) : Assumptions for limit state of collapse–
(1) Tensile strength of concrete is ignored.
(2) The maximum compressive stress of concrete is 0.45 f_{ck}.
(3) The maximum compressive strain in concrete due to axial compression should be 0.002.
(4) The maximum compressive strain in concrete subjected to axial compression and bending and when there is no tension on the section shall be 0.0035–0.75 × strain at the least compressed extreme fibre.

1142. Which of the following codes is relevant to fire safety?

(a) IS 456 – 2000 (b) IS 1256 – 1967
(c) IS 800 – 1950 (d) None of the above

Maharashtra PSC Mains 2018 Paper-1

Ans. (b) : IS 800 – 1950 : Code of practice for general steel construction.
(2) IS 1256 –1967 : Code of practice for building by laws.
(3) IS 456 – 2000 : Code of practice for reinforced cement concrete.

1143. The partial safety factors for material strength are

(a) 1.15 for concrete and 1.5 for steel
(b) 1.5 for concrete and 1.15 for steel
(c) 1.5 for both concrete and steel
(d) 1.15 for both concrete and steel

Maharashtra PSC Mains 2018 Paper-1

Ans. (b) : The partial safety factors for concrete = 1.5
The partial safety factors for steel = 1.15

1144. What are the different limit states of design as per IS 456 : 2000?

1. Limit state of failure
2. Limit state of damage
3. Limit state of collapse
4. Limit state of serviceability

Answer Options

(a) 1 and 4 (b) 2 and 3
(c) 3 and 4 (d) 1 and 2

Maharashtra PSC Mains 2018 Paper-1

Ans. (c) : There are the two types of limit states of design as per IS 456 : 2000 :
1. Limit state of collapse
2. Limit state of serviceability

1145. In limit state method a balance beam section is defined as one in which

(a) Both steel and concrete reach their maximum permissible stress simultaneously
(b) The stress in steel and concrete is same
(c) Both steel and concrete reach their maximum permissible strain simultaneously
(d) The beam section balances the load perfectly

GPSC Poly. Tech. Lect. 2016

Ans. (c) : In limit state method a balance beam section is defined as a steel and concrete reach their maximum permissible strain simultaneously.
Plane section normal to the axis remain plane after bending.

1146. The ratio of permissible shear stress in limit state method of design and working stress method of design is

(a) 25:16 (b) 3:5
(c) 16:25 (d) 4:5

GOA PSC Assistant Prof. 2020

Search on Telegram @apna_pdf


Ans. (a) : The ratio of permissible shear stress in limit state method of design and working stress method as per IS 456-2000, for M15 it is 2.5:1.6
i.e. = 25:16.

1147. The maximum strain at failure in tension steel having yield stress f_y and young's modulus E_s as per limit state method is

(a) $0.2+f_y/(1.5E_s)$ (b) $0.002+f_y/(1.5E_s)$
(c) $0.002+f_y/(1.15E_s)$ (d) $0.2+f_y/(1.15E_s)$

Rajasthan AE Nagar Nigam Shift-3, 2016

Ans. (c) : The maximum strain at failure in tension steel having yield stress f_y and young's modulus



1148. Partial safety factor for steel and concrete according to IS 456-2000 for the limit state of collapse is

(a) 1.15 & 1.5 (b) 1.5 & 1.8
(c) 1.8 & 1.5 (d) 2.5 & 0.15

Rajasthan AE Nagar Nigam Shift-3, 2016

Ans. (a) : Partial safety factor for steel = 1.15
Partial safety factor for concrete = 1.5

1149. As per IS:456-2000, expansion joint is to be provided in structure, when the length of structure exceeds

(a) 35 m (b) 45 m
(c) 55 m (d) 65 m

Sikkim PSC AE 2017

Ans. (b) : As per IS:456-2000, structures exceeding 45m in length are designed with one or more expansion joint.

1150. The strength of a concrete cylinder is less than the strength of a concrete cube. This is due to

(a) The difference in the slenderness ratio of the specimen
(b) The difference in the shape of the cross section of the specimen
(c) The difference area of cross section of the cylinder and cube
(d) The difference in the method of testing both types of specimen

Sikkim PSC AE 2017

Ans. (c) : Cube strength of concrete is nearly 1.25 times the cylindrical strength, because the contact area of a standard cube mould with the upper plates in the testing machine is more which results in more confinement.

1151. Lateral torsional buckling will occur in :

(a) Beams whose compression flange is embedded in the slab
(b) Beams which are laterally restricted by horizontal bracings
(c) Beams which are laterally unsupported
(d) Beams whose web are restrained by lateral beams

TRB Poly. Lect. Tech. 2017

Ans. (c) : Lateral torsional buckling will occur in beams which are laterally unsupported.

1152. The factored moment of resistance of a singly reinforced concrete beam of width 220 mm is 145 kN-m. The effective depth of beam is nearly equal to (Use M 20 grade of concrete and Fe 415 grade of steel)

(a) 720 mm (b) 488 mm
(c) 640 mm (d) 380 mm

UJVNL AE 2016

Ans. (b) : As we know that for balanced section and Fe 415 grade of steel.
Moment of resistance = $0.138\ f_{ck}\ bd^2$
$\Rightarrow 0.138\ f_{ck}\ bd^2 = 145$ kNm
$0.138 \times 20 \times 220 \times d^2 = 145 \times 10^6$

$$d^2 = \frac{145\times10^6}{0.138\times20\times220}$$

$d = 488.67$ mm
$d \simeq 488$ mm (nearest option)

1153. For ultimate load design of prestressed concrete girders used for bridges, combination of load factors used is (here L.L. and D.L. are live load and dead load respectively)

(a) 1.5 D.L. + 2.5 L.L. (b) 1.0 D.L. + 2.0 L.L.
(c) 1.0 D.L. + 2.5 L.L. (d) 2.0 D.L. + 2.0 L.L.

APPSC AEE 2012

Ans. (a) : For ultimate load design of prestressed concrete girder used for bridges, combination of load factors.
1.5 D.L. + 2.5 L.L. As per IS 456 – 2000

1154. In the limit state design of concrete structures, the strain distribution is assumed to be

(a) linear (b) non-linear
(c) parabolic (d) rectangular

APPSC AEE 2012

Ans. (a) : In LSM, it is assumed that plane section remain plane before and after bending i.e. strain variation is linear.

1155. The partial factor of safety for steel in limit state design in the design of Reinforced Concrete Structure is :

(a) 1.75 (b) 1.15
(c) 1.65 (d) 1.5

SJVNL ET 2019

Ans. (b) : The partial factor of safety for steel in limit state design in the design of Reinforced Concrete Structure is 1.15.


1156. The shape of the stress-strain curve of concrete up to a strain of 0.002 is.....

(a) Linear (b) Hyperbolic
(c) Semi circular (d) Parabolic

SJVNL ET 2019

Search on Telegram @apna_pdf

Ans. (d) :



So, the shape of stress - strain curve of concrete up to a strain of 0.002 is parabolic and after that rectangular.

1157. In limit state design, when Fe 415 steel is used, the limiting value of the depth of the neutral axis is

(a) 0.446 d (b) 0.46 d
(c) 0.48 d (d) 0.53 d

BPSC Poly. Tech. Lect. 2016

Ans. (c) : As per IS 415:2000 limit state method
For Fe 415 → x_{ulim} = 0.48 d
For Fe 500 → x_{ulim} = 0.46 d
For Fe 250 → x_{ulim} = 0.53 d

1158. The moment of resistance of a balanced section in limit state design is

(a) 0.25 $f_{ck}bd^2$ (b) 0.35 $f_{ck}bd^2$
(c) 0.5 $f_{ck}bd^2$ (d) 0.15 $f_{ck}bd^2$

BPSC Poly. Tech. Lect. 2016

Ans. (b) : Moment of resistance for balance section in limit state method.

$MOR_{balanced} = 0.36\ f_{ck}\ bd^2$

1159. In limit state design, permissible bond stress in case of deformed bars is more than of plain bars by P%, where P is :

(a) 60 (b) 25
(c) 40 (d) 50

UPPCL AE 2015

Ans. (a) : According IS 456 – 2000.
Permissible bond stress in case of deformed bar > (permissible bond stress of plain bars) 60%.

1160. In limit State Method of design, ratio of compressive strength to characteristic strength of concrete is

(a) 0.5 (b) 0.67
(c) 0.446 (d) 1.0

BPSC AE Aug. 2019 Paper-V


Ans. (b) The compressive strength of concrete = 0.67 × [characteristic strength of concrete (f_{ck})]
Design compressive strength of concrete = 0.45 f_{ck}

1161. The maximum strain in the tension reinforcement in the section at failure in LSM shall not be less than

(a) $0.02+\frac{f_y}{0.87E_S}$ (b) $0.035+\frac{f_y}{0.87E_S}$
(c) $0.035+\frac{f_y}{1.15E_S}$ (d) $0.002+\frac{f_y}{1.15E_S}$

BPSC AE Aug. 2019 Paper-V

Ans. (d) :



Strain diagram

So, maximum strain in tension reinforcement is $0.002+\frac{fy}{1.15E_s}$

1162. The limit state of serviceability of a steel structure includes all of the following except.

(a) Corrosion (b) Crack due to fatigue
(c) Fire (d) Fracture due to fatigue

UPRVUNL AE 2016

Ans.: (d) Serviceability limit state design of structures includes factors such as durability, overall stability, fire resistance, deflection, cracking and exclusive vibration.

1163. In limit state approach spacing of reinforcements primarily controls

(a) Collapse (b) Cracking
(c) Deflection (d) Durability

GPSC AE June 2019

Ans. (b) : In limit state method spacing of reinforcements primarily controls by creaking.
The code specifies minimum and maximum limits for spacing between parallel reinforcing bars in layer. The minimum limits are necessary to ensure that concrete can be placed easily & maximum limits are specified for bars in tension for purpose of controlling crack width & improving bond.

1164. For limit state method of design, permissible bearing stress for M20 grade concrete is

(a) 9 N/mm^2 (b) 11.25 N/mm^2
(c) 13.40 N/mm^2 (d) 17 N/mm^2

GPSC AE June 2019

Ans. (a) : For limit state method of design, permissible bearing stress for M20 grade of concrete is 9N/mm^2 as per IS 456 : 2000.

1165. In which of the following method, safety measures in design are introduced by appropriate choice of 'Load Factor'?

(a) Working Stress Method
(b) Ultimate Strength Method
(c) Limit State Method
(d) All of the above

GPSC AE June 2019

Ans. (b) : Ultimate strength method is safety measures in design are introduced by appropriate choice of load factor.

1166. In limit state of serviceability, the partial safety factor for wind load is taken as

(a) 1.0 (b) 1.15
(c) 1.5 (d) 0.9

GPSC AE Dec 2018

Search on Telegram @apna_pdf

Ans. (a) : In limit state of serviceability, the partial safety factor for wind load is taken as 1.0.

1167. The maximum compressive strain in concrete in axial compression is taken as

(a) 0.002 (b) 0.0035
(c) 0.0025 (d) 0.003

GPSC AE Dec 2018


Ans. (a) : The maximum compressive strain in concrete in axial compression is taken as 0.002.

1168. In limit state design of concrete for flexure the area of stress block is taken as:

(a) $0.360\ f_{ck}\ x_u$ (b) $0.446\ f_{ck}\ x_u$
(c) $0.87\ f_{ck}\ x_u$ (d) $0.420\ f_{ck}\ x_u$

PTCUL AE 2016
ESE 2011

Ans. (a) :



Area of stress block = $0.36\ f_{ck}\ x_u$. in LSM.

1169. Flexural tensile strength of M25 grade of concrete as per IS 456 is:

(a) 3.5 N/mm^2 (b) 4.5 N/mm^2
(c) 0.45 N/mm^2 (d) 1.2 N/mm^2


PTCUL AE 2016

Ans. (a) : Flexural tensile strength of concrete $\left(F_{cr}\right) = 0.7\sqrt{f_{ck}}$

f_{ck} = characteristic strength in N/mm^2.
For M25 grade of concrete
$F_{cr} = 0.7\sqrt{25} = 3.5$ N/mm^2


1170. For a tall building, which framing system from the following, column placement is most economical for resisting lateral loads:

(a)




System - I

(b)




System - II

(c)



System - III

(d)



System - IV

PTCUL AE 2016

Ans. (c) : In figure option no. (c) for a tall building column placement is most-economical for resisting lateral loads.

1171. Match list I with list II and select the correct answer using code given below the two list in each question.

List I	List II
A. Doubly reinforced beam	1. Serviceability
B. Limit state design	2. Durability
C. Minimum cover	3. Reduction in sectional depth
D. Span depth ratio	4. Ultimate moment capacity

Code:

	A	B	C	D
(a)	3	4	2	1
(b)	2	1	3	4
(c)	4	3	1	2
(d)	1	2	3	4

PTCUL AE 2016
MPPSC AE 2014
ESE 2011

Ans. (a) : (i) Doubly reinforced beam used for reduction in sectional depth.
(ii) Limit state design used for ultimate moment capacity.
(iii) Minimum cover provided for durability.
(iv) Span depth ratio used for serviceability.

Direction : Match list I with list II in Q. No. 1172 select the correct answer using code given below the two list in each question.

1172.

List I	List II (Slump in mm)
A. Pre cast work	1. 90
B. Footing	2. 75
C. Columns	3. 50
D. Beams	4. 25

Code:

	A	B	C	D
(a)	1	2	3	4
(b)	3	4	1	2
(c)	2	3	1	4
(d)	4	3	2	1

PTCUL AE 2016

Ans. (d) : As per IS 456 : 2000

Pre cast work	–	25
Footing	–	50
Columns	–	75
Beams	–	90


Search on Telegram @apna_pdf

1173. Consider the singly reinforced beam shown in figure below : At the cross-section XX, which of the following statement is TRUE at the limit state ?

(a) The variation of stress is linear and that of strain is non-linear.
(b) The variation of strain is linear and that of stress is non-linear.
(c) The variation of both stress and strain is linear.
(d) The variation of both stress and strain is non-linear.

AP TRANSCO AEE 2017

Ans. (b) :



The variation of strain is linear and that of stress is non-linear.

1174. Which one of the following states falls under the Limit state of Serviceability as per IS-456?

(a) Stability under load
(b) Loss of equilibrium of a structure
(c) Floor vibration
(d) Formation of mechanism

AP TRANSCO AEE 2017
APTRANSCO 2017
Rajasthan AE (Nagar Nigam) 2016

Ans. (c) : In Limit state method for which designing does not considered instead of this criteria only used to check the service condition or serviceability of the member.
i.e.:- Cracking, Floor vibration, deflection, shrinkage and creep.

1175. According to the concept of Limit State design as per IS 456 : 2000, the probability of failure of a structure is

(a) 0.09 to 0.10 (b) 0.9 to 0.01
(c) 0.10 to 0.20 (d) 0.01 to 0.02

AP TRANSCO AEE 2017

Ans. (a) According to the concept of Limit State design as per IS 456:2000, the probability of failure of a structure is 0.09 to 0.10.

1176. The value of factor of safety adopted in foundation design is

(a) 1.2 to 1.5 (b) 1.5 to 2.0
(c) 2 to 3 (d) 3 to 4

UPRVUNL AE 2015

Ans. (c) : The value of factor of safety adopted in foundation design is 2 to 3.

1177. In limit state design, under–reinforced section is one in which

(a) Tensile strain in steel reaches yield value while maximum compressive strain in concrete is less than its ultimate crushing strain.
(b) Maximum tensile stress in steel reaches its permissible value while maximum compressive stress in concrete is less than its permissible value.
(c) Maximum compressive strain in concrete reaches the ultimate crushing value while tensile strain in steel is less than its yield value.
(d) Maximum compressive stress in concrete reaches its permissible value while tensile stress in steel is less than its permissible value.

MPPSC AE 2014

Ans. (a) : In limit state design, under-reinforced section is one in which–tensile strain in steel reaches yield value while max-compressive strain in concrete is less than its ultimate crushing strain.

1178. For limit state of collapse, as per IS456:2000, the partial safety factor for material strength of steel is _____:

(a) 1.15 (b) 0.87
(c) 1.0 (d) 1.5

UPPCL AE 2018

Ans. (a) : For limit state of collapse, as per IS 456 : 2000, The partial safety factor for material strength of steel is 1.15 and the partial safety factor for concrete material is 1.5.

1179. Choose correct option for:

i. Limit state of collapse	**P. Cracking**
ii. Limit state of serviceability	**Q. Deflection**
iii. Limit state of durability	**R. Rupture**
	S. Fire resistance
	T. Environment/ chemical actions
	U. Accidental collapse

	P	Q	R	S	T	U
(a)	i	ii	iii	ii	i	ii
(b)	iii	ii	iii	ii	ii	i
(c)	ii	ii	i	iii	iii	iii
(d)	iii	ii	iii	ii	i	i
(e)	ii	ii	i	ii	iii	ii

Haryana PSC AE 2018 Paper–I

Ans. (c) : Limit state of collapse
(1) Flexure (b) Compression
(c) Shear (d) Torsion
Limit state of serviceability
(1) Excessive deflection
(2) Premature or excessive cracking
(3) Excessive vibrations
Limit state of durability
(1) Fire Resistance
(2) Environmental/Chemical action
(3) Accidental collapse.

Search on Telegram @apna_pdf

1180. In the limit state design for flexure, IS : 456-2000, assumes that maximum strain in tension reinforcement in the section at failure shall not be less than -

(a) $\frac{f_y}{E_s} + 0.002$ (b) $\frac{f_y}{E_s} - 0.002$

(c) $\frac{f_y}{1.15E_s} + 0.002$ (d) $\frac{f_y}{1.15E_s} - 0.002$

(where f_y = characteristics strength of steel, E_s = modulus of elasticity of steel)

Rajasthan VP ITI 2018

Ans. (c) :

$$E_{su} = \left(\frac{f_y}{1.15E_s}\right) + 0.002$$

OR

$$E_{su} = \left(\frac{0.87f_y}{E_s}\right) + 0.002$$

E_{su} = Strain in steel at time of failure
f_y = Characteristic strength of steel
E_s = Modulus of elasticity (steel) = 2×10^5 N/mm^2

1181. According to IS : 456-2000, in the limit state method for design of beams, the limiting values of depth of neutral axis for steels with f_y = 250, 415 and 500 MPa are given by–

(a) 0.43d, 0.48d and 0.56d respectively
(b) 0.46d, 0.48d and 0.53d respectively
(c) 0.56d, 0.48d and 0.43d respectively
(d) 0.53d, 0.48d and 0.46d respectively

Rajasthan VP ITI 2018

Ans. (d) :

Grade of steel	Yield stress f_y (N/mm^2)	Limiting value (x_{umax})	Maximum strain
Mild steel Fe 250	250	0.53d	0.00308
HYSD - Fe 415	415	0.48d	0.00380
HYSD - Fe 500	500	0.46d	0.00417

1182. The split tensile strength of M15 grade concrete when expressed as a fraction of its compressive strength is :

(a) 0.1 to 0.15 (b) 0.15 to 0.20
(c) 0.20 to 0.25 (d) None of the above

UP Jal Nigam AE 2016

Ans. (b) : Split tensile strength is 5% to 12% higher than direct tensile strength. The ratio of split tensile strength to compressive strength for different grades of concrete, are given below.
M10 → 10–15%
M15 → 15–20%
M20 → 20–25%
M30 → 25–30%

According to IS 456-2000 : The ratio of split tensile stronger to compressive strength is given by $\frac{0.7\sqrt{f_{ck}}}{f_{ck}}\times100$
for M-15, f_{ck} = 15 N/mm^2

$$= \frac{0.7\sqrt{15}}{15}\times100 = 18\%$$

So, 15 – 20% should be the choice.

1183. In the limit state method, the maximum strain in concretes in bending compression is taken to be

(a) 0.35 (b) 0.035
(c) 0.350 (d) 0.0035

WBPSC AE 2003

Ans. (d) : The maximum strain in concrete in compression in bending is taken as 0.0035 where as maximum strain in tension reinforcement is taken as $\frac{f_y}{1.15E_s} + 0.002$.

1184. In the limit state method of R.C. design, maximum permissible compressive strain concrete is

(a) 0.035 (b) 0.0035
(c) 0.02 (d) 0.002

WBPSC AE (PHE) 1998

Ans. (b) : The maximum strain in concrete in compression in bending is taken as 0.00035 where as maximum strain in tension reinforcement is taken as $\frac{f_y}{1.15E_s} + 0.002$.

1185. In limit state method of design the partial safety factor for concrete is

(a) 1.4 (b) 1.2
(c) 1.15 (d) 1.5

WBPSC AE (Common) 1998

Ans. (d) : Partial safety factor of concrete for WSM–
FOS for concrete = 3
FOS for steel = 1.78
L.S.M–
FOS for concrete = 1.5
FOS for steel = 1.15

1186. Splicing of reinforcement in flexure members is taken-up at a location where bending moment is less than _____ the moment of resistance at that section and not more than _____ of bars are spliced at any particular section.

(a) 75%, 50% (b) 50%, 75%
(c) 25%, 50% (d) 50%, 50%

TSPSC Deputy Engineer 2015

Ans. (d) : Splicing of reinforcement in flexure members is taken-up at a location where bending moment is less than 50% the moment of resistance at that section and not more than 50% of bars are spliced at any particular section.

Search on Telegram @apna_pdf

11. Pre-stressed Concrete

1187. In the design of pre-stressed concrete structures, which of the following limit state will come under the limit state of serviceability?

1. Flexure
2. Shear
3. Deflection
4. Cracking

Select the correct answer using the codes gives below :

(a) 1 and 4 (b) 3 and 4
(c) 2, 3 and 4 (d) 2 and 3

OPSC AEE 2019 Paper–I
ESE 2016, 1998


Ans. (b) : Limit state of serviceability
- Deflection
- Cracking
- Vibrations

1188. If the loading on a pre-stressed rectangular beam is uniformly distributed, and supported at either ends, the tendon to be provided should be

(a) straight below centroidal axis
(b) parabolic with convexity downward
(c) parabolic with convexity upward
(d) straight above centroidal axis

TNPSC AE 2019

Ans. (b) We know In Pre-stressed Concrete BMD diagram is apposite sign of shape of cable provided.




1189. If the tendon is placed at an eccentricity 'e' below the centroidal axis along the longitudinal axis of a rectangular beam (sectional modulus Z and stressed load P in tendon) the stress at the extreme top edge

(a) is increased by $\frac{Pz}{e}$
(b) is increase by $\frac{Pe}{z}$
(c) is decrease by $\frac{Pe}{z}$
(d) remains unchanged

TNPSC AE 2019

Ans. (c)



For Extreme top edge

$$\frac{P}{A} - \frac{P.e}{I} \text{ or } \frac{P}{b.d} - \frac{P.e}{I}$$


decreased by eccentricity loading

1190. The locus of the point of application of the resultant force at any given section of a pre-stressed concrete beam is the

(a) Elastic line
(b) Pressure line or thrust line
(c) C line
(d) P line

TNPSC AE 2019

Ans. (b) The line joining the locus of the resultant compression at various sections of a prestressed concrete beam is called pressure line or thrust line.
Cable line (P-line)- In this the actual value of P-force, moment; & eccentricity is used to analyze the section
Pressure line (C-line)- In this it is a line joining the location of C-force at different cross section in the beam



$$P = \frac{M}{e}$$

1191. The function of reinforcements in pre-stressed concrete is to

(a) Provide sufficient bond
(b) Resist tensile stresses
(c) Provide sufficient torsion resistance
(d) Produce initial compressive stress in concrete in the tension zone

TNPSC AE 2019

Ans. (d) The function of reinforcement in pre-stressed concrete is to provide initial compressive stress in concrete in the tension zone by pre-tension and post-tensioned.

1192. A simply supported pre-stressed concrete beam is expected to carry uniformly distributed load. The tendons should preferably be

TNPSC AE 2018
ESE-2011, 2001


OR

If the loading on a simply supported pre-stressed concrete beam is uniformly distributed, the centroid of tendons should be preferably


(a) a circular profile with convexity upward
(b) a straight profile below the centroidal axis
(c) a parabolic profile with convexity downward
(d) a straight profile along the centroidal axis

Gujarat PSC AE 2017
ESE-2016

Ans. (c) :



Search on Telegram @apna_pdf



For simply supported beam carrying udl. The shape of the BMD is parabolic profile, for the given external load in order it may offer considerable and effective downward force. So, tendon will be parabolic profile with convexity downward.

1193. In post-tensioning, the elastic loss in a stressed tendon resulting from the shortening of the member when additional tendons are stressed is called as

(a) Loss of prestress
(b) Bond loss
(c) Sequence stressing loss
(d) Anchorage loss
(e) Shrinkage loss

CGPSC AE 2014 Shift–I

Ans. (c) : Post tensional member, for more than one tendon, If the tendons are structural sequentially, there is loss in tendon during subsequent stretching of the other tendons is called an sequence stressing loss.

1194. As per the limit state design of steel structures, the IS 800 code on steel design stipulates the partial safety factor for resistance of member to bucking as :

(a) 1.10 (b) 1.25
(c) 1.50 (d) 1.00
(e) 0.80

CGPSC AE 2014 Shift–I

Ans. (a) : As per IS 800 (Cl 5.4.1)
Partial safety factor for material (γ_m)
Resistance of member to buckling (γ_{m0}) : 1.10

1195. According to IS 1343, the limit state of serviceability of pre-stresses sections shall satisfy

(a) Deflection and cracking
(b) Cracking and maximum compression
(c) Cracking, deflection and minimum compression
(d) Cracking deflection and minimum compression
(e) Deflection and maximum compression

CGPSC AE 2014 Shift–I

Ans. (a) According to IS 1343, the limit state of serviceability of pre-stressed concrete section shall satisfy :

→ Cracking
→ Deflection } due to creep & shrinkage
→ Vibration

1196. Which of the following pre-stressing system is employed in manufacturing prestressed concrete sleepers for railways?

(a) Post-tensioning
(b) Partial pre-stressing
(c) Pre-tensioning
(d) Pre-tensioning followed by post-tensioning
(e) Post-tensioning with accelerated curing

CGPSC AE 2014 Shift–I
ESE-2005

Ans. (c) : Pre-tensioning is generally employed in manufacturing concrete sleepers for railways.

1197. The net resultant stresses at bottom fiber of a section are zero means the resultant thrust must be passing from

(a) extreme top fiber (b) neutral axis
(c) upper kern point (d) lower kern point

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (c) • For a section symmetric about a vertical axis, the kern zone is within the levels of the upper and lower kern point.
• When the resultant compression (c) under service loads is located at the upper kern point, the stress at the bottom edge is zero.
• When compression (c) at transfer of prestress is located at the bottom kern point, the stress at the upper edge is zero.

1198. In a post-tensioned pre-stressed concrete beam, jacking force is applied from one end only. The loss of stresses in steel due to friction between steel and surrounding material will be maximum at

(a) Jacking end
(b) Mid span
(c) Anchored end
(d) Loss of stresses in steel due to friction is uniform throughout the span

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (c) The loss during anchorage, in the post-tensioning systems, when the cable is tensioned and the jack is released to transfer prestress to concert the friction wedges employed to grip the wires, slip over a small distance before the wires are finally housed between the wedges.

1199. Minimum strength of concrete at transfer (f_{ci}), to avoid cracking of extreme fiber at a pre-stressed concrete beam with reference to limit state of serviceability, maximum compression in flexure should be

(a) $0.7\sqrt{f_{ck}}$ (b) $0.5\ f_{ck}$
(c) $0.24\sqrt{f_{ck}}$ (d) f_{ck}

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (b) The code (Cl. 22.8.2.1) also recommended that the strength of concrete at the time of transfer (f_{ci}) should be at least equal to half the characteristic compressive strength of concrete. Hence,

$\boxed{f_{ci} \geq 0.5 f_{ck}}$

1200. Minimum grade of concrete to be used for pre and post-tension pre-stressed concrete construction are

(a) M30 and M40 respectively
(b) M30 in both cases
(c) M40 in both cases
(d) M40 and M30 respectively

TSPSC AEE 2017
Maharashtra PSC AE (Mains) 2012 Paper–I

Search on Telegram @apna_pdf

Ans : (d) As per IS 1343-1980 the minimum grades of concrete in pre-tensioned and post tensioning are M40 and M30 respectively.

1201. The resist bursting tension, designed reinforcement is distributed in the zone of .....from the loaded face of the end block, where $2y_0$ is depth of equivalent prism.

(a) $0y_0$ to $2y_0$ (b) $0y_0$ to y_0

(c) $0.2y_0$ to $2y_0$ (d) $0.2y_0$ to y_0

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (c) For post tensioned members with bonded tendons (i.e. grouted after tensioning) the bursting force F_{bst} will be distributed in a region extending from $0.2y_0$ to $2y_0$. From the loaded face and should be resisted by reinforcement in the form of spirals or closed links, uniformly distributed throughout this region.

1202. What is the correct order of increase in ultimate moment of resistance of
I. Pre-tension section
II. Post-tension bonded section
III. Post-tension unbounded section,
keeping all other parameters same.

(a) I, II and III
(b) III, II and I
(c) II, III and I
(d) All sections will have same UMR

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (b) • **Pre-tensioned Concrete**–It is cast around already tensioned tendons. This method produces a good bond between the tendon and concrete.

• Post-tensioned bounded in which tendons are permanently bounded to the surrounding concrete by the in situ grouting of their encapsulating ducting (after tendon tensioning).

• Unbonded post tensioning by allowing the tendons permanent freedom of longitudinal movement relative to the concrete.

1203. Deflection of a simply supported pre-stressed concrete beam of span 'l' and flexural rigidity 'EI', due to a straight cable carrying pre-stressing force 'P' and eccentricity 'e' below the neutral axis is

(a) $\frac{5Pel^2}{48EI}\uparrow$ (b) $\frac{Pel^2}{8EI}\uparrow$

(c) $\frac{Pel^2}{8EI}\uparrow$ (d) $\left(\frac{Pel^2}{8EI}+\frac{5Pel^2}{8EI}\right)\uparrow$

Maharashtra PSC AE (Mains) 2012 Paper–I


Ans : (c) Maximum central deflection–

$$\delta = \frac{L^2}{8R}$$


$$\frac{1}{R} = \frac{Pe}{EI}$$

$$\therefore \left[\delta = \frac{PeL^2}{8EI}\ (\text{upward})\right]$$

1204. A cantilever beam of span 'L' is supporting a u.d.l. of intensity 'w'. Most suitable cable profile will be

(a)  parabolic cable profile

(b)  parabolic cable profile

(c)  parabolic cable profile

(d)  parabolic cable profile

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (c) A cantilever beam of span 'L' is supporting a u.d.l. of intensity 'w'. Most suitable cable profile will be

 parabolic cable profile

1205. Principal tensile stresses at any section and at any fiber in a pre-stressed concrete beam are influenced by

(a) Horizontal pre-stress in concrete
(b) Vertical pre-stress in concrete
(c) Shear stress in concrete
(d) All of the above

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (d)

1206. Efficiency of a rectangular pre-stressed concrete section with dimensions b = 0.5 is

(a) bd (b) 0.5 bd

(c) 0.5 (d) 0.333

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (d)

1207. Which of the following statements is/are true with reference to a load balancing cable?
Statement I : The flexural stresses are uniform at any-section throughout the span at service state.
Statement II: The flexural stresses are zero in the extreme fibers at any-section throughout the span at service stage.
Statement III: The shear stresses are zero at any section throughout the span at service stage.

(a) I only (b) I and III only

(c) II and III only (d) None of these

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (b)

1208. As per IS 1343-1980, loss of pre-stress in steel due to shrinkage in concrete in a pre-tension beam is ....., if $E_s = 2 \times 10^5$ MPa.

(a) 60 MPa (b) 200 MPa


(c) 20 MPa (d) 0.02 f_s MPa


Maharashtra PSC AE (Mains) 2012 Paper–I


Ans : (a) The loss of prestress due to creep of concrete can be estimated by the creep coefficient method, as recommended in the IS code IS 1343-1980 loss of prestress in steel due to shrinkage in concrete in a pre-tension beam is 60 MPa.


Search on Telegram @apna_pdf

1209. There is a post-tensioned pre-stressed concrete beam with effective simply supported span of 8 m. This beam with rectangular cross section is pre-stressed with parabolic cable with 200 kN force, having eccentricity 200 mm above neutral axis at mid-span and 200 mm below it at support. The cable can be replaced by an equivalent effect as

(a) 

(b) 

(c) 

(d) 

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (c)

1210. In regard to pre-stressed concrete design, the final deflection, due to all loads including the effects of temperature, creep and shrinkage and measure from the as-cast level of the supports of floors, roofs and all other horizontal members should not normally exceed span/X, where X is :

(a) 350 (b) 250
(c) 300 (d) 200

CIL MT 2017

Ans. (b) : In regard to pre-stressed concrete design, the final deflection, due to all loads including the effects of temperature, creep and shrinkage and measure from the as-cast level of the supports of floors, roofs and all other horizontal members should not normally exceed span/250.

1211. The minimum grade of concrete for pre-tensioned pre-stressing concrete member is–

(a) M30 (b) M40
(c) M60 (d) M70

APPSC Poly. Tech. Lect. 2020

Ans. (b) : minimum grade of concrete for pre-tensioned pre-stressed concrete member is M40. which in post tensioning pre-stressed concrete member minimum grade of concrete is M30.

1212. In a post-tensioning system, high tension steel wires 5 mm to 8 mm diameter about 12 in number are arranged to form a group into a cable with a spiral spring inside. This system is known as

(a) The Freyssinet System
(b) The Magnel Blaton System
(c) P.S.C. Monowire System
(d) C.C.L. Standard System

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (a) Freyssinet system was introduced by the french engineer freyssinet and it was the first method to be introduced. High strength steel wires of 5 mm or 7 mm diameter numbering 8 or 12 or 16 or 24 grouped into a cable with a helical spring inside

1213. In pre-tensioned system, when pre-stressed force is transferred by releasing tendon, the end of wire swells and develops wedge effect. At the end, pre-stressing force becomes zero. This is known as

(a) Hoyer effect (b) Shear effect
(c) Wobbling effect (d) Bursting effect

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (a) In prestressed concrete, the frictional force resulting from the tendency of the assume their original diameter (i.e. their diameter before prestressing)

1214. A beam of span 'L' carries a U.D.L. of 'w' per m run and pre-stressing force in the cable is 'P'. What will be the eccentricity of parabolic cable at centre (i.e. dip) so as to nullify the bending effect?

(a) $\frac{3L^2}{3P}$ (b) $\frac{3wL^2}{5P}$
(c) $\frac{wL^2}{8P}$ (d) $\frac{wL^3}{8P}$

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (c)

1215. Shrinkage strain developed in post-tensioning beam when pre-stressing force transfer at the age of 't' days is

(a) $\frac{0.003}{\log_{10}(t+2)}$ (b) $\frac{0.002}{\log_{10}(t+2)}$
(c) $\frac{0.0035}{\log_{10}(t+2)}$ (d) $\frac{0.001}{\log_{10}(t+1)}$

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (b) The approximate value of shrinkage strain for design shall be assumed as follows (IS 1383)

- for pre tensioning = 0.0003
- for post-tensioning = $\frac{0.002}{\log_{10}(t+2)}$

1216. The method of pre-stressing concrete in which pre-stressing steel is tensioned against the hardened concrete is:

(a) Pre tensioning (b) post tensioning
(c) initial pre-stressing (d) jack tensioning

KPSC AE 2020

Ans. (b) The method of pre-stressing concrete in which pre-stressing steel is tensional against the hardened concrete is post tensioning.

Pre-tensioning :

In pre-tensioning system the high strength steel tendons are pulled between two end abutments prior to the casting of concrete and the abutments are fixed at the ends of pre-stressing bed.

Once the concrete attains the desired strength for pre-stressing the tendons are cut loose from the abutments.

Search on Telegram @apna_pdf

Post-tensioning : In post tensioning systems the ducts for the tendons are placed along with the reinforcement before the casting of concrete.
The tendons are placed in the ducts after casting of concrete.
The duct prevents contact between concrete and the tendons during the tensioning operation.

1217. In post-tensioned pre-stressed concrete beam, the end block zone in the zone between the end of the beam and the section where :
(a) No lateral stresses exist
(b) Only longitudinal stresses exist
(c) Only shear stress exist
(d) Shear stresses are maximum


Nagaland PSC CTSE 2017 Paper–I
ESE-2016, 2000

Ans. (b) : The zone Between the end of the beam and the section where only longitudinal stresses exist is generally referred to as the anchorage zone or end block zone.

1218. The propagation of a shear crack in pre-stressed concrete member depends on:
(a) tensile reinforcement
(b) compression reinforcement
(c) shear reinforcement
(d) shape of the cross-section of the beam

Nagaland PSC CTSE 2017 Paper–I
[UPPSC State Eng. A.E. 2011]
[UPPSC State Eng. A.E. 2003]
ESE 2000

Ans : (d)



Propagation of shear crack depends upon the shape of the beam it has nothing to do with the amount of tension, compression or shear reinforcement provided.

1219. Pre-stressed concrete means
(a) Compressive stress induced in concrete before loading
(b) Compressive stress induced in steel before loading
(c) tensile stress induced in steel before loading
(d) Tensile stress in concrete before loading

Nagaland PSC CTSE 2017 Paper–I

Ans. (c) : Pre-stress concrete means tensile stress induced in steel Before loading.

1220. According to Indian standard the total amount of shrinkage for a pre-tensioned beam is taken as:
(a) 3×10^{-4} (b) 3×10^{-5}
(c) 3×10^{-6} (d) 3×10^{-7}

Nagaland PSC CTSE 2017 Paper–I

Ans. (a) : According to Indian standard code,
$\rightarrow$Loss of stress due to shrinkage of concrete $\rightarrow(3\times10^{-4})\ E_s$
Here $E_s \rightarrow$ Young Modulus for tendon wire

1221. As per IS code, the minimum grade of concrete for the design of pre-stressed concrete structure is–
(a) M20 (b) M25
(c) M15 (d) M30

UKPSC AE 2013 Paper–I


Ans : (d) In pre-stressed members high grade of concrete is used. w/c ratio is also kept low. To prepare concrete mix we used admixtures and to compact we use vibrators. In high strength concrete shrinkage cracks are very less, creep is less and loss of stress in steel is also very less some facts about per stressed concrete.
(i) water cement ratio – 0.45
(ii) slump value = 75mm
(iii) Grade of cement –
(a) For pre-tensioned member = M–40
(b) for post-tensioned member = M–30

1222. A pre-stressed concrete beam of size 300 mm × 900 mm is pre-stressed with an initial pre stressing force of 810 kN at an eccentricity of 360 at mid span. Stress at the top fiber due pre-stress along (–) Tension, (+) Compression
(a) $+3\ N/mm^2$ (b) $-7.2\ mm^2$
(c) $+10.2\ N/mm^2$ (d) $-4.2\ mm^2$

UKPSC AE 2013 Paper–I

Ans : (d) Given, P = 810 kN, e = 360
By using formula

$$\sigma_c = \frac{P}{A} - \frac{Pey}{I}$$



$A = 300\times900 = 270000mm^2$

$$I = \frac{300\times900^3}{12}$$

$$\sigma_c = \frac{810\times1000}{270000} - \frac{810\times360\times450\times1000}{\left(300\times900^3\right)/12}$$

$$= \frac{810\times1000}{270000} - 7.2 \ = 3-7.2$$

$= -4.2\ N/mm^2$

1223. The purpose of high tensile strength steel wires in pre-stress concrete is–
(a) To provide adequate bond stress
(b) To resist tensile stresses
(c) To impart initial compressive stress in concrete
(d) All options are correct

UKPSC AE 2013 Paper–I

Ans : (d) The purpose of high tensile strength steel wires in pre-stress concrete is to provide adequate bond stress, to resist tensile stresses and to impart initial compressive stress in concrete.

1224. Which of the following losses occurs only in post–tensioning pre–stressed concrete structures –
(a) Loss due friction

Search on Telegram @apna_pdf

(b) Shrinkage of concrete
(c) Creep of concrete
(d) Elastic shortening of concrete

UKPSC AE 2013 Paper–I

Ans : (a) Loss of pre-stress which results due to various reasons is of the order of 20-40% of the initial pre-stress.
Reasons for pre-stress loss are as follows–
(i) Elastic shortening of concrete
(ii) creep of concrete
(iii) Shrinkage of concrete
(iv) Relaxation of pre-stress
(v) Friction losses
Friction losses occur only in post-tensioned members.

1225. Concrete for pre-stressing work should have minimum compressive strength of :
(a) 200 kg/cm^2 (b) 250 kg/cm^2
(c) 300 kg/cm^2 (d) 350 kg/cm^2

(UKPSC AE (Paper-I) 2007)

Ans : (c) Min grade of concrete used in pre-stressing work is M 30 .
$\therefore$ min. compressive strength = 30 N/mm^2 = 300 kg/cm^2.

1226. Fully pre-stressed concrete beam resists
(a) all the vertical loads by pre-stress
(b) live loads by pre-stress
(c) part of the loads by pre-stress
(d) none of the above

(UKPSC AE (Paper-I) 2007)

Ans : (c) Fully pre-stressed concrete beam resists part of the load by pre-stress.

1227. Pre-stressed concrete is more desirable in case of cylindrical pipe subjected to :
(a) internal fluid pressure
(b) external fluid pressure
(c) equal internal and external fluid pressure
(d) none of the above

UKPSC AE (Paper-I) 2007
ESE 1995

Ans : (a) If a cylindrical pipe is subjected to internal fluid pressure then tensile stresses will develop in it. As we known that tensile strength of concrete is almost zero, therefore, pre-stressed concrete is most desirable in this case.

1228. Which one of the following is categorised as a long term loss of pre-stress in a pre-stressed concrete member?
(a) loss due to elastic shortening
(b) loss due to friction
(c) loss due to relaxation of strands
(d) loss due to anchorage slip

(UKPSC AE 2012 Paper–I)

Ans : (c) Anchorage slip– Account should be taken of losses due to wedge drawn in of the anchorage devices, during the operation after tensioning and due to the anchorage itself. This loss occurs in long term in pre-tensioned members.

1229. In pre-stressed concrete member, it is advised to use
(a) low strength concrete only.
(b) high strength concrete only.
(c) low strength concrete but high strength steel.
(d) high strength concrete and high strength steel.

(UKPSC AE 2012 Paper–I)

Ans : (d) In pre-stress members concrete and steel of high grade are used. The code suggest a minimum M 40 mix for pre tensioned and M 30 mix for post tensioned systems. High tensile steel of strength 1750 N/mm^2 is available in form of wires which are either stress relieved or cold drawn from high tensile steels bars.

1230. The ultimate strength of the steel used for pre-stressing is nearly–
(a) 250 N/mm^2 (b) 415 N/mm^2
(c) 500 N/mm^2 (d) 1500 N/mm^2

RPSC AE (GWD) 2014
ESE 1999

Ans : (d) High tensile steel are generally available in form of wires which are either stress relieved, as-drawn or cold drawn from high tensile steel bars and strands composed of several twisted wires to form a single element.

Characteristic strength (MPa)	**Diameter (mm)**					
	1.5	3	4	5	7	8
Stress relieved and cold drawn	–	1900	1750	1600	1500	1400
As drawn	2350	1800	1750	1600	–	–

1231. The minimum grade of concrete that can be used for pre-tensioned beam system is:
(a) M20 (b) M25
(c) M30 (d) M40

UPPSC AE 12.04.2016 Paper–I
[BPSC A.E. Paper V 2001(I)]
[UK Combined A.E (I) 2007]

Ans : (d) Minimum grade of concrete
For pre-tensioned pre-stressed concrete = M40
For post-tensioned pre-stressed concrete = M30

1232. Primary aim of pre-stressing is to
(a) eliminate crushing of concrete due to compressive stresses
(b) eliminate crushing of concrete due to tensile stresses
(c) make the beam oversafe
(d) None of the above

[UPPSC State Eng. A.E. 2008]

Ans : (b) Pre-stressing is done to :
- Eliminate cracking of concrete due to tensile stresses.
- Get smaller concrete sections.
- Make large span structures.
- Improve shearing resistance.
- Saving on column and foundation due to lighter weight of super structure.


Search on Telegram @apna_pdf

1233. In the conventional pre-stressing the diagonal tension in concrete

(a) increases (b) decreases
(c) does not change (d) all of the above

UPPSC State Eng. A.E. 2011, 2003

Ans : (b) In a pre-stressed concrete member, the shear stress is generally accompanied by a direct shear in the axial direction of the member, and if transverse vertical pre-stressing is adopted, compressive stresses in the direction perpendicular to the axis of the member will be present in addition to the axial pre-stress.
In most general care on an element subjected to a two-dimensional stress system is shown below.



Principal tensile stressed in pre-stressed member

The maximum and minimum principle stresses developed are given by

$$f_{max/min} = \left[\left(\frac{f_x + f_y}{2}\right) \pm \frac{1}{2}\sqrt{(f_x - f_y)^2 + 4\tau_v^2}\right]$$

In pre-stressed concrete members, the direct stresses f_x and f_y being compressive, the magnitude of the principal tensile stress is considerably reduced, and in some cases even eliminated, so that under working loads, both major and minor principal stresses are compressive, thereby eliminating the risk of diagonal tension cracks in concrete.

1234. A concrete in which internal stresses are introduced by a planned manner is known as

(a) Pre-stressed concrete
(b) Plain concrete
(c) Lime concrete
(d) Reinforced concrete

[UPPSC State Eng. A.E. 2007(I)]

Ans : (a) Pre-stress concrete is the one in which the member have been introduced internal stresses of such magnitude and distribution that stresses resulting from the external loading is counter balanced to desired degree.

1235. Pre-stressing is an act of introducing predetermined ....forces in to the member.

(a) compressive (b) tensile
(c) bursting (d) none of these

(BPSC AE Paper V 2001)

Ans : (a) Pre-stressing is an act of introducing predetermined compressive forces into the member.

1236. In a simply supported pre-stressed concrete beam subjected to uniformly distributed load on entire span, the ideal shape of the cable profile will be

(a) concentric with the centre of cross-section
(b) at constant eccentricity over the entire span
(c) varying linearly with zero eccentricity at ends and maximum eccentricity at mid-span/
(d) parabolic with zero eccentricity at ends and maximum eccentricity at mid-span

(JPSC Combined AE Paper V 2013)
ESE 1997

Ans : (d) In a simply supported pre-stressed concrete beam subjected to uniformly distributed load on entire span, the ideal shape of cable profile will be parabolic with zero eccentricity at the ends and maximum eccentricity at the mid-span.

1237. In a 10 m long simply–supported pre-stressed concrete beam, if pre-stressing force = P; eccentricity = e; area of cross–section = A; section modulus = Z; bending moment due to dead load M_g; bending moment due to live load M_q; Bending moment due to dead load and live load at top fiber at mid–span is given by

(a) $\left(\frac{P}{A} - \frac{P_e}{Z}\right) + \left(\frac{M_q}{Z}\right) + \left(\frac{M_g}{Z}\right)$


(b) $\left(\frac{P}{A} + \frac{P_e}{Z}\right) + \left(\frac{M_q}{Z}\right) + \left(\frac{M_g}{Z}\right)$

(c) $\left(\frac{P}{A} - \frac{P_e}{Z}\right) - \left(\frac{M_q}{Z}\right) - \left(\frac{M_g}{Z}\right)$

(d) $\left(\frac{P}{A} + \frac{P_e}{Z}\right) - \left(\frac{M_q}{Z}\right) - \left(\frac{M_g}{Z}\right)$

MPPSC AE 2016

Ans : (a)



$$\sigma_T = \frac{P}{A} - \frac{Pe}{Z} + \frac{M_q}{Z} + \frac{M_g}{Z}$$ on top fibers

$$\sigma_b = \frac{P}{A} + \frac{Pe}{Z} - \frac{M_q}{Z} + \frac{M_g}{Z}$$ on bottom fibers

$\frac{P}{A}$ = compressive stress due to pre-stressing

$\frac{P_e}{Z}$ = bending stress due to pre-stressing

$\frac{M_q}{Z}$ = Bending stress due to live load

$\frac{M_g}{Z}$ = Bending stress due to dead load.

1238. A pre-stressed concrete beam has a cross section with the following properties

Area A = 46,400mm^2

I = 75.8 ×10^7 mm^4

Y_{bottom} = 244 mm, Y_{top} = 156 mm

It is the subjected to a pre-stressing force and eccentricity 'e' so as to have a zero stress at the top fiber. The value of 'e' is given by

Search on Telegram @apna_pdf

(a) 66.66 mm (b) 66.95 mm
(c) 104.72 mm (d) 133.33 mm

RPSC POLY. TECH. LECT. 2014

Ans : **(c)** Let the stress on top fiber due to pre-stressing force be zero

$$\sigma = \frac{P}{A} - \frac{Pey_{top}}{I} = 0 \Rightarrow \frac{P}{A} = \frac{Pey_{top}}{I}$$

$$e = \frac{I}{Ay_{top}} = \frac{75.8\times10^7}{46400\times156}$$

$$\boxed{e = 104.72\,mm}$$

1239. The loss of pre-stress due to elastic shortening of concrete is least in
(a) One wire pre-tensioned beam
(b) One wire post-tensioned beam
(c) Multiple wire pre-tensioned beam with sequential cutting of wires
(d) Multiple wire post-tensioned beam subjected to sequential pre-stressing

RPSC POLY. TECH. LECT. 2014

Ans : **(b)** Loss of pre-stress due to elastic shortening will be least if one wire post tensioned beam is formed.

1240. The percentage loss of pre-stress due to anchorage slip of 3mm in a concrete beam of length 30m which is post-tensioned by a tendon with an initial stress of 1200 N/mm^2 and modulus of elasticity equal to 2.1×10^5 N/mm^2 is
(a) 0.0175 (b) 0.175
(c) 1.75 (d) 17.5

RPSC POLY. TECH. LECT. 2014
ESE-2014, 2012

Ans : **(c)** Loss due to anchorage slip is $\frac{E_s\Delta}{L}$

Given, $E_s = 2.1\times10^5$ N/mm^2 $\Delta = 3$mm L= 30000mm

$$\text{Loss of pre-stress} = \frac{2.1\times10^5\times3}{30000} = 21\ N/mm^2$$


Percentage loss due to slip

$$= \frac{21\ N/mm^2}{1200\ N/mm^2}\times100 = 1.75\%$$

1241. Which one of the following is categorized as a long term loss of pre-stress in a pre-stressed concrete member.
(a) Loss due to elastic shortening
(b) Loss due to friction
(c) Loss due to relaxation of strands
(d) Loss due to anchorage slip

RPSC POLY. TECH. LECT. 2014

Ans : **(c)**



1242. Which of the following types of losses of pre-stressing occurs only in pre-tensioning and not in post-tensioning case
(a) Friction
(b) Creep of concrete
(c) Relaxation of stress in steel
(d) Elastic shortening (deformation) of concrete

RPSC VPITI - 2012

Ans : **(d)** When pre-stress is applied simultaneously in all strands there is no loss due to elastic shortening of concrete in post tensioned members.

1243. The loss of pre-stress due to shrinkage of concrete is the product of
(a) Modulus ratio and percentage of steel
(b) Modulus of elasticity of concrete and shrinkage of concrete
(c) Modulus of elasticity of steel and shrinkage of concrete
(d) Modular ratio and modulus of elasticity

RPSC LECTURE - 2011

Ans : **(c)** Loss of pre-stress due to shrinkage of concrete is expressed as $\Delta\sigma = \varepsilon_{sn}E_s$
ε_{sn} = Shrinkage strain
E_s = modulus of elasticity of steel

1244. In which one of the following post-tensioning anchorage systems, the high-tension bars are threaded at their ends?
(a) Gifford-Udall (b) Freyssinet
(c) Lec-McCall (d) Magnel-Blaton


MPPSC AE 2017

Ans. (c) : In the Lee-McCall system, the tendons comprise high-tensile bars of diameter varying form 12-40 mm which are threaded at the ends. After tensioning each bar is anchored by screwing a nut and washer tightly against the end plates.

1245. For the production of pre-tensioned members on large scale, a system usually adopted is _____.
(a) Gifford Udall System
(b) Magnel Blaton System
(c) Hoyer System
(d) P.S.C Monowire System

Maharashtra PSC (Mains) 2015 Paper–I
OPSC AEE 2015 PAPER–I

Ans. (c) : Hoyer system of pre-tensioning is generally used for mass production. The end abutments are kept sufficient distance apart, and several members are cast in a single line. The shuttering is provided at the sides and between the members.
This system is also called the along line method.



1246. Pre-stressed concrete members which are designed to allow significant tensile stresses to occur at service loads and such tensile regions are usually additionally reinforced with non-pre-stressed reinforcement are known as _____.
(a) Pre-stressing tension members
(b) Fully pre-stressing members
(c) Non-pre-stressing members
(d) Partial pre-stressing members

Maharashtra PSC (Mains) 2015 Paper–I


Search on Telegram @apna_pdf

Ans. (d) : Types of pre-stressing,
1. Full pre-stressing (or class 1 structure)
⇒ No tensile stress is allowed.
2. Limited pre-stressing or (class-2 structure)
⇒ Tensile stress under service loads is within the cracking stress of concrete.
3. Partial pre-stressing or (class-3 structure)
⇒ Tensile stresses are such that due to stresses, crack width is within the allowable limit.

1247. A simply supported pre-stressed concrete beam of 300 × 500 mm in c/s is subjected to a superimposed load of 20 KN/m over a span of 10 m. If a pre-stressing force of 1000 KN is applied through a straight tendon located along centroidal axis then what is the extreme top fiber stress at the end support-
(a) 20 MPa (b) 26.67 MPa
(c) 19.33 MPa (d) 6.67 MPa

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (b) :



$$\sigma_A = \frac{P}{A} + \frac{My}{I}$$

$$\sigma_A = \frac{1000\times10^3}{300\times500} + \frac{20\times10^2\times10^6}{8} \times \frac{\frac{500}{2}\times10^6}{300\times\frac{(500)^3}{12}}$$

$= 26.67 \text{ N/mm}^2 = 26.67 \text{ MPa}$

1248. Which statement is not applicable to pre-stressed concrete members?
(a) It combines high strength concrete with high strength steel in an active manner
(b) High tension steel wires are used to transfer tensile stresses to concrete section
(c) Pre-stressing the steel against the concrete to counter balance any tensile stress produced by any dead load and live load
(d) Load balancing concept enables the transformation of a flexure member into a member under direct stress


Maharashtra PSC (Mains) 2015 Paper–I

Ans. (b) : 2nd statement is wrong since high tension steel wires are used to transfer compressive stresses and not tensile stresses to concrete section.

1249. A simply supported pre-stressed concrete beam of span 10 m and subjected to U.D.L. of 30 KN/m (inclusive of self weight). A pre-stressing force of 1500 KN is applied through a parabolic cable having zero eccentricity at both ends and maximum value (h) at centre of span then what will be the dip-
(a) 250 mm (b) 100 mm
(c) 50 mm (d) 25 mm

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (a) :



Applying load balancing concept,

$$\frac{8Ph}{L^2} = 30\text{kN/m}$$


$$\frac{8\times1500\text{kN}\times h}{(10\ m)^2} = 30\text{ kN/m}$$

$$h = \frac{30\times100}{8\times1500}\times10^3\ mm = 250\text{ mm}$$

1250. In post-tensioned elements, the zone within which the applied pre-stressing force on steel is fully dissipated into concrete and made to act as a distributed force is known as____.
(a) Transmission zone (b) Anchor zone
(c) Distribution zone (d) End block zone

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (b) :



Stress trajectories in end zone or anchor zone.

1251. A post tensioned pre-stressed concrete beam is tensioned successively by 4 cables of equal area and equal stress. The percentage loss in each cable is found to be 6%, 4%, 2% and 0% respectively, What will be the total percentage loss in pre-stressing force
(a) 12% (b) 4%
(c) 3% (d) 6%

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (c) : Total percent loss $= \frac{6+4+2}{3+1} = 3\%$

1252. In case of curved ducts, the loss of pre-stress depends upon the radius of curvature (R) of the duct and the coefficient of friction (μ) between duct surface and the tendon. The tension at any point of the cable distance '*x*' from the end is given by _____.

Search on Telegram @apna_pdf

(a) $P_0 e^{-\frac{\mu x}{R}}$ (b) $P_0 e^{-\mu R}$

(c) $P_0 \text{Re}^{-\mu x}$ (d) $P_0 e^{-\frac{\mu R}{x}}$

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (a) : The tension at any point of the cable distance 'x' from the end is given by $P_0 e^{-\mu x/R}$.

1253. During tensioning of pre-stressing tendons the breakage of wires in any one pre-stressed concrete member shall *not* exceed-

(a) 2.5% (b) 7.5%

(c) 10% (d) 12.5%

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (a) : Maximum limit for breakage of wires in any member is 2.5%.

1254. The loss due to creep in pre-stressed concrete shall be determined considering-

(a) All loads and pre-stressing force

(b) Live loads and pre-stressing force

(c) Permanent loads and pre-stressing force

(d) Permanent loads only

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (c) : Live loads are not considered for creep only permanent load and pre-stressing forces are considered as creep occurs due to sustained loading.

1255. What is the maximum possible eccentricity in a pre-stressed concrete beam of circular cross-section? Diameter of the section is *d*. Tension is not allowed anywhere and any time in the cross-section. Neglect dead load (self-weight)-

(a) $\frac{d}{8}$ (b) $\frac{d}{6}$

(c) $\frac{d}{4}$ (d) $\frac{d}{3}$

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (a) :

1256. In a pre-tensioned pre-stressed concrete cross-section.

***Statement 1 :* The stress in wires is assumed to be zero at the end supports and increases to its final maximum value over its transmission length.**

***Statement 2 :* The bond stress between concrete and pre-stressed wires is maximum near the end supports and decreases to nearly zero over its transmission length.**

(a) Statements 1 and 2 are true

(b) Statement 1 is true and statement 2 is false

(c) Statement 1 is false and statement 2 is true

(d) Statement 1 and 2 are false

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (a) : Stresses are provided in steel cables. For this stress to get transferred fully to the concrete a certain region is required called transmission zone where force from steel gets transferred to concrete.


1257. The extreme stress at the top and bottom edges of a pre-stressed beam when tendons are placed along the longitudinal axis of the beam are-

(a) $\frac{P}{A} \pm \frac{M}{Z}$ (b) $\frac{P}{Z} \pm \frac{M}{A}$

(c) $\frac{P}{A} \pm \frac{M}{I}$ (d) $\frac{P}{I} \pm \frac{M}{A}$

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (a) :



Hence extreme stress will be

$$f_{t/b} = \frac{P}{A} \pm \frac{M}{Z}$$


1258. A simply supported rectangular pre-stressed concrete beam is subjected to uniformly distributed live load over its entire span, such that the resulting stress at the mid span at bottom fiber is zero. The eccentricity at that section is $\frac{d}{6}$ below the C.G., where *d* is the depth of the beam. Location of the thrust line at that section is-

(a) At C.G. (b) $\frac{d}{6}$ above C.G.

(c) $\frac{d}{6}$ below C.G. (d) $\frac{d}{3}$ below C.G.

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (b) :



$$\frac{P}{A} + \frac{Pd}{6z} - \frac{wl^2}{8z} = 0$$

$$P = \frac{3w^2}{8d}$$

$$e' = \frac{M}{P} - e$$

$$= \frac{wl^2}{8} \times \frac{8d}{wl^2} - \frac{d}{6} = \frac{d}{3} - \frac{d}{6} = +\frac{d}{6}$$

1259. A 4.8 m long post-tensioned pre-stressed concrete beam is pre-stressed by a parabolic cable with eccentricity of 15 mm above C.G. at both supports and 45 mm below C.G. at the mid span. The beam is tensioned from one end. In the estimation of maximum loss due to friction, what should be the cumulative angle turned by the parabolic profile?


(a) 0.01 radians (b) 0.1 radians

(c) 0.15 radians (d) 0.02 radians

Maharashtra PSC (Mains) 2017 Paper–I

Search on Telegram @apna_pdf

Ans. (b) :



Loss due to friction = $P_0 (\mu\alpha + kx)$

$\alpha = 2\theta$

h = 15 + 45 = 60 mm

$$\alpha = 2\left(\frac{4h}{l}\right)$$

$$= 2 \times \frac{4 \times 60}{4.8 \times 1000} = 0.1 \text{ radians}$$

1260. Which of the following losses occurs only in post-tensioning?

(a) Shrinkage of concrete
(b) Elastic shortening of concrete
(c) Loss due to friction
(d) Creep of concrete

OPSC AEE 2015 PAPER–I

Ans. (c) :
Pre-tensioned PSC beam :
- Loss due to shrinkage.
- Loss due to creep.
- Loss due to relaxation of steel.
- Loss due to elastic shortening.


⇒ **Post-tensioned PSC beam :**
- Loss due to creep.
- Loss due to friction.
- Loss due to anchorage slip.
- Loss due to relaxation of steel.
- Loss due to shrinkage.

1261. Normally pre-stressing wires are arranged in the

(a) upper part of the beam
(b) lower part of the beam
(c) centre
(d) anywhere

BPSC AE 2019 Paper (V) Section-I

Ans. (b) : Normally pre-stressing wires are arranged in the lower part of the beam because lower part subjected to tension and the wires have good strength in tension.



1262. Total amount of shrinkage strain for a pre-tensioned member is

(a) 3×10^{-4} (b) 3×10^{-5}
(c) 3×10^{-6} (d) 3×10^{-7}

APPSC AEE (Mains) 2016

Ans. (a) : Total amount of shrinkage strain for a pre-tensioned member is of the 3×10^{-4}.

1263. What type of stresses are artificially induced by Pre-stressed concrete in a structure before it is loaded?

(a) Tensile (b) Torsional
(c) Shear (d) Compressive

APPSC AEE (Mains) 2016


Ans. (d) : Concrete section is strong in compression and weak in tension hence compressive stresses are induced to counter the tensile stresses generated in concrete.

1264. In a pre-stressed concrete member

(a) High strength concrete should be used
(b) Normal strength concrete should be used
(c) High strength concrete and low tensile steel should be used
(d) High strength concrete and high tensile steel should be used

APPSC AEE (Mains) 2016

Ans. (d) : Pre-stressed concrete is a form of concrete used in construction.
In a pre-stressed concrete member the internal stresses are introduced in a planned manner so that the stresses resulting from the super imposed loads are counteracted to the desired degree.



1265. A suspension cable, supporting loads will be under

(a) compression
(b) tension
(c) bending
(d) compression and bending

TNPSC AE 2018

Ans. (b) : Suspension cables are under tensile loading. They can not bear compressive load and buckle in compression.

1266. The number of wire in Magnel cable varies between

(a) 2 to 64 (b) 10 to 100
(c) 20 to 120 (d) 8 to 78

TNPSC AE 2018

Ans. (a) : The number of wires in Magnel cable varies from 2 to 64. Magnel – Biaton post tensioning system adopts metallic sandwich plates for wedding and distribution plates for anchoring the wires.

1267. In the pre-tensioning system, the pre-stress is imparted to concrete by

(a) compression
(b) the bond between steel and concrete
(c) tension
(d) bearing

TNPSC AE 2018

Ans. (b) : In the pre-tensioning system, the pre-stress is imparted to concrete by bond between steel and concrete where as in post tensioned beams, pre-stress is imparted by bearing at ends.

Search on Telegram @apna_pdf

1268. An ordinary mild steel bar has been pre-stressed to working stress of 200 MPa. If the Young's modulus of steel is 200 GPa and permanent negative strain due to shrinkage and creep is 0.0008, what is the effective stress left in the steel?
of 200 MPa. If the Young's modulus of steel is 200 GPa and permanent negative strain due to shrinkage and creep is 0.0008,

(a) 190 MPa (b) 170 MPa
(c) 85 MPa (d) 40 MPa

[HPPSC 2016-II]
UPRVUNL AE 2015
ESE-2006

Ans. (d) : Initial pre-stress = 200 MPa
Shrinkage strain (ε_s) $= 8 \times 10^{-4}$
Modulus of elasticity for steel 200 GPa= 200×10^3 MPa
Loss of pre-stress = $\varepsilon_s.E_s$
$= 8 \times 10^{-4} \times 200 \times 10^3 = 160$ MPa
$\therefore$ Remaining stress = 200– 160 = 40 MPa

1269. The suitable system for pre-tensioned beams is:

(a) Hoyer (b) Freyssinet
(c) Roebling (d) BBRV system

Karnataka PSC AE 2017 Paper - II

Ans. (a) : Hoyer's method of pre-stressing is the most common and most widely used method of pre-tensioning. It is also known as long line method.

1270. Most common method of pre-stressing used for factory productions is-

(a) Long line method
(b) Freyssinet system
(c) Magnel-Blaton system
(d) Lee-McCall system

RPSC AE 2018

Ans. (a) Hoyer system or long line method is often adopted in Pre-tensioning large scale production and two bulk heads or abutments independently anchored to the ground are provided several meters a part, say 100 m wires are stretched between the bulk heads. Moulds are placed enclosing the wires.

1271. As per IS 1343-1980, the minimum characteristic strength pre-stressed concrete for post-tensioned and pre-tensioned work is :

(a) 25 MPa and 30 MPa respectively
(b) 25 MPa and 35 MPa respectively
(c) 30 MPa and 35 MPa respectively
(d) 30 MPa and 40 MPa respectively

GPSC AE Class (1&2) Paper - 2 2017

Ans. (d) : As per IS 1343-1980, the minimum characteristic strength pre-stressed concrete for post-tensioned and pre-tensioned work is 30 MPa and 40 MPa respectively.

1272. The loss in pre-stress in pre-tensioning system is primarily due to

(a) Elastic deformation of concrete and cable slippage
(b) Creep and elastic deformation
(c) Shrinkage and creep
(d) Shrinkage and elastic deformation

GPSC AE (CLASS 1 & 2) 2019
ESE 2002


Ans : (c) : The loss in pre-stressed in pre-tensioned are mainly due to
(1) Shrinkage $\rightarrow (3\times10^{-4})\ E_s$
(2) Creep $\rightarrow \phi.m.f_c$.
(3) Loss of stress due to elastic shortening of concrete $\rightarrow \phi.m.f_c$.
(4) Relaxation $\rightarrow$ 1%, 5% of initial pre-stress.

1273. If a simply supported post-tensioned beam of span 'L' is pre-stressed by a straight tendon at a uniform eccentricity 'e' below the centroidal axis and a pre-stressing force 'P' with flexural rigidity of beam as EI, then the maximum central deflection of the beam is

(a) $PeL^2/8EI$(downwards)
(b) $Pel^2/48EI$ (Upwards)
(c) $Pel^3/8EI$ (Upwards)
(d) $PeL^2/8EI$ (Upwards)

GPSC AE (CLASS 1 & 2) 2019
ESE-2003

Ans : (d) :



$$H = \frac{pel^2}{8h}$$

1274. Minimum grade of concrete for pre tensioned pre-stressed concrete:

(a) M20 (b) M30
(c) M40 (d) M45

Kerala PSC AE 2015

Ans. (c) : Minimum grade of concrete for different purpose
(i) PCC - M15 (1 : 2 : 4)
(ii) RCC - M20 (1 : 1.5 : 3)
(iii) Standard concrete grade– M-25 (1 : 1 : 2)
Design mix concrete
(iv) Post tensioned PSC - M30
(v) Pre tensioned PSC - M40

1275. When reinforcement bars placed short of their required length need to be extended, we use:

(a) anchorages
(b) standard bends and hooks
(c) development length
(d) splices

Kerala PSC AE 2015

Ans. (d) : Splices are used for increasing length by joining two reinforced bar in concrete structural member and force is transferred from one to another.
Splicing is basically done by 3 methods:
(i) Lapping of reinforcement bars
(ii) Mechanical joints
(iii) Welded joints

1276. A partially pre-stressed member is one in which

(a) limited tensile stresses and controlled cracking are permitted under service loads

Search on Telegram @apna_pdf

(b) mild steel is used in addition to pre-stressing steel
(c) no tensile stresses are permitted under service loads
(d) limited tensile stresses are permitted but no cracking under service loads

TNPSC AE 2018
ESE 1996

Ans. (a) :
(i) Partial pre-stressing member is tensile stresses such that the cracks with is within the allowable limit.
(ii) Limited pre-stressing is limited tensile stresses and controlled cracking are permitted under service load.
(iii) Full pre-stressing is no tensile stresses allowed.

1277. Which of the following statements are correct with reference to ensuring minimum shrinkage of pre-stressed concrete?
1. The water-cement ratio and proportion of cement paste should be kept minimum to reduce shrinkage.
2. Aggregates of larger size, well graded for minimum void, need a smaller amount of cement paste, and attendant shrinkage will be smaller.
3. Harder and denser aggregates of low water absorptions and high modulus of elasticity will exhibit small shrinkage.

(a) 1 and 2 only (b) 1 and 3 only
(c) 2 and 3 only (d) 1, 2 and 3

ESE 2019


Ans. (d) : Shrinkage in concrete is its contraction due to drying and chemical charges. It depends upon the quantity of water, type of aggregates used in the mix and surrounding atmospheric conditions.
If minimum shrinkage is desired, the water cement ratio and the proportion of cement paste should be kept to a minimum aggregates of larger size, well graded for minimum void, need a smaller amount of cement paste, and shrinkage will be smaller. Harder and denser aggregates of low absorptions and high modulus of elasticity will exhibit small shrinkage. Shrinkage is relatively small for cement high in tricalcium silicate and low in the alkalies and the oxides of sodium and potassium.
The loss of pre-stress due to shrinkage may be of the order of 4 to 6% for pre-tensioned work and 3 to 4% for post-tensioned work.

1278. Consider the following statements:
1. In a reinforced concrete member subjected to flexure, the externally applied moment is resisted by an internal couple formed by steel and concrete and their magnitudes vary with the applied moment, while the lever arm of the internal couple remains constant
2. In a pre-stressed concrete member, the external moment is resisted by an internal couple, but it is the lever arm that changes with the loading conditions and the stress in steel remains practically constant
Which of the above statements is/are correct?
(a) 1 only (b) 2 only
(c) Both 1 and 2 (d) Neither 1 nor 2

ESE 2018

Ans. (c)

RCC PSC



As W↑: T↑: C↑: z (constant) where Z = lever arm
As W↑: Z↑: P(constant)
Both 1 and 2 are correct

1279. An RCC structure with fundamental time period of 1.2 sec vibrates at a forcing frequency of 10 rad/sec. The maximum dynamic displacement is X% of static displacement. The value of X is
(a) 10.1 (b) 28.9
(c) 37.7 (d) 50.2

ESE 2018

Ans. (c) : Time 'T' = 1.2sec.

ω_n = Natural frequency = $\frac{2\pi}{T} = \frac{2\pi}{1.2}$ rad/sec.

ω = Forced frequency = 10 rad/sec.

r = Frequency ratio = $\frac{\omega}{\omega_n} = \frac{10}{\frac{2\pi}{1.2}} = \frac{10\times1.2}{2\pi} = \frac{6}{\pi}$

- Response magnification factor :

$$R_{mf} = \frac{\text{Dynamic displacement}}{\text{Static displacement}}$$

$$R_{mf} = \frac{1}{\left|\left(1-r^2\right)\right|} \text{ for negligible damping.}$$

$$R_{mf} = \frac{1}{\left|1-1.90^2\right|} = 0.377$$


- The maximum dynamic displacement is 37.7% of static displacement.

1280. Consider the following statements regarding suspension cables :
1. The horizontal component of the cable tension in a suspension bridge is constant at every point along the length of the cable
2. Stiffening girders in a suspension bridge carry only the live load
Which of the above statements is/are correct ?
(a) 1 only (b) 2 only
(c) Both 1 and 2 (d) Neither 1 nor 2

ESE 2018

Search on Telegram @apna_pdf

Ans. (c)



- Horizontal component of cable tension at each section is the same and it is equal to horizontal reaction at support.
- Suspension cable bridges are suitable only for small spans and light loads, in case suspension bridges are to be used for large spans and rolling loads as per roadways, these bridges are stiffened with three hinged stiffening girder to make them stiff and thus decreases the sag under the rolling load.
- When the bridges is loaded with uniformly distributed load, whole of the load is directly taken by the cables and there will be no effect on the stiffening girder.
- Stiffening girders help in keeping the cable in shape and resist part of the shear force and bending moment due to live loads.

1281. A simply supported pre-stressed concrete beam is of 25 m span. The initial stress is 1000 MPa. The slip in the jack during tensioning has been 2 mm. If E_s = 200 GPa, the loss of pre-stress due to anchorage slip is

(a) 16% (b) 12%
(c) 10% (d) 1.6%

ESE 2017

Ans. (d) Span length 'ℓ' = 25m

Initial stress (σ_o) = 1000 MPa
Anchorage slip (Δ) = 2mm
E_s = 200 GPa
Loss of stress (due to anchorage slip) $\Delta\sigma$

$$\Delta\sigma = \frac{\Delta}{L}\times E_s = \frac{2}{25\times10^3}\times200\times10^3$$

$$\left[\Delta\sigma = 16\,N/mm^2\right]$$

$$\%\ \text{Loss} = \frac{\Delta\sigma}{\sigma_0}\times100 = \frac{16}{1000}\times100$$


$$\boxed{\%\ \text{Loss of prestress in \%} = 1.6\%}$$

1282. A cable of insignificant weight, 18 m long, is supported at its two ends, 16 m apart, at the same level. The cable supports at its mid-reach a load of 120 N. The tension in the cable is nearly


(a) 136 N (b) 131 N
(c) 126 N (d) 121 N


ESE 2017

Ans. (b)



Apply $\Sigma F_{..} = 0$ at C.





$$\left[x = \sqrt{17}\right]$$

$$\boxed{x = 4.123m}$$

So,

$$2T\sin\theta = 120$$

$$\left[\sin\theta = \frac{4.123}{9}\right]$$

$$2T\times\frac{4.123}{9} = 120$$

$$T = \frac{60\times9}{4.123}$$

$$\boxed{T = 131N}$$

1283. In pre-stressed concrete

(a) forces of tension and compression change but lever arm remains unchanged
(b) forces of tension and compression remains unchanged but lever arm changes with moment
(c) both forces of tension and compression as well as lever arm changes
(d) both forces of tension and compression as well as lever arm remains unchanged

ISRO Scientist/Engineer 2015

Ans : (b) : In pre-stressed concrete forces of tension and compression remains unchanged but lever arm changes with moment.

1284. As per Indian Standard code of practice for pre-stressed concrete (IS 1343 - 1980), the minimum grade of concrete to be used for post tensioned and pre-stressed structural elements are respectively

(a) M 20 for both (b) M 40 & M 30
(c) M 15 & M 20 (d) M 30 & M 40

ISRO Scientist/Engineer 2014

Ans : (d) Minimum grade of concrete–
for pre-tensioned pre-stressed concrete = M40
for post-tensioned pre-stressed concrete = M30

1285. The final deflection of a structure due to all loads including the effects of temperature, creep and shrinkage and measured from the as- cast level of support of floor, roofs and all other horizontal forces should not normally exceed.

(a) span/350 (b) span/250
(c) span/450 (d) span/550

ISRO Scientist/Engineer 2014

Ans : (b) In regard to pre-stressed concrete design the final deflection due to all loads including the effects of temperature, creep and shrinkage and measure from the as-cast level of the supports of floors, roofs and all other horizontal member should not normally exceed span/250.

Search on Telegram @apna_pdf

1286. A concrete beam pre-stressed with a parabolic tendon is shown in the sketch. The eccentricity of the tendon is measured from the centroid of the cross section. The applied pre-stressing force at service is 1620KN. The uniformly distributed load of 45 KN/m includes self weight.

The stress (in N/mm^2) in the bottom fiber at Mid Span is

(a) Tension 2.94
(b) Compression 2.94
(c) Tensile 4.32
(d) Compression 4.32

ISRO Scientist/Engineer 2014

Ans : (b)

1287. The propagation of Shear Crack in pre-stressed concrete member depends on

(a) Tensile Reinforcement
(b) Compression Reinforcement
(c) Shear reinforcement
(d) Shape of the Cross-section of beam

ISRO Scientist/Engineer 2013

Ans : (d) The Shear cracks in pre-stressed concrete members are of two major types.
⇒ Web Shear Cracks
⇒ Flexure Shear Cracks
Cracks depends on the span-to-depth ratio of the beam and loading.

1288. The ultimate moment capacity of a simply supported PSC beam is determined using

(a) Force and moment equilibrium conditions
(b) Stress and strain relationship of concrete and steel
(c) Moment equilibrium and compatibility condition
(d) Force equilibrium equation alone

APTRASCO 2017
ESE 1999

Ans : (a/c)

1289. At the time of transfer of pre-stress.....losses occur.

(a) no (b) instantaneous
(c) time dependent (d) minor

APTRASCO 2017

Ans : (b) At the time of transfer of pre-stress instantaneous losses occur.

1290. Match the following and pick the correct series:

(i) End block	(1) No tensile stress developed
(ii) Type I	(2) Pre-tensioned beam
(iii) Transmission length	(3) Elastic shortening
(iv) Loss of pre-stress	(4) Bursting tension

	(i)	(ii)	(iii)	(iv)
(a)	(1)	(2)	(3)	(4)
(b)	(2)	(3)	(4)	(1)
(c)	(4)	(1)	(2)	(3)
(d)	(1)	(3)	(2)	(4)

APTRASCO 2017
ESE - 2003

Ans : (c) • The transmission length is the length of bond anchorage of the prestressing wire from the end of a pre-tensioned member to the point of full steel stress.
• Type-I–Having no tensile stress developed.

1291. Pre-stressing losses in post-tensioned and pre-tensioned beams are respectively :

(a) 15% and 20% (b) 20% and 15%
(c) 5% and 15% (d) 20% and 20%

OPSC AEE 2019 Paper–I

Ans. (b) : Pre-stressing losses 20% and 15% in post-tensioned and pre-tensioned beams are respectively.

1292. Most common method of pre-stressing used for factory production is :

(a) Long line method
(b) Freyssinet system
(c) Magnel-Blaton system
(d) Lee-Macall system

OPSC AEE 2019 Paper–I

Ans. (a) : Pre-tensioning method is also called long line method. It is suitable for short span and mass production.

Pre-tensioning

In this method the concrete is pre-stressed with tendons before it is placing in position. This method is developed due to bonding b/w the concrete and steel tendons. Pre-tensioning is preferred when the structural element is small and easy to transported.

1293. In pre-stressed concrete :

(a) Forces of tension and compression change but lever arm remains unchanged.
(b) Forces of tension and compression remain unchanged but lever arm changes with the moment.
(c) Both forces of tension and compression and lever arm change.
(d) Both forces of tension and compression and lever arm remain unchanged

OPSC AEE 2019 Paper–I

Ans. (b) :
In pre-stressed concrete
The principle behind pre-stressed concrete is that compressive stresses induced by high strength steel tendons in a concrete member before loads are applied will balance the tensile stresses imposed in the member during service.
In pre-stressed concrete forces of tension and compression remain unchanged but lever arm changes with the moment.

1294. Which one of the following is categorized as long term loss of pre-stress in a PSC member?

(a) Loss due to elastic shortening
(b) Loss due to relaxation of strands
(c) Loss due to anchorage slip
(d) Loss due to friction

PSPCL AE 2012

Ans. (b) : Long term loss of prestessed member in PSC method is time dependent which occurs during service life of structure that include loss due to creep and relaxation and shrinkage.
– Short term losses occurs immediate by Eg. losses like elastic shortening of concrete, anchorage slip, frictional losses.

Search on Telegram @apna_pdf

1295. A post-tensioned prestressed concrete beam is having a cross-section of 300 × 300. The area of end block is 100 × 100 mm. Instead of 100 × 100 mm end block, 150 × 150 mm end block is provided. What will be the reduction in bursting forces? Let the load in tendons be P_k.

(a) 0.03 P_k (b) 0.04 P_k
(c) 0.045 P_k (d) 0.05 P_k

Maharashtra PSC Mains 2018 Paper-1

Ans. (d) : As per IS 1343-1980

Bursting force $F_{bst} = P_k\left[0.32 - 0.3\frac{y_{po}}{y_o}\right]$

P_k = Prestress
y_{po} = length of side of bearing plate
y_o = transverse dimension of end zone
Case-1 :

$$F_{bst\,1} = P_k\left[0.32 - 0.3\times\frac{100}{300}\right]$$
$$= P_k \times 0.22$$

Case-2 :

$$P_k\left[0.32 - 0.3\times\frac{150}{300}\right]$$
$$= P_k \times 0.17$$

$F_{bst\,1} - F_{bst\,2} = (0.22 - 0.17)\,P_k$
$= 0.05\,P_k$

1296. Prestressing in a concrete beam with sloping or curve profile

(a) increases shear strength
(b) increases flexural strength
(c) decreases shear strength
(d) Both (a) and (b)

Maharashtra PSC Mains 2018 Paper-1

Ans. (d) : Prestressing in a concrete beam results in improved shear resistance, due to the effect of compressive prestress, which reduces the principal tensile stress.

1297. The bearing stress on concrete after accounting for all losses due to relaxation of steel, elastic shortening, creep of concrete, slip and seating of anchorage shall not exceed _____ (where, f_{ci} is the concrete strength at transfer, A_{br} is bearing area and A_{pun} is punching area)

(a) $0.16f_{ci}\sqrt{\frac{A_{br}}{A_{pun}}}$ or 0.8 f_{ci} whichever is smaller

(b) $0.48f_{ci}\sqrt{\frac{A_{br}}{A_{pun}}}$ or 0.8 f_{ci} whichever is smaller

(c) $0.25f_{ci}\sqrt{\frac{A_{br}}{A_{pun}}}$ or 0.8 f_{ci} whichever is smaller

(d) $0.34f_{ci}\sqrt{\frac{A_{br}}{A_{pun}}}$ or 0.8 f_{ci} whichever is smaller

Maharashtra PSC Mains 2018 Paper-1

Ans. (b) : On the areas immediately behind external anchorages, the permissible unit bearing stress on the concrete, after accounting for losses due to relaxation of steel, elastic shortening and seating of anchorages, shall not exceed $0.48f_{ci}\sqrt{\frac{A_{br}}{A_{pun}}}$ or 0.8 f_{ci} whichever is smaller, where f_{ci} is the cube strength of transfer, A_{br} is the bearing area and A_{pun} is the punching area.

1298. The approximate value of shrinkage strain for design of post-tensioning member is Where 't' = age of concrete at transfer in days.

(a) $\frac{0.0001}{\log_{10}(t+2)}$ (b) 0.0003
(c) $\frac{0.0002}{\log_{10}(t+2)}$ (d) $\frac{0.0003}{\log_{10}(t+2)}$

Maharashtra PSC Mains 2018 Paper-1

Ans. (c) : For post tensioned beam, total residual shrinkage strain = $\frac{2\times10^{-4}}{\log_{10}(t+2)}$

1299. In case of prestressed concrete element, which statement in not correct?

(a) Concrete remains uncracked and it protects steel from corrosion.
(b) It can be used more effectively in liquid retaining structures.
(c) The stiffness of structure is less due to uncracked condition of concrete.
(d) Shear resisting capacity is increased due to pre-compression.

Maharashtra PSC Mains 2018 Paper-1

Ans. (c) : Advantage of prestressed concrete:
(1) More shear resistance due to effect of compressive prestress.
(2) More effective in water retaining structures.
(3) Reduced deflection, Hence more stiffener.

1300. Prestressing force transmitted to concrete as initial stress to counteract the internal stress developed due to external loads is called

OR

The pre-stressed concrete is considered as a combination of steel and concrete, with steel taking tensile force passing through the tendon and concrete taking compressive force passing through the C.G. of stress distribution so that the two material form a resisting couple to resist external moment. This concept is called as


(a) Stress concept
(b) Strength concept
(c) Force concept
(d) Load balancing concept

Maharashtra PSC Mains 2018 Paper-1
Maharashtra PSC AE (Mains) 2012 Paper–I

Ans. (a) : Pre-stressing force transmitted to concrete as initial internal stress to counteract the internal stress developed due to external loads is called balancing concept.

Search on Telegram @apna_pdf


1301. A simply supported beam of span 9 m is subjected to two point loads, each of 10 kN acting at $\frac{1}{3}$ of span as shown in the figure. It self-weight of beam is neglected, then how much prestressing force is required to counter-balance the external loads if θ = 30°?



(a) 5 kN (b) 10 kN
(c) 20 kN (d) 30 kN

Maharashtra PSC Mains 2018 Paper-1

Ans. (c) :



$e = 3 \sin 30° = \frac{3}{2} = 1.5m$

for concept load balance

$P_e = 10 \times 3$

$P \times 1.5 = 30$

$P = 20$ kN

1302. The maximum effective reinforcement ratio of a bounded prestressed concrete beam at failure according to IS : 1343 is limited to a value of

(a) 0.15 (b) 0.40
(c) 0.25 (d) 0.40

Maharashtra PSC Mains 2018 Paper-1

Ans. (b) : As per table 11, of IS 1343, maximum effective reinforcement ratio $\left(\frac{A_p f_p}{bd f_{ck}}\right)$ is 0.4.

1303. For pre-tensioned prestressed concrete, the grade of concrete shall be not less than

(a) M_{30} (b) M_{40}
(c) M_{50} (d) M_{60}

GPSC AE March 2018

Ans. (b) : Minimum grade of concrete for
Pretension member = M 40
Post tension member = M 30

1304. Which of the following losses of prestress occurs only in pre-tensioning and not in post-tensioning ?

(a) elastic shortening of concrete
(b) shrinkage of concrete
(c) creep of concrete
(d) loss due to friction

GPSC AE March 2018

Ans. (a) : Elastic shortening of concrete losses occurs in pre-tensioning only

Loss of stress = $f_c(m)$

f_c = average stress, m = modular ratio

1305. The amount of reinforcement provided in precast concrete piles is usually governed by

(a) hammer force
(b) direct load on the pile
(c) frictional resistance
(d) handling forces

GPSC AE March 2018

Ans. (d) : Concrete piles usually have a strength in excess of 700 kPa and net pr. of 150 kPa. Handling may be done for reinforcement and handling force is considered.

1306. Vertical limits within which cable is to be provided in a post-tensioned prestressed concrete element is called as

(a) End block
(b) Safe cable zone
(c) Anchorage zone
(d) Transmission length zone

GPSC Poly. Tech. Lect. 2016
Maharashtra PSC AE (Mains) 2012 Paper–I

Ans. (b) : An allowable cable zone is produced within which the profile may take any shape. The term cable is used to denote the resultant of all the individual tendors.

1307. Loss of prestress due to friction between prestressed tendons and surrounding concrete depend upon

(a) Curvature of Tendon
(b) Wobbling effect
(c) Both (a) and (b)
(d) None of the above

GPSC Poly. Tech. Lect. 2016

Ans. (c) : Loss of prestress due to friction–There will be considerable movement of sliding of tendon relative to the surrounding concrete depend upon curvature of tendon and wobbling effect during tensioning operation.

1308. In case of prestressing system, the loss of stress in steel due to creep of concrete, the creep coefficient is given by

(a) $\frac{\text{Creep strain}}{\text{Elastic strain}}$ (b) $\frac{\text{Elastic strain}}{\text{Creep strain}}$
(c) $\frac{\text{Creep stress}}{\text{Elastic stress}}$ (d) $\frac{\text{Creep stress}}{\text{Elastic strain}}$

GPSC Poly. Tech. Lect. 2016

Ans. (a) : The creep of concrete causes loss of stress in tensioned steel. The creep coefficient of concrete for loss of prestress is defined as the ratio of creep strain to the elastic strain.

1309. Which of the following is not a loss in Pretensioning system of Prestressing?

(a) Elastic deformation of concrete

Search on Telegram @apna_pdf

(b) Shrinkage of concrete
(c) Friction loss
(d) Creep of concrete

GPSC Poly. Tech. Lect. 2016

Ans. (c) : Loss in pretensioning system of prestressing due to creep and shrinkage of the concrete, Elastic deformation of concrete.

1310. The stage at which the tendon force is released on concrete permanently is called
(a) Pre-tensioning
(b) Post-tensioning
(c) Anchoring
(d) Transfer

UPSC JWM 2017

Ans. (d) : When concrete structure subjected to loading for super structure then dead load transfer to beam to column at column to footing is called transfer.

1311. The loss of prestress due to elastic shortening of concrete is least in
(a) One wire pre-tensioned beam
(b) One wire post-tensioned beam
(c) Multiple wire pre-tensioned beam with sequential cutting of wires
(d) Multiple wire post-tensioned beams subjected to sequential prestressing

UPSC JWM 2017

Ans. (b) In one wire post-tensioned beam tension force are coming after loading applied on beam v counteract tension.

1312. Grouting of ducts in post-tensioned concrete construction causes
(a) Reduction in pre-stress
(b) Increase in pre-stress
(c) Reduction in corrosion
(d) Increase in corrosion


UPSC JWM 2017

Ans. (c) : Grouting of ducts surrounding post tensioning tendon provide the necessary mechanical to tranfer stress between tendons of concrete of protect against corrosion.

1313. A concrete beam of rectangular cross-section of 200mm × 400 mm, is prestressed with a force of 400 kN at an eccentricity of 100 mm. The maximum compressive stress in the concrete is
(a) 3.5 N/mm^2 (b) 5.5 N/mm^2
(c) 8.5 N/mm^2 (d) 12.5 N/mm^2

UPSC JWM 2017

Ans. (d) :



$$\sigma_c = \frac{-pe\, y_{max}}{I} - \frac{P}{A}$$

$$= -\frac{400\times10^3\times100\times200\times12}{200\times400^3} - \frac{400\times10^3}{200\times400}$$

$$= -7.5-5$$

$$\sigma_c = -12.5 \text{ N/mm}^2$$

1314. In pre-stressed concrete members the final deflection due to a X loads including the effects of temperature, creep and shrinkage shall not exceed
(a) Span/350 (b) Span/250
(c) Span/300 (d) Span/180

GOA PSC Assistant Prof. 2020

Ans. (b) : The final deflection due to all loads including the effects of temperature creep and shrinkage should normally not exceed (span/250) is the first recommendation made by IS: 1343-1980 with regard to limit state of deflection.

1315. The use of concordant cables in prestressed continuous beams induces
(a) initial support reactions
(b) no initial support reactions
(c) excess cracking
(d) excess deflection

TRB Poly. Tech. Lect. 2012
ESE-2006, 2010

Ans. (b) A concordant cable profile is a profile given for the cable such that the consequent C-line coincides with P-line, when external loads are not applied. This mean when a concordant profiles is provided there will be no reactions at the supports due to prestressing alone.

1316. Losses in prestress in pretensioned beams are more than the losses in post tensioned beams due to the
(a) effect of elastic shortening
(b) frictional force through bonding
(c) excess shrinkage
(d) anchorage slip

TRB Poly. Tech. Lect. 2012

Ans. (a) : Losses in pre-stress in pre-tensioned beams are more than the losses in post tensioned beam due to the effect of elastic shortening.

1317. A simply supported beam of span 24 m is to be designed to carry a central concentrated load of 200 kN. If 40 cm is the dip of the cable at the loading point from the neutral axis, the effective prestress is
(a) 300 kN (b) 3000 kN
(c) 200 kN (d) 2000 kN

TRB Poly. Tech. Lect. 2012

Ans. (*) :

1318. After pre-stressing process is completed, a loss in stress is due to
(a) shrinkage of concrete
(b) elastic shortening of concrete
(c) creep of concrete and steel
(d) all the above

UKPSC(Urban engineering)-2011

Ans. (d) : The reduction in the pre-stressing force is called loss in prestess, this process completed by shrinkage of concrete, elastic shortening of concrete, creep of concrete and steel.

Search on Telegram @apna_pdf


1319. The profile of a tendon is parabolic with a central dip 'h' and effective prestressing force is 'P' and the span is 'L'. What is the equivalent upward acting uniform load?

(a) $\frac{8hL}{P}$ (b) $\frac{8h^2L}{P}$

(c) $\frac{8hP}{L^2}$ (d) $\frac{8hP}{L}$

UJVNL AE 2016
ESE-2006

Ans. (c) :



$$w_0 = \frac{8P \times h}{l^2}$$

$$w_0 = \frac{8Ph}{l^2}$$

1320. Which of the following system is suitable for pre tensioning of the members.


(a) Freyssinet system (b) Gifford-udal system

(c) Lee-Me call system (d) Hoyer system

UJVNL AE 2016
ESE-2005

Ans. (d) : The Hoyer system is generally used for the production on larger scale of pre-tensioned structure element of the structure only such type of method consist of stretching the wires at greater distance apart.

1321. If 'P' is the prestressing force applied at a maximum eccentricity 'g' at mid span (figure), to balance the concentrated load 'W', the balancing load will be



(a) 2.5 Pg/L (b) 3.0 Pg/L

(c) 3.5 Pg/L (d) 4.0 Pg/L

APPSC AEE 2012

Ans. (d) : $P.g = \frac{WL}{4}$

$$W = \frac{4Pg}{L}$$

1322. In pre-tensioning process of pre-stressing, the tendons are :

(a) not bonded to the concrete

(b) partially bonded to the concrete

(c) bonded to the concrete

(d) generally bonded but sometimes can remain unbonded

UPPCL AE 2015
ESE-2003

Ans. (c) : In pre-tensioning, the steels tendon are tensioned before the concrete is cost. The tenders are temporarily anchored against some abutments and the cut after the concrete has been placed.

1323. Loss of stress in the prestressing steel due to elastic shortening of concrete in rectangular concrete beam (120 mm × 200 mm) prestressed with a force of 150 kN at an eccentricity 20 mm, cross-sectional area of prestressing steel 187.50 mm^2, modulus of elasticity of steel and concrete is 2.1×10^5 MPa and 30000 MPa respectively is

(a) 5% (b) 7%

(c) 6% (d) 8%

BPSC AE Aug. 2019 Paper-V

Ans. (b) : Rectangular beam = 120 mm × 200 mm

Prestressing force = 150kN (P)

Eccentricity (e) = 20 mm $A_{st} = 187.5\ mm^2$

$E_{st} = 2.1\times10^5$ MPa $E_c = 30000$MPa

$$\text{Loss of stress due to elastic shortening} = \frac{P}{A_c}\left(\frac{E_s}{E_c}\right)$$

$$\text{shortening} = \frac{150\times1000}{120\times200-187.5}\left(\frac{2.1\times10^5}{30000}\right)$$

$$= 44.10\ N/mm^2$$

$$\text{Initial stress} = \frac{P}{A_{st}} = \frac{150\times1000}{187.5}$$

$$= 800\ N/mm^2$$

Loss of stress due to elastic shortening of concrete

$$= \frac{44.10}{800}\times100 = 5.51\% \approx 6\%$$

1324. Prestressing is possible by using

(a) Mild steel

(b) High strength deformed bars

(c) High tensile steel

(d) High carbon steel

GPSC AE June 2019

Ans. (c) : Prestressing is possible by using High tensile steel. Prestressed concrete also reduce the overall weight of structures. High yield strength steel alloys are used to producing permanent pre-compression in areas subjected to tension.

1325. The grade of concrete for prestresses members should be in the range of

(a) M20-M30 (b) M80-M100

(c) M30-M60 (d) M15-M30

GPSC AE June 2019

Ans. (c) : The grade of concrete for prestressed members should be in the range of M30–M60.

1326. If the beam is prestressed using mild steel at an initial stress of 140N/mm^2, then the initial strain is (take E of Mild steel as 2 × 10^5 N/mm^2)

(a) 0.006 (b) 0.007

(c) 0.028 (d) 0.0028

GPSC AE June 2019

Search on Telegram @apna_pdf

Ans. (b) : initial stress = 140 N/mm^2
$E = 2 \times 10^5$ N/mm^2
$\sigma = \varepsilon E$
Strain $(\varepsilon) = \frac{\sigma}{\delta} = \frac{140}{2\times10^5} = 0.007$
Initial strain = 0.007

1327. Which of the following losses is present in Post-tensioning but absent in Pre-tensioning?
(a) Relaxation of Stress in Steel
(b) Creep of Concrete
(c) Shrinkage of Concrete
(d) Anchorage Slip

GPSC AE June 2019

Ans. (d) : Losses in various prestressing system–

Types of Loss	Pretensioning	Post Tensioning
(1) Anchorage slip	No	Yes
(2) Friction loss	No	Yes
(3) Creep & shrinkage of concrete	Yes	Yes
(4) Relaxation of steel	Yes	Yes

1328. A post tensioned concrete beam is prestressed by means of three cables each 100 mm^2 area and stressed to 1100 MPa. All three cables are straight and located at an eccentricity of 50 mm. If modular ratio (m) = 6 and stress in concrete at the level of steel (f_c) = 5 MPa, then what is the loss of stress in cables due to elastic shortening if all cables are simultaneously tensioning and anchoring?
(a) 90 MPa (b) 60 MPa
(c) 30 MPa (d) 0 MPa

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (d) : In post tensioned concrete loss due to elastic shortening is zero.

1329. At the time of initial tensioning, the maximum tensile stress f_{pi} immediately behind the anchorage shall not exceed ..... of the ultimate tensile strength f_{pu} of the wire or bar or strand.
(a) 55% (b) 69%
(c) 76% (d) 85%

Maharashtra PSC (Mains) 2019 Paper–I
ESE-2007

Ans. (c) : At the time of initial tensioning, the maximum tensile stress f_{pi} immediately behind the anchorage shall not exceed 76% of the ultimate tensile strength f_{pu} of the wire or bar or strand.

1330. A system usually adopted in the production of pre-tensioned members like railway sleepers, poles, etc. on large scale is .....
(a) Magnel-Blaton system
(b) P.S.C. Monowire system
(c) Hoyer system
(d) Gifford-Udall system

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (c) : A system usually adopted in the production of pretensioned members like railway sleepers, poles etc.

1331. On the areas immediately behind external anchorages, the permissible unit bearing stress on the concrete, after accounting for losses due to relaxation of steel, elastic shortening and seating of anchorages, shall not exceed .....
(a) $0.48 f_{ci}\sqrt{\frac{A_{bearing}}{A_{punching}}}$ or $0.8\ f_{ck}$ whichever is smaller
(b) $0.45 f_{ci}\sqrt{\frac{A_{bearing}}{A_{punching}}}$ or $0.40\ f_{ck}$ whichever is smaller
(c) $0.48 f_{ci}\sqrt{\frac{A_{bearing}}{A_{punching}}}$ or $0.76\ f_{ck}$ whichever is smaller
(d) $0.40 f_{ci}\sqrt{\frac{A_{bearing}}{A_{punching}}}$ or $0.78\ f_{ck}$ whichever is smaller

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (a) : $0.48\ f_{ci}\sqrt{\frac{A_{bearing}}{A_{punching}}}$ or $0.8\ f_{ck}$ whichever is smaller.

1332. The net downward force of pre-stressed concrete beam with bent tendon is given as:
(a) w – 2p sin θ (b) w + 2p sin θ
(c) Zero (d) 2

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (a) The net downward force of prestressed concrete beam with bent tendon is given as
W - 2P sin θ

1333. High tensile bars threaded at the ends are used in:
(a) Freyssinet system
(b) Gifford-Udall system
(c) Lee-McCall system
(d) Magnel - Blaton system

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (c) : High tensile bars threaded at the ends are used in Lee-McCall system.

1334. In a prestressed concrete beam, the ratio of applied prestressing force (P) to the concrete capacity of the section in compression is known as
(a) Moment ratio (R)
(b) Eccentricity ratio (∈)
(c) Reinforcement ratio (m)
(d) Efficiency factor (ρ)

Maharashtra PSC (Mains) 2019 Paper–I

Search on Telegram @apna_pdf

Ans. (d) : In a prestressed concrete beam, the ratio of applied prestressing force (P) to the concrete capacity of the section in compression is known as efficiency factor (ρ)

1335. A simply supported prestressed concrete beam of span 10 m is subjected to a point load of 10 kN at centre. Prestressing force of 2000 kN is applied through inclined tendon, zero eccentricity at support and 'e' at mid-span. To nullify the external point load effect, how much 'e' should be provided? Neglect the self weight of beam.

(a) 12.5 mm (b) 50 mm
(c) 70 mm (d) 85 mm

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (a) : $M_{max} = P \times e$

$$M_{max} = \frac{WL}{4} = \frac{10 \times 10 \times 10^3}{4} = 25000 \text{ kN-mm}$$

$M_{max} = P \times e$
$25000 = 2000 \times e$
$e = 12.5$ mm

1336. As per IS, the minimum characteristic strength of concrete to be used in pre-tensioned and and post-tensioned pre-stressed concrete works shall be respectively :

(a) 30 MPa, 25 MPa (b) 35 Mpa, 25 MPa
(c) 40 MPa, 30 MPa (d) 40 MPa, 25 MPa

BHEL ET 2019

Ans. (c) : As per IS, the minimum characteristic strength of concrete to used in pre tensioned and post tensioned prestressed concrete works shall be respectively 40 MPa and 30 MPa.

1337. Which of the following is categorized as a long term loss of prestress in a prestressed concrete member:

(a) Loss due to relaxation of strands
(b) Loss due to anchorage slip
(c) Loss due to friction
(d) Loss due to elastic shortening

PTCUL AE 2016

Ans. (a) : Loss due to relaxation of strands is categorized as a long term loss of prestress in a prestressed.

1338. A prestressed concrete rectangular beam of size 300×900mm is prestressed with an initial prestressing force of 700kN at an eccentricity of 350mm at midspan ,stress at top fiber at midspan due to prestress alone is :-

(a) 46 MPa (tension)
(b) 8.64 MPa (compression)
(c) 2.59 MPa (compression)
(d) Zero

UPPCL AE 2014

Ans. (b) : Stress of top fiber $= \frac{P}{A} + \frac{Pey}{I}$

$$= \frac{700 \times 10^3}{300 \times 900} + \frac{700 \times 10^3 \times 350 \times 450}{300 \times \frac{900^3}{12}}$$

$= 8.64$ MPa

1339. The profile of the prestressing steel in prestressed concrete member follows

(a) Axial force diagram
(b) Shear force diagram
(c) Bending moment diagram
(d) None of the above

APPSC AEE 2016

Ans. (c) : Profile of prestressing steel in prestressed concrete member follows bending moment diagram.

1340. For simply supported prestressed concrete beam having uniformly distributed load on its entire span the pre stressing tendon has the maximum eccentricity at

(a) The supports
(b) The centre having maximum moment
(c) The quarter points
(d) The section having maximum shear

GPSC AE January 2018

Ans. (b) : In a simply supported prestressed concrete beam for UDL on entire span, bending moment diagram has parabolic shape and maximum moment at centre,
$\boxed{M = Pe}$ so, $\boxed{M_{max} = Pe_{max}}$
maximum eccentricity will be at centre.

1341. The loss of pre-stress due to shrinkage of concrete is the product of

(a) Modular ratio and percentage of steel
(b) Modulus of elasticity of concrete and shrinkage of concrete
(c) Modulus of elasticity of steel and shrinkage of concrete
(d) Modular ratio and modulus of elasticity of steel.

MPPSC AE 2014

Ans. (c) The loss of stress due to shrinkage of concrete is estimated as (IS:1343)-
loss of stress=$\varepsilon_{cs} \times E_s$
ε_{cs}- Total residual shrinkage strain having value 3×10^{-4} for pre tensioning and $\left[\frac{2 \times 10^{-4}}{\log_{10}(t+2)}\right]$ for post tensioning.
t – age of concrete of transfer in days
E_s – modulus of elasticity of steel

1342. Pre-stressed concrete is more desirable in case of

(a) Cylindrical pipes subjected to internal fluid pressure
(b) Cylindrical pipes subjected to external fluid pressure
(c) Cylindrical pipes subjected to equal internal and external fluid pressures
(d) Cylindrical pipes subjected to end pressures

MPPSC AE 2014

Ans. (a) : Pre-stressed concrete is more desirable in case of cylindrical pipe subjected to internal fluid pressure.

Search on Telegram @apna_pdf

1343. Consider the following two statements, in the context of a post-tensioned beam of fixed cross-section:
Statement I: Bursting tensile forces will affect the end zone reinforcement
Statement II: Bursting tensile forces increase with increase in the size of the bearing plate
Which of the following is CORRECT?
(a) Both Statement I and Statement II are true
(b) Statement I is false, but Statement II is true
(c) Both Statement I and Statement II and false
(d) Statement I is true, but Statement II is false

UPPCL AE 2018

Ans. (d) : Statement I :
Bursting tensile forces will affect the end zone reinforcement.
Statement II:
Bursting tensile force does not increase with increase in the size of the bearing plate.

1344. Loss in pre-stress due to friction occurs _____.
(a) Only in post-tensioned beams
(b) in neither pre-tensioned nor post-tensioned beams
(c) only in pre-tensioned beams
(d) in both pre-tensioned and post-tensioned beams

UPPCL AE 2018

Ans. (a) Loss in pre-stressed due to friction occurs only in post-tensioned beams.

1345. For a loss due to the shrinkage of concrete, the shrinkage strain value for pre-tensioned element is :
(a) 0.0003 (b) 0.0002
(c) 0.0006 (d) 0.0004

DMRC AM 2020

Ans. (a) : For a loss due to the shrinkage of concrete, the shrinkage strain value for pre-tensioned elements is 0.0003.

1346. As per IS 1343 : 1980, members having no tensile stress permitted under working conditions are known as :
(a) limited pre-stressed members
(b) partially pre-stressed members
(c) half pre-stressed members
(d) fully pre-stressed members
(e) initially pre-stressed members

CGPSC AE 2017

Ans. (d) As per IS 1343 : 1980, number having no tensile stress permitted under working condition are known as fully pre-stress and members.

1347. The minimum clear cover for post-tensioned members as per IS codal recommendations is :
(a) 30 mm (b) 20 mm
(c) 50 mm (d) 15 mm
(e) 75 mm

CGPSC AE 2017

Ans. (a) The minimum clear cause for post - tensioned members as per IS code recommendations is 30 mm.

1348. As per IS code, for pre-tensioning the total residual shrinkage strain is :
(a) 3×10^{-4} (b) 2×10^{-4}
(c) 6×10^{-4} (d) 2.5×10^{-5}
(e) 5.5×10^{-5}

CGPSC AE 2017

Ans. (b) As per IS code, for pre-tensioning the total residual shrinkage strain is 2×10^{-4}.

1349. The concrete used for post-tensioned system should have a cube strength of :
(a) 60 N/mm^2 (b) 10 N/mm^2
(c) 30 N/mm^2 (d) 50 N/mm^2
(e) 20 N/mm^2

CGPSC AE 2017

Ans. (c) The concrete used for post - tensional system should have a cube strength of 30 N/mm^2.

1350. A concrete beam of rectangular cross-section of 200 mm × 400 mm is prestressed with a force of 400 kN at an eccentricity of 100 mm. The maximum compressive stress in the concrete is:
(a) 12.5 N/mm^2 (b) 7.5 N/mm^2
(c) 5.0 N/mm^2 (d) 2.5 N/mm^2

Haryana PSC AE 2017
ESE-2012

Ans. (a) : Compressive stress $= \frac{P}{A} \pm \frac{Pe}{Z}$

$$\frac{400 \times 10^3}{(200 \times 400)} \pm \frac{400 \times 10^3 \times 100}{5.3 \times 10^6}$$

$$Z = \frac{BD^2}{6} = \frac{200 \times 400^2}{6} = 5.33 \times 10^6\, mm^3$$

$= 5 \pm 7.5 = -2.5$ MP or + 12.5 MPa

1351. Prestressing force in a wire under thermal stressing can be estimated from which of the following?
1. Pressure gauge with jack
2. Elongation of wire
3. Temperature rise
Select the correct answer using the codes given below:
(a) 1 and 2 only (b) 1 and 3 only
(c) 2 and 3 only (d) 2 only

Haryana PSC AE 2017
ESE-2007

Ans. (c) :

1352. In a prestressed member it is advisable to use -
(a) High strength concrete only
(b) High strength concrete & high tensile steel
(c) Low strength concrete but high, tensile steel
(d) High strength concrete but low tensile steel

Rajasthan VP ITI 2018
ESE-2014

Ans. (b) In a prestressed member it is advisable to use high strength concrete & high tensile steel

Search on Telegram @apna_pdf

1353. For a pretensioned rectangular plank of length L, the uplift at centre on release of wires from anchorages due to pretensioning only will be -

(a) $PL^2e/8EI$ (b) $PL^2e/10EI$


(c) $PL^2e/12EI$ (d) $PL^2e/16EI$

(where P = force, e = constant eccentricity and EI = flexural rigidity)


Rajasthan VP ITI 2018
ESE 1996, 2006

Ans. (a) The value of deflection in prestressed member


$$\Delta = \frac{-PeL^2}{8EI}$$



$$\Delta = \frac{-5PeL^2}{48EI}$$



1354. Following figure shows the analysis of a pre-stressed concrete beam with a parabolic cable.



What would be the net downward load?

(a) 12 kN/m (b) 13 kN/m

(c) 14 kN/m (d) 15 kN/m

UPRVUNL AE 2014
ESE 2009

Ans. (c) : A parabolic tendon carrying a tension P will provide an upward uniformly distributed load or pressure is given by–

$$\left[W_c = \frac{8Pe}{L^2}\right]$$

eccentricity 'e' = 200 mm, P = 1000 kN, L = 10m

$$W = \frac{8 \times 1000 \times 200 \times 10^3}{(10)^2} = 16\,kN/m$$

$\therefore$ Net downward loading = $30 - W_c$

$= 30 - 16 = 14$ kN/m

1355. In pre-stressed concrete why do we prefer M 40 concrete over M 20 concrete?

(a) To overcome bursting stresses at the ends

(b) To avoid brittle failure of concrete

(c) To eliminate the effect of shrinkage

(d) To economize the use of cement

UPRVUNL AE 2014
ESE-2004

Ans. (a) : M-40 will have more bond strength and bearing as compared to M-20 because it is less liable to shrinkage cracks and has higher modulus of elasticity and smaller ultimate creep strain.

1356. The strain distribution in the limit state design of pre-stressed concrete structure is assumed to be :

(a) Linear

(b) Non-linear

(c) Parabolic

(d) Parabolic and rectangular

UPRVUNL AE 2014
ESE-2003

Ans. (a) : It is assumed that plane sections normal to the axis remain plane after bending.
This implies that the strain distribution is assumed to be linear.

1357. Why is high grade concrete used in pre-stressed concrete?

(a) To control the pre-stress loss

(b) To have concrete of low ductility

(c) To have concrete of high brittleness

(d) To have low creep

UPRVUNL AE 2014

Ans. (a) : In pre-stressed concrete high grade concrete used to control the pre-stress loss.

1358. For estimating ultimate strength in flexure of a prestressed beam, the stress block in concrete

(a) should be parabolic

(b) should be parabolic-rectangular

(c) should be rectangular

(d) may be of any shape which provides agreement with the test data

UPRVUNL AE 2014
ESE 2001

Ans. (d) : For estimating ultimate strength in flexure of a prestressed beam, the stress block in concrete may be of any shape which provide agreement with the test data.

1359. How do the tendons bond in pre-tensioning process of pre-stressing?

(a) Bonded to the concrete

(b) Partially bonded to the concrete

(c) Not bonded to the concrete

(d) Generally bonded but sometimes remain unbounded to the concrete

UPRVUNL AE 2014

Ans. (a) Pre-Tensioning : In pre-tensioning system, the high strength steel tendons are pulled
Between two end abutments prior to the casting of concrete and the abutments are fixed at the ends of a prestressing bed.

Search on Telegram @apna_pdf

Once the concrete attains the desired strength for prestresing the tendons are cut loose from in the abutments.
The prestress is transferred to he concrete from the tendons, due to the bond between them.

1360. The primary reason for the use of high strength concrete in prestressed structural elements is that

UPRVUNL AE 2014
ESE 1995

or

For pre-stressed structural elements, high strength concrete is used primarily because

(a) Both shrinkage and creep are more
(b) Shrinkage is less but creep is more
(c) Modulus of elasticity and creep values are higher
(d) Of high modulus of elasticity and low creep

UPRVUNL AE 2015
GPSC AE (CLASS 1 & 2) 2019

Ans : (d) High grade cement is used in pre-stress members as they have high modulus of elasticity and low value of creep. Modulus of elasticity of a material shows the rigidity of that material. Creep shows the deformation due to load. According to IS code 456-2000.

$$E_c = 5000\sqrt{f_{ck}}$$

E_C is modulus of elasticity
f_{ck} – compressive strength of concrete.

1361. IS: 1343-1980 limits the minimum characteristic strength of pre-stressed concrete for post tensioned works and pretension work as :

(a) 25 MPa, 30 MPa respectively
(b) 25 MPa, 35 MPa respectively
(c) 30 MPa, 35 MPa respectively
(d) 30 MPa, 40 MPa respectively

HPPSC Poly. Lect. 2016

Ans : (d) For post tensioning work minimum grade of concrete as specified in IS 1343 is M35, while for pre-tension prestressed work grade of concrete specified in IS 1343 in M 40.


1362. Stress at transfer in top most fiber in prestressed structure is:

(a) $f_{sup} - \frac{M_g}{Z_t} \le f_{tt}$ (b) $f_{sup} + \frac{M_g}{Z_t} \ge f_{tt}$

(c) $f_{sup} - \frac{M_g}{Z_t} \ge f_{tt}$ (d) $f_{sup} + \frac{M_g}{Z_t} \le f_{tt}$

IRCON AE 2017

Ans. (b) : Top fiber stress =



$$f_{sup} + \frac{M_g}{z_t} \le f_{tt}$$

z_t = section modulus at top
M_g = bending moment at top fiber
f_{tt} = Total stress at top
f_{sup} = direct stress
Bottom fiber stress:

$$f_{sup} - \frac{M_g}{z_t} \le f_{bt}$$

1363. In case of pretensioning, tensioning force should be applied

(a) gradually and uniformly
(b) quickly
(c) in steps
(d) none of the above

WBPSC AE 2014

Ans. (a) : In case of pretensioning, tensioning force should be applied gradually and uniformly.

1364. Post tensioning is common in structures like

(a) Electric poles (b) slabs
(c) Small water tanks (d) Bridges

WBPSC AE 2001

Ans. (d) : In post tension, the tenders are tensioned after the concrete has hardened. Post tensioning is common is structures like bridges.

1365. In prestressed concrete construction high tensile steel is used for prestressing because

(a) It can retain enough residual strength after initial losses
(b) It required less quantity of steel
(c) It matches well with high strength concrete
(d) It has high ductility

WBPSC AE (PHE) 1998

Ans. (a) : High strength concrete is less liable to shrinkage cracks and has lighter modulus of elasticity and smaller ultimate creep strain resulting in a smaller loss of prestress steel therefore high tensile steel is made for prestress concrete.

1366. Long term losses in a post-tensioned girded are due to

(a) elastic shortening, creep, shrinkage
(b) creep, shrinkage, relaxation
(c) creep, shrinkage, slip
(d) relaxation, friction, creep, shrinkage

WBPSC AE (Common) 1998

Ans. (b) : Long term loss of prestessed member in PSC method is time dependent which occurs during service life of structure that include loss due to creep and relaxation and shrinkage.
– Short term losses occurs immediate by Eg. losses like elastic shortening of concrete, anchorage slip, frictional losses.

1367. In pre-stressed concrete members, percentage concrete sectional area utilised

(a) 50% (b) 67%

Search on Telegram @apna_pdf

(c) 75% (d) 100%

WBPSC AE (Common) 1998

Ans. (c) : In pre stressed concrete member, percentage concrete sectional area utilised is 75%.

1368. The loss stress due to creep in steel in a pre-stress problem is given by the formula _____, where α = creep coefficient, f_c = stress in concrete, E_c = modulus of elasticity of concrete and E_s = modulus of elasticity of steel.

(a) $\alpha(f_c/E_c)\,E_s$ (b) $\alpha(f_c/2E_c)\,E_s$

(c) $\alpha(f_c/E_s)\,E_c$ (d) $2\alpha(f_c/E_c)\,E_s$

TSPSC Deputy Engineer 2015

Ans. (a) : Creep coefficient $= \dfrac{\text{Creep strain}}{\text{Elastic strain}}$

$$\alpha = \frac{E_c}{E_e}$$

$$E_c = \alpha E_e$$

$$E_c = \alpha\left[\frac{f_c}{E_e}\right]$$

Hence, loss of stress in steel $= E_c E_s$

$$= \alpha\left[\frac{f_c}{E_e}\right]E_s$$

1369. The principal reason for adopting pre-stressing cable profiles in flexure members as parabolic is due to the fact that _____.

(a) They need to resist both bending moments and shear force in members.

(b) The strength of pre-stressing cables is maximum in parabolic shapes only.

(c) The profile of moment caused by self weight of structure is parabolic and to counter this, the cable profile also needs to be parabolic.

(d) Its a regular practice.

TSPSC Deputy Engineer 2015

Ans. (c) : For adopting pre-stressing the profile of moment caused by self weight of structure is parabolic and to counter this, the cable profiles also need to be parabolic.

1370. The minimum grade of concrete to be used for pre-tensioned and post-tensioned prestressed concrete work respectively is

(a) M 30, M 30 (b) M 40, M 40

(c) M 40, M 30 (d) M 30, M 40

TSPSC AEE 2017

Ans. (c) : In pre-stressed members high grade of concrete is used. w/c ratio is also kept low. To prepare concrete mix we used admixtures and to compact we use vibrators. In high strength concrete shrinkage cracks are very less, creep is less and loss of stress in steel is also very less some facts about per stressed concrete.

(i) water cement ratio – 0.45

(ii) slump value = 75mm

(iii) Grade of cement –

(a) For pre-tensioned member = M–40

(b) for post-tensioned member = M–30

1371. The type of prestressed concrete member in which tensile stresses are allowed but no visible cracking is

(a) Type 1 (b) Type 2

(c) Type 3 (d) Type-4

TSPSC AEE 2017

Ans. (b) : • **Type-1**– Refers to a fully prestressed concrete and no tensile stresses.

• **Type-2**–To limit prestressing of concrete where tensile stresses do not exceed the cracking stresses of concrete.

• **Type-3**–The structure are those which allow tensile stresses to occur leading to limited crack widths and that too under extraordinary loading conditions which may occur rearly on the structure.

1372. In pre-stressed concrete, concrete of high strength is used

Consider the following statements:

1. It results in smaller cross-section

2. Bearing stresses are generated in anchorage zones

3. Shrinkage cracks are reduced.

Of the above the correct statements are:

(a) 1 and 2 (b) 2 and 3

(c) 3 and 1 (d) 1, 2 and 3

Chandigarh SDE 2017

Ans. (d) : High strength concrete–

• High strength concrete is less liable to the shrinkage cracks.

• It also has s higher modulus of elasticity and smaller creep strain, resulting in smaller loss of prestress.

• By using high strength concrete the cross-sectional area required for member will be reduced resulting less dead weight moment.

1373. What will be the maximum possible uniformly distributed load (inclusive of self-weight) over the entire span of a simply supported beam of span '*L*' such that the deflection at midspan at service condition is zero? The cross-section is rectangular. The prestressing force '*P*' is applied with uniform eccentricity '*e*'. Assume no losses-

(a) $\dfrac{8Pe}{L^2}$ (b) $\dfrac{8.8Pe}{}$

(c) $\dfrac{9.6Pe}{L^2}$ (d) $\dfrac{10.4Pe}{L^2}$

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (c) : For no deflection at midspan,

δ due to self (weight + udl) + (δ due to eccentric force P on cable) = 0

$$\frac{5wl^2}{384EI} + \frac{Pel^2}{8EI} = 0$$

$$w = \frac{9.6Pe}{L^2}$$

Search on Telegram @apna_pdf

07.

Design of Steel Structures

1. Rivet & Bolts Connections

1. The permissible tensile stress in bolts used for column base is :

(a) $120 N/mm^2$ (b) $150 N/mm^2$

(c) $0.6 f_y$ (d) $0.4 f_y$

Where f_y is the yield stress

UPPCL AE 2014

UKPSC AE (Paper-I) 2007

Ans : (a) Permissible tensile stress in bolts used for columns base is $120\ N/mm^2$ and permissible compressive stress is $0.6\ f_y$. maximum permissible bending tensile stress $\sigma_{bt} = 0.66\ f_y$. For flexural member like beam, plate girder etc.

2. A steel plate is 30 cm wide and 10 mm thick. A rivet of nominal diameter of 18 mm is driven. The net sectional area of plate is

(a) $18.00\ cm^2$ (b) $28.20\ cm^2$

(c) $28.05\ cm^2$ (d) $32.42 cm^2$

UPPSC AE 12.04.2016 Paper–I

UPPSC State AE, 2008, 2003

UKPSC AE 2012 Paper–I

(ESE 2010)

Ans : (c) Given B = 30 cm = 300 mm, t = 10 mm

Given nominal diameter d = 18 mm

Gross diameter of hole (D) = 18 + 1.5 = 19.5 mm

Net sectional area = (B – nD) t

$= (300–19.5) \times 10$

$= 2805\ mm^2$

$= 28.05\ cm^2$

3. Two steel plate each 300mm wide and 10mm thick are connected by single bolt. If the plates are in tension and diameter of bolt hole in 20 mm, the net section area of the plate will be

(a) $2686\ mm^2$ (b) $2780\ mm^2$

(c) $2800\ mm^2$ (d) $3000\ mm^2$

(UTTRAKHAND AE 2013)

(JPSC Combined AE Paper V 2013)

(UTTRAKHAND AE Paper 2013)

Ans : (b) Given, B = 300 mm

t = 10 mm

Nominal diameter d = 20 mm

Gross diameter of hole (D) = 20 + 2 = 22 mm

Net sectional area = (B–nD) × t

$= (300 – 22) \times 10$

$= 2780\ mm^2$

4. Load factor is defined as

(a) $\frac{\text{ultimate load}}{\text{yield load}}$ (b) $\frac{\text{yield load}}{\text{working load}}$

(c) $\frac{\text{ultimate load}}{\text{working load}}$ (d) None of these

[UPPSC State Eng. A.E. 2004 (I)]

ESE 2000

Ans : (c) Load factor $= \frac{\text{failure load (ultimate load)}}{\text{working load}}$

Also, load factor $= \frac{W_C}{W_W} = \frac{M_p}{M} = \frac{f_y Z_p}{f Z}$

load factor $= \left(\frac{f_y}{f}\right) \times \left(\frac{Z_p}{Z}\right)$, $\frac{Z_p}{Z} = \text{sape factor}$

Load factor = FOS × shape factor.

5. For an I beam the shape factor is 1.12 the factor of safety in bending is 1.5. If the allowable stress is increased by 20% for the wind and earthquake loads, then the load factor is

(a) 1.10 (b) 1.25

(c) 1.35 (d) 1.40

MPPSC AE 2014

Ans. (d)

$$\text{Load Factor} = \frac{\text{FOS} \times \text{Shape Factor}}{\text{allowable increase in stress}}$$

$$= \frac{1.5 \times 1.12}{1.2}$$

Load Factor = 1.40

6. The main advantage of a steel member is that it

(a) has high strength

(b) is gas and water tight

(c) has long service life

(d) all of these

APPSC AEE 2012

[UPPSC State Eng. A.E. 2011]

Ans : (d) Advantages of steel member :

(a) has high strength

(b) is gas and water tight

(c) has long service life

7. Rolled steel tubes are referred by their

(a) Outer diameter (b) Inner diameter

(c) Average diameter (d) Outer radius

RPSC POLY. TECH. LECT. 2014

Ans : (a) Rolled steel tubes are referred by their outer diameter and their thickness.

8. If T is the tensile force and μ is the coefficient of friction, then in a steel bolt the horizontal frictional force (F) induced is given by :

(a) $F = \mu + T$ (b) $F = \mu/T$

Search on Telegram @apna_pdf

(c) $F = \mu - T$ (d) $F = \mu T$

Rajasthan AE (Nagar Nigam) 2016

Ans. (d) : $F = \mu T$
F = frictional force
μ = coefficient of friction
T = Tensile force

9. Which of the following load combinations are not mentioned in IS 800
(a) Dead load + Erection load
(b) Dead load + Imposed load
(c) Dead load + imposed load + wind load
(d) Dead load + earthquake load
(e) Dead load + Earthquake load + wind load

CGPSC AE 2014 Shift–I

Ans. (e) : As per IS 800-2007 (Cl 3.5)
Load combination to be considered
(a) DL + IL (IL $\Rightarrow$ Imposed load)
(b) DL+IL + wind or earthquake load
(c) DL + WL or EL
(d) DL + erection load

10. According to IS 800, in case of structural steel design, the span length of a flexural member in a continuous frame system shall be taken as the distance between :
(a) centre to centre of the support + twice the eccentricity
(b) diametrically opposite ends of the support
(c) centre to centre of the support
(d) edge to edge of the support

CIL MT 2017

Ans. (c) : According to IS 800, in case of structural steel design, the span length of a flexural member in a continuous frame system shall be taken as the distance between centre to centre of the support.

11. To manufacture Cast Iron, coke, limestone and _____ are re-melted.
(a) Iron (b) Pig iron
(c) Cast iron (d) Wrought iron

LMRC AM 2019

Ans. (b) For manufacturing cast iron, pig iron is re-melted along with coke, lime stone or can be made directly from molten pig iron.

12. What is the ultimate tensile strength of structural mild steel?
(a) 160N/mm^2 (b) 260N/mm^2
(c) 420N/mm^2 (d) None of the above

GESCOM (KARNATAKA) AE 2011

Ans : (c) Ultimate tensile strength of structural mild steel is 420 N/mm^2

13. Weight of steel per cubic metre is taken to be :
(a) 7900 kg (b) 3000 kg
(c) 1200 kg (d) 800 kg

Nagaland PSC CTSE 2017 Paper–I

Ans. (a) : As per IS 800 : 2007 (Cl 2.2.401), Unit mass of steel, (P) = 7850 kg/m^3

14. Which is the Poisson's ratio for structural steel as recommended in IS 800?
(a) 0.15 (b) 0.3
(c) 0.2 (d) 0.25

CIL MT 2017

Ans. (b) The Poisson's ratio for structural steel as recommended in IS 800 is 0.3.
- Modulus of elasticity, $E = 2.0 \times 10^5$ N/mm^2
- Modulus of rigidity, $G = 0.769 \times 10^5$ N/mm^2
- Coefficient of thermal expansion = $12 \times 10^{-6}/^0$C

15. The yield strength of structural TMT steel bar is about
(a) 250 N/mm^2 (b) 315 N/mm^2
(c) 415 N/mm^2 (d) 215 N/mm^2

TNPSC AE 2019

Ans. (c) Yield strength of structural TMT steel bar is about 415 N/mm^2

16. Bolts are most suitable to carry
(a) shear force
(b) bending moment
(c) axial tension
(d) shear force and bending moment

Nagaland PSC CTSE 2017 Paper–I
GUJRAT PSC AE - II 2017
[UPPSC State Eng. A.E. 2004 (I)]
[UPRVUNL A.E. 2015]

Ans : (c) Bolts are most suitable to carry 'Axial' tension. Types of failure in bolts are
(i) Shear failure of bolts
(ii) Bearing failure of bolts
(iii) Tension failure of bolts

17. In a steel plate with bolted connections, the rupture of the net section is a mode of failure under
(a) Tension (b) Compression
(c) Flexure (d) Shear

Gujarat PSC AE 2017

Ans : (a) If tensile load on plate is more than the tensile strength of the plate, the plate fails in tension through rupture.
Tensile strength = $p_t = (p - d) \times t \times ft$
where - p = pitch
d = gross diameter of bolt, t = thickness of plate

18. The minimum pitch of the rivet shall not be less than
(a) d (b) 1.5 d
(c) 2.0 d (d) 2.5 d

LMRC AM 2019
BPSC AE 2019 Paper (V) Section-I
TNPSC AE 2018, GPSC AE Dec 2018
Nagaland PSC CTSE 2017 Paper–I
Gujarat PSC AE 2017,
Maharashtra PSC (Mains) 2017 Paper–I
CGPSC AE 2014 Shift–I
APPSC AEE 2012, TNPSC AE 2012
UPPSC State Eng. A.E. 2004(I), 2007(I)

Ans : (d)
Minimum pitch = 2.5 times the nominal dia of rivet
= 2.5 d
Nominal dia = dia of shank(d)
Maximum pitch
(a) 16t or 200 mm (whichever is less for tension member)
(b) 12t or 200 mm (whichever is less for compression member)
(c) 32 t or 300 mm (which ever is less for tack rivet)
where t = thickness of thinner out side plate.

Search on Telegram @apna_pdf

19. A solid steel plate having yield strength of 250 MPa, the design strength in yielding (N/mm^2) is

(a) 200 N/mm^2 (b) 217 N/mm^2
(c) 227 N/mm^2 (d) 250 N/mm^2

[MPPSC AE 2016]

Ans : (c) Yield strength of plate $f_y = 250$ N/mm^2
Partial safety factor for yield = 1.1

design strength in yield = $\frac{f_y}{\gamma_{mo}}$

$$= \frac{250 N/mm^2}{1.1} = 227.27 \text{ N/mm}^2$$

20. Rivets and bolts subjected to both shear stress (Tvf, cal) and axial tensile stress (Stf, cal) shall be so proportioned that the stresses do not exceed the respective allowable stresses Tvf and Stf and the value of (Tvf, cal/Tvf)+(Stf, cal/Stf) does not exceed :

(a) 0.90 (b) 1.00
(c) 1.80 (d) 1.20
(e) 1.40

TRB Poly. Lect. Tech. 2017
KPTCL AE 2016
CGPSC AE 2014 Shift–I

Ans. (b) : As per IS 800 - 2000, (Cl 11.6.25)
If the bolt is subjected to combined shear & tension, then the expression should satisfy,

$$\left[\frac{f_{sb}}{f_{asb}}\right]^2 + \left[\frac{f_{tb}}{f_{atb}}\right]^2 \le 1.0$$

21. Diameter of a rivet hole is made larger than the diameter of the rivet by

(a) 1.00 mm for rivet diameter up to 12 mm
(b) 1.50 mm for rivet diameter exceeding 25 mm
(c) 2.00 mm for rivet diameter over 25 mm
(d) none of these

TNPSC AE 2012

Ans. (c) Diameter of rivet hole is made larger than the diameter of rivet by 1.5 mm for diameter below 25 mm & 2 mm for rivet diameter above 25 mm.

22. The modulus of elasticity for mild steel is approximately equal to

(a) 0.1×10^5 N/mm^2 (b) 0.8×10^5 N/mm^2
(c) 1.0×10^5 N/mm^2 (d) 2.1×10^5 N/mm^2

Rajasthan VP ITI 2018
CGPSC AE 2014 Shift–I
TNPSC AE 2012

Ans. (d) The modulus of elasticity for mild steel is approximately equal to 2.1×10^5 N/mm^2.

23. Which of the following failures of bolted joint can be avoided by providing sufficient edge distance?

(a) Bearing failure of bolt
(b) Shear failure of bolt
(c) Shear failure of plate
(d) Tensile failure of plate

Gujarat PSC AE (N.W.R.) 2020
Nagaland PSC CTSE 2017 Paper–I
Sikkim PSC AE 2017
MPPSC AE 2014

Ans. (c) : By providing proper edge distance, we can prevent shear failure, splitting failure and bearing failure of plates.

24. In an eccentric connection, when the axis of load is lying in the plane of bolted joint, the bolts are subjected to –

(a) only shear stresses
(b) only tensile stresses
(c) both tensile and shear stresses
(d) tensile, shear and bending stresses

Gujarat PSC AE (N.W.R.) 2020

Ans. (a) : In an eccentric connection, when the axis of load is lying in the plane of bolted joint, the bolts are subjected to only shear stresses. Due to twisting moment tortional shear stresses are developed in the bolts.

25. Determine the rivet value of 20 mm diameter rivets connecting 12 mm thick plate if it is in single shear. Gross area of rivet is 363.05 mm^2, permissible stresses in shear and bearing are 80 MPa and 250 MPa respectively.

(a) 64.5 kN (b) 645 kN
(c) 29.044 kN (d) 290.44 kN

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (c) Given, thickness of plate (t) = 12 mm
diameter of rivet = 20 mm
diameter of hole (d) = 20 + 1.5 = 21.5 mm
gross area of rivet (A) = 363.05 mm^2
shear stress (f_s) = 80 MP = 80 N/mm^2
bearing stress (f_b) = 250 MPa = 250 N/mm^2
$\because$ Shear strength of rivet

$$P_s = \frac{\pi}{4} d^2 \times f_s$$

$$P_s = \frac{\pi}{4} \times (21.5)^2 \times 80$$

$$\boxed{P_s = 29.044 \text{ kN}}$$

$\because$ Bearing strength of rivet

$$P_b = d \times t \times f_b$$

$$P_b = 21.5 \times 12 \times 250$$

$$\boxed{P_b = 64.500 \text{ kN}}$$

Therefore strength of rivet is 29.044 kN.

26. The distance between the center of two consecutive rivets measured along a row of rivets is called as :

(a) Eccentric distance (b) Edge distance
(c) Gauge (d) Pitch

BPSC AE Aug. 2019 Paper-V
Rajasthan AE (Nagar Nigam) 2016

Ans. (d) : Pitch– Centre to centre spacing of the bolts in a row, measured along the direction of load.


27. The distance between rivet centers measured along transverse to the direction of force is

(a) Gauge (b) Pitch
(c) End distance (d) Maximum pitch

Maharashtra PSC AE (Mains) 2012 Paper–I

Search on Telegram @apna_pdf

Ans : (a) Gauge– Centre to centre spacing of the bolts of adjacent rows, perpendicular to the direction of load.



28. How is the efficiency of a riveted joint defined?

(a) The least strength of a riveted plate to the greatest strength of the riveted joint
(b) The least strength of a riveted joint to the strength of a solid plate
(c) The greatest strength of a riveted joint to the strength of a solid plate
(d) All of the above

GESCOM (KARNATAKA) AE 2011

Ans : (b) : Strength of riveted joint is its minimum strength. Efficiency of riveted joint ratio of is least strength of riveted joints to the strength of solid plate.

$$\frac{\text{Actual strengh of joit}}{\text{Strength of solid plate}} \times 100$$

29. A screw

(a) Is partially full of threads
(b) Is entirely full of threads
(c) Is always fitted with nuts
(d) All of the above

GESCOM (KARNATAKA) AE 2011

Ans : (a) A screw is partially full of threads.

30. Yielding in structural members with partial safety factor as 1.1 is governed by :

(a) net area of connected lug angle
(b) sectional area
(c) effective area
(d) gross area

Rajasthan AE (Nagar Nigam) 2016

Ans. (d) : Strength of member in tension

$$\left.\begin{aligned} T_{nd_1} &= \frac{0.9A_n f_u}{\gamma_{m_1}} \\ T_{nd_2} &= \frac{A_g f_y}{\gamma_{m_0}} \end{aligned}\right\} \text{minimum of them}$$

Where f_u = ultimate tensile stress
A_g = gross area
A_n = Net area of cross section
γ_{m0}, γ_{m1} = partial safety factor respectively for yielding and bolt material

$$\gamma_{mo} = 1.1; \quad \gamma_{m_1} = 1.25$$

31. What is the ratio of the yield stress in power driven shop rivets relative to the permissible bearing stress of mild steel ?

(a) 1.0 (b) 0.8
(c) 0.6 (d) 0.4

Nagaland PSC CTSE 2017 Paper–I

Ans. (b) : Yield stress in mild steel = 250 N/mm^2
For hand driven rivets.
Permissible bearing stress in rivet (σ_{Pt}) = 300 N/mm^2

$$\frac{250}{300} = 0.83$$

For power driven rivet.

32. For field rivets, the permissible stresses are reduced by what percentage ?

(a) 10% (b) 15%
(c) 25% (d) $33\frac{1}{3}\%$

Nagaland PSC CTSE 2017 Paper–I

Ans. (a) : IS 800–1984 Recommendation
Max. Permissible stress in Rivet & Bolt, in case of field rivet is reduced by 10%

33. The maximum shear stress of steel member flexure shall not exceed :

(a) 0.4 f_y (b) 0.66 f_y
(c) 0.5 f_y (d) 0.45 f_y

SJVNL ET 2019
Nagaland PSC CTSE 2017 Paper–I

Ans. (d) : As per IS 800-2007 ,

Case	Permissible stress
in shear	Max. permissible $A_{vg} = 0.40\ f_y$ max. permissible = $0.45\ f_y$
in Bending	$0.66\ f_y$
in Bearing (at support)	$0.75\ f_y$

34. As per IS 800-1971 the working shear stress on gross area of power driven rivets is :

(a) 785 kg/cm^2 (b) 945 kg/cm^2
(c) 1025 kg/cm^2 (d) 1575 kg/cm^2

Nagaland PSC CTSE 2017 Paper–I

Ans. (c) : As per IS. 800–1971 the working shear stress on gross area of power driven rivet is 1025 kg/cm^2

35. The gross diameter of a rivet is the diameter of-

(a) Cold rivet measured before driving
(b) Rivet measured after driving
(c) Rivet hole
(d) None of these

RPSC ACF 2011
OPSC AEE 2015 PAPER–I

Ans. (c) Gross diameter : Diameter of the hole, assuming that rivet fills the hole completely.
for $d \le 25$ mm, $d_g = d + 1.5$ mm
for $d > 25$ mm, $d_g = d + 2$ mm
Where, d = Nominal diameter of rivet.

36. On which connection, load is not eccentric?

[UPPSC State Eng. A.E. 2011]
(ESE 2001)

OR

Loads on a connection is not eccentric for

AP (VSS-1) PART - A 2017
(JPSC Combined AE Paper V 2013)

Search on Telegram @apna_pdf


OR

Which of the following joint type is not eccentric

(a) Lap joint
(b) Single cover butt joint
(c) Double cover butt joint
(d) None of these

RPSC POLY. TECH. LECT. 2011

Ans : (c) Double cover butt joint is not eccentric.




37. Which of the following types of the riveted joint is free from bending stress

(a) Lap joint
(b) Butt joint with single cover plate
(c) Butt joint with double cover plate
(d) None of the above

RPSC ACF 2011

Ans : (c) Double cover butt joint is free from bending stresses as the forces are along the longitudinal direction and eccentricity is zero.



38. Select the correct statement

(a) Material cost of rivet is higher than of bolt
(b) Tensile strength of a bolt is less than that of a rivet
(c) Bolts are used as temporary fastenings whereas rivets are used as permanent fastening
(d) Riveting is less noisy than bolting

RPSC ACF 2011

Ans : (c) In any steel structure bolts are used as temporary fastening whereas rivet is used as permanent fastening of members.

39. When the axis of load lies in the plane of rivet group, the rivets are subjected to

(a) Only shear stresses
(b) Only tensile stresses
(c) Both (a) and (b)
(d) None of the above

RPSC ACF 2011

Ans : (a) When load lies in the plane of rivet group, the rivets are subjected to only shear stresses.

40. When the bolts are subjected to reversal of stresses, the most suitable type of bolt is

(a) Black bolt
(b) Ordinary unfinished bolt
(c) Turned & fitted bolt
(d) High strength bolt

LMRC AM 2018
RPSC ACF 2011

Ans : (d) High strength bolt also known as HSFG (High strength friction grip) bolt. They are made from bars of medium carbon heat-treated steel and from alloy steel. They transfer loads primarily by friction and not by shear. High strength bolts have replaced rivets and black bolts and are being used in structures such as high rise building, bridges, machines etc. Which are subjected to large stresses or reversible stresses.

41. Eccentricity of connections introduces:

(a) Primary stresses (b) Vibrating stresses
(c) Secondary stresses (d) None of the above

[UPPSC AE 12.04.2016 Paper–I]

Ans : (c) Eccentricity of connections introduces secondary stresses.

42. What is the value of Partial Safety Factor for Shop Fabricated Welds?

(a) 1.10 (b) 1.20
(c) 1.25 (d) 1.50

Gujarat PSC AE (N.W.R.) 2020

Ans. (c) Partial safety factor 1.25 is applied to this value to get permissible ultimate tensile stress.

43. As per the Indian Standard (IS) 800:2007, the partial safety factor for material resistance governed by yielding failure of the steel is

(a) 1.10 (b) 1.15
(c) 1.20 (d) 1.50

[MPPSC AE 2016]

Ans : (a) IS : 800 : 2007, according to this, partial safety factor for material, γ_m

(1) Resistance governed by yielding $\gamma_{mo} = 1.1$
(2) Resistance of member to buckling, γ_{mo} 1.1
(3) Resistance governed by ultimate stress $\gamma_{m1} = 1.25$
(4) Resistance to connection :

	Shop fabrication	field fabrication
(i) Bolts – friction type, γ_{mf}	1.25	1.25
(ii) Bolts – Bearing type, γ_{mb}	1.25	1.25
(iii) Rivets - γ_{mr}	1.25	1.25
(iv) Welds, γ_{mw}	1.25	1.5

44. A plate of size 100 mm × 10 mm having yield strength of 250 MPa, the design strength of plate in yielding of the cross–section is

(a) 167 kN (b) 200 kN
(c) 217 kN (d) 227 kN

[MPPSC AE 2016]

Ans : (d) Given plate size 100 mm × 10 mm
yield strength (f_y) = 250 MPa
Area of cross-section of plate = 100 × 10 mm^2 = 1000 mm^2
partial safety factor of yield = 1.1
Design strength of plate =

$$\frac{\text{Area} \times \text{yield strength}}{\text{partial safety factor}} = \frac{A_g \times f_y}{\gamma_{mo}}$$

$$= \frac{1000\ mm^2 \times 250 N/mm^2}{1.1} = 227.27 KN$$

or say 227 kN

Search on Telegram @apna_pdf

45. If the rivet diameter is 30 mm, the diameter of rivet hole shall be

(a) 31 mm (b) 31.5 mm
(c) 32 mm (d) 32.5 mm

UPPSC State Eng. A.E. 2004, 2007 (I)

Ans : (c) Diameter of rivet hole
d' = Nominal dia (d) + 1.5 mm for d < 25 mm
d' = Nominal dia (d) + 2 mm for d > 25 mm
the dia of hole is also called gross dia of rivet here
Rivet dia (d) = Nominal dia = 30 mm > 25 mm
gross dia, d' = 30 + 2
d' = 32 mm

46. If the diameter of a rivet is more than 25mm. The diameter of rivet hole as compared to nominal diameter of rivet will be:

(a) more by 1.5mm (b) more by 2.0mm
(c) more by 2.5mm (d) equal

[UPPSC State Eng. A.E. 2007]


Ans : (b) Nominal dia > 25 mm
the gross dia = 25+ 2
d' + 2
= $\boxed{d = d' + 2mm}$

47. The rivets in a lap joint will be in....shear.

(a) single (b) double
(c) tearing (d) bearing

(BPSC AE Paper V 2001)

Ans : (a) Rivets in lap point will be subjected to single shear, whereas double cover butt joint is subjected to double shear.



48. If the thickness of plate to be connected by a rivet is 16mm, the suitable size of rivet will be

(a) 16mm (b) 20mm
(c) 24mm (d) 27mm

[UPPSC State Eng. A.E. 2004 (I)]

Ans : (c) The diameter or rivet suitable to the thickness of member is $d = 6.05\sqrt{t_{min}}$ (Unwins formula)
Where,
t_{min} = thickness of thinner plate
t_{min} = 16 mm
$d = 6.05\sqrt{16} = 24.2\,mm \approx 24\,mm$

49. The load factor applied to dead loads or live loads in the design of steel structures is–

(a) 1.3 (b) 1.5
(c) 1 (d) 2.2

(UTTRAKHAND AE 2013)

Ans : (c) In limit state of strength design load factor for combination of dead load or live load is 1.5 for both of them.
In limit state of serviceability it is 1.
Load factor = fos × shape factor

50. In upper bound theorem plastic analysis for a given frame subjected to a set of loads P, the value of P which is found to correspond to any assumed mechanism must be–

(a) Greater than the collapse load P_u
(b) Less than the collapse load P_u
(c) Either greater than or equal to collapse load P_u
(d) None of the above

(UTTRAKHAND AE 2013)

Ans : (c) Kinematic or upper bound theorem– For a given frame subjected to a set of loads P, the value P which is found to correspond to any assumed mechanism, must be either greater than or equal to the collapse load.

51. The gross diameter of a 20 mm rivet is

(a) 20 (b) 25
(c) 21.5 (d) 22

(BPSC AE Paper V 2001)

Ans : (c) Gross diameter = 20+1.5
= 21.5 mm
for bolt diameter upto 25 mm; gross diameter = rivet diameter + 1.5 mm.
Rivet diameter greater than 25 mm; gross diameter = bolt diameter + 2

52. Which of the options given below are true about how the commonly used structural steels are made?

1. Very low carbon steels, < 0.1%
2. Low carbon steel 0.1 to 0.25%
3. Medium carbon steel 0.25 to 0.6%
4. High carbon steel 0.6 to 1.1%

(a) 1 is true (b) 1 and 2 are true
(c) 1, 2 and 3 are true (d) All are true

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (c) :

Types of carbon steel	Carbon content
1. Very low carbon steel	< 0.1%
2. Low carbon steel	0.1 to 0.25%
3. Medium carbon steel	0.25 to 0.6%
4. High carbon steel	0.6 to 0.95%

53. Which of the following equations is correct for bolt, subjected to both combined shear and tension?
Where,
V = Applied shear at service load
V_{sdf} = Design shear strength
T_e = Externally applied tension at service load
T_{ndf} = Design tension strength

(a) $\left(\frac{V}{V_{sdf}}\right)^2 + \left(\frac{T_e}{T_{ndf}}\right)^2 \le 1$

(b) $\left(\frac{V}{V_{sdf}}\right)^2 + \left(\frac{T_e}{T_{ndf}}\right)^2 \ge 1$

(c) $\left(\frac{V}{V_{sdf}}\right) + \left(\frac{T_e}{T_{ndf}}\right) \le 1$

(d) $\left(\frac{V}{V_{sdf}}\right) + \left(\frac{T_e}{T_{ndf}}\right)^2 \ge 1$

Maharashtra PSC (Mains) 2018, 2015 Paper-1
KPTCL AE 2016


Search on Telegram @apna_pdf

Ans. (a) : For safety of bolted connection is checked in combined shear and tension by using interaction equation of IS 800 : 2007

$$\left(\frac{V_b}{V_{db}}\right)^2+\left(\frac{T_b}{T_{db}}\right)^2\le 1$$

V_b = factored shear force on bolt
V_{db} = Design shear capacity of bolt
T_b = Factored tensile force
V_{db} = Design tension capacity of oelt


54. The maximum design force for a rivet in the following bracket connection, if spacing between adjacent rivets is 150 mm, is-



(a) 150 kN (b) 175 kN
(c) 200 kN (d) 212.5 kN

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (a) :



Rivet '2' is critical rivet, direct shear force on the rivet

$$(F_d)=\frac{450}{5}=90kN$$

Torsional force on the rivet

$$(F_t)=\frac{Pe.R_i}{\Sigma r_i^2}=\frac{450\text{kN}\times 160\times 150(\text{mm})^2}{4(150)^2\ \text{mm}^2}$$

= 120 kN

Resultant force on rivet

$$F_r=\sqrt{F_d^2+F_t^2}=\sqrt{(120)^2+(90)^2}$$

= 150 kN

55. The rolled '*I*' section for a given depth having largest moment of inertia, I_{XX} is designated as-

(a) ISMB (b) ISHB
(c) ISLB (d) ISWB

OPSC AEE 2015 PAPER–I

Ans. (b) : ISHB – Indian standard heavy beam
ISMB – Indian standard medium beam
ISLB – Indian standard light beam
ISWB – Indian standard wide beam

56. The yield stress of mild steel of normally rolled structural steel is about (in N/mm^2)-

(a) 240 to 260 (b) 330 to 360
(c) 420 (d) 550

OPSC AEE 2015 PAPER–I

Ans. (a) : Yield stress ≈ 250 MPa
Ultimate stress ≈ 410 MPa

57. Corrosion resistance of stainless steel is due to

(a) Chromium (b) Vanadium
(c) Carbon (d) Sulphur

TNPSC AE 2018
GPSC AE Class (1&2) Paper-2, 2017


Ans. (a) : Effect of impurities in iron is as follows:-
(i) Carbon – Reduces melting point and imparts hardness.
(ii) Sulphur – It renders cast iron hard and brittle
(iii) Chromium – Impart resistance to corrosion.
(iv) Phosphorus – Increases fluidity and leads to loss of toughness.
(v) Manganese – It impart hardness and brittleness.

58. As per IS 800-2007, the buckling class for hot-rolled tubular sections is

(a) a (b) b
(c) c (d) d

(TNPSC AE 2018)

Ans. (a) :

Cross-Section	Limit	About Axis	Buckling Curve
	Hot Rolled	any	a
	Cold Formed	any	b

59. As per IS : 800 - 2007, the partial safety factor for materials,

(a) 1.10 (b) 0.85
(c) 1.25 (d) 1.05

[HPPSC 2016-II]

Ans. (d) : As per IS 800 - 2007, partial safety factors for materials γ_m is 1.05

Definition	Safety factor
(1) Resistance governed by yielding, γ_{m0}	1.10
(2) Resistance governed by buckling, γ_{m0}	1.10
(3) Resistance governed by ultimate stress, γ_{m1}	1.25

60. For the 16 mm nominal diameter rivets, the diameter of the rivet hole is kept equal to :

(a) 14.0 mm (b) 14.5 mm
(c) 17.5 mm (d) 18 mm

[HPPSC 2016-II]

Ans. (c) : Gross diameter (d_g) of rivet or hole diameter of rivet is given by
d_g = d + 1.5 mm, d ≤ 25 mm
= d + 2 mm, d > 25 mm
given, d = 16 mm
∴ d_g = 16 + 1.5 = 17.5 mm

Search on Telegram @apna_pdf

61. According to IS 800-2007, the nominal shear capacity of M20 bolt of grade 4.6 with one shear plane passing through bolt shank and one shear plane passing through threaded portion is:

(a) 45.27 kN (b) 117.52 kN
(c) 56.21 kN (d) 129.14 kN

Karnataka PSC AE 2017 Paper - II

Ans. (d) : Nominal shear capacity


$$= \frac{f_{ub}}{\sqrt{3}}\left(n_n A_n + n_s A_s\right) = V_{nsb}$$

Design shear capacity $= \frac{V_{nsb}}{\gamma_{mb}} = \left(\frac{V_{nsb}}{1.25} = V_{dsb}\right)$

$$V_{nsb} = \frac{400}{\sqrt{3}} \times \left[1\frac{\pi}{4}(20)^2 + 1 \times 0.78 \times \frac{\pi}{4} \times (20)^2\right]$$

= 129.14kN

62. Which section to be considered in the design for the net area of flat ?



(a) 1-5-6-3 (b) 2-7-4
(c) 1-5-7-4 (d) 1-5-7-6-3

JPSC AE (Pre) 2019

Ans. (d) : The section giving minimum area of plate is considered for design. So, section 1–5–7–6–3 is used for net area of flat.

63. Reduction in design shear capacity of bolts due packing plate in excess of 6 mm is expressed (as per IS (800-2007) by :

(a) $1\text{-}0.125t_{pm}$ (b) $1\text{–}0.12t_{pm}$
(c) $1\text{–}0.25t_{pm}$ (d) $1\text{–}0.0125t_{pm}$

Where t_{pm} : thickness of thicker packing plate (in mm)

Rajasthan JEn (Degree) 2016

Ans. (d) : Reduction Factor for packing plates is $1\text{-}0.0125\ t_{pm}$.

64. Gauge length of steel specimen as per codal provision is :

(a) 6d (b) 5d
(c) 8d (d) $5.65\sqrt{A_0}$

Where d : larger dimension of the specimen; A_0 : Cross sectional area of the specimen

Rajasthan JEn (Degree) 2016

Ans. (d) Gauge length of steel specimen as per codal provision is $5.65\sqrt{A_0}$.

65. High Strength Friction Grip Bolts can be used for

(i) Slip resistant connection
(ii) Bearing type connection
(iii) Shear connection

(a) (i) and (ii) (b) and (iii)
(c) (ii) and (iii) (d) (i), (ii) and (iii)

GPSC AE (CLASS 1 & 2) 2019


Ans : (a) : HSFG are high strength structural bolts which have been tightened such as to induce tension in the bolt shank. As the tension in the bolt is high, the interface can't move relative to each other (No slip for shear resist). Primarily loads are transferred by friction and not shear.

66. Diamond pattern of bolting is beneficial over chain and staggered bolting because

(a) It transmits maximum force
(b) It has maximum efficiency
(c) It is easy to fabricate
(d) It leads to minimum deflection

GPSC AE (CLASS 1 & 2) 2019

Ans : (a) :



The diamond riveting strength is more than other as in (1) - (1) section as only 1 bolt hole is deducted in section, $P=(B–d)\ t\times f_t$

So strength is more than chain riveting as in chain riveting 3 bolt diameter is deducted so resulting strength of chain riveting decreases

t = thickness of main plate
d = diameter of bolt hole
B = width of plate
f_t = Tensile stress

$$\uparrow \eta(\text{efficiency}) = \frac{\text{Rivet value}\left(P_s \text{ or } P_b\right)_{\min^m}}{\text{total strength of plate}}$$

67. Structural steel of grade Fe410 A has ultimate tensile strength of:

(a) 410 MPa (b) 328 MPa
(c) 300 MPa (d) 520 MPa

Kerala PSC AE 2015

Ans. (a) : Fe 410 A has ultimate strength of 410 MPa and yield strength of 250 MPa.

68. The diameter of bolt hole for a bolt of nominal size 12 mm is:

(a) 12.0 mm (b) 12.5 mm
(c) 13.0 mm (d) 14.0 mm

Kerala PSC AE 2015

Ans. (c) :

Nominal size of fastener	Standard clearance
12-14 mm	1.0 mm
16-24 mm	2.0 mm
> 24 mm	3.0 mm

Diameter of bolt hole = Nominal size of fastener + Standard clearance
= 12 mm + 1 mm = 13 mm

→ in case of rivet
Gross dia (d) = D + 1.5 mm [if D ≤ 25 mm]
d = D + 2mm [D > 25 mm]
D = Nominal dia


Search on Telegram @apna_pdf

69. Gauge of the bolt is the distance between two consecutive bolts in

(a) the direction perpendicular to the direction of load/stress
(b) the direction of load/stress
(c) the direction at 45° to the line of action of force
(d) an inclined direction


TNPSC AE 2018

Ans. (a) :



Gauge is the distance between adjacent lines, or the distance between the back of the rolled section and the first bolt line, or centre to centre distance between two consecutive bolts in the direction perpendicular to the direction of load.

70. Statement (I): In a bolted joint, all similarly placed bolts share the load equally.



Statement (II): Bolts are placed in holes having slightly larger diameters.

(a) Both Statements-I and Statement-II are individually true and Statement-II is the correct explanation of Statement-I.
(b) Both Statements-I and Statement-II are individually true but Statement-II is NOT the correct explanation of Statement-I
(c) Statement-I is true but Statement-II is false.
(d) Statement-I is false but Statement-II is true.

ESE 2018

Ans. (b)

- The diameter of the hole is about 1.5 to 2.0 mm larger than the bolt diameter for ease in fitting.
- In a bolted joint, all similarly placed bolts share the load equally.

71. A single angle of thickness 10 mm is connected to a gusset by 6 numbers of 18 mm diameter bolts, with pitch of 50 mm and with edge distance of 30 mm. The net area in block shear along the line of the transmitted force is


(a) 1810 mm^2 (b) 1840 mm^2
(c) 1920 mm^2 (d) 1940 mm^2

ESE 2018

Ans. (a)

Angle thickness, t = 10mm
End distance, e = 30mm
Pitch distance, p = 50mm
Diameter, d = 18mm

Diameter of bolt hole, d_o = 18 = 18mm



- Net area in block shear = $\left((5p+e)-5d_o-\frac{d_o}{2}\right)t$

Net area in block shear along the line of force

$$=\left((5\times50+30)-5\times18-\frac{18}{2}\right)\times10$$

Area = (250 + 30 – 90 – 9) × 10

$\boxed{\text{Area} = 1810mm^2}$

72. What is the efficiency of joint when strength of bolt per pitch length is 60kN and strength of plate per pitch length is 150kN?

(a) 30 percent (b) 40 percent
(c) 35 percent (d) 25 percent

DSSSB AE 2019

Ans. (b)

Efficiency of joint

$$=\frac{\text{strength of bolt per pitch}}{\text{strength of plate per pitch}}\times100$$

$$=\frac{60}{150}\times100=40\%$$


73. The distance between the centres of adjacent rivets in the same row is called

(a) Pitch (b) Lap
(c) Gauge (d) Staggered lap

ISRO Scientist/Engineer 2018

Ans : (a)

- The distance between the centres of adjacent rivets in the same row is called Pitch. It is also the centre to centre distance between two adjacent rivet along rivet line measured parallel to the direction of force.



74. As compared to field rivets, the shop rivets are:

(a) stronger (b) weaker
(c) equally strong (d) of unknown quality

WBPSC Poly Lect. 2019

Ans. (a) : As compared to field rivets, the shop rivets are stronger.

75. A tie bar 50 mm × 8 mm is to carry a load of 80 kN. A specimen of the same quality steel of cross-sectional area is 250 mm^2. For a maximum load of 125 kN carried by the specimen, the factor of safety in the design will be :

(a) 3.0 (b) 2.5
(c) 2.0 (d) 1.5

ESE 2020

Search on Telegram @apna_pdf

Ans. (b)

$$\text{Yield Strength of Steel} = \frac{\text{Maximum Load}}{\text{Cross-sectional Area}}$$

$$= \frac{125\times10^3}{250}$$

$$= 500 \text{ N/mm}^2$$

For tie bar,

$$\text{Working stress} = \frac{80\times1000}{50\times8}$$

$$= 200 \text{ N/mm}^2$$

Now,

$$\text{Factor of Safety (FOS)} = \frac{\text{Yield Strength}}{\text{Working Stress}}$$

$$= \frac{500}{200}$$

$$\boxed{\text{FOS} = 2.5}$$

76. A punch of 20 mm diameter is used to punch a hole in 8 mm thick plate. If the force required to create a hole is 110 kN, the average shear stress in the plate will be nearly.

(a) 410 MPa (b) 320 MPa
(c) 220 MPa (d) 140 MPa

ESE 2020

Ans. (c) : Given,
diameter of punch (d) = 20 mm
thickness of plate (t) = 8 mm
Punching force = Shear Resisting Force
$110 \times 10^3 = \tau \times$ [shearing area]
$110 \times 10^3 = \tau \times [\pi \times d \times t]$
$110 \times 10^3 = \tau \times [\pi \times 20 \times 8]$

$$\text{Shear stress } (\tau) = \frac{110\times10^3}{\pi\times20\times8}$$

$$\tau = 218.8 \text{ MPa}$$

$$\simeq \boxed{\tau = 220 \text{ MPa}}$$

77. In rolled steel I beams, shear force is mostly resisted by

(a) Web only (b) Top flange only
(c) Both web and flange (d) Bottom flange only

TNPSC AE 2018

Ans. (a) : Shear force is maximum near the neutral axis of beam. In rolled steel I beams, 95% of shear stress is resisted by the web and bending moment is resisted by the flanges.

78. If a timber beam 8 cm wide and 16 cm deep is to be converted into an equivalent steel section of the same depth for analysis purpose, then the width of the equivalent section for a modular ratio of 20 will be

(a) 160 cm (b) 2.5 cm
(c) 0.4 cm (d) 12 cm

APPSC AEE MAINS 2016

Ans. (c) : 0.4cm

79. Rupture of the net section in steel plate with bolted connections occurs due to :

(a) Tension (b) Compression
(c) Flexure (d) Combined

PSPCL AE 2012

Ans. (a) : In steel plate with bolted connection, the rupture occurs due to tension force in the member applied.
– In tension member we take net section area as effective area whereas in compression member effective area is gross area.

80. What is the yield strength of bolt of class 4.6?

(a) 400 N/mm^2 (b) 240 N/mm^2
(c) 250 N/mm^2 (d) 500 N/mm^2

Maharashtra PSC Mains 2018 Paper-1

Ans. (b) : For bolt of grade property 4.6 represents the ultimate tensile strength is 400 N/mm^2 and yield strength 0.6 times 400 which is 240 N/mm^2.

81. The Indian standard code which deals with steel structure is

(a) IS : 456 (b) IS : 875
(c) IS : 800 (d) IS : 1893

Maharashtra PSC Mains 2018 Paper-1
Haryana PSC AE 2018 Paper–I

Ans. (c) : The Indian standard code which deals with steel structure is IS : 800.

82. Number of bolts required in a bolted joint is equal to

(a) $\dfrac{\text{Force}}{\text{Bolt value}}$

(b) $\dfrac{\text{Force}}{\text{Strength of bolt in shearing}}$

(c) $\dfrac{\text{Force}}{\text{Strength of bolt in bearing}}$

(d) $\dfrac{\text{Force}}{\text{Strength of bolt in tearing}}$

Maharashtra PSC Mains 2018 Paper-1

Ans. (a) : Number of bolts required = $\dfrac{\text{Force}}{\text{Bolt value}}$

83. In case of staggered pitch, pitch may be _____ of values specified for not staggered pitch.

(a) increased by 20% (b) increased by 50%
(c) decreased by 20% (d) decreased by 50%

GPSC AE March 2018

Ans. (b) In case of staggered pitch may be increased by 50% of values specified above provided gap distance is less than 75 mm (sec clause 10.2.3.4 of code IS 800 : 2007)
Staggered system $p_{max} = 18t$ or 300 mm
non-staggered $p_{max} = 12$ or 200 mm (non-staggered)

84. For commonly used HSFG bolts (IS1367 part3, grade 8.8) yield stress f_{yb} is

(a) 280 N/mm^2 (b) 360 N/mm^2
(c) 640 N/mm^2 (d) 940 N/mm^2

GPSC AE March 2018

Ans. (c) : Grade of HSFG bolt = 8.8
Ultimate stress = 8 × 100 = 800 N/mm^2
Yield stress = 0.8 × 800 = 640 N/mm^2

Search on Telegram @apna_pdf

85. The prying forces are additional

(a) shearing forces on the bolts because of long joint
(b) bending forces on the bolts because of long joint
(c) tensile forces due to the flexibility of connected parts leading to deformation
(d) forces due to friction between the connected parts

GPSC AE March 2018
AP TRANSCO AEE 2017

Ans. (c) : When connection subjected to tension force, the connected parts can lead to deformation that increases the tension applied to the bolts, the additional force is generated in bolts due to joint plate is known as pyring force.

86. Using Unwin formula diameter of rivet is found. In this formula thickness is in

(a) mm (b) cm
(c) dm (d) m

Vizag steel MT 2017

Ans. (a) : Unwin's formula - $\phi = 6.04\sqrt{t}$
ϕ = diameter of rivet
t = thickness of thinner plate (in mm)

87. Which of the following connections develop the full moment capacity of connecting members and retain the original angle between the members under any joint rotation.

(a) Semi-rigid (b) Simple
(c) Rigid (d) None of the above

GPSC Poly. Tech. Lect. 2016

Ans. (c) : Rigid Joint–A joint connections that develop the full moment capacity of connecting members and retain the original angle between the members any joint rotation is known as rigid joint.

88. Diameter of a bolt hole is usually taken as :

(a) Gross diameter of bolt
(b) Nominal diameter of bolt
(c) Nominal diameter + 1.5 mm
(d) Nominal diameter + 2.0 mm

Nagaland PSC CTSE 2017 Paper–I
UPSC JWM 2017

Ans. (d)

Nominal diameter of bolt 'd'	Diameter of hole 'd_0'
12	13
14	15
16 to 24	$d_0 + 2$ mm
27 to 30	$d_0 + 3$ mm

Usually bolts hole diameter is taken nominal diameter + 2 mm.

89. Efficiency of a riveted joint having the minimum pitch as per IS: 800 is

Sikkim PSC AE 2017
Punjab MCP SDO 2015
[UPPSC State Eng. A.E. 2004 (I)]

(a) 40% (b) 50%
(c) 60% (d) 70%

Ans : (c) P = minimum pitch = 2.5 d

$$\text{Efficiency}(\eta) = \frac{(p-d)}{p} \times 100$$
$$= \left(\frac{2.5d-d}{2.5d}\right) \times 100$$
$$\eta = 60\%$$

90. Design wind pressure (p_z) for building can be obtained after knowing wind velocity (V_z) using equation .....

(a) $p_z = 0.5V_z^2$ (b) $p_z = 0.6V_z^2$
(c) $p_z = 0.7V_z^2$ (d) $p_z = 0.8V_z^2$

GPSC R&B AE 2016


Ans. (b) : Design wind pressure = $p_{d_z} = 0.6V_z^2$
v_z = wind velocity (m/s)
p_d is in N/m^2 at height z.

91. As per IS : 800 - 2007, the distance between centre of fasteners shall not be less than ..... in bolted connections.

(a) 2.5 times the nominal dia. of the fastener
(b) 3 times the nominal dia. of the fastener
(c) 1.5 times the nominal dia. of the fastener
(d) 2 times the nominal dia. of the fastener

GPSC R&B AE 2016

Ans. (a) : Pitch is the distance between c/c of two consecutive fasteners along the applied load.



92. For pin connection of joints, allowable shear stress and bearing stress are ..... respectively:

(a) 100 MPa and 300 MPa
(b) 100 MPa and 250 MPa
(c) 150 MPa and 300 MPa
(d) 150 MPa and 350 MPa

GPSC R&B AE 2016

Ans. (a) : Bearing strength of bolt

$$= V_{dpb} = \frac{2.5 k_b d t f_u}{\gamma_{m_b}} ; \; k_b \text{ is minimum of } \begin{cases} \frac{f_{ub}}{f_u} \\ e/3d_0 \\ \frac{p}{3d_0} - 0.25 \end{cases}$$

For pin connection→
Allowable shear stress = 100 MPa.
Bearing stress = 300 MPa

93. As per IS : 875 - Part - III, topography factor is denoted as ..... for wind loadings.

(a) K_1 (b) K_2
(c) K_3 (d) K_4

GPSC R&B AE 2016

Search on Telegram @apna_pdf

Ans. (c) : As per IS : 875-Part-III
Design wind speed $v_b = K_1K_2K_3K_4\ V_b$
$K_1 = 1$ risk coefficient of design life 50 years.
$K_2 = 0.8$ terrain category
$K_3 = 1.0$ topographic factor
K_4 = importance factor in cyclonic region.

94. As per IS : 875 (Part - II) - 1987, for residential buildings, imposed floor loads in form of uniformly distributed load for all rooms and kitchens of dwelling house is .....

(a) 20 KN/m^2 (b) 10 KN/m^2
(c) 2 KN/m^2 (d) 3 KN/m^2

GPSC R&B AE 2016

Ans. (c) : As per IS : 875 (Part - II) - 1987. For residential buildings, live loads are given as

S.N.	Description (In Kitchen)	UDL (kN/m^2)
1.	Dwelling house	2
2.	Hostels, hotels and hospitals	3

95. Maximum carbon content allowed in mild steel, to metal for construction is .....

(a) 1.10% (b) 0.75%
(c) 0.10% (d) 0.90%

GPSC R&B AE 2016

Ans. (c) : Low carbon steel or mild steel contain carbon in the range of 0.5 to 0.25%. For construction, the sheet metal uses mild steel having carbon content upto 0.10%.

96. According to IS: 800-1962, the coefficient of expansion of steel per degree centigrade per unit length, is taken as :

(a) 0.000008 (b) 0.00001
(c) 0.000012 (d) 0.000014

KPTCL AE 2016

Ans. (c) : According to IS 800-1962, the coefficient of expansion of steel per degree centigrade per unit length is taken as 0.000012

97. The slenderness ratio of single angle discontinuous struts connected by a single rivet or bolt, shall not exceed :

(a) 110 (b) 130
(c) 150 (d) 180

KPTCL AE 2016

Ans. (d) The slenderness ratio of single angle discontinuous struts connected by a single rivet or bolt, shall not exceed 180.

98. The maximum pitch of rivets for compression and tension members should not exceed :

(a) 32 t (b) 200 mm
(c) 40 t (d) both 32 t and 200 mm

KPTCL AE 2016

Ans. (d)
- 16t or 200 mm (which ever is less) – for tension member.
- 12t or 200 mm (which ever is less) – for compression member
- 32t or 300 mm (which ever is less) – for tack rivet

99. Grade of steel is designated as Fe415 if

(a) The upper yield stress of the steel is 415 N/mm^2
(b) The ultimate stress of steel is 415 N/mm^2
(c) The characteristic strength of steel is 415 N/mm^2
(d) The partial safety factor is 1.15

Rajasthan Nagar Nigam AE Shift-2, 2016

Ans. (c) : Fe415 is a grade of high strength deformed steel bar for concrete. Tensile strength when it is subjected to elongation of steel is 415 N/mm^2.

100. Which one of the following is the desirable section in a situation where torsion is dominant?

(a) I- section (b) Channel section
(c) Angle section (d) Box type section

Rajasthan Nagar Nigam AE Shift-2, 2016


Ans. (d) : Box type section because among above the polar moment of inertia is maximum for box type section.

101. If two plates are placed end to end and joined by two cover plates then what type of joint is it?

(a) Double cover butt joint
(b) Butt joint chain riveted
(c) Lap joint
(d) Chain riveted

Rajasthan AE Nagar Nigam Shift-3, 2016

Ans. (a) :



Double Cover Butt Joints

End to end placed two plate with two cover plates called Double cover butt joints.

102. Rolled steel beams are designated by Indian standard series and its

(a) Depth of section and weight per meter
(b) Weight per meter and flange width
(c) Flange width and weight per meter
(d) Weight per meter and depth of section

Sikkim PSC AE 2017

Ans. (a) : The Rolled steel beams are designated by the series to which beam sections belong, followed by depth in (mm) of the section and weight in kN per meter length of the beam.

103. What is the design wind pressure if the design wind speed is 50 m/s?

(a) 1.5 kN/m^2 (b) 1.8 kN/m^2
(c) 2 kN/m^2 (d) 1 kN/m^2

TANGEDCO AE 2018

Ans. (a) : Wind pressure $= \frac{1}{2}\rho_{air}v^2$

$= \frac{1}{2}\times 1.2\times(50)^2 = 1500\ \text{N/m}^2 = 1.5\ \text{kN/m}^2$

Search on Telegram @apna_pdf

104. Two plates are connected by lap joint using four bolts of 20 mm diameter. If the joint is subjected to a tensile force of 100 kN, the shear stress in the bolt is

(a) 25 N/mm^2 (b) 31.4 N/mm^2
(c) 79.6 N/mm^2 (d) 50 N/mm^2

TRB Poly. Tech. Lect. 2012

Ans. (c) : 4 bolts taken tensile force = 100 kN

$\therefore$ 1 bolt take $= \frac{100}{4}$

$\because$ Hence shear stress $= \frac{\text{Force}}{\text{Area of bolt}}$

$$= \frac{25\times1000}{\frac{\pi}{4}(20)^2}$$

$$= \frac{100\times1000}{400(\pi)} = \frac{250}{\pi}$$

Shear stress = 79.59 N/mm^2

105. A steel plate is 300 mm wide and 40 mm thick is connected using 24 mm dia bolts of 3 number. The net sectional area of the plate is

(a) 9840 mm^2 (b) 8940 mm^2
(c) 9480 mm^2 (d) 8490 mm^2

TRB Poly. Tech. Lect. 2012

Ans. (b) : Nominal dia to bolt = 24 mm
Dia of hole = 24 + 1.5 = 25.5 nm
Net sectional area = (300 – 25.5 × 3) × 40
= 8940 mm^2

106. A threaded rod is placed inside a tube and fastened by nuts at both ends. The pitch of the thread is p. For quarter turn what is the advancement of the nut?

(a) p (b) p/2
(c) p/4 (d) p/3

TRB Poly. Tech. Lect. 2012

Ans. (c) : We know,
1 turn = 360° = P (Pitch)
$\therefore$ For quarter turn, advancement will be $\frac{P}{4}$

107. Rolled steel angle sections are classified:

(a) Equal angles (b) Unequal angles
(c) Bulb angles (d) All the above

UJVNL AE 2012

Ans. (d) : Rolled steel angle sections are classified as
1. Equal angles
2. Unequal angles
3. Bulb angle

108. The partial safety factor for steel as per IS 456 – 1978 is taken as

(a) 1.15 (b) 1.35
(c) 1.50 (d) 1.65

APPSC AEE 2012

Ans. (a) : As per IS code 456 : 2000
Partial safety factor for $\begin{cases}\text{steel} = 1.15\\ \text{concrete} = 1.5\end{cases}$

109. If 't' is the thickness of the plate, tacking rivets should have a pitch in line NOT exceeding :

(a) 32t or 200 (b) 32t or 300
(c) 16t or 300 (d) 16t or 200

SJVNL ET 2019

Ans. (b) : For tacking rivets,
Pitch = min^m (32 t or 300)

110. What is the formula to find the nominal diameter of rivet using Unwin's Formula?

(a) $4.23\sqrt{t}$ (b) $5.35\sqrt{t}$
(c) $3.75\sqrt{t}$ (d) $6.04\sqrt{t}$

SJVNL ET 2019

Ans. (d) : Nominal diameter = 6.04 $\sqrt{t}$ mm
t = thickness of plate.

111. What is the bulk modulus for steel in N/m^2?

(a) 125×10^9 (b) 160×10^9
(c) 2.2×10^9 (d) 75×10^9

SJVNL ET 2019

Ans. (b) : Bulk modulus for steel is 160×10^9 N/m^2

112. According to I.S. specifications, rivets or bolts carrying a calculated shear stress through a packing more than 6 mm thick should be increased by how many percentage for each 2 mm thickness of packing?

(a) 3.5% (b) 1.5%
(c) 5% (d) 2.5%

SJVNL ET 2019

Ans. (d) : As per IS : 800 : 1971 recommends that in a splice plate the number of rivets carrying calculated shear stress through a packing greater than 6 mm thick is to be increased by 2.5% for every 2.0 mm thickness of packing.

113. For high-strength friction bolts, what is the factor of safety for wind load?

(a) 1.2 (b) 1.15
(c) 1.4 (d) 1.5

SJVNL ET 2019

Ans. (a) : For high – strength friction bolts, the factor of safety for wind load is 1.2.

114. Distance between the centre of two consecutive rivets measured along a row is called.....

(a) Eccentricity (b) Pitch
(c) Edge distance (d) Gauge

SJVNL ET 2019

Ans. (b) : Distance between the centre of two consecutive rivets measured along a row is called pitch. It is parallel to the load also.

115. Which of the following bolts have high tensile strength?

(a) High strength bolt (b) Unfinished bolts
(c) Turned bolt (d) Ribbed bolt

SJVNL ET 2019

Ans. (a) : High strength bolts are made from high strength carbon steel or from tempered alloy steel.
The high– strength materials tends to increase the bolt strength roughly by 25% to 50%.

Search on Telegram @apna_pdf

116. According to IS 800, the distance between the centers of any two adjacent fasteners shall not exceed : (t is thickness of the thinner plate)

(a) 24t or 250 mm (b) 16t or 300 mm
(c) 32t or 300 mm (d) 16 t or 200 mm

UPPCL AE 2015
CGPSC AE 2014 Shift–I

Ans. (c) : According to IS 800 : 2007, the distance between the centers of any two adjacent fasteners shall not exceed 32t or 300 mm (t = thickness of thinner plate)

117. What is the maximum yield stress given by IS 1786 for Fe415 S?

(a) 415 (b) 540
(c) 490 (d) 450

UPPCL AE 2015

Ans. (b) : Maximum yield stress given by IS 1786 for Fe 415S equals stress for 0.2 percent strain and is 540 N/mm^2

118. What should be the minimum yield stress (MPa) of Fe600 as per IS 1786-2008?

(a) 625 (b) 575
(c) 550 (d) 600

UPPCL AE 2015

Ans. (d) : As per IS 1786 – 2008
Fe – 600
minimum yield stress is 600 MPa.

119. Two bolted plates under tension with alternative arrangement of bolt holes are shown in figures 1 and 2. The hole diameter, pitch, and gauge length are d, p and g, respectively. Which one of the following conditions must be ensured to have higher net tensile capacity of configuration shown in Figure 2 than that shown in Figure 1?




Figure 1




Figure 2

(a) $p^2 > 2gd$ (b) $p^2 < \sqrt{4gd}$
(c) $p^2 > 4gd$ (d) $p > 4gd$

AP TRANSCO AEE 2017

Ans. (c) :

$$T_{dn} = \frac{0.9F_u}{\gamma_m}A_{net}$$

$$T_{dn} \propto A_{net}$$

$$(T_{dn})_{max} \propto (A_{net})_{max}$$

$$(A_{net})_{max} = \frac{p^2}{4g}$$

$\boxed{p^2 > 4g}$ for max. A_{net}.

120. The nominal diameter of the bolt is 14 mm then the diameter of bolt hole will increase by-

(a) 1.0 mm (b) 1.5 mm
(c) 2.0 mm (d) 1.25 mm

UPPCL AE 2014

Ans. (a) : $d' = d + 1mm$ *when* $12 \le d < 16mm$
$d' = d + 2mm$ *when* $16 \le d \le 24mm$
$d' = d + 3mm$ *when* $d > 24mm$
d' = dia of bolt hole
d = nominal diameter of bolt

121. _____riveting is used in structural units

(a) Chain (b) Zig-zag
(c) Diamond (d) None of the above

APPSC (PHE) AE Paper-2 2012


Ans. (c) : In the structural units, Diamond riveting is used.

122. Load on connection is not eccentric for

(a) Lap joint
(b) Single cover butt joint
(c) Double cover butt joint
(d) All the above

APPSC AEE 2016
ESE 2001

Ans. (c) : Load on double cover butt joint in not eccentric



123. As per IS-800, the minimum pitch of bolts in a row of bolts is recommended as the diameter of the bolt times

(a) 2.0 (b) 2.5
(c) 3.0 (d) 4.0

APPSC AEE 2016
APPSC AE 2016 (Mains)

Ans. (b) : Pitch p shall not less than 2.5d, where d is the nominal diameter of bolt.
• Pitch shall not be more than-
(A) 16t or 200mm whichever is less in case of tension member.
(B) 12t or 200mm which ever is less in case of compression member, where t is thickness of thinnest member.

124. What is minimum edge distance from centre of the bolt of diameter, d to nearest edge of plate in case of rolled, machine-flame cut, sawn and planed edges?

(a) 3.0 d (b) 1.5 d
(c) 2.0 d (d) 2.5 d

GPSC AE January 2018

Ans. (b) : In case of rolled, machine flame cut, sawn and planed edge:
(edge distance) e ≥ 1.5d (d = bolt diameter)
edge distance is distance b/w centre of bolt and nearest edge of plate.

Search on Telegram @apna_pdf

125. In design of steel structures using Working Stress method of design, the factor of safety (FOS) is applied to .....

(a) Loading
(b) Yield stress of material
(c) Sectional properties of the members
(d) Safe bearing capacity (SBC) of soil

GPSC AE January 2018

Ans. (b) : In working stress method,
For concrete FOS ≤ 3
For steel FOS = 1.75 to 1.85.
In this theory, the materials (concrete and steel) are assumed to be stressed well below their elastic limit under design loads.

126. Bending compressive and tensile stresses respectively are calculated based on

(a) Net area and gross area
(b) Gross area and net area
(c) Net area in both cases
(d) Gross area in both cases

UPRVUNL AE 2015

Ans. (b) : IS.800.2007
- **In tension member -** Net area will be considered.
- **In compression member-** Gross area will be considered.

127. In a composite construction

(a) Interface slipping is prevented by using shear connector
(b) Differential shrinkage is overcome by using the same grade of concrete for both the components
(c) Precast member is always designed to carry the weight of in-situ concrete without props.
(d) The in-situ concrete cannot be prestressed.

MPPSC AE 2014

Ans. (a) In a composite construction, interface slipping is prevented by using shear connector.

128. Minimum pitch in a riveted joint shouldn't be

(a) Less than 200 mm
(b) More than 200 mm
(c) Greater than 2.5 times the gross diameter of the rivet
(d) Less than 2.5 times the nominal diameter of the rivet

GPSC AE June 2019

Ans. (d) : Minimum pitch in a reverted joint should not be less than 2.5 times the nominal diameter of the rivet as per IS 800 : 1984.

129. The magnitude of tensile and compressive residual stress in rolled sections may reach

(a) $0.2f_y$ & $0.8f_y$ (b) $0.3f_y$ & $0.5f_y$
(c) $0.4f_y$ & $0.5f_y$ (d) $0.3f_y$ & $0.6f_y$

GPSC AE June 2019

Ans. (b) : The magnitude of tensile and compressive residual stress in rolled sections may reach $0.3f_y$ and $0.5f_y$.
f_y = minimum yield stress in steel in N/mm^2.

130. The difference between gross diameter and nominal diameter for rivets upto 25mm diameter is

(a) 1 mm (b) 1.5 mm
(c) 2 mm (d) 2.5 mm

GPSC AE June 2019

Ans. (b) : The difference between gross diameter and nominal diameter for rivets upto 25 mm diameter is 1.5 mm.
Gross dia = nominal dia + 1.5 mm, for nominal dia ≤ 25 mm
Gross dia = nominal dia + 2 mm, for nominal dia > 25 mm

131. What is the hole diameter for a bolt of 25 mm diameter?

(a) 25 mm (b) 26 mm
(c) 28 mm (d) 30 mm

GPSC AE Dec 2018

Ans. (c) : d' = d + 3, for d > 24 mm
d' = 25 + 3 = 28 mm

132. When the maximum distance between centres of two adjacent rivets connecting the members subjected to either compression or tension exceed the maximum pitch, then the additional rivets which are not subjected to the calculated stress are used, and are known as

(a) Auxiliary rivets (b) Tacking rivets
(c) Long grip rivets (d) Packing rivets

GPSC AE Dec 2018
ESE 2011

Ans. (b) : Tacking rivets are used if the minimum distance between centers of two adjacent rivets exceed 32t or 300 mm, whichever is less. Tacking rivets are not considered to calculate stress

133. If d is gross diameter of rivet and p is the pitch of a riveted joint, the efficiency of the joint is given by

(a) $\frac{p-d}{p}$ (b) $\frac{p-d}{d}$
(c) $\frac{d}{p-d}$ (d) $\frac{d}{p+d}$

GPSC AE Dec 2018
UPPCL AE 2014

Ans. (a) :

Efficiency of joint, $\eta = \frac{\text{Strength of joint in tearing}}{\text{Tensile strength of plate}}$

$$\eta = \frac{A_n \times f_{ut}}{A \times f_{ut}}$$

where, A_n = net area, A = total area

$$\eta = \frac{(p-d)t}{pt}$$

$$\boxed{\eta = \frac{p-d}{p}}$$

Search on Telegram @apna_pdf

134. Initial tension in HSFG bolts is known as:

(a) Test load (b) Start load
(c) Primary load (d) Proof load

PTCUL AE 2016

Ans. (d) : The initial tension in HSFG bolts firmly holds the joining parts between the bolts head and the nut and this initial tension is known as proof load.

135. The distance between centre to centre of two adjacent rivet holes should not be less than:

(a) 2.5 times the diameter of rivet
(b) 1.5 times the diameter of rivet
(c) 1.5 times the diameter of rivet hole
(d) 1.5 times diameter of rivet + 2 mm

DMRC AM 2020
Nagaland PSC CTSE 2017 Paper–I
PTCUL AE 2016


Ans. (a) : The distance between centre to centre of two adjacent rivet holes should not be less than 2.5 times the diameter of rivet. IS : 800 – 1984

136. If the diameter of a bolt is 20 mm, then the maximum number of bolt(s) that can be accommodated in one row in a 140 mm wide flat section is (are) :

(a) 2 (b) 3
(c) 1 (d) 4

LMRC AM 2018

Ans. (a) : Minimum edge distance = 1.5 d
= 1.5 × 20 = 30 mm



After providing edge distance spacing between bolts
= 140 – 30 × 2
= 80 mm
Minimum Pitch = 2.5 d
= 2.5 × 20
= 50 mm
If we provide three bolts between two bolts then its pitch distance 40 mm, then minimum pitch will be reduced 50 mm. So only two bolts are provided in one row.

137. A steel built up column is subjected to an axial force of 2000 kN. The lacing system has to be designed for resisting a transverse shear of:

(a) 60 kN (b) 50 kN
(c) 30 kN (d) 20 kN

CIL MT 2020

Ans. (b) : Lacing is designed for 2.5% of applied load so that, 0.025 × 2000 = 50 kN.

138. In which connection can the number of rivets on the web of a beam and the number of rivets on the flange of a column be calculated from the strength of rivet?

(a) Shear connection (b) Tee connection
(c) Angle connection (d) Moment connection

DMRC AM 2020

Ans. (a) : In shear connection the number of rivets on the web of a beam and the number of rivets on the flange of a column be calculated from the strength of rivet.

139. The yield strength range for high strength quenched and tempered steels as per IS : 2003 should be :

(a) 600-650 MPa (b) 550-700 MPa
(c) 710-820 MPa (d) 900-950 MPa
(e) 1,000-950 MPa

CGPSC AE Shift II 2018

Ans. (b) The grid strength range for high strength quenched and tempered steels as per IS : 2003 should be 550-700 MPa.

140. As per IS 800 for a nominal diameter of 12 mm bolt, the diameter of the hole provided should be :

(a) 15 mm (b) 13 mm
(c) 20 mm (d) 24 mm
(e) 50 mm

CGPSC AE Shift II 2018

An0s. (b) As per IS 800 for a nominal diameter of 12 mm bolt, the diameter of the hole provided should be 13 mm.
$d' = d + 1$ mm when $12 \le d < 16$ mm
$d' = d + 2$ mm when $16 \le d \le 24$ mm
$d' = d + 3$ mm when $d > 24$ mm
d = nominal dia of bolt.
d' = dia of bolt hole.

141. Wrought iron contains carbon upto:

(a) 0.25% (b) 1.0%
(c) 1.5% (d) 2%
(e) 2.5%

Haryana PSC AE 2018 Paper–I

Ans. (a) : Wrought iron contains carbon upto 0.25% wrought iron has carbon 0.15% and cost iron has 2 to 4% of carbon and mild steel has 0.15 to 0.30% of carbon.

142. Steel structures are ideally suitable for impact loads because they have high:

(a) Toughness value (b) Elastic modulus
(c) Design stress (d) Plastic modulus

Haryana PSC AE 2017
ESE 2008

Ans. (a) Steel structures are ideally suitable for impact loads because they have high toughness value.

143. A steel section is subjected to a combination of shear and bending actions. The applied shear force is V and the shear capacity of the section is V_s. For such a section, high shear force as per IS : 800-2007 is defined as -

(a) $V > 0.45\ V_s$ (b) $V > 0.60\ V_s$
(c) $V > 0.75\ V_s$ (d) $V > 0.90\ V_s$

Rajasthan VP ITI 2018

Ans. (b) $V > 0.60\ V_s$ (As per IS : 800 - 2007)

144. For rivets in tension with counter-sunk heads, the tensile value shall be ?

(a) Reduced by 25%
(b) Reduced by 33.33%

Search on Telegram @apna_pdf

(c) Increased by 25%
(d) Increased by 33.33%

Rajasthan VP ITI 2018

Ans. (b) For rivet in tension with counter sunk heads, the tensile value will be reduced by 33.3%.

145. If the thickness of thinnest outside plate is 10 mm, then the maximum pitch of rivets in tension will be taken as -
(a) 100 mm (b) 120 mm
(c) 160 mm (d) 200 mm

Rajasthan VP ITI 2018

Ans. (c) Pitch is minimum of 16t or 200 mm.
Therefore pitch = 16 × 10 = 160 mm.

146. The value of permissible bending stress 0.66 fy is applicable for IS 800-84 :
(a) Laterally restrained beam
(b) Laterally unrestrained beam
(c) Both (a) & (b)
(d) None of the above

UP Jal Nigam AE 2016

Ans. (a) : The value of permissible bending stress $0.66f_y$ is applicable for IS 800-1984 : Laterally restrained beam.

147. For single angle discontinuous strut is connected to a gusset plate with one rivet only:
(a) Effective length = l, permissible stress = 100 percent
(b) Effective length = l, permissible stress =80 percent
(c) Effective length = 0.8l, permissible stress = 100 percent
(d) None of the above

UP Jal Nigam AE 2016

Ans. (b) For single angle discontinuous strut is connected to a gusset plate with one rivet only
Effective length = l, permissible stress =80 percent.

148. When the line of action of load lies in the plane of the group of rivets/bolts and the centre of gravity of rivet group does not lie on the line of action of the load the rivet is subjected to :
(a) Shear and bending
(b) Shear and torsion
(c) Shear and tension
(d) Twisting and bending

UP Jal Nigam AE 2016

Ans. (b) : When the line of action of load lies in the plane of the group of rivets/bolts and the centre of gravity of rivet group does not lie on the line of action of the load the rivet is subjected to shear and torsion.

149. Let 108 mm be the pitch of the rivet and 27 mm is the gross diameter of rivet then efficiency of joint per pitch length in percent
(a) 75 (b) 54.17
(c) 29.17 (d) 25

UP Jal Nigam AE 2016

Ans. (a) : pitch (p) = 108 mm
gross diameter (d) = 27 mm

$$\text{Efficiency} = \frac{p-d}{p}\times 100$$

$$\text{efficiency} = \frac{108-27}{108}\times 100$$

$$= \frac{81}{108}\times 100 = 75\%$$

150. For the compression members, the distance between the centers of two adjacent fasteners (Pitch) in a line lying in the direction of stress shall not exceed ..... or whichever is less. Take t as the thickness of thinner plate.
(a) 16 t, 200 mm (b) 16 t, 450 mm
(c) 12 t, 200 mm (d) 12 t, 450 mm

HPPSC Poly. Lect. 2016

Ans : (c) The distance between the center of two adjacent rivets in line with the direction of stress shall not exceed 12 t or 200 mm which is less. The distance between centers of two adjacent rivets in line with the direction of stress shall not exceed 16 t or 200 mm whichever less in tension member.

151. In the case of bolted, riveted or welded trusses and braced frames, the effective length of the compression members shall be taken as ..... times the distance between centers of connections.
(a) 0.7 to 1.0 (b) 0.7 to 0.85
(c) 1.0 to 20 (d) 0.5 to 0.7

HPPSC Poly. Lect. 2016

Ans : (a) In the case of bolted, riveted or welded trusses and braced beams, the effective length of the compression members shall be taken as 0.7 to 1.0 times the distance between connections.

152. Which of the following is NOT the method of tensioning steel?
(a) Mechanical (b) Hydraulic
(c) Thermal (d) Physical


IRCON AE 2017

Ans. (d) : Tensioning of steel is done as Post-tensioning and pre-tensioning by mechanical, hydraulic and thermal method, but there is no physical method for tensioning of steel.

153. The diameter of a bolt hole with respect to the nominal diameter of 12 mm to 14 mm of the bolt as per IS Code, should be:
(a) 1.40 mm more as a standard clearance
(b) 2.60 mm more as a standard clearance
(c) 1.00 mm more as a standard clearance
(d) 1.20 mm more as a standard clearance

JUVNL AE 2016

Ans. (c) :




154. The carbon content in mild steel is in the range of:
(a) 0.15 to 0.30% (b) 2.00 to 4.50%
(c) 0.09 to 0.11% (d) 1.00 to 1.50%

JUVNL AE 2016

Search on Telegram @apna_pdf

Ans. (a) : 0.15 to 0.30% of C.
Low carbon steel – upto 0.15% C
Mild steel – 0.15 - 0.30% C
Medium carbon steel – 0.35 - 0.65% C
High carbon steel – 0.65 - 1.75% C


155.



Rivet shape shown above is known as :
(a) Pen shape
(b) Snap shape
(c) Flat counter sunk
(d) Round counter sunk

GPHC AE 2018

Ans : (c)
Type of Rivet Shape :



156. Diameter of holes for bolts/rivets less than 25 mm diameter should be larger by
(a) 1.5 mm (b) 2.5 mm
(c) 2.0 mm (d) None of the above

WBPSC AE 2014

Ans. (a) : Diameter of rivet hole is made larger than the diameter of rivet by 1.5 mm for diameter below or equal to 25 mm and 2 mm for rivet diameter above 25 mm.
1.5 mm $\rightarrow d \le 25$ mm
2.0 mm $\rightarrow d > 25$ mm

157. The permissible stress for crippling of a steam beam is equal to
(a) 0.75 f_y (b) 0.66 f_y
(c) 0.8 f_y (d) 0.6 f_y

WBPSC AE 2007

Ans. (b) : The permissible stress for crippling of a steam beam is 0.66 f_y. As per IS : 800 – 2007.

158. If d is the gross diameter of rivet and p is the pitch of rivets the efficiency riveted joint is given by
(a) $\frac{p+d}{d}$ (b) $\frac{p}{p-d}$
(c) $\frac{p-d}{p}$ (d) $\frac{d}{p-d}$

WBPSC AE (MCD) 1998

Ans. (c) : Efficiency of joints =

$$\eta = \frac{\text{Strength of joint in tearing}}{\text{Tensile strength of plate}} \times 100$$

$$\eta = \frac{A_{net} \times f_{ut}}{A \times f_{ut}}$$

A_{net} = Net area
A = total area

$$\eta = \frac{(p-d)t}{p \times t}$$

$$\boxed{\eta = \frac{p-d}{d}}$$

159. When effect of wind or earthquake load is taken into account the permissible stresses on rivets, bolts and tension rods may be exceeded by
(a) 25% (b) $33\frac{1}{3}\%$
(c) 35% (d) 40%

WBPSC AE (PHE) 1998

Ans. (a) : When wind and earthquake loads are considered permissible stress in connections are increased by 25%.

160. Diameter of a rivet hole for rivet diameter less than 25 mm is usually considered as
(a) 1.5 mm + nominal diameter of rivet
(b) 2.0 mm + nominal diameter of rivet
(c) 2.50 mm + nominal diameter of rivet
(d) 3.0 mm + nominal diameter of rivet

WBPSC AE (PHE) 1998

Ans. (a) : d' = d + 1.5 when $d \le 25$ mm
d' = d + 2 when $d > 25$ mm
where d' = gross diameter of rivet.
d = nominal diameter of rivet.

161. Ratio of permissible bearing stress in power driver field rivets with respect to that for shop rivet is
(a) 1.0 (b) 0.9
(c) 0.8 (d) 0.6

WBPSC AE (PHE) 1998

Ans. (c) :
Permissible bearing stress of shop rivet in field = 250
Permissible bearing stress of shop rivet in shop = 300
Ratio = $\frac{250}{300} = 0.833 = 0.8$

162. Maximum permissible longitudinal pitch of rivets, in rivet joints in compression momoers, is
(a) 16t (b) 12t
(c) 16D (d) 12D

WBPSC AE (PHE) 1998

Ans. (b) : Maximum pitch for the compression member is 12t or 200mm, which ever is less, will be taken.

163. In a steel tension member, it's maximum strength in case of adequately designed bolted connections is governed by _____.

Search on Telegram @apna_pdf

(a) The slenderness of the member
(b) The tensile strength of net sectional area of the member.
(c) The strength of the bolted connection.
(d) The section modulus of the member

TSPSC Deputy Engineer 2015

Ans. (b) : In a steel, tension member, its maximum strength in case of adequately designed bolted connection is governed by tensile strength of net sectional area of the member.

164. A steel plate is 200 mm wide and 10 mm thick. A bolt of nominal diameter 16 mm is driven. The net effective sectional area of the plate is

(a) 2000 sq.mm (b) 1840 sq.mm
(c) 1820 sq.mm (d) 1740 sq.mm

TSPSC AEE 2017

Ans. (c) : Given,
g = 200 mm
d = 18 mm
t = 10 mm
A net $\Rightarrow$ (g–d) t
g = gross
d = dia of hole = d= 16+ 2 = 18 mm
A net = (200–18) 10 = 1820 sq. mm

165. The design yield stress of steel according to IS : 456-1978 is

(a) 0.37 f_y (b) 0.57 f_y
(c) 0.67 f_y (d) 0.87 f_y

Chandigarh AE 2017

Ans. (d) : The designed yield structure of steel according to IS 456-1978 is 0.87 fy.

166. According to IS specifications, maximum pitch of rivets in compression is

(a) lesser of 200 mm and 12t
(b) lesser of 200 mm and 16t
(c) lesser of 300 mm and 32t
(d) lesser of 300 mm and 24t

Chandigarh AE 2017

Ans. (a) : Maximum pitch per the compression member is 12t or 200, which ever is less will be taken.

167. For field rivets, the permissible stresses are reduced by what percentage?

(a) 15% (b) 10%
(c) 25% (d) 33.5%

Chandigarh SDE 2017

Ans. (b) : For field rivets permissible stress are taken 90% of the shop rivet. So it is reduced 10% of shop rivet.

168. Bolts are most suitable to carry

(a) shear (b) bending
(c) axial tension (d) shear and bending

Chandigarh SDE 2017

Ans. (c) : Bolt are suitable to carry axial tension of the section.

169. A 16 gauge steel sheet will roughly have thickness equal to

(a) 6 mm (b) 4 mm
(c) 3 mm (d) 1.5 mm

Chandigarh SDE 2017

Ans. (d) : 14 gauge steel = 1.6 mm
18 gauge steel = 1 mm
20 gauge steel = 0.80 mm

170. For an I-beam shape factor is 1.12, the factor of safety in bending is 1.5. If the allowable stress is increased by 20% for wind and earthquake loads, then the load factor is

(a) 1.1 (b) 1.25
(c) 1.35 (d) 1.4

Gujarat PSC AE 2017

Ans : (d) Factor of safety = $\frac{\text{yield stress}}{\text{Allowable stress}}$

with increase in allowable stress, the factor of safety will reduce to $\frac{1.5}{1.2} = 1.25$

$\therefore$ Load factor = fos $\times$ shape factor
$= 1.25 \times 1.12 = 1.40$

2. Weld Connections

171. For a pair of identical steel channel section, tacked - welded as a tension element. What is the net area of cross-section for design purposes?

(a) Net area of the webs only
(b) Net area of the flanges only
(c) Net area of the webs and flanges
(d) Web area plus a portion of the area of the flanges

Haryana PSC AE 2017

Ans. (c) : Net area of the webs and flanges.

172. A butt weld is specified by

(a) effective throat thickness
(b) plate thickness
(c) size of weld
(d) penetration thickness

Gujarat PSC AE 2017
WBPSC AE 2012

Ans : (d) A butt weld is specified by penetration thickness.

173. Two plates of Fe410 grade and thickness 14 mm and 12 mm are to be shop welded by a single V-groove weld joint. The joint is subjected to a factored tensile force of 350 kN. Assuming effective length of 150 mm, the strength of the weld is

(a) 350 kN (b) 410 kN
(c) 225 kN (d) 250 kN
(e) 125 kN

CGPSC AE 2014 Shift–I

Ans. (c) : Groove weld is designed as butt weld

hence strength $= \frac{L_w \times t_w \times f_y}{\gamma_{mw}}$

$L_w =$ 150 mm

$t_w = \frac{5}{8} \times$ thickness of thinner connected member in case of single butt joint.

Search on Telegram @apna_pdf

$= \frac{5}{8} \times 12 = 7.5$ mm

$\gamma_{mw} = 1.25$

f_y = smaller of yield stress of fillet weld & parent metal here in question only strength of parent metal $f_u = 410$ MPa has given.

Hence strength of parent metal will be less and commonly 250 MPa used

lesser of $\begin{cases} 410\,\text{MPa} \\ 250\,\text{MPa} \end{cases}$

$$\text{strength} = \frac{150 \times 7.5 \times 250}{1.25} < \frac{150 \times 7.5 \times 410}{1.25}$$

$= 225$ kN < 369 kN

174. Calculate the pitch strength of fillet weld per 1 mm of 6 mm size with allowable shear stress in the weld 100 MPa.

(a) 700 N (b) 600 N
(c) 424 N (d) 420 N

TNPSC AE 2015

Ans. (c) Effective size = KS = 0.707 × 6 = 4.242 mm
Pitch strength per mm length
= f × 1 × 4.242
= 100 × 4.242 = 424 N

175. What shall be the minimum effective throat thickness of a fillet weld in case of structural steel design?

(a) 4 mm (b) 3 mm
(c) 5 mm (d) 2 mm

GPSC AE March 2018
CIL MT 2017

Ans. (b) : According to IS 816 : 1969, 3 mm shall be the minimum effective throat thickness of a fillet weld in case of structural steel design.

176. A circular shaft of diameter 150mm is welded to a rigid plate by an external all-round fillet weld of size 10mm. If a torque of 10kNm is applied to the shaft, then find maximum shear stress developed in the fillet weld.

(a) 80.8N/mm^2 (b) 40.0N/mm^2
(c) 56.5N/mm^2 (d) 65.4N/mm^2

APPSC Poly. Tech. Lect. 2020

Ans. (b) : 40.4 N/mm^2
Round fillet weld of size = 10mm
Given, Torque (T) = 10kNm
D = 150mm $\Rightarrow$ r = 75 mm
Polar moment of inertia, $I_P = Ar^2$
$= (KS)(\pi D)\, r^2$
$= (0.707 \times 10) \times \pi \times 150\,(75)^2$
$= 18740581.93\ \text{mm}^4$
Now, From eq^n of Torsion

$$\frac{T}{I_P} = \frac{\tau}{r}$$

$$\tau = \frac{Tr}{I_P}$$

$$= \frac{(10 \times 10^6) \times 75}{18740581.93} = 40.020\ \text{N/mm}^2$$

177. The effective length of fillet weld of length 200 mm and size 12 mm is

(a) 188 mm (b) 176 mm
(c) 388 mm (d) 200 mm

GPSC Poly. Tech. Lect. 2016
Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (b) Effective length of fillet weld = weld length – 2 × weld size = 200 – 2 × 12
= 200 – 24 = 176 mm

178. The type of weld used for joining two surfaces approximately at right angles to each other is known as

(a) Butt weld (b) U groove weld
(c) V groove weld (d) Fillet weld

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (d) These welds are commonly referred to as tee joint, which are two pieces of metal perpendicular to each other or lap joints, which are two pieces of metal that overlap and are welded at the edges.

179. A standard fillet weld consists of isosceles triangle with which of the following angles ?

(a) 60 degrees (b) 45 degrees
(c) 20 degrees (d) 75 degrees

Nagaland PSC CTSE 2017 Paper–I
Rajasthan AE (Nagar Nigam) 2016

Ans. (b) : When the cross section of fillet weld is 45^0 isosceles triangle it is known as standard fillet weld.

180. A fillet weld is not recommended if the angle between the fusion faces is :

(a) equal to 60^0 (b) equal to 120^0
(c) equal to 90^0 (d) less than 60^0

Rajasthan AE (Nagar Nigam) 2016

Ans. (d) According to IS 816- 1969, A fillet weld is not recommended if the angle between the fusion faces is less than 60^0.

181. Two plates of thickness 14 mm and 16 mm are to be joined by a double-V Butt weld. The effective length of the weld is 175 mm, the allowable stress in tension is 150 N/mm^2 and the joint is subjected to a tensile force of 280 kN. Find the strength of the weld in kN.

(a) 200.5 kN (b) 157.5 kN
(c) 467.5 kN (d) 367.5 kN

Rajasthan AE (Nagar Nigam) 2016

Ans. (d) :
Strength of weld = effective thickness × length × allowable stress
effective thickness = thickness of thinner member for double V groove weld
t = 14m, l = 175 mm, stress = 150 N/mm^2
Strength of weld = 14 × 175 × 150 = 367.5 kN.

182. The minimum thickness of plates in a steel stack should be :

(a) 4 mm (b) 6 mm
(c) 8 mm (d) 10 mm

Nagaland PSC CTSE 2017 Paper–I

Ans. (b) : The minimum thickness of plates in a steel stack should be 6 mm.

Search on Telegram @apna_pdf

183. Which of the following does not describe a weld type ?

(a) Butt (b) Plug
(c) Zig-Zag (d) Lap

Nagaland PSC CTSE 2017 Paper–I

Ans. (c) : Zig-Zag is not a type of a weld. It is a type of rivet. Butt, plug, Lap, fillet, slot, seam are the types of welds.

184. Which one of the following is the mode of failure in a fillet weld material?

(a) Tension (b) Shear
(c) Bearing (d) Crushing

AP (VSS-1) PART - A 2017
UKPSC AE 2012 Paper–I
ESE 2001

Ans : (b) A fillet weld may be subjected to direct, bending and shear stresses but shear controls the design since the fillet weld always fails in shear.

185. Two flats (110mm × 16mm) and (110mm × 12mm) are welded by double V butt weld. if permissible stress is 142 N/mm^2, the strength of weld will be–

(a) 167.75 kN (b) 195.56 kN
(c) 187.44 kN (d) 210.25 kN

(UTTRAKHAND AE 2013)

Ans : (c) Given,
$L_w = 110mm$, $t_e = 12mm$, $f = 142N/mm^2$
Strength of weld in tension $T_{dw} = f.L_w t_e$

$T_{dw} = 142N/mm^2 \times 12mm \times 110mm = 187.44$ kN

186. The effective length of fillet weld is

(a) Total length – 2 × throat size
(b) 0.7 × Total length
(c) Total length – 2 × weld size
(d) Total length – (weld size $\times\sqrt{2}$)

GPSC AE Dec 2018 / Rajasthan VP ITI 2018
JPSC Combined AE Paper V 2013
UKPSC AE 2012 Paper–I / RPSC VPITI 2012
UPPSC State Eng. A.E. 2003, ESE 1997

OR

Effective length of a weld is equal to

(a) Overall length – weld size
(b) Overall length – throat thickness overall
(c) Overall length – 2 × weld size
(d) Length – 2 × throat thickness

GPSC AE (CLASS 1 & 2) 2019
Maharashtra PSC Mains 2018 Paper-1
RPSC AEn.- 2013, ESE 2011


Ans : (c) Effective length is the length of the fillet weld for which the specified size and throat thickness of weld exist. It is taken equal to its overall length minus twice the weld size. The deduction is made to allow for craters to be formed at the ends of the welded length. End returns are made equal to twice the size of the weld to relieve the latter from high stress concentrations at their ends.
Effective length = Total length – 2 × weld size.

187. For a standard 45^0 fillet, the ratio of size of fillet of throat thickness is

(a) 1 : 1 (b) 1 : 1.414
(c) 1.414 : 1 (d) 2 : 1

MPPSC AE 2014
RPSC A En.– 2013

Ans : (c)



$$\sin\theta = \frac{t}{S}$$

$$\theta = 45^o;\ \therefore \frac{S}{t} = \frac{1}{\sin 45^o} = \sqrt{2}$$


$$\boxed{S : t = 1.414 : 1}$$

188. The effective length of fillet weld should not be less than-

(a) Two times weld size
(b) Four times weld size
(c) Six times weld size
(d) Weld size

GPSC R&B AE 2016 / OPSC AEE 2015 PAPER–I
UPPSC State Eng. A.E. 2004 (I)
RPSC ACF 2011

Ans. (b) :



Minimum effective length of fillet weld should not be less than 4 times the weld size.

189. In the fillet weld the weakest section is the

(a) smaller side of the fillet
(b) throat of the fillet
(c) side perpendicular to force
(d) side parallel to force

Rajasthan Nagar Nigam AE Shift-2, 2016
APPSC AEE 2016 / GPSC Assistant Prof. 2016
UJVNL AE 2016 / RPSC ACF 2011
UPPSC CIVIL ENGG. A.E. 2013
UPPSC STATE ENGG. A.E. 2008 / ESE 1996

Ans : (b) In the fillet weld the weakest section is the throat of the fillet.

t = Effective throat thickness
S = size of weld

$$\boxed{t = k.S}$$

Here, 'k' depends upon angle between fusion faces.

Search on Telegram @apna_pdf

190. If the angle between fusion faces of a fillet weld is 60^0-90^0, the effective throat thickness as per Indian standard is equal to:

(a) $\frac{1}{\sqrt{2}}$ size of weld (b) $\frac{1}{\sqrt{3}}$ size of weld

(c) $\sqrt{2}$ size of weld (d) $\sqrt{3}$ size of weld

UPPSC State Eng. A.E. 2008
UPPSC AE 12.04.2016 Paper–I

Ans : (a) Effective length $\frac{1}{\sqrt{2}} = 0.707\ l$

191. The effective throat thickness of a fillet weld depends upon-

(a) angle between fusion faces
(b) length of weld
(c) permissible shear stress
(d) type of weld

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (a) : Effective throat thickness,

$$t = K \times s$$

Where s = size of weld and K is a parameter which depends on angle between fusion faces.

Angle between fusion faces	Constant, K
$60^o - 90^o$	0.70
$90^o - 100^o$	0.65
$101^o - 106^o$	0.60
$107^o - 113^o$	0.55
$114^o - 120^o$	0.50

192. The size of the fillet weld is indicated by

(a) side of the triangle of the fillet
(b) throat of the fillet
(c) length of the weld
(d) size of the plate

UPPSC State Eng. A.E. 2007(I)
UKPSC AE Paper I 2007

Ans : (a) The size of the fillet weld is indicated by side of the triangle of the fillet

Minimum size of weld

Thickness of thicker plate (mm)	size of weld (mm)
0 - 10 mm	3 mm
10 - 20 mm	5 mm
20 - 32 mm	6 mm
32 - 50 mm	8 mm (in Ist run) 10 mm (final size)

Maximum size of weld :

1. for square edge maximum (mm) size of weld
= thickness of thinner plate - 1.5 mm
2. for round edge maximum size (mm)
$= \frac{3}{4} \times$ normal thickness of plate

193. Welded connections are preferred over riveted connections because

(a) they are economical
(b) easy in connection
(c) the loss of member strength is smaller
(d) they reduce the secondary strength

[UPPSC State Eng. A.E. 2007(I)]

Ans : (c) Advantages of welded joint over–

1. As no holes are required for welding, so the loss of member is smaller.
2. Welded joints are economical as less labour and material are required at joint.
3. The welded connection look better than the usually bulky riveted joints.
4. The speed of fabrication is higher with welding process.
5. The welding process requires less working space than the riveting process.
6. No noise is produced in the welding process as that in riveting process.

194. The cross section of the weld throat is the

(a) minimum dimension
(b) average dimension
(c) maximum dimension
(d) None of these

[UPPSC State Eng. A.E. 2004 (I)]

Ans : (a) Throat is the weakest section of weld which has minimum dimension.


195. If a structure is under fatigue stresses, then the welded joints as compared to riveted joints will fail-

(a) Earlier (b) Later
(c) At the same time (d) Not at all

Maharashtra PSC (Mains) 2017 Paper–I
WBPSC AE 2007

Ans. (a) : Fatigue is the weakening of material caused by repeatedly applied loads. During riveting, rivets are hammered and they completely fill the holes leaving no scope of expansion and contraction. Due to this, high stresses generate in rivets under fatigue loading and they fail earlier.

196. For the fillet weld cross - section shown in figure the throat thickness is :



(a) AB (b) BC
(c) AD (d) BD

[HPPSC 2016-II]
(JPSC Combined AE Paper V 2013)

Ans. (d) : Effective throat thickness is minimum thickness of weld at any section. In the given figure BD, which is perpendicular to CA is the minimum distance from point B on line AC, therefore effective throat thickness is BD.


197. The ratio of effective throat of fillet weld to its size is

(a) less than 0.707 (b) greater than 0.707
(c) 0.85 (d) 0.707

TNPSC AE 2018

Search on Telegram @apna_pdf

Ans. (a) : Effective throat thickness depends upon angle of fusion faces, it varies between 0.707 to 0.5.



$$\frac{1}{2}\times s\times s=\frac{1}{2}\times t\times\sqrt{2}s$$

$$t=\frac{s}{\sqrt{2}}=0.707s$$

$$\frac{t}{s}=0.707$$

198. The fusible material used in welding to dissolve and facilitate the removal of oxides and other undesirable substances is known as

(a) inert material (b) inert gas
(c) flux (d) catalytic agent

Maharashtra PSC Mains 2018 Paper-1

Ans. (c) : Material used to prevent, dissolve or facilitate removal of oxides and other undesirable surface substances.

199. Effective throat size of a fillet is

(a) A function of the angle between the fusion sides
(b) Equal to the hypotenuse of the weld triangle
(c) The perimeter of the weld divided by the size of the weld
(d) 0.707 times the size of the weld

UPSC JWM 2017

Ans. (a) : Effective thickness = KS
at temperature $60 - 120^0$
K = 0.707 to 0.5
S ∈ size of weld.

200. The maximum stress in a fillet weld will develop at the

(a) throat (b) long leg
(c) face (d) short leg

Rajasthan AE Nagar Nigam Shift-3, 2016

Ans. (a) : In order to determine strength of field joint, throat as a analysing point is considered.

201. The shortest distance from the root of the fillet weld to the face of the weld is called.....

(a) Effective area
(b) Effective throat thickness
(c) Effective length
(d) Effective depth

SJVNL ET 2019

Ans. (b) : The shortest distance from the root of the fillet weld to the face of the weld is called Effective throat thickness.

202. Effective area of fillet weld is equal to the product of.....

(a) Effective length and effective width
(b) Effective length and effective throat thickness
(c) Effective throat thickness and effective width
(d) Effective throat thickness and transverse spacing

SJVNL ET 2019

Ans. (b) : Effective area of fillet weld is equal to the product of effective length and effective throat thickness

203. End returns in fillet welds should not be less than .....

(a) Twice of size of the weld
(b) 1.5 times of size of weld
(c) Size of the weld
(d) 0.5 times of size of weld

GPSC AE January 2018

Ans. (a) : As per IS code, Effective length of fillet weld is taken equal to overall length minus twice the weld size.
Here, twice the weld size is the value of end returns in fillet.

204. Partial Safety Factor (r_{m0}) for field welds is .....

(a) 1.25 (b) 1.50
(c) 1.00 (d) 2.00

GPSC AE January 2018

Ans. (b) : Partial safety factor for material resistance governed by IS: 800 - 2007-
γ_{m1} = 1.5 for field welding
γ_{mo} = 1.25 for shop welding

205. The metal added at the joint while welding is known as .....

(a) weld metal (b) filler
(c) fillet metal (d) all the above are correct

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (b) : The metal added at the joint while welding is known as filler.

206. The design shear stress for which of the following weld types is same as that for fillet welds?

(a) Plug weld only
(b) Slot weld only
(c) Plug and Slot weld only
(d) Slot and Butt weld only

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (c) : The design shear stress for plug and slot weld is same as that for fillet weld.

207. Spot welding is used when two plates are placed:

(a) One below the other
(b) One butting against the other
(c) One next to other
(d) At right angle to each other

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (b) : Spot welding is used when two plates are placed one butting against the other.

208. In the case of a single-V butt welded joint, the effective throat thickness is taken as

Search on Telegram @apna_pdf

(a) $\frac{5}{8}\times$ thickness of thinner part

(b) $\frac{2}{5}\times$ thickness of thinner part


(c) $\frac{3}{5}\times$ thickness of thinner part

(d) $\frac{4}{7}\times$ thickness of thinner part

GPSC Assistant Prof. 2016

Ans. (a) : In case of a single-V butt welded joint, effective throat thickness = $\frac{5}{8}\times$ thickness of inner part.

209. Consider the fillet welded joint shown in the figure. The welded surfaces meet at 60º–90º (angle between fusion faces). The weld size is 8 mm and permissible stress in the weld is 110 MPa. What is the safe load P that can be transmitted by this welded joint, considering weld failure only?



(a) 315 kN (b) 220 kN
(c) 154 kN (d) 616 kN

UPPCL AE 2018

Ans. (c) : Angle between welded joint = 60^0-90^0
Throat thickness of fillet weld = ks
$= 0.7 \times 8$
Permissible stress in weld = 110 MPa

$$\tau_{perm} = \frac{P}{0.7(200\times 8 + 50\times 8)}$$

$P = 110 \times 0.7 \times 250 \times 8$
$P = 154$ kN

210. As per IS 800 : 2007 the size of a fillet weld should not be less than.....mm nor more than the thickness of the thinner part.

(a) 2 (b) 5
(c) 3 (d) 10
(e) 12

CGPSC AE Shift II 2018

Ans. (c) As per IS 800 : 2007 the size of a fillet weld should not be less than 3 mm nor more than the thickness of the thinner part.

211. As per IS 816 : 1969 the width or diameter of the weld should be :

(a) less than three times the thickness or 25 mm, whichever is greater
(b) less than five times the thickness or 35 mm, whichever is greater
(c) less than ten times the thickness or 45 mm, whichever is greater
(d) less than two times the thickness or 50 mm, whichever is greater
(e) les than five times the thickness or 70 mm, whichever is greater

CGPSC AE Shift II 2018

Ans. (a) As per IS 816 : 1969 the width or diameter of the weld should be less than three times the thickness or 25 mm, whichever is greater.

212. The size of fillet welds whall not be less than ..... and not more than ..... respectively. Take t is the thickness of the thinner plate of elements being welded.

(a) 3 mm, 1 t (b) 7 mm, 0.5 t
(c) 10 mm, 1 t (d) 15 mm, 0.5 t

HPPSC Poly. Lect. 2016

Ans : (a) The effective throat thickness of a fillet weld shall not be less than 3 mm and shall generally not exceed 0.7 t times the thickness or 1 t, where t is thickness of thinner plate.

213. Fillet welds used for joining the lapped plates are generally of right angled triangles shape. The size of the fillet weld is specified by:

(a) hypotenuse of the triangle
(b) throat of the fillet
(c) smaller side of the triangle
(d) smaller side of the plate welded

JUVNL AE 2016

Ans. (c) : The size of filled weld is specified by smaller side of the triangle because fillet welds used for joining the lapped plates are generally of right angled triangle.

214. The type of weld used for joining two surfaces approximately at right angle to each other is known as

(a) U groove weld
(b) Double V groove weld
(c) Square butt weld
(d) Fillet weld

WBPSC AE (MCD) 1998

Ans. (d) : Fillet welds are given normally lap joints or where, the members are coincide at the right angle.

215. Weakest section in a fillet weld is

(a) throat of the fillet
(b) side perpendicular to load axis
(c) side parallel to load axis
(d) hypotenuse of the fillet triangle

WBPSC AE (PHE) 1998

Ans. (a) : Throat is the weakest section of the weld which has minimum dimension.

216. The strength of the welded joint

(a) is always less than the strength of the elements
(b) cannot exceed 80% the strength of the elements
(c) cannot exceed 90% of the strength elements
(d) may be more than the strength of the elements

WBPSC AE (PHE) 1998

Ans. (d) : The strength of the welded joint may be more than the strength of the elements.

217. A fillet weld of size 5 mm and total length 100 mm is used to connect two steel plates. What is the effective area of fillet weld?

Search on Telegram @apna_pdf

(a) 500 sq.mm (b) 315 sq.mm
(c) 350 sq.mm (d) 450 sq.mm

TSPSC AEE 2017

Ans. (b) : Weld size (s) = 5 mm
Total length (L) = 100 mm
effective length (l_{eff}) = L – 2s = 100 – 2 × 5 = 90 mm
effective area of filled weld = t × l_{eff} = k.s × l_{eff}
= 0.707 × 5 × 90
= 318 ≈ 315 mm^2

218. Fillet weld is not recommended if the angle between fusion faces is
1. less than 45º **2. greater than 120º**
3. less than 60º **4. greater than 145º**
(a) 1 and 2 (b) 1 and 4
(c) 2 and 3 (d) 3 and 4

Chandigarh AE 2017

Ans. (c) : According to the IS : 816 - 1969 –
The angle between fusion face should not be greater than 1200 and not to be less than 60^0.

3. Tension Members

219. The maximum permissible slenderness ratio of tension members liable to reversal of stress due to action of wind and earthquake is-
(a) 300 (b) 350
(c) 400 (d) 425

OPSC AEE 2015 PAPER–I/ HPPSC 2016-II
RPSC POLY. TECH. LECT. 2011

Ans. (b) : The maximum permissible slenderness ratio of tension members liable to reversal of stress due to action of wind and earthquake is 350.

220. Tensile strength of single unequal angle section is calculated as per IS-800:2007 for two cases: 1) longer leg is connected to gusset plate, 2) shorter leg is connected to gusset plate.
Which of the strength will be same in both the cases?
(a) Design strength due to Rupture of Critical Section
(b) Design strength due to Yielding of Gross Section
(c) Design strength due to Block Shear
(d) None of the above

Gujarat PSC AE (N.W.R.) 2020

Ans. (b) Tensile strength of single unequal angle section is calculated as per IS-800:2007 for two cases:
1) Longer leg is connected to gusset plate,
2) Shorter leg is connected to gusset plate. The design strength due to Yielding of Gross Section will be same in both the cases.

221. For an industrial building, the allowable vertical deflection of a cantilever beam of span 5m supporting the brittle cladding and subjected to live load is _____.
(a) 41.66 mm (b) 33.33 mm
(c) 10 mm (d) 20 mm

HPPSC AE 2016

Ans. (b) : Maximum allowable vertical deflection for industrial building with cantilever support is

$$= \frac{\text{Span}}{150} = \frac{5000}{150} = 33.33\,\text{mm}$$

222. The maximum permissible slenderness ratio for steel ties likely to be subjected to compression is :
(a) 400 (b) 350
(c) 250 (d) 180

UKPSC AE (Paper-I) 2007


Ans : (d) The member are always under compression. They are called pure compression member the maximum slenderness ratio is 180 (less value because of buckling possibility).

(i) A tension member in which reversal of stresses due to loads other than wind or seismic force occur.	180
(ii) A member normally acting as a tie in a roof truss or a bracing system subjected to possible reversal of stress resulting from action of the wind or earthquake forces.	350
(iii)Tension members (other than pre-tensioned)	400


223. Failure by block shear at an end connection of a plate involves:
(a) Shear along two planes, tension along two planes
(b) Shear along one planes, tension along two planes
(c) Shear along two planes, tension along one plane
(d) Shear along one plane, tension along one plane

Kerala PSC AE 2015

Ans. (c) :




Block shear failure along (1) - (2) - (3) - (4) in which planes (1) - (2) and (3) - (4) are shear planes and (2) - (3) is a tension plane.
Block shear strength is given as
Block shear failure for plate
(i) Shear yielding + Tension rupture



T_{db_1} = Block shear strength

$$= \frac{f_y}{\gamma_{m0}} \frac{A_{vg}}{\sqrt{3}} + \frac{0.9 f_u}{\gamma_{m1}} A_{tn}$$

(ii) Shear rupture and tension yielding



T_{db_2} = Block shear strength

Search on Telegram @apna_pdf

$$= \frac{f_y}{\gamma_{m0}} A_{tg} + \frac{0.9 f_u}{\sqrt{3}\,\gamma_{m1}} A_{vn}$$

$T_{db} = \text{minimum}\left\{T_{db_1}, T_{db_2}\right\}$

224. A flat of size 160 mm × 10 mm is used as a tension member in a roof truss. It is connected to a gusset plate by chain bolting. Assuming yield stress as 250 N/mm^2 the design strength due to yielding of gross section, T_{dg} is

(a) 336.3 kN (b) 325 kN
(c) 460 N (d) 363.6 kN

TNPSC AE 2019

Ans. (d) Design tensile strength of member by considering gross section yielding $= \frac{A_g \times f_y}{\gamma_{m_o}}$

$$= \frac{160 \times 10 \times 250}{1.1} = 363.36 \text{ kN}$$

225. According to IS 800, the maximum effective slenderness ratio for members always under tension (other than pre-tensioned members) is

(a) 180 (b) 250
(c) 300 (d) 400
(e) 350

TRB Poly. Lect. Tech. 2017
CGPSC AE 2014 Shift–I

Ans. (d) : The maximum effective slenderness ratio for member always in tension other than pre-tensioned member is 400. High value because here is no buckling possibility in pure tension member.

226. A cable resists external loads by virtue of

(a) bending
(b) compression
(c) compression and bending
(d) torsion
(e) tension

CGPSC AE 2014 Shift–I


Ans. (e) Cable structure, a form of long span structure is subjected to tension. If $\lambda > 400$, tension member behave like a cable.

227. The ratio of the stiffness of a member to the total stiffness of all the members meeting at a joint is called as

(a) Relative stiffness of the structure
(b) Distribution factor for that member
(c) Carry over factor for that member
(d) Absolute stiffness of that member
(e) End correction

CGPSC AE 2014 Shift–I

Ans. (b) :



$$DF_{(AB)} = \frac{K_{AB}}{K_{AB} + K_{AC} + K_{AD}}$$

i.e. DF of a member $= \frac{\text{stiffness of that member}}{\text{total stiffness of all member meeting at a joint}}$

228. A 12mm thick plate is connected to two 6 mm plates on either side and subjected to tension then maximum value of pitch 'P' is :

(a) 72mm (b) 200mm
(c) 120mm (d) 96mm

APPSC Poly. Tech. Lect. 2020

Ans. (d) : 96mm
Given,
Thickness of plate, t = 6mm
And, for tension member
max^m pitch $\not>$ 16t
or whichever is less
200mm
16t = 16 × 6 = 96 mm
So, max^m pitch = min 96mm, 200mm
= 96 mm

229. The design strength of a tension member is given by a minimum of-
(i) block shear strength of end region
(ii) rupture of critical section.
(iii) yielding of net section
Which of the above statement(s) is/are correct?

(a) Only (i) (b) (i) and (ii)
(c) (i) and (iii) (d) (i), (ii) and (iii)

Gujarat PSC AE (N.W.R.) 2020

Ans. (b) : The design strength of a tension member is given by a minimum of block shear strength of end region and rupture of critical section.

230. Due to the flexibility of the connected plates under tension, an additional force is induced in the bolts. This phenomenon is known as-

(a) unbuttoning (b) shear lag
(c) Bauschinger effect (d) prying action

Gujarat PSC AE (N.W.R.) 2020

Ans. (d) : Due to the flexibility of the connected plates under tension, an additional force is induced in the bolts, this phenomenon is known as prying action.

231. The net effective cross-sectioned area of a single angle section connected by one leg to the gusset plate is

(a) $\frac{3A_1}{3A_1 + A_2}$ (b) $\frac{5A_1}{5A_1 + A_2}$
(c) $\frac{3A_1}{3A_1 - A_2}$ (d) $\frac{5A_1}{5A_1 - A_2}$

Maharashtra PSC AE (Mains) 2012 Paper–I

Search on Telegram @apna_pdf

Ans : (a) The net effective cross-sectioned area of a single angle section connected by one leg to the gusset plate is $\frac{3A_1}{3A_1 + A_2}$.

232. The design strength of member under axial tension is given by_____.

(a) $T_{dg} = A_g \times f_y$ (b) $T_{dg} = A_g \times f_y \times \gamma_{mo}$

(c) $T_{dg} = A_g \times f_y/\gamma_{mo}$ (d) $T_{dg} = A_g / f_y \times \gamma_{mo}$

LMRC AM 2019

Ans. (c) We know that design strength of member under axial tension = $A_g \times \frac{f_y}{\gamma_{mo}}$

A_g = Gross area of cross section

f_y = Yield strength of member

γ_{mo} = Partial safety factor against yielding (1.1)

233. The framed structure in which separate straight members are so arranged and connected at their ends that the external load applied at the joints will cause only direct forces in the members is known as :

(a) Beam (b) Plate girder

(c) Truss (d) Portal frame

Nagaland PSC CTSE 2017 Paper–I

Ans. (c) : The framed structure in which separate straight members are so arranged & connected to their end that the external load applied at joint will cause only direct forces in members is known as Truss.

234. By which one of the following method is an appropriate quick solution possible for frames subjected to transverse load ?

(a) By cantilever or portal method

(b) By strain energy method

(c) By moment distribution method

(d) By matrix method

Nagaland PSC CTSE 2017 Paper–I

Ans. (a) : The cantilever method or portal method – is an approximate method for calculating shear force and moments developed in beam and columns of a frame or structure due to lateral load.

235. The working stress for structural steel in tension is of the order of

(a) 15 N/mm^2 (b) 75 N/mm^2

(c) 150 N/mm^2 (d) 750 N/mm^2

UKPSC AE 2012 Paper–I

ESE 2003

Ans : (c) Working stress for tension and compression is 0.6 f_y

$\sigma_s = 0.6\ f_y$

$= 0.6 \times 250 = 150$ N/mm^2.

236. A member in a steel structure is introduced as a tension member. The structure is built in a seismic zone 5 (highest possible) and there could be a reversal of stress to compression, when earthquake comes. What should be the maximum slenderness ratio of this member?

(a) 180 (b) 200

(c) 250 (d) 350

UP RVNL AE 2016

Ans : (d) Maximum slenderness ratio of tension member where there is reversal of stresses due to earthquake is taken 350.

237. According to IS : 226 – 1975 axial direct stress in tension member should be by the formula :

(a) 0.56 f_y (b) 0.66 f_y

(c) 0.70 f_y (d) 0.6 f_y

UKPSC AE (Paper-I) 2007

ESE 2008

Ans : (d) According to IS : 800 – 1984, direct axial stress in tension should not be greater than 0.6 f_y.

238. Distance between the centres of two adjacent fasteners in a line, lying in the direction of stress in tension members should be

(a) < 16t or 200 mm whichever is less

(b) < 32 t or 300 mm whichever is less

(c) > 16 t or 200 mm whichever is more

(d) > 32 t or 300 mm whichever is more

RPSC GWD A.En.- 2014

Ans : (a) Distance between the centres of two adjacent fasteners in a line, for tension member is –
16t or 200 mm, which ever is less, will be taken.

239. The maximum centre to centre distance between bolts in tension member of thickness 10 mm is

(a) 200 mm (b) 160mm

(c) 120 mm (d) 100 mm

UKPSC AE 2012 Paper–I

Ans : (b) The distance between the centers of two consecutive bolts in direction of stress should not exceed 16t or 200mm, whichever is less in tension member and 12t or 200mm, whichever is less in compression member
for t = 10 mm, maximum distance = 16 × 10 = 160 mm

240. A steel member which is subjected to primary tension is called :

(a) tie (b) strut

(c) sling (d) none of the above

UKPSC AE (Paper-I) 2007

Ans : (a) Tie is a tension member, strut is a compression member.

241. When an equal single angle is used as tension member, the contribution of outstanding leg towards effective area is

(a) same as that of connected leg

(b) less than that of connected leg by a factor

(c) two times that of connected leg

(d) one and half times connected leg

UPPSC State Eng. A.E. 2011

Ans : (b) Contribution of outstanding leg is less than that of connected leg by a factor.

242. Consider the following statements.

1. If a lug angle is required for making connection in an angle section tension member, effective area of member will be the gross area of bolts holes.

2. In a double angle tension member with angles of opposite sides of a gusset plate,

Search on Telegram @apna_pdf

the net area provided will be same as for double angles on the same sides of gusset plate

(a) Only (1) is correct
(b) Only (2) is correct
(c) Both (1) and (2) are correct
(d) Neither (1) nor (2) is correct

UPPSC State Eng. A.E. 2011


Ans : (b) Only 2 is correct because in angle tension member effective area consider in place of gross area.

243. In a beam that carries axial load also, that effect of deflection may be ignored, when the axial load is

(a) compressive (b) tensile
(c) concentrated (d) uniformly distributed

[UPPSC State Eng. A.E. 2007(I)]

Ans : (b) Axially tensile load counter balance the deflection caused by transverse loading on the beam. Hence in this case effect of deflection may be ignored.



244. As per IS : 800 the minimum number of rivets used for attaching the lug angle to the gusset or other supporting member is:

(a) 8 (b) 6
(c) 4 (d) 2

[UPPSC State Eng. A.E. 2007]

Ans : (d) As per IS : 800 the minimum number of rivets used for attaching the lug angle to the gusset or other supporting member is 2.

245. For steel members exposed to weather and not accessible for repainting, the thickness of steel should not be less than

(a) 4.5 mm (b) 6 mm
(c) 8 mm (d) 10 mm

BPSC Combined AE Paper V 04.12.2012
Haryana PSC AE 2018 Paper–I

Ans : (c) For steel members which are exposed to weather and not accessible for repainting, the thickness of steel should not be less than 8 mm. If the member can be repainted then minimum thickness is taken as 6mm.

246. In the case of a tension member consisting of two angles back to back on the same side of gusset plate, what is k equal to? (Area of connected leg = A_1, Area of outstanding leg = A_2)

(a) $\frac{3A_1}{3A_1+A_2}$ (b) $\frac{3A_1}{A_1+3A_2}$
(c) $\frac{5A_1}{A_1+5A_2}$ (d) $\frac{5A_1}{5A_1+A_2}$

UPPSC State Eng. A.E. 2003
UK Combined A.E. Paper (I) 2012
ESE 2006


Ans : (d) For single angle

$$K = \frac{3A_1}{3A_1+A_2}$$

For angles connected back to back on the same side of the gusset plate

$$K = \frac{5A_1}{5A_1+A_2}$$


247. For the eccentric connection of bracket shown in figure, which bolt will have the maximum resultant force?



(a) Bolt A (b) Bolt B
(c) Bolt D (d) Bolt E

JPSC Combined AE Paper V 2013

Ans : (a) In the given figure



Direct stress in the bolts = $\frac{P}{6}$

Torsional stress in bolts = $\frac{P_e r_i}{\Sigma r_i^2}$

Total stress = $\sqrt{T_d^2 + T_t^2 + 2T_d T_t Cos\theta}$

Cos θ is positive for bolt A and F.

∴ Stress will be maximum for bolt A and F.

248. The permissible stress in steel (σ_{st}) is 130 MPa in a water tank of diameter 1.3 m which is designed to resist direct tensile force (T) of 260 kN per meter width. Determine the required area of tension steel in mm^2/m-

(a) 500 (b) 2000
(c) 33800 (d) 2×10^9

MPPSC AE 2017

Search on Telegram @apna_pdf

Ans. (b) : Required area of steel in tension per m length

$$\frac{260\times10^3\ N}{130\ N/mm^2} = 2000\ mm^2$$

249. The maximum slenderness ratio for a steel tension member is

(a) 100 (b) 200
(c) 400 (d) 500

TNPSC AE 2018
APPSC AE 2016 (Mains)

Ans. (c) :

	Type of member	Maximum Slenderness Ratio
(i)	A member in which reversal of stresses due to loads other than wind or seismic force occur	180
(ii)	A member acting as tie in roof truss or a bracing system subjected possible reversal of stresses due to wind or earthquake forces	350
(iii)	Tension members (other than pre tensioned)	400

250. A lug angle

(a) increases the joint length and shear lag
(b) increases the shear lag
(c) reduces the joint length and shear lag
(d) reduces only the shear lag

TNPSC AE 2018


Ans. (c) : A lug angle is additional angle used to join tension member to reduce the length of joint and consequently the size of gusset plate. It also reduces shear lag.

251. A single angle is connected by one leg only, If the area of outstanding leg is x, net area of connecting leg is y and k is reduction factor whose value is less than 1, then the net effective area of angle in tension will be

(a) x + y (b) x + ky
(c) y + kx (d) k (x + y)


[HPPSC 2016-II]

Ans. (c) :



Connected leg is free from shear lag effect, hence there is no reduction of area but outstanding leg area is reduced due to effect of shear lag.
Net area in tension = y + Kx

252. Determine block shear strength of tension members shown in figure if grade of steel is Fe-410 :



(a) 309.06 kN (b) 216.49 kN
(c) 258.49 kN (d) 326.54 kN

JPSC AE (Pre) 2019

Ans. (b) :

$A_{vg} = (1\times100+50)\times8 = 1200\ mm^2$
$A_{vn} = [(1\times100)+50+(2-0.5)\times20]\times8 = 1440 mm^2$
$A_{tg} = 35\times8 = 280 mm^2$
$A_{tn} = (35-0.5\times20)\times8 = 200 mm^2$

$$T_{db1} = \frac{A_{vg}f_y}{\sqrt{3}\gamma_{m_0}} + \frac{0.9A_{tn}f_u}{\gamma_{m_1}}$$

$$= \frac{1200\times250}{\sqrt{3}\times1.1} + \frac{0.9\times200\times4}{1.25} = 216.49kN$$

and, $$T_{db_2} = \frac{A_{tg}f_y}{\gamma_{m_0}} + \frac{0.9A_{vn}f_u}{\sqrt{3}\gamma_{m_1}}$$

$$= \frac{280\times250}{1.1} + \frac{0.9\times1440\times41}{1.25\times\sqrt{3}} = 309.06kN$$

So, block shear strength of tension member is 216.49kN

253. Design strength in tension of a steel plate subjected to failure by rupture mode is expressed as :

(a) $0.9\frac{A_nf_u}{\gamma_{m_1}}$ (b) $0.9\frac{A_gf_y}{\gamma_{m_0}}$
(c) $1.2\frac{A_nf_u}{\gamma_{m_1}}$ (d) $1.5\frac{A_nf_u}{\gamma_{m_0}}$

Where A_n = net area; A_g = gross area, f_y = yield stress; fu = ultimate stress; γ_{m_1} = partial safety against ultimate stress factor; γ_{m_0} = partial safety factor against yield and buckling.

Rajasthan JEN (Degree) Shift - II 2016

Ans. (a) Design strength in tension of a steel plate subjected to failure by rupture mode is expressed as $0.9\frac{A_nf_u}{\gamma_{m_1}}$.

254. Which one of the following is not a factor considered for calculating the net effective area of a tension member?

(a) Ductility factor (b) Geometry factor
(c) Shear lag factor (d) Buckling factor

GPSC AE (CLASS 1 & 2) 2019

Search on Telegram @apna_pdf

Ans : (d) : Buckling factor is not considered in tension member for calculating net effective area.

255. A tension splice section is designed for

(a) Maximum factored tensile load
(b) Design strength of the tension member
(c) Maximum service load
(d) Maximum of factored tensile load and 0.3 times the design strength of tension member

GPSC AE (CLASS 1 & 2) 2019

Ans : (d) A tension splice member is designed for maximum of factored tensile load and $0.3\times F_S$ (design strength of section of tension member)

256. Which of the following is/are considered as a limit state?

(i) Attainment of yield point of tension members
(ii) Excessive elongation of the tension members
(a) Only (i) (b) Only (ii)
(c) (i) and (ii) (d) None of the above

GPSC AE (CLASS 1 & 2) 2019

Ans : (b) : In limit state we go for ultimate strength as upto strength of material i.e., excessive elongation of the tension member.

257. Consider the following statements with reference to the design of welded tension members :

1. The entire cross-sectional area of the connected leg is assumed to contribute to the effective area in the case of angles
2. Two angles, back –to-back and tack welded as per the codal requirements, may be assumed to behave as a tee-section.
3. A check on slenderness ratio may be necessary in some cases.

Which of the above statements are correct?

(a) 1 and 2 only (b) 1 and 3 only
(c) 2 and 3 only (d) 1, 2 and 3

ESE 2018

Ans. (d)

- Connected leg has direct connection with gusset plate therefore entire area contributes to effective area.
- As per IS 800 : 2007 two angles placed back-to-back and tack welded area assumed to behave as tee section.
- Check for slenderness ratio is necessary in some case i.e., in reversal of stresses.

258. The design strength of a tension member is governed by

1. Rupture at a critical section
2. Yielding of gross area
3. Block shear of end region

Select the *correct* answer using the codes given below.

(a) 1 only (b) 2 only
(c) 3 only (d) 1, 2 and 3

ESE 2017

Ans. (d) : According to IS code – 800 : 2007. Design strength of member is governed by :–

- Strength due to yielding of gross section.
- Rupture of critical section.
- Block shear of end region.

→ Yield strength of plate 'T_{dg}'–

$$\left[T_{dg}=\frac{f_y A_g}{\gamma_{M_o}}\right] \quad \text{where, } \gamma_{mo}=1.1$$

→ Rupture strength of plate is given by–

$$\left[T_{dn}=0.9\frac{f_u A_n}{\gamma_{m_1}}\right] \quad \text{where } \gamma_{m1}=1.25$$

$$\left[A_n=\left[b-n_{dh}+\Sigma\frac{P_1^2}{4g_1}\right]t\right]$$

→ Block shear strength of plate.

$$=\text{Minimum of}\begin{cases}\dfrac{A_{vg}f_y}{\sqrt{3}\gamma_{m_o}}+\dfrac{A_{tn}\times 0.9f_u}{\gamma_{m_1}}\\ \dfrac{A_{vn}0.9f_u}{\sqrt{3}\gamma_{m_1}}+\dfrac{A_{tg}\times f_y}{\gamma_{m_o}}\end{cases}$$


259. The tensile strength of the plate is given by
f_y = ultimate tensile stress of the plate in MPa.
A_n = Net area of the plate.
γ_{m1} = partial safety factor
γ_{mo} = Partial safety factor for material resistance governed by yielding.

(a) $0.2f_y\dfrac{A_n}{\gamma_{m_1}}$ (b) $0.9\dfrac{f_u A_n}{\gamma_{m_0}}$

(c) $0.9\dfrac{f_u A_n}{\gamma_{m_1}}$ (d) $0.9f_u A_n$

DSSSB AE 2019

Ans. (c)



Tensile strength of the plate $\left(T_b\right)=0.9A_n\times\dfrac{f_u}{\gamma_{m_1}}$

260. A strut is a structural member subjected to

(a) Tension in a direction parallel to its longitudinal axis
(b) Tension in a direction perpendicular to its longitudinal axis
(c) Compression in a direction parallel to its longitudinal axis
(d) Compression in a direction perpendicular to its longitudinal axis

GPSC AE Dec 2018
ISRO Scientist/Engineer 2017

Search on Telegram @apna_pdf

Ans : (c) : A strut is a structural member subjected to compression in a direction parallel to its longitudinal axis.


261. Net sectional area of a tension member is equal to its gross sectional area

(a) Plus the area of the rivet holes
(b) Divided by the area of the rivet holes
(c) Multiplied by the area of the rivet holes
(d) Minus the area of the rivet holes

ISRO Scientist/Engineer 2018

Ans : (d) :

- Net cross-sectional area = Gross sectional area - Area of rivet holes.
- In tension members



For plated P_1 :

- Diameter of rivet hole = d_n, pitch of rivet = P
- Thickness of plate = t_1, gauge of rivet = g
- Net cross sectional area along section
  1-2-4-5 = $(b-2\times d_n)\times t_1$
- Net cross sectional area along section.
  6-7- = $(B-d_n)\times t_1$
- Net cross sectional area along
  $$1\text{-}2\text{-}3\text{-}7 = (B-2d_n)\times t_1 + \frac{P^2}{4g}\times t$$
- Net cross sectional area along
  $$1\text{-}2\text{-}3\text{-}4\text{-}5 = (B-3d_n)\times t_1 + \frac{P^2}{4g}t_1 + \frac{P^2}{4g}\times t_1$$
- The Failure (rupture) section will be one with least net cross-sectional area.

262. Which one is not a possible mode of failure in case of tension members?

(a) Yielding of gross section
(b) Rupture at the net section
(c) Instability of the element
(d) Block shear

AP (VSS-1) PART - A 2017

Ans : (c) Instability of the element is not a possible mode of failure in case of tension members

263. A steel section is subjected to a combination of shear and bending actions. The applied shear force is V and the shear capacity of the section is V_S. For such a section high shear force is defined as

(a) $V > 0.6\,V_S$ (b) $V > 0.7\,V_S$
(c) $V > 0.8\,V_S$ (d) $V > 0.9\,V_S$

APTRANSCO 2017

Ans : (a) If $V > 0.6\,V_S$ then it is case of high shear force.

264. Two bolted plates under tension with alternative of bolt holes are shown in figures 1 and 2. The hole diameter, pitch, and gauge length are d, p and g, respectively.




Figure 1




Figure 2

Which one of the following conditions must be ensured to have higher net tensile capacity of configuration shown in Figure 2 than that shown in Figure 1?

(a) $p^2 > 2gd$ (b) $p^2 < \sqrt{4gd}$
(c) $p^2 > 4gd$ (d) $p > 4gd$

APTRANSCO 2017

Ans : (c)

Tensile capacity of figure 1 $p_t = (p-d).t.\sigma_{at}$

Tensile capacity of figure 2 $p_t = \left(p - 2d + \frac{p^2}{4g}\right).t.\sigma_{at}$

$(p_t)_{\text{figure 1}} < (p_t)_{\text{figure 2}}$

$$(p-d)\,t.\sigma_{at} < \left(p - 2d + \frac{p^2}{4g}\right)t.\sigma_{at}$$

$$d < \frac{p^2}{4g}$$

$$\boxed{p^2 > 4gd}$$

265. In case of plastic design, the calculated maximum shear capacity of a beam as per IS:800 shall be (where A_w effective cross-sectional area resisting shear and f_y is the yield stress of the steel) :

(a) $0.55\,A_w f_y$ (b) $0.65\,A_w f_y$
(c) $0.75\,A_w f_y$ (d) $0.85\,A_w f_y$

OPSC AEE 2019 Paper–I

Ans. (a) : The maximum shear capacity of beam is $0.55\,A_w f_y$ where A_w is the effective cross-sectional area, resisting shear and f_y is yield stress.

266. Given that the effective area of a tension member is A_e and the yield stress is σ_y. In order to obtain the ultimate strength of the tension member, as per the plastic design concept $A_e\,\sigma_y$ is to be multiplied by

(a) 1.1 (b) 0.95
(c) 0.85 (d) 0.75

OPSC AEE 2019 Paper–I

Ans. (c) : The maximum load capacity of tension member is $0.85\,A_c F_y$, for compression member the load capacity is $0.7\,A_e\sigma_{ac}$

267. A tie bar 50 mm × 8 mm is to carry a load of 80 kN. A specimen of same quality steel of cross-sectional area is 250 mm^2. If the maximum load carried by the specimen is 125 kN, the gauge length will be :

(a) 133 mm (b) 126 mm

Search on Telegram @apna_pdf

(c) 113 mm (d) 106 mm

ESE 2020

Ans. (c) : Cross-sectional area of tie bar (A) = 50 × 8
= 400 mm^2

Gauge length of tie bar (ℓ_g) = $5.65\sqrt{\text{Area}}$
= $5.65\sqrt{400}$
= 113 mm

268. For a tension member, the design shear capacity of bolts carrying shear through packing plate in excess of 6 mm shall be decreased by a factor of (Note: t_{pk} is the thickness of the thicker packing plate)

(a) 1-0.125 t_{pk} (b) 1-0.0125 t_{pk}
(c) 1-0.250 t_{pk} (d) 1-0.0250 t_{pk}

GPSC AE March 2018

Ans. (b) : For tension member,
Packing factor = 1 – 0.0125 t_{pk}
t_{pk} : thickness of thicker plate for plate difference greater than 6 mm.

269. The ratio of the effective length to the least radius of gyration of a tie member of a roof truss, which gets subjected to reversal of stress shall not exceed :

(a) 200 (b) 250
(c) 350 (d) 300

KPTCL AE 2016

Ans. (c) : The ratio of the effective length to the least radius of gyration of tie member of a roof truss, which get subjected to reversal of stress shall not exceed 350.
For pure compression member maximum slenderness ratio is 180^0.
Maximum slenderness is ratio for a tension member subjected to reversal of stress = 180^0.

270. In design of tension member, the length of the connection can be reduced by using :

(a) Bearing stiffener (b) Splice plate
(c) Lug angle (d) Gusseted base

TRB Poly. Lect. Tech. 2017

Ans. (c) : Lug angle are used to reduce the length of connection.
Lug angles are used to reduce the shear lag.

271. A tension member consists of two angles 60 × 60 × 8 the angles being placed back to back on the same side of the gusset plate. One leg of each angle is connected to the gusset plate. The outstanding legs are also connected by tack rivets. Find the safe tension for the member. Use 16mm diameter rivet

(a) 196.56 kN (b) 203.45 kN
(c) 156.56 kN (d) 208.61 kN

TRB Poly. Lect. Tech. 2017

Ans. (a) :
Given,
L_1 = 60 mm
L_2 = 60 mm
t = 8 mm
d_1 = d + 1.5 = 16 + 1.5 = 19.5 mm

net are = $\boxed{A_1 + A_2K}$
Angles are placed back to back – IS : 800 – 1984

then $K = \dfrac{5A_1}{5A_1 + A_2}$

$A_1 = 2\left[L_1 - d - t/2\right]t$

$A_1 = 2\left[60 - 17.5 - 8/2\right]8$

$A_1 = 616 \text{ mm}^2$

$A_2 = 2\left[L_2 - t/2\right]t$
$= 2\ [60 - 8/2]\ 8$

$A_2 = 896 \text{ mm}^2$

$K = \dfrac{5A_1}{5A_1 + A_2} = \dfrac{5 \times 616}{5 \times 616 + 896}$

K = 0.77
Then net area –
A net = $A_1 + A_2 K = 616 + (896 \times 0.77) = 1305.92 \text{ mm}^2$
Permissible stresses 150 N/mm^2
∴ Strength of the tension member
Net area × permissible stress
1305.95 × 150 = 195.88 kN ≃ 196.56 kN

272. In the case of a single-angle section in tension connected by one leg only, the net effective area of the angle is taken as $A_1 + A_2k$, where k is


(a) $\dfrac{4A_1}{4A_1 + A_2}$ (b) $\dfrac{3A_1}{3A_1 + A_2}$

(c) $\dfrac{3A_2}{3A_1 + A_2}$ (d) None of the above

(A_1 is effective area of connected leg and A_2 is gross area of unconnected leg)

BPSC Poly. Tech. Lect. 2016

Ans. (b) : Single angle section in tension connected by one leg only



$A_{net} = A_1 + KA_2$

where,

$$\boxed{K = \frac{3A_1}{3A_1 + A_2}}$$

where,
A_1 = Net section area of connected leg
A_2 = Gross area of outstand leg (unconnected leg)

273. A member in a steel structure is introduced as a tension member. The structure is built in a seismic zone 5 (highest possible) and there could be a reversal of stress to compression, when earthquake comes. What should be the maximum slenderness ratio of this member?

(a) 180 (b) 250
(c) 300 (d) 350

UPRVUNL AE 2016

Search on Telegram @apna_pdf

Ans.: (d) Maximum slenderness ratio for various types of tension member.

S.No.	Type of tension member	Max. Slenderness
1.	Tension member in which there can be reversal of direct stress due to loads other than wind or earthquake force	180
2.	A member normally acting as a tie in roof truss or a bracing system but subjected to possible reversal of stress due to wind or earthquake forces	350
3.	Tension member i.e., members always under tension (other than pretension member)	400

274. If a tension member is subjected to possible reversal of stresses due to wind, the slenderness ratio of the member should not exceed -

(a) 350 (b) 180
(c) 250 (d) 200

UPPCL AE 2014

Ans. (a) : For tension member subjected to reversal of stresses due to wind, the slenderness ratio of the member should not exceed 350.

275. As per IS 800 : 1984, the permissible stress in axial tension in the net effective area of the section shall not exceed_____(where f_y is minimum yield stress in steel in N/mm^2)

(a) 0.85 f_y (b) 1.15 f_y
(c) 0.65 f_y (d) 0.6 f_y

GPSC AE June 2019

Ans. (d) : As per IS800 : 1984 the permissible stress in Axial tension in the net effective area of the section shall not exceed 0.6 f_y.

276. The ratio of Young's modulus of high tensile steel to that of mild steel is about

(a) 0.5 (b) 1.0
(c) 1.5 (d) 2.0

GPSC AE June 2019

Ans. (b) : Young's modulus of both high tensile steel and mild steel is equal its ratio is 1.0.

277. A steel rod of 20 mm diameter is used as a tie member in the roof bracing system, and may be subjected to possible reversal of stress due to wind load. What is the maximum permissible length of the member ?

(a) 1750 mm (b) 3000 mm
(c) 2500 mm (d) 2000 mm

BHEL ET 2019

Ans. (a) : Given – Dia of rod = 20 mm. For a tension member subjected to reversed of stress due to action of wind, maximum slenderness ratio = 350

$\lambda = 350$

$$\lambda = \frac{\text{effective length}}{\text{least lateral dimension}}$$

Least lateral dimension $I_{min} = I_{min} = \sqrt{\frac{I}{A}}$

$$I_{min} = \sqrt{\frac{\frac{\pi d^4}{64}}{\frac{\pi d^2}{4}}}$$

$$I_{min} = \sqrt{\frac{\frac{\pi \times (20)^4}{64}}{\frac{\pi (20)^2}{4}}} = 5$$

$$\therefore \lambda = \frac{l_{eff}}{I_{min}}$$

$$350 = \frac{l_{eff}}{5}$$

$l_{eff} = 350 \times 5 = 1750$ mm

278. Pick odd one out with respect to failure of tension members.

(a) Lateral torsional flexural buckling
(b) Net section rupture
(c) Block shear failure
(d) Gross section yielding

UPPCL AE 2019

Ans. (a) Different types of failure in Tension members:
(a) yielding of Gross section (T_{dg})
(b) Rupture of net section (T_{dn})
(c) Block shear failure (T_{db})

279. In case of single angle in tension connected by one leg only the net effective area as per codal provision is

(a) Gross area of holes (b) $a + \frac{b}{1 + 0.33\frac{b}{a}}$

(c) $a + \frac{b}{1 + 0.2\frac{b}{a}}$ (d) $a + \frac{b}{1 + 0.35\frac{b}{a}}$

WBPSC AE 2012

Ans. (b) : In case of single angle in tension connected by one leg only the net effective area as per codal provision is $a + \frac{b}{1 + 0.33\frac{b}{a}}$.

Where,
a = Area of connected leg
b = Area of unconnected leg

280. Lug angles are

(a) Angles of unequal size
(b) Angles with extra reinforcement to take bending moment
(c) Angles with holes drilled for riverts
(d) Angles used to reduce the length of connection

Search on Telegram @apna_pdf

WBPSC AE 2001

Ans. (d) : Lug angle is a small piece of angle used to connect outstands leg of the members to the gusset plates. It reduce the length of connection to the gusset plate and to reduce shear lag effect.

281. A single angle member in tension is connected by one leg only. If the area of the connecting and outstanding leg are respectively 'a' and 'b' then the net effective area of the angle is equal to

(a) $a-\dfrac{b}{1+0.35\dfrac{b}{a}}$ (b) $a+\dfrac{b}{1+0.2\dfrac{b}{a}}$

(c) $a+\dfrac{b}{1+0.35\dfrac{b}{a}}$ (d) $a+\dfrac{a}{1+0.35\dfrac{b}{a}}$

WBPSC AE (MCD) 1998

Ans. (b) : A single angle member in tension is connected by one leg only the net effective area will be

$$A_{net} = a+\frac{b}{1+0.2\dfrac{b}{a}}$$

a = Area of connected leg
b = Area of unconnected leg

282. Projection of a plate or flange in tension, beyond its connected to a web, or other line of support shall not exceed

(a) 16 t (b) 20 t
(c) 25 t (d) 40 t

WBPSC AE (PHE) 1998

Ans. (c) : As per IS : 800 - 1984 projection of a plate or flange in tension, beyond its connected to a web, or other line of support shall not exceed 25t.

283. The Lug angle is a member which _____.


(a) is connected to the main tension member to transfer the tensile force economically to the point.
(b) is connected to the main tension member for erection purpose.
(c) is connected to the main tension member to increase its strength locally.
(d) is connected to the main tension member to increase its stiffness.

TSPSC Deputy Engineer 2015

Ans. (a) : Lug angle is a member which is connected to the main tension member to transfer the tensile force economically to the point. It also reduce the length of connection to the gusset plate and to reduce the shear lag effect.

4. Compression Members

284. The effective length of the compression member shown in the figure is equal to :



(a) 1.2 L (b) 0.5 L
(c) 2.0 L (d) 1.5 L

Ans : (a) In figure the condition is : Effective held in position and restrained against rotation at one end, on the other end restrained against rotation but not held in position.

	Degree of restraint	effective length
(i)	effective held in position and restrained against rotation at one end, on the other end restrained against rotation but not held in position.	1.2 L
(ii)	effective held in position and restrained at one end, and the other end is partially restrained against rotation but not held in position.	1.5 L
(iii)	Effectively held in position at one end but not restrained against rotation, and at the other end restrained against rotation but not held in position	2.0 L
(iv)	Effectively held in position and restrained against rotation at one end but neither held in position nor restrained against rotation at the other end	2.0 L

285. The lacing bars in a steel column should be designed to resist :

(a) Bending moment due to 2.5% of the column load.
(b) Shear force due to 2.5% of the column load
(c) 2.5% of the column load only
(d) Both (a) and (b)

OPSC AEE 2019 Paper–I / TNPSC AE 2015
UPPSC State Eng. A.E. 2004 (I)
BPSC AE Paper V 2001

Ans. (b) : As per IS 800–1984 clause 5.7.2.1. The lacing of compression members shall be proportioned to resist a total transverse shear 'V' equal to at least 2.5% of the axial force in the member.

286. In the design of steel structures, the ratio of the effective length of a member to the radius of gyration of the cross-section about the axis under consideration is called as

(a) Modulus of elasticity (b) Slenderness ratio
(c) Stress ratio (d) Aspect ratio

(RRB SSE Secundrabad (Shift-I), 02.09.2015)

Ans : (b) Ratio of effective length to the radius of gyration is known as slenderness ratio

$$\lambda = \frac{\ell_e}{r_{min}}$$

ℓ_e = effective length

r_{min} = minimum radius of gyration

Search on Telegram @apna_pdf

287. If a compression member of length L is restrained in rotation and translation at both the ends, then what is its effective length?

(a) 0.80 L (b) 1.2 L
(c) 1.0 L (d) 0.65 L

CIL MT 2017

Ans. (d) : If a compression member of length L is restrained in rotation and translation at both the ends then 0.65 L is its effective length.

288. A compression member in a roof truss is called

(a) stanchion (b) post
(c) strut (d) column

TNPSC AE 2019

Ans. (c) Strut is compression member in roof truss.

- Stanchion – upright post member that provide support for other object, it may be connected by bolt.
- Post or stanchion almost same.
- Boom → Compression member in crane.

289. Slenderness ratio is the ratio of

(a) unsupported length to the maximum radius of gyration
(b) least radius of gyration to the unsupported length
(c) unsupported length to the least radius of gyration
(d) maximum radius of gyration to the unsupported length

TNPSC AE 2012, 2019
APTRANSCO 2017

Ans. (c) Slenderness ratio = $= \frac{\text{unsupported length}}{\text{least radius of gyration}}$

$\lambda = \frac{l_{eff}}{r_{min}}$

290. The slenderness ratio $\left(\frac{\ell}{r}\right)$ of lacing flats is limited to

(a) 145 (b) 180
(c) 250 (d) 350

Haryana PSC AE 2018 Paper–I
LMRC AM 2018 / GPSC AE March 2018
Maharashtra PSC Mains 2018 Paper-1
Karnataka PSC AE 2017 Paper - II
Gujarat PSC AE 2017 / UPPCL AE 2015
UKPSC AE 2012 Paper–I
UPPSC State Eng. A.E. 2004 (I) & 2007(I)
ESE 2004, 05 / WBPSC AE (PHE) 1998

Ans : (a) Slenderness ratio of lacing bar should be less than 145. Angle of inclination of lacing bar with longitudinal axis should be kept between 40°-70°.

In single lacing system, thickness of lacing $t \not< \frac{1}{40}$ of its effective length. For double lacing system it should not be less than $\frac{1}{60}$ of its effective length.

Overlap of lacing should not be less than four times the thickness of the bar or the member, whichever is less.

291. In steel design as per IS 800, following are included in the limit state of serviceability except

(a) Fire
(b) Corrosion
(c) Crack due to fatigue
(d) Vibrations in the structure
(e) Snow load

CGPSC AE 2014 Shift–I

Ans. (e) : As per IS 800, Limit state of serviceability include.
(i) deformation & deflection
(ii) vibration in the structure
(iii) repairable damage or crack due to fatigue
(iv) corrosion, durability
(v) fire

292. A purely compression member (with negligible eccentricity) having its effective length equal to 9 times its radius of gyration would be treated as :

(a) Pedestal
(b) Strut
(c) Long column
(d) Rotating shaft
(e) Member subjected to bending and shear

CGPSC AE 2014 Shift–I

Ans. (a) : A purely compression member (with negligible eccentricity) having its effective length less than 12 times its radius of gyration, would be treated as pedestal.

293. A column is subjected to an eccentric load of 10 kN at an eccentricity of 50 mm. The moment induced is

(a) 500 N-mm (b) 500000 N-mm
(c) 50 kN-m (d) 50 N-mm

TNPSC AE 2012

Ans. (b) : Moment induced due to eccentricity
M = p×e = 10000×50
M= 500000 N-mm

294. As per IS 800, what is the maximum allowable effective slenderness ratio for structural steel that is always under tension?

(a) 180 (b) 250
(c) 400 (d) 350

CIL MT 2017

Ans. (c) : As per IS 800,

	Type of member	λ_{max}
(i)	A member carrying compressive load resulting from dead load or live load.	180
(ii)	A tension member in which reversal of direct stress is due to loads other than earthquake	180
(iii)	A member subjected to compressive load due to wind or earthquake	250
(iv)	A member normally acting as a tension member but in which reversal of stress is due to wind or earthquake.	350
(v)	Compression flange of beam.	300
(vi)	A member always under tension except	400

Search on Telegram @apna_pdf

	pre-tensioned member.	

295. Which of the following is NOT a method recommended by IS 800 for assessing the period of structural adequacy of structural steel design?

(a) By direct application of single test
(b) Methods given in specialist literature
(c) By calculating the limiting temperature of steel
(d) Based on previous case studies in the local area

CIL MT 2017

Ans. (d) : Based on previous case studies in the local area is NOT a method recommended by IS 800 for assessing the period of structural adequacy of structural steel design.


296. Which one of the following forces is used for the design of battens of a builtup column?

(a) Axial load (b) Twisting moment
(c) Vertical shear (d) Transverse shear

Gujarat PSC AE (N.W.R.) 2020

Ans. (d) : Transverse shear force is used for the design of battens of builtup column.

297. Equal angles star section shown in the figure is designed as a compression member. Governing axis of the section is–



(a) x-x (b) y-y
(c) u-u (d) v-v

Gujarat PSC AE (N.W.R.) 2020

Ans. (c) Equal angles star section shown in the figure is designed as a compression member. Governing axis of the section is u-u as member is unsymmetrical about that axis.

298. The axial force in each lacing in double lacing system is

(a) $\frac{V}{4n\sin\theta}$ (b) $\frac{V}{2n\sin\theta}$
(c) $\frac{V}{n\sin\theta}$ (d) $\frac{2V}{n\sin\theta}$

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (a) For double lacing system on two parallel planes the force (compressive or tensile)

in each bar $\boxed{F=\frac{V}{4\sin\theta}}$

and for single lacing $\boxed{F=\frac{V}{2\sin\theta}}$

299. Secant's formula

(a) Determines the allowable stress in axial compression
(b) Determines the allowable stress in coaxial compression
(c) Determines the allowable strain in axial compression
(d) Determines the allowable strain in coaxial compression

Nagaland PSC CTSE 2017 Paper–I
GESCOM (KARNATAKA) AE 2011

Ans : (a) The Secant's formula indicates that in addition to the axial load F and cross-section area A, the maximum stress also depends on the eccentricity ratio $\frac{ec}{r^2}$ and slenderness ratio $\frac{l}{r_{min}}$

$$\sigma_{max}=\frac{F}{A}\left[1+\frac{ec}{r^2}\sec\left(\sqrt{\frac{F}{EA}}\frac{L}{2r}\right)\right]\le\sigma_{allow}$$

300. Partial safety factor for limit state of serviceability in steel structure for DL + WL/EL is_____.

(a) 1.1 (b) 1.0
(c) 0.9 (d) 1.2

LMRC AM 2019

Ans. (b) Partial safety factor for unit state of serviceability in steel structure for DL + WL/EL is 1.

301. Effective length of compression member with one end fixed and the other end free is _____.

(a) 1.20L (b) 1.00L
(c) 0.67L (d) 2.00L

LMRC AM 2019

Ans. (d)

Description		Effective Length
One end fixed End other hinged		$\frac{\ell}{\sqrt{2}}$
Both ends fixed		$\frac{\ell}{2}$
Both end hinged		ℓ
One end fixed and other free		2ℓ

Search on Telegram @apna_pdf

302. The unsupported length of transverse ties should not exceed _____ times the diameter of tie in two directions:

(a) 36 (b) 42
(c) 48 (d) 16

KPSC AE 2020

Ans. (c) : The unsupported length of transverse ties should not exceed 48 times the diameter of tie in two directions.

303. Lap splices are not recommended to be used for rebar diameter above

(a) 32 mm (b) 36 mm
(c) 25 mm (d) 28 mm

(LMRC AE 2017 I–Shift)

LMRC AM 2015

Ans : (b) Lap splices are not used if rebar diameter is above 36 mm.

304. Splices for compression members are designed as

(a) Short columns
(b) Long columns
(c) Intermediate columns
(d) None of above

(UKPSC AE 2012 Paper–I)

Ans : (a) The following specification are followed in the design of splices:-
(i) Splices are designed as short columns.
(ii) Where the ends of the compression member are faced for the complete bearing over the whole area, these should be spliced to hold the connected members accurately in position, and to resist any tension when bending is present.
(iii) Where such members are not faced for complete bearing, splices should be designed to transmit all the forces to which these are subjected.

305. A steel column in a multi-storeyed building carries an axial load of 125 N. It is built up of 2 ISMC–350 channels connected by lacing. The lacing carries a load of

(a) 125.125 N (b) 12.525 N
(c) 3.126 N (d) Zero

UKPSC AE 2012 Paper–I

(ESE 2003)

Ans : (c) Lacing is designed for 2.5% of the axial force in column.

$$\text{lacing load} = \frac{2.5}{100} \times 125 = 3.125\text{N}$$

306. Which of the following is not a compression member?

(a) Strut (b) Tie
(c) Rafter (d) Boom

UKPSC AE 2012 Paper–I

(ESE 2005)

Ans : (b) Tie is a tension member, whereas strut, rafter and boom are compression members.

307. Minimum number of battens required in a battened column is

(a) 2 (b) 3
(c) 4 (d) 6

UKPSC AE 2012 Paper–I

Ans : (c) Minimum number of battens in battened column is four. Effective length of battened column is increased by 10%.

308. In compression member pitch of tacking rivets at a line should not be more than :

(a) 1000mm (b) 600 mm
(c) 650 mm (d) 700 mm

UKPSC AE (Paper-I) 2007

Ans : (b) In compression member pitch of tacking rivets should not be more than 600 mm. In tension member pitch of tacking rivets should not be more than 1000 mm.

309. In columns lap length is kept as :

(a) equal to development length
(b) greater than development length
(c) less than development length
(d) none of the above

(UKPSC AE (Paper-I) 2007)

Ans : (a) In column lap length is equal to the development length. If the diameter of bar is equal to or greater than 36 mm then overlap is not provided and welding is preferred.

310. The effective length of a compression members which is effectively held in position at both ends but not restrained in rotation is

(a) L (b) 0.85 L
(c) 1.2 L (d) 1.5 L

UPPSC Civil Eng. A.E. 2013(I]
RPSC ACF - 2011
UPPSC State Eng. A.E. 2008

Ans : (a) Effective length of a compression member which is effectively held in position at both ends, but not restrained against rotation the effective length will be $\boxed{l = 1.00\text{L}}$

311. The effective length of a structural steel compression member of length L effectively held in position and restrained against rotation at one end but neither held in position nor restrained against rotation at the other end, is

(a) L (b) 1.2L (c) 1.5L (d) 2.0L

OPSC AEE 2019 Paper–I
GPSC AE Dec 2018
UPPSC State Eng. A.E. 2003

Ans : (d)

	Degree of restraint	effective length
(i)	effective held in position and restrained against rotation at one end, on the other end restrained against rotation but not held in position.	1.2 L
(ii)	effective held in position and restrained at one end, and the other end is partially restrained against	1.5 L

Search on Telegram @apna_pdf

	rotation but not held in position.	
(iii)	Effectively held in position at one end but not restrained against rotation, and at the other end restrained against rotation but not held in position	2.0 L
(iv)	Effectively held in position and restrained against rotation at one end but neither held in position nor restrained against rotation at the other end	2.0 L

312. To get the effective length of a prismatic steel compression member of length L fully restrained at both the ends, L is usually multiplied by what factor?

(a) 0.65 (b) 0.80
(c) 1.00 (d) 1.20

(UP RVNL AE 2016)

Ans. (a) For compression member






End condition	Recommended value l_{eff}
1.Both end held in position and restrained against rotation	0.65 *l*
2. Held in position at both end and restrained against rotation in one end	0.8 *l*
3. Held in position at both end and not restrict in both end	*l*
4. One end fix and other is free	2 *l*

313. The effective length of a column, held in position and restrained in direction at one end and the other end is free, is equal to–

(a) 0.67 L (b) L
(c) 1.2 L (d) 2.00 L

UTTRAKHAND AE 2013
ESE 1998

Ans : (d) Effective length of prismatic compression member :

	Schematic representation	Effective length
1.		**2.0 L**
2.		**2.0 L**
3.		**1.0 L**
4.		**1.2 L**
5.		**0.8 L**
6.		**0.65 L**

314. As per IS code, the maximum pitch of rivets in compression flange (thickness 't') of a built up beam is–

(a) Lesser of 200 mm and 12t
(b) Lesser of 250 mm and 12t
(c) Lesser of 200 mm and 16t
(d) Lesser of 250 mm and 16t

(UTTRAKHAND AE 2013)

Ans : (a) The distance between the centers of two consecutive rivets in direction of stress should not exceed 16t or 200mm, whichever is less in tension member and 12t or 200mm, whichever is less in compression member

315. According to IS 800, the slenderness ratio of the bracing member shall be limited to:

(a) 100 (b) 60
(c) 120 (d) 150

LMRC AE 2017 I–Shift
ESE 2016

Ans : (c) Slenderness Ratio:- It is ratio of effective length to the minimum radius of gyration of the member.

$$\text{Slenderness Ratio} = \frac{L}{K}$$

For bracing member it is limited upto 120.
For short column it should be less than 32.
For medium column it is in between 32 and 120.
For long column it is greater than 120.
For hangers slenderness ratio160.

316. In a riveted connection, the minimum width of lacing bars shall be times the nominal dia of the end rivet

(a) 2 (b) 2.5
(c) 3 (d) 3.5

RPSC GWD A. En. – 2014

Ans : (c) Minimum flat width of lacing bar should not be less than three times the nominal diameter of the end connector.

317. As per IS:800-1984, if the diameter or rivets is 18mm, then the minimum width of lacing plate should be:

(a) 50mm (b) 55mm
(c) 60mm (d) 65mm

[UPPSC State Eng. A.E. 2007]

Ans : (b) Minimum width = 3d = 3 × 18 = 54mm.

318. For same load, unsupported length and end conditions a laced column as compared to a battened column

(a) Is stronger (b) Is weaker
(c) Is equally strong (d) Cannot be compared

RPSC VPITI 2012

Ans : (a) For same load, unsupported length and the end conditions of a laced column as compared to a battened column is stronger. For eccentric loading battened column is not good. In battened column the effective length is increased by 10%.

319. Angle of inclination of axis of member for lacing bars shall not be greater than

RPSC ACF 2011

OR

The inclination of lacing bars with the axis of the compressive member should not be more than

Search on Telegram @apna_pdf

(a) 30^0 (b) 40^0
(c) 60^0 (d) 70^0

(BPSC AE 2012 Paper–V)

Ans : (d) Slenderness ratio of lacing bar should be less than 145. Angle of inclination of lacing bar with longitudinal axis should be kept between 40°-70°.

In single lacing system, thickness of lacing $t \not< \frac{1}{40}$ of its effective length. For double lacing system it should not be less than $\frac{1}{60}$ of its effective length.

overlap of lacing should not be less than four times the thickness of the bar or the member, whichever is less.

320. What is the recommended value of the effective length if the end condition effectively held in position and restrained in direction at both end?

(RPSC VPITI 2012)

OR

As per IS : 800, the effective length of a compression member effectively held in position and restrained against rotation at both ends is

(a) 0.80L (b) 1.2L
(c) 0.65L (d) 2.5L

[UPPSC State Eng. A.E. 2007(I)]

Ans : (c) The effective length of a compression member effectively held in position and restrained against rotation at both ends is 0.65 L.

1.	Effectively held in position and restrained against rotation at both ends	0.65 L
2.	Effectively held in position at both ends and restrained against rotation at end	0.80 L
3.	Effectively held in position at both ends, but not restrained against rotation	1.00 L

321. The maximum permissible slenderness ratio for steel ties likely to be subjected to compression is :

(a) 400 (b) 350
(c) 250 (d) 180

(UKPSC AE (Paper-I) 2007)
(RPSC POLY. TECH. LECT. 2011)

Ans : (c)

Sl. No.	Types of member	Maximum slenderness ratio
1.	A member carrying compressive loads resulting from dead load and super imposed load	180
2.	A member subjected to compressive loads resulting from wind/earthquake force provided the deformation of such member does not adversely affect the stress in any part of the structure.	250
3.	A member normally carrying tension but subjected to reversal of stress due to wind or earthquake forces	

322. Effective length of a column is the length between the points of:

(a) Support
(b) Maximum moment
(c) Zero moment
(d) Zero shear

[UPPSC AE 12.04.2016 Paper–I]

Ans : (c) Effective length of a column is the length between the points of contraflexure i.e. between zero moment.

323. As per IS: 800-1984, the allowable bending compressive stress in rolled I-beams and channels when compressive flange is continuously laterally supported should be:

(a) 165 N/mm^2 (b) 175 N/mm^2
(c) 185 N/mm^2 (d) 200 N/mm^2

[UPPSC State Eng. A.E. 2007]

Ans : (a) As per IS: 800-1984, the allowable bending compressive stress in rolled I-beams and channels when compressive flange is continuously laterally supported should be 165 N/mm^2.

324. The Indian Standard (IS) 800:2007 divides various compression member cross–sections into how many buckling classes?

(a) 1 (b) 2
(c) 3 (d) 4

[MPPSC AE 2016]

Ans : (d) Classification of cross section and their characteristic-

(1) Plastic → Can develop plastic hinges and have the rotation capacity required for failure of the structure by formation of plastic mechanism.
(2) Compact → Can develop plastic moment of resistance but have inadequate plastic hinge rotation capacity for formation of plastic mechanism before buckling are classed as compact section.
(3) Semi compact → Cross section in which the extreme fiber in compression can reach yield stress but cannot develop plastic moment of resistance due to local buckling.
(4) Slender →In these, the elements buckle locally even before attainment of yield stress.

325. If the vertical plane of load coincides with the vertical centroidal axis of the section, the torsion is not developed in the following section:

(a) an angle section (b) a T-section
(c) an I-section (d) a channel section

[UPPSC State Eng. A.E. 2007 & 2007 (I)]

Ans : (c) If the vertical plane of load coincides with the vertical centroidal axis of the section, the torsion is not developed in an I-section.


Search on Telegram @apna_pdf

326. Two ISMC 400 channels placed back to back at a spacing of 250 mm carry an axial load of 1600kN. The lacing system should be designed to resist a transverse shear equal to :

(a) 40kN (b) 80kN
(c) 100 kN (d) 160 kN

UPPSC State Eng. A.E. 2003, 2007

Ans : (a)



Lacing are designed to resist transverse shear equal to 2.5% of total axial force on the column taken into account

$$V = \frac{2.5}{100} \times P$$

Here, $P = 1600kN$

$$V = \frac{2.5}{100} \times 1600$$

$$\boxed{V = 40kN}$$

327. The maximum slenderness ratio of a steel column, the design of which is governed by wind or seismic force is

(a) 150 (b) 180
(c) 250 (d) 350

[UPPSC State Eng. A.E. 2004 (I)]

Ans : (c) The slenderness ratio for compression members should be :

1. Subjected to dead load and live load = 180
2. Member subjected to compression due to EQ and wind force = 250
3. For compression flange of beam = 300
4. For ties or bracing member of truss = 350.

328. In a simply supported beam of span L each end is restrained against torsion, compression flange being unrestrained. According to IS : 800, the effective length of the compression flange will be equal to

(a) L (b) 0.5L
(c) 0.75 L (d) 0.70 L

[UPPSC State Eng. A.E. 2003]

Ans : (a)

Type of member	End condition of beam	Effective length, *l*
simply supported beams	Restrained against torsion and	
	(i) Unrestrained against lateral bending	L
	(ii) Partially restrained against lateral bending	0.85L
	(iii) Fully restrained against lateral bending	0.7 L
	(iv) Effective lateral bracing at intervals along the length	Distance between intersections of bracings with member

329. The strength of 'strut' depends on

(a) diameter of rivet used
(b) thickness of gusset plate
(c) net area of strut
(d) slenderness ratio of strut

(BPSC AE 2012 Paper–V)

Ans : (d) Compressive strength of strut depends upon its slenderness ratio. If slenderness ratio increase, its strength decreases.

330. The most economical section for a steel column is

(a) rectangle section (b) solid section
(c) I-section (d) tubular section

(BPSC AE 2012 Paper–V)

Ans : (d) In the given members, tubular sections are most economical as for the given area they have maximum moment of inertia. MOI for given area in different section : –
Tubular section > I-section > Rectangular section > solid section.

331. The effective length of a balanced column can be increased by.....of the corresponding effective length of similar laced column.

(a) 5% (b) 8%
(c) 15% (d) 10%

GPSC AE June 2019

(BPSC AE Paper V 2001)

Ans : (d) The effective length of battened column is increased by 10%.

332. The angle of inclination of lacing bars (double or single) with respect to the axis of the stanchion shall be :

(a) Not less than 30^0 nor more than 60^0
(b) not less than 25^0 nor more than 50^0
(c) not less than 45^0 nor more than 80^0
(d) not less than 40^0 nor more than 70^0

(BPSC AE Paper V 2006)

Ans : (d) Slenderness ratio of lacing bar should be less than 145. Angle of inclination of lacing bar with longitudinal axis should be kept between 40°-70°.

333. In the built-up compression members, the number of battens should be such that the member is divided into not less than

(a) two ways (b) three ways
(c) four ways (d) six ways

(JPSC Combined AE Paper V 2013)

Ans : (b) The number of battens should be such that the member is divided into at least three ways within its actual length.

334. A compression member having gross and effective cross-sectional areas of 1500 mm^2 and 1250 mm^2, respectively. If the design

Search on Telegram @apna_pdf

compressive stress is 150 MPa, the design compressive strength of the column will be-

(a) 8.33 kN (b) 10 kN
(c) 188 kN (d) 225 kN

MPPSC AE 2017

Ans. (d) : For compression members design strength is calculated based on gross cross sectional area.
Hence design compressive strength
$= 150 \text{ MPa} \times 1500 \text{ mm}^2$
$= 225 \text{ kN}$

335. The channels or angles in the compression chords of the steel truss girder bridges are turned outward in order to increase

(a) cross-sectional area
(b) section modulus
(c) torsional constant
(d) radius of gyration

BPSC AE 2019 Paper (V) Section-I

Ans. (d) : Channels or Angles in the compression chords of the steel truss girder bridges are turned outward in order to increase the radius of gyration which reduces the slenderness ratio of the member. Hence it increases resistance against buckling.

336. For compression member having the same effective length about any cross-sectional axis the most preferred section from the point of view of strength is

(a) a box (b) an I-section
(c) a circular tube (d) a single angle

APPSC AE 2016 (Mains)

Ans. (a) : A box section is preferred since it will give maximum moment of inertia.

337. The critical load for a column of length L will be minimum when :

(a) both end are hinged
(b) both ends are rigid
(c) one end is fixed and other hinged
(d) one end is fixed and other free

[HPPSC 2016-II]

Ans. (d) : Euler's critical load, $P_c = \dfrac{\pi^2 E}{\lambda^2} \times A$

$\lambda = \dfrac{KL}{r} = \dfrac{L_{eft}}{r}$

End condition	L_{eff}
(1) Both end fixed	$\frac{L}{2}$
(2) One fixed, one free	2L
(3) One fixed, other hinged	$L/\sqrt{2}$
(4) both ends hinged	L

$\therefore P_e$ is minimum for one end fixed and other end free.

338. The splice plate for the steel column is generally designed as :

(a) Short column
(b) Long column
(c) Intermediate column
(d) Based on slenderness ratio

Karnataka PSC AE 2017 Paper - II

Ans. (c) : The splice plate for the steel is designed as intermediate column.
Intermediate columns– Steel columns with a slenderness ratio of $40 \le \lambda \le 120$ are defined as Intermediate columns.

339. What shall be width to thickness ratio for single angle section of class 1 to prevent local buckling ? (Take f_y = 250 Mpa)

(a) 15.7 (b) 10.5
(c) 9.4 (d) 8.4

Rajasthan JEN (Degree) Shift - II 2016

Ans. (c) : Width thickness ratio for single action section of class-I to prevent local buckling

$\dfrac{b}{t} = 9.4 \in$

where, $\in = \sqrt{\dfrac{250}{f_y}} = \sqrt{\dfrac{250}{250}} = 1$

therefore: $\dfrac{b}{t} = 9.4 \times 1$

$\boxed{\dfrac{b}{t} = 9.4}$

340. Intermediate vertical stiffeners in plate girders are used to -

(a) Prevent local buckling of the web
(b) Prevent local buckling of the flange
(c) Prevent excessive deflection
(d) Increase the bearing strength of the web

RPSC AE 2018

Ans. (a) Intermediate vertical stiffeners in plate girders are used to prevent local buckling of the web.

341. A symmetrical channel section is made of a material which is equally strong in tension and compression. It is used as a simply supported beam with its web horizontal to carry vertical loads. It will be -

(a) Strongest if the web is used as a top face
(b) Strongest if the web is used as a bottom face
(c) Equally strong in (1) and (2)
(d) Not possible to state which of the above statement is correct

RPSC AE 2018

Ans. (c) Symmetrical section will be equally strong to carry horizontal and vertical loads.

342. In the simplified design of angle iron purlins, which one of the following assumption would not be valid -

(a) Load component acting normal to the slope is considered
(b) Bending moment about the minor axis is considered
(c) Allowable bending stress is not reduced
(d) Slope of the roof should not exceed 30^0

RPSC AE 2018

Ans. (b) : An angle iron purlin is unsymmetrical about the both axes. IS : 800 - 1984 permits the use of the

Search on Telegram @apna_pdf

angle section as a purlin provided the slope of the roof truss is less than 30^0. The bending moment about the minor axis is neglected.

343. A welded plate girder has : $b/t_f = 6.7$ and $d/t = 9.1$. The section of plate girder will be classified as :

(a) Slender (b) Semi-compact
(c) Compact (d) Plastic

Where b = flange width, t_f = flange thickness; d = depth of the girder, t = web thickness

Rajasthan JEN (Degree) Shift - II 2016


Ans. (d) A welded plate girder has : $b/t_f = 6.7$ and $d/t = 9.1$. The section of plate girder will be classified as plastic.

344. A strut is a structural member subjected to :

(a) tension in a direction parallel to its longitudinal axis
(b) tension in a direction perpendicular to its longitudinal axis
(c) compression in a direction parallel to its longitudinal axis
(d) compression in a direction perpendicular to its longitudinal axis

GPSC AE Class (1&2) Paper - 2 2017

Ans. (c) : A strut is a compression member subjected to compressive stress along or parallel to longitudinal axis.



345. To prevent local buckling in Plate girders, the horizontal stiffeners are provided

(a) at a distance 0.2 times the depth of web from compression end
(b) at a distance 0.2 times the depth of web from tension end
(c) at a distance 0.4 times the depth of web from compression end
(d) at a distance 0.4 times the depth of web from tension end

GPSC AE (CLASS 1 & 2) 2019

Ans : (a) : Horizontal stiffener are provided at a distance of $(0.2d_w)$ $d_w \rightarrow$ depth of web from the compression end ($d_w/t_w > 200$), these are provide to prevent local buckling of web
Vertical stiffener are provided at a spacing of 0.33d and maximum of 1.5d, this is to prevent local buckling of web or web crippling.

346. Splices for a compression member are designed as

(a) Pedestal (b) Long column
(c) Compression block (d) Short column

GPSC AE (CLASS 1 & 2) 2019

Ans : (c) : Short column is designed as splices in compression member. Such as column, struts and lattice girder and bracing etc.


347. The effective depth of end battens should be

(i) More than twice the flange width of component columns
(ii) More than the distance between CG of component columns
(iii) Less than twice the flange width of component columns
(iv) Less than the distance between CG of component columns

(a) (i) and (ii) (b) (i) and (iv)
(c) (i) and (iv) (d) (ii) and (iii)

GPSC AE (CLASS 1 & 2) 2019

Ans : (a) :



b = flange width

$\boxed{d > 2b}$

d = effective depth > $\frac{3}{4}a$


a = Centroid distance between columns

348. The maximum permissible slenderness ratio of single angle section connected with one bolt only and being used as a strut under dead and live loads is

(a) 350 (b) 300
(c) 250 (d) 180

GPSC AE (CLASS 1 & 2) 2019

Ans : (d) : When angle strut which is single angled bolted discontinuous $\boxed{\frac{l}{r} = 180}$



For only dead and live load.

349. The effect of shear lag is

(a) Less in small length of connection
(b) Less in large length of connection
(c) Non-existent in angle section
(d) Non-existent in channel section

Search on Telegram @apna_pdf

GPSC AE (CLASS 1 & 2) 2019

Ans : (b) : The effect of shear lag in large connection is less because the concentrated stress get distributed at each end connection and no strain is remained in any sections.

350. A flat compression element of a cold formed steel section, stiffened both edges parallel to the direction of stress is called:

(a) Stiffened compression element
(b) Un-stiffened compression element
(c) Multiple stiffened element
(d) Flat element

Kerala PSC AE 2015

Ans. (a) : Stiffened compression element: A structural element, subject to compressive forces, that has been reinforced or stiffened, along a line perpendicular to its weak axis of bending, in order to provide additional strength against buckling.

351. Common hot rolled steel axial compression members fail by:

(a) Gross section yielding
(b) Critical section rupture
(c) Block shear
(d) Flexural buckling

Kerala PSC AE 2015

Ans. (d) : Flexural buckling is most prominent failure in hot rolled steel sections under axial compression.
Block shear- It depending on the connection design, there can be several different block failure under axial tension.

352. As per Indian Standards, the maximum bearing pressure at the column base should not exceed the bearing strength equal to:

(a) 0.40 f_{ck} (b) 0.45 f_{ck}
(c) 0.50 f_{ck} (d) 0.60 f_{ck}

Kerala PSC AE 2015

Ans. (d) : The maximum bearing pressure at the column base should not exceed the bearing strength equal to .60f_{ck}.
→ Some stresses are also depend on yield stress
Maximum shear = .45 f_y
Average shear stress = .40 f_y
Bearing stress = .75 f_y

353. Consider the following statements for the design of a laced column:

1. In a bolted connection, the minimum width of the lacing bar shall be three times the nominal diameter of the end bolt
2. The thickness of the flat of a single lacing system shall be not less than one-fortieth of its effective length
3. The angle of inclination of the lacing bar should be less than 40^0 with the axis of the built-up column
4. The lacing shall be designed for a transverse shear of 2.5% of the axial load on the column.

Which of the above statements are correct?

(a) 1, 2 and 3 only (b) 1, 2 and 4 only
(c) 1, 3 and 4 only (d) 1. 2. 3 and 4

ESE 2018

Ans. (b) : Lacing bars whether in double or single laced system shall be inclined (θ) at an angle not less than 40^0 nor more than 70^0 to the longitudinal axis of laced column ($40^o \le \theta \le 70^0$)
(Clause 7.6.4 of IS 800 : 2007).

354. Consider the following statements in respect of column splicing:

1. Splices should be provided close to the point of inflection in a member
2. Splices should be located near to the point of lateral restraint in a member
3. Machined columns for perfect bearing would need splices to be designed for axial force only

Which of the above statements are correct?

(a) 1 and 2 only (b) 1 and 3 only
(c) 2 and 3 only (d) 1, 2 and 3

ESE 2018

Ans. (a)
- Splices should be located near to point of lateral restraint.
- Splices should be provided close to point of inflection and point of contra flexure.
- Machined columns need splices to be designed for axial force and bending moment.

355. According to IS 456-2000 Column or strut is a compression member whose effective length exceeds:

(a) 3 times the least lateral dimension
(b) 2 times the least lateral dimension
(c) 5 times the least lateral dimension
(d) 4 times the least lateral dimension

DSSSB AE 2019

Ans. (a) According to IS 456-2000 column or strut is a compression member whose effective length exceeds three times the least lateral dimension.

356. The lacing bars in the built up columns are designed to resist a transverse shear equal to _____ of the column axial load.

(a) 1/40 (b) 1/60
(c) 1/30 (d) 1/10

AP (VSS-1) PART - A 2017

Ans : (a) Lacing bars are designed to bear 2.5% of transverse shear

357. The best double angle section in case of compression member is

(a) equal angles on the same side of the gusset plane
(b) equal angles on opposite side of the gusset
(c) unequal angles with short legs back to back
(d) unequal angles with long legs back to back

AP (VSS-1) PART - A 2017

Search on Telegram @apna_pdf

Ans : (d) The best double angle section in case of compression is unequal angle with long legs back to back.

358. Localized bearing stress caused by the transmission of compression from the wide flange to the narrow web causes a failure called

(a) Web buckling (b) Web shear flow
(c) Web bearing (d) Web crippling

APTRANSCO 2017

Ans : (d) Web crippling is caused due to transmission of compression from the wide flange to the narrow web.
Web buckling– Web buckling occurs when the vertical compression stress in the web of mid height reaches the critical buckling stress as the thin web acts as a long slender column.

359. Consider the following stipulations in designing a laced column :

(i) Single lacing systems on opposite planes shall preferably be in the same direction so that one is the shadow of the other.
(ii) Lacing bar should be a flat section.
(iii) The slenderness ratio of the lacing bars for compression shall not exceed 180.
(iv) Laced compression members are to be provided with tie plates at ends.

Which of the following observations is/are correct?

(a) Only (i) (b) (i) and (iii)
(c) (ii) and (iv) (d) (i) and (iv)

APTRANSCO 2017

Ans : (c) To design a laced column, the lacing bar should be a flat section and laced compression member are to be provided with tie plates at ends.

360. Prying forces are :

(a) Shearing forces on the bolts because of the joints
(b) Tensile forces due to the flexibility of connected parts
(c) Bending forces on the bolts because of the joints
(d) Forces due to the friction between connected parts

APTRANSCO 2017

Ans : (b) Prying forces are tensile forces due to flexibility of connected parts. When connection subjected to tension forces the connected part and leads to deformation that increases the tension applied to the bolt so that the additional force is generated in the bolts due to joints plates.


361. For a compression member with double angle section, which of the following section will give larger value of minimum radius of gyration?

(a) Equal angles back to back.
(b) Unequal legged angles with long legs back to back.
(c) Unequal legged angles with short legs back to back.
(d) Both (b) and (c)

OPSC AEE 2019 Paper–I

Sikkim PSC AE 2017

Ans. (b) : For a double angle section back to back it is desirable to use unequal angles with the long legs back to back to achieve a balance b/w radius of gyration values about zz and yy axis's.



362. Battens provided for a compression member shall be designed to carry a transverse shear equal to

(a) 2.5% of axial force is member
(b) 5% of axial force in member
(c) 10% of axial force in member
(d) 20% of axial force in member

OPSC AEE 2019 Paper–I
GPSC AE Dec 2018
PTCUL AE 2016
Rajasthan JEn (Degree) 2016

Ans. (a) : As per IS 800 : 1984, battens shall be designed to carry the bending moment and shear arising from transverse shear force 'V' of 2.5% of the total axial force on the whole compression member.

363. The channels or angles in the compression chords of the steel truss girder bridges are turned outward in order to increase :

(a) Cross-section area (b) Section modulus
(c) Torsional constant (d) Radius of gyration

OPSC AEE 2019 Paper–I


Ans. (d) : Channel or Angles in the compression chords of the steel truss girder bridges are turned outward in order to increase the radius of gyration which reduces the slenderness ratio of the member. Hence it increases resistance against buckling.

364. A column, base is subjected to moment. If the intensity of bearing pressure due to axial load is equal to stress due to the moment, then the bearing pressure between the base and concrete is


(a) Uniform compression throughout.
(b) Zero at one end and compression at the other end.
(c) Tension at one end and compression at the other end.
(d) Uniform tension throughout

OPSC AEE 2019 Paper–I

Ans. (b)



Search on Telegram @apna_pdf



365. As per IS:800, for compression flange, the outstand of flange plates should not exceed, if "t" is thickness of thinnest flange plate :

(a) 12t (b) 16t
(c) 20t (d) 25t

OPSC AEE 2019 Paper–I

Ans. (b) : As per IS 800 – 1984 clause 3.5-2.1 for compression flange, the outstand of flange plates should not exceed 16t, where 't' is the thickness of the flange of a section or of a plate.

366. In the case of structural steel sections (in terms of their outstanding length), the minimum ratio of thickness of elements in compression is specified to prevent–

(a) Bending failure (b) Shear failure
(c) Local buckling (d) Tension failure

Gujarat PSC AE (N.W.R.) 2020
ESE 1998

Ans. (c) : In the case of structural steel sections (in terms of their outstanding length), the minimum ratio of thickness of elements in compression is specified to prevent Local buckling.

367. A compression member effectively held in position and restrained in direction at one end but not held in position or restrained in direction at the other end. If its actual length is L, then its effective length is equal to

(a) 0.67 L (b) L
(c) 1.5 L (d) 2 L

APPSC AEE MAINS 2016

Ans. (d) For compression member

End condition	Recommended value l_{eff}
1.Both end held imposition and restrained against rotation	0.65 *l*
2. Held in position at both end and restrained against rotation in one end	0.8 *l*
3. Held in position at both end and not restriclined in both end	*l*
4. One end fix and other is free	2 *l*

368. Effective length of compression member which is effectively held in position and restrained against rotation at both ends is

(a) 0.65 *l* (b) 0.75 *l*
(c) 0.80 *l* (d) 0.85 *l*

Maharashtra PSC Mains 2018 Paper-1

Ans. (a) : As per IS 456 : 2000 theoretical value is 0.5 *l* recommended value of effective length is 0.65 *l*.

369. The inclination of a lacing bar with the axis of the compression member is θ. Then 'θ' shall not be less than

(a) 30° (b) 40°
(c) 50° (d) 70°

Maharashtra PSC Mains 2018 Paper-1

Ans. (b) : Lacing bars, whether in double or single systems, shall be inclined at an angle not less than 40° nor more than 70° to the axis of the built-up member.

370. The thickness of battens shall be

(a) 1/10th of effective length of batten
(b) 1/15th of effective length of batten
(c) 1/10th of the distance between the innermost connecting lines of rivets, bolt or welds
(d) 1/15th of the distance between the innermost connecting lines of rivets, bolt or welds

GPSC AE March 2018

Ans. (d) : Thickness of batten plates $\geq \frac{1}{50} \times$ distance b/w innermost connecting lines of rivets, bolts or welds.

$\frac{1}{15} > \frac{1}{50}$, so ok.

371. The design compressive stress of an axially loaded compression member in IS-800-2007 is given by

(a) Rankine formula
(b) Secant formula
(c) Merchant Rankine formula
(d) Perry Robertson formula

GPSC AE March 2018

Ans. (d) : According to IS: 800-2007.
The Perry-Robertson formula is an elastic approach and is based on failure when the stress at the extreme fibre of section reaches yield and design compressive stress of an axially loaded compressive member is analysed.

372. If the effective length of a prismatic compression member is 0.8 L, then the support conditions should be (Note: L is the unsupported length)

(a) at one end both rotation and translation is restrained, whereas at the other end translation is restrained, but the rotation is free
(b) at both ends both translation and rotation are restrained
(c) at both ends translations are restrained but rotations are free
(d) at one end translation is restrained while at the other end rotation is restrained

GPSC AE March 2018

Ans. (a) For compression member

End condition	Recommended value l_{eff}
1. Both end held in position and restrained against rotation	0.65 *l*
2. Held in position at both end and restrained against rotation in one end	0.8 *l*
3. Held in position at both end and not restrict in both end	*l*
4. One end fix and other is free	2 *l*

Search on Telegram @apna_pdf

373. Lacing bar shall be inclined at an angle θ which should be between

(a) 20° - 50° (b) 30° - 60°
(c) 40° - 70° (d) 50° - 80°

GPSC AE March 2018

Ans. (c) : Angle of lacing (θ_2) = 40° - 70°
generally 45°

374. The effective slenderness ratio of batten is increased by (in percentage)

(a) 20 (b) 10
(c) 5 (d) No increment

Vizag steel MT 2017
KPTCL AE 2016

Ans. (b) : If battens are used the effective length of column is increased by 10%.
∴ Effective slenderness ratio are increased by 10%.

$$\left\{\lambda = \frac{L_v}{r_{min}}\right\}$$

375. When strut connected by single rivet at each end, maximum slenderness ratio (l) of compression member is

(a) 300 (b) 350
(c) 180 (d) 250

GPSC Poly. Tech. Lect. 2016

Ans. (c) : When strut connected by single rivet at each end, maximum slenderness ratio (λ) for compression member is 180.

376. Lacing bars in a built-up steel column should be designed to resist

(a) Axial force (b) Shear force
(c) Bending moment (d) Torsion

UPSC JWM 2017

Ans. (b) : Lacing are provided to resist horizontal force (shear force) on columns and lacing are subjected to axial force. 2.5% of shear force.

377. Intermediate vertical stiffeners are provided in a plate girder if the web thickness in terms of d (distance between the flanges) is

(a) $\frac{d}{165}$ (b) $\frac{d}{115}$
(c) $\frac{d}{85}$ (d) $\frac{d}{65}$

UPSC JWM 2017

Ans. (c) : Intermediate stiffeners are provide when there are concentrated load acting on the plate girder.
Thickness of web is less than $\frac{1}{85}$th of depth of web, then the web may be buckle due to shear.

378. Bearing stiffeners in plate girders are provided at

(a) Mid-span (b) Quarter point
(c) Equal intervals (d) Supports

UPSC JWM 2017

Ans. (d) : Stiffeners are provided to support other member and when attached to beam then web & flange stiffen against deformation.

379. The effective length of a battened strut effectively held in position but not restrained against rotation at both ends is taken as :

(a) 1.8 L (b) L
(c) 1.1 L (d) 1.3 L

Punjab MCP SDO 2015

Ans. (c) : The effective length of a battened strut effectively held in position but not restrained against rotation at both ends is taken as 1.1L.

380. As per IS : 800, for compression flange, the outstand of flange plates should not exceed :

(a) 12t (b) 16t
(c) 32t (d) 20t

GOA PSC Assistant Prof. 2020
Punjab MCP SDO 2015

Ans. (b) : IS : 800, for compression flange, the outstand of flange plates should not exceed 16t.
IS : 800, for tension flange, the outstand of flange plates should not exceed 20t.

381. The lug angle is

(a) Used with single angle member
(b) Not used with double angle member
(c) Used with channel member
(d) All of the above

GOA PSC Assistant Prof. 2020

Ans. (d) : The lug angle is
(1) Used with single angle member
(2) Not used with double angle member
(3) Used with channel member

382. The batten plates used to connect the components of built-up column are designed to resist

(a) longitudinal shear only
(b) transverse shear only
(c) longitudinal shear and moment arising from transverse shear
(d) vertical shear only

TRB Poly. Tech. Lect. 2012

Ans. (c) : The batten plates are designed to resist simultaneously the moments longitudinal shear arising due to transverse shear force.

383. Buckling load in a steel column is

(a) related to length
(b) directly proportional to the slenderness ratio
(c) inversely proportional to the slenderness ratio
(d) non linearity of the slenderness ratio

TSGENCO_2015

Ans. (c) : Buckling load,

$$P_c = \frac{\pi^2 E}{\lambda^2}$$

$$P_c \propto \frac{1}{\lambda^2}$$

where, λ = slenderness ratio
P_c = Buckling load

Search on Telegram @apna_pdf

384. The best arrangement to provide unified behaviour in built up steel columns is by

(a) lacing (b) battening
(c) tie plates (d) perforated cover plates

TSGENCO_2015

Ans. (a) : The best arrangement to provide unified behaviour in built up steel columns is by lacing.

385. The thickness of battens shall be not less than :

(a) $\frac{1^{th}}{80}$ of the distance between the innermost connecting lines of rivets, bolts or welds

(b) $\frac{1^{th}}{50}$ of the distance between the innermost connecting lines of rivets, bolts or welds

(c) $\frac{1^{th}}{70}$ of the distance between the innermost connecting lines of rivets, bolts or welds

(d) None of the above

TRB Poly. Lect. Tech. 2017

Ans. (b) : The thickness of battens shall be not less than $\frac{1^{th}}{50}$ of the distance between the innermost connecting lines of rivets, bolts or welds.

386. A joint when provided in the length of a column is called.....

(a) Batten (b) Lacing
(c) Splice (d) Lug angle

SJVNL ET 2019

Ans. (c) : A splice is a joint made within the length of a stanchion, a beam or any other structural member.

- It is aimed at transferring the internal force from one structural part to the adjacent one without being a weak point of the structure in relation to strength, stiffness and ductility.

387. Where the imposed load is variable and exceeds three-quarters of the dead load, arrangements of live load acting on the floor under consideration shall not include which of the following case?

(a) Imposed load on all spans
(b) Imposed load on two adjacent spans
(c) Imposed load on alternate spans
(d) Imposed load on spans under consideration

UPRVUNL AE 2016

Ans.: (a) Where the imposed load is variable and exceed ¾ of the dead load, arrangements of live load acting on the floor under, consideration shall not include the case of Imposed load on all spans.

388. The maximum width of a covered steel building section should preferably be restricted to X m beyond which suitable provisions for the expansion joint may be made, where X is :

(a) 50 (b) 90
(c) 150 (d) 200

UPRVUNL AE 2016

Ans.: (c) The maximum width of a covered steel building section should preferably be restricted to 150m beyond which suitable provision for the expansion joint may be made.

389. The effective length of a battened strut of actual length L, effectively held in position at both ends but not restrained in direction, is taken as

(a) L (b) 1.1L
(c) 1.5L (d) 1.8L

AP TRANSCO AEE 2017

Ans. (d) : Battened column effectively held in position at both ends but not restrained in direction.
Effective length = 1.8 L

390. Localized bearing stress caused by the transmission of compression from the wide flange to the narrow web causes a failure called

(a) Web buckling (b) Web shear flow
(c) Web bearing (d) Web crippling

AP TRANSCO AEE 2017

Ans. (d) : Web crippling : Localized bearing stress caused by transmission of compression from wide flange to narrow web causes a failure called web crippling.

391. Consider the following stipulations in designing a laced column :

i. Single lacing systems on opposite planes shall preferably be in the same direction so that one is the shadow of the other.
ii. Lacing bar should only be a flat section.
iii. The slenderness ratio of the lacing bars for compression shall not exceed 180.
iv. Laced compression members are to be provided with tie plates of ends.

Which of the following observations is/are correct ?

(a) i only (b) i and iii
(c) ii and iv (d) i and iv

AP TRANSCO AEE 2017

Ans. (d) Observation in designing a laced column.

i. Single lacing systems on opposite planes shall preferably be in the same direction so that one is the shadow of the other.
ii. Laced compression members are to be provided with tie plates at ends.
iii. Effective slenderness ratio = 1.05 time $\frac{KL}{r}$, the slenderness ratio of lacing bars shall not exceed 145.

392. Slenderness ratio of a medium column is between

(a) 125 to 160 (b) 20 to 30
(c) 32 to 120 (d) 165 to 180

UPPCL AE 2014

Ans. (c) : Slenderness ratio of a medium column is between 32 to 120.

393. A steel column in a structure carries a load of 125 kN. It is built up of 2 ISMC 350 channels connected by lacing. The lacing carries a load of

(a) 125 kN (b) 12.5 kN
(c) 3.125 kN (d) Zero

APPSC AEE 2016

Ans. (c) : Lacing carries the 2.5% of loading that carries the column structure.

Lacing carries the load $= \frac{125 \times 2.5}{100}$

Search on Telegram @apna_pdf


= 3.125 kn

394. What will be effective length of prismatic compression member having unsupported length 'L' if one end is restrained for translation and rotation and other end is free for translation and rotation?

(a) 0.65 L (b) 1.0 L
(c) 0.8 L (d) 2.0 L

GPSC AE January 2018

Ans. (d) : For compression member-

End conditions	Recommended value (l_{eff})
1. 	0.65 *l*
2. 	0.8 *l*
3. 	*l*
4. 	2 *l*

One end fixed and other end free one end restrained for translation and rotation, other end is free for both is case 4.

395. To avoid buckling in a compression member

(a) Slenderness ratio should be less
(b) Radius of gyration should be less
(c) Slenderness ratio should be more
(d) Area of cross section should be less

GPSC AE January 2018

Ans. (a) : The more the slenderness ratio (λ), the compression member having more tendency to buckle. So, slenderness ratio must be less to reduce buckling.

$$\lambda = \frac{kl}{r}$$ r = radius of gyration

396. To account for shear deformation effects in battened columns, the ratio of the effective slenderness ratio $(KL/r)_e$ to the maximum actual slenderness ratio $(KL/r)_0$ of column is to be considered as

(a) More than 1 (b) 1.0
(c) 0.5 (d) 0.1

GPSC AE January 2018

Ans. (a) : Effective slenderness ratio of the batten column is increased by 10% to account for shear deformation effect

$$\lambda_{eff\ batten\ column} = 1.1\left(\frac{kl}{r}\right)$$

$$\lambda_{column} = \frac{kl}{r}$$

397. The effective slenderness ratio for laced column shall be ..... times the maximum actual slenderness ratio to account for shear deformations.

(a) 1.5 (b) 2.5
(c) 0.75 (d) 1.05

GPSC AE January 2018

Ans. (d) : Effective slenderness ratio of laced column is increased by 5% to the account for shear deformation effect.

$$\lambda_{laced\ column} = 1.05\left(\frac{kl}{r}\right)$$

$$\lambda_{column} = \frac{kl}{r}$$

398. For steel columns with lacing, the lacing is usually designed to resist transverse shear V_t which is dependent on.

(a) Axial load on column
(b) Shear force on column
(c) Bending moment in column
(d) Axial force in lacing

GPSC AE January 2018

Ans. (a) : Design shear strength = 2.5% of column axial load, for lacing member

$$V_t = 2.5\% \times P_{axial\ column}$$

399. What is the value of Maximum effective slenderness ratio (KL/r) for a compression flange of beam against lateral torsional buckling?

(a) 180 (b) 250
(c) 300 (d) 350

GPSC AE January 2018

Ans. (c) : Maximum effective slenderness ratio for a compression flange of beam against lateral torsional buckling

$$\lambda_{max} = \frac{kL}{r} = 300$$

400. What is the value of Maximum effective slenderness ratio (KL/r) for a member carrying compression loads resulting from dead loads and imposed loads only?

(a) 180 (b) 250
(c) 300 (d) 350

GPSC AE January 2018

Ans. (a) : Slenderness ratio for a member carrying compression load resulting from dead and impact loads

$$\lambda_{compression} = \frac{kl}{r} \le 180$$

401. The channels or angles in the compression chords of the steel truss girder bridges are turned outward in order to increase

(a) Cross-sectional area (b) Sectional modulus
(c) Torsional constant (d) Radius of gyration

MPPSC AE 2014

Ans. (d) : The channel or angles in the compression chords of the steel truss girder bridges are turned outward in order to increase radius of gyration.

Search on Telegram @apna_pdf

402. IS: 800-2007 limits the width-to-thickness ratio of the elements of a steel section to place a check on

(a) bending buckling
(b) torsional buckling
(c) flexural-torsional buckling
(d) local buckling

GPSC AE Dec 2018

Ans. (d) : IS: 800-2007 limits the width-to-thickness ratio of the elements of a steel section to place a check on local buckling.

403. As per IS: 800-2007, the design compressive stress of an axially loaded compression member is given by

(a) Rankine formula
(b) Secant formula
(c) Merchant Rankine formula
(d) Perry Robertson formula

GPSC AE Dec 2018

Ans. (d) : As per IS: 800-2007, the design compressive stress of an axially loaded compression member is given by Perry Robertson formula.

404. If L is the length between the inner end bolts or welds of a lacing bar, the thickness of the lacing bar for a single lacing system should not be less than

(a) L/30 (b) L/40
(c) L/50 (d) L/60

GPSC AE Dec 2018

Ans. (b) : thickness of lacing bar for a single lacing system $< \frac{L}{40}$
where L = length b/w inner end bolts or welds.

405. In a double lacing system, the angle of inclination of lacing bar to the axis of the member should be in the range of

(a) 5º to 15º (b) 15º to 40º
(c) 40º to 70º (d) 70º to 105º

GPSC AE Dec 2018

Ans. (c) : In a double lacing system, the angle of inclination of lacing bar = 40º to 70º.

406. For connecting lacing flats to column section with 18mm diameter bolt, the minimum width of flat required is

(a) 36 mm (b) 54 mm
(c) 72 mm (d) 90 mm

GPSC AE Dec 2018

Ans. (b) : Minimum width of lacing bars = 3d
$= 3 \times 18 = 54$ mm.

407. The following statements (S1 to S4) pertain to a compression member.

S1 : The effective length depends on the boundary conditions of member at ends.
S2 : The elastic critical stress in compression decreases with decrease in slenderness ratio.
S3 : The ratio of the effective length to the radius of gyration of the member is termed as slenderness ratio of member.
S4 : The elastic critical stress in compression is independent of the slenderness ratio.

Identify the correct statements.

(a) S1 and S3 (b) S2 and S4
(c) S1, S2, S4 (d) S2, S3, S4

BHEL ET 2019


Ans. (a) : For compression member :
- The effective length depends on the boundary conditions of member at ends.
- The ratio of the effective length to the radius of gyration of the member is turned as slenderness ratio of member.

408. Recommended value of effective length of a compression member , which is effectively held at both ends, but not restrained against rotation is

(a) 0.80 L (b) 1.50 L
(c) 2.00 L (d) 1.00 L

GPSC Assistant Prof. 2016

Ans. (d) As per IS 800-1984, when effectively held in position at both end but not restrained against rotation.
then Recommended value of effective length = 1.00 L



409. According to IS 800, the slenderness ratio of the branching member shall be limited to:

(a) 100 (b) 60
(c) 120 (d) 150

LMRC AM 2015

Ans (c) According to IS 800, the slenderness ratio of the branching member shall be limited to 120.

410. Column or strut is a compression member, the effective length of which exceeds X times the least Lateral dimension: where X is

(a) 12 (b) 3
(c) 6 (d) 9

LMRC AM 2015

Ans (b) Column or strut is a compression member, the effective length of which exceeds 3 times the least Lateral dimension.
Pedestal is a compression member, the effective length of which does not exceeds three time the least lateral dimension.

411. The effective length ratio for columns with both ends fixed is :

(a) 1.2 (b) 2.0
(c) 0.5 (d) 3.0
(e) 4.2

CGPSC AE Shift II 2018

Ans. (c) The effective length ratio for column with both ends fixed is 0.5.

412. The maximum effective slenderness ratio for a tension member in which reversal of direct

Search on Telegram @apna_pdf

stress occurs due to loads other than wind or seismic force :

(a) 180 (b) 220
(c) 550 (d) 430
(e) 500

CGPSC AE Shift II 2018
GPSC Poly. Tech. Lect. 2016
GPSC Assistant Prof. 2016

Ans. (a) The maximum effective slenderness ratio for a tension member in which reversal of direct stress occurs due to loads other than wind or seismic force is 180.

	Type of member	λ_{max}
1.	A tension member in which a reversed of direct stress occurs due to loads other than wind or seismic force.	180
2.	A member carrying compressive loads resulting from dead loads and imposed load.	180
3.	A member subjected to compressive forces resulting only form combination with wind/earthquake actions, provided the deformation of such members does not adversely effect the stress in any part of the structure.	250
4.	Compression flange of a beam restrained against lateral torisonal buckling	300
5.	A member normally acting as a tie in a roof truss or a bracing system not considered effective when subjected to possible reversal of stresses resulting from the action of wind or earthquake forces.	350

413. Lug angles:

(a) Are unequal angles
(b) Are used to reduce the length of connection
(c) Increases shear lag
(d) All of the above options
(e) None of the above options

Haryana PSC AE 2018 Paper–I

Ans. (b) : Lug angle is used in designing of tension member.
It is used to connect outstanding legs of member to gusset plate.
The purpose is to reduce length of connection to gusset plate and reduce shear lag effect.

414. Maximum permissible slenderness ratio of compression members which carry dead and superimposed load is:

GOA PSC Assistant Prof. 2020
GPSC AE June 2019
Haryana PSC AE 2018 Paper–I
CGPSC AE Shift II 2018
(BPSC AE Paper V 2006)
(ESE 2004)

OR

The slenderness ratio (as per IS : 800) of a member, carrying compressive loads arising from combined dead loads and imposed loads, should not exceed

(a) 350 (b) 250
(c) 180 (d) 80
(e) 70

AP TRANSCO AEE 2017
APTRANSCO 2017
GPSC Assistant Prof. 2016

Ans. (c) : As per IS : 800-1964 (Cl.3.7)
Maximum slenderness Ratio (λ max)

Member	λ max
A member carrying compressive load resulting from dead load and imposed load	180
A Tension member in which reversal of direct stress due to load other than wind and seismic force	180
A member subjected to compressive forces resulting from wind EQ force provide deformation of such member does not affect stress	250
Compression flange of beam	300
A member normally act as a tie in Roof Truss	350
Tension member other than Pre-tension	400

415. The thickness t of a single flat lacing should not be less than-

(a) $1/30^{th}$ length between inner end rivets
(b) $1/40^{th}$ length between inner end rivets
(c) $1/50^{th}$ length between inner end rivets
(d) None of these

Rajasthan VP ITI 2018

Ans. (b) In single lacing system, thickness of lacing $t \not< \frac{1}{40}$ of its effective length or length between inner end rivets.
For double lacing system thickness of lacing (t) $\not< \frac{1}{60}$ of its effective length or length between inner end rivets.

416. The effective length of column is expressed in terms of equivalent length of compression member of :

(a) Both ends hinged
(b) Both ends fixed
(c) One end hinged and other fixed
(d) None of the above

UP Jal Nigam AE 2016

Ans. (a) : The effective length of column is expressed in terms of equivalent length of compression member of both ends hinged.

Description	Effective length

Search on Telegram @apna_pdf

(1) One end fixed and other hinged		$\frac{l}{\sqrt{2}}$
(2) Both ends fixed		$\frac{l}{2}$
(3) One end fixed and other end force		$2l$
(4) Both ends hinged		l

417. In context of structural steel sections, why the minimum ratio of thickness of elements in compression in terms of outstanding length is specified?

(a) To prevent bending failure
(b) To prevent shear failure
(c) To prevent local buckling
(d) To prevent tension failure

UPRVUNL AE 2014

Ans. (c) : To prevent the minimum ratio of thickness of elements in compression in terms of outstanding length is specified.

418. A steel section is subject to a combination of shear and bending actions. The applied shear force is V and the shear capacity of the section is Vs. For such as section, high shear force (as per IS : 800-2007) is defined as :

(a) $V > 0.6\ V_S$ (b) $V > 0.7\ V_S$
(c) $V > 0.8\ V_S$ (d) $V > 0.9\ V_S$

AP TRANSCO AEE 2017
HPPSC Poly. Lect. 2016

Ans : (a) In IS : 800-2007 $V > 0.6\ V_S$
V = Applied shear force
V_s = Shear capacity of the steel
when a steel member is subjected to combined shear and bending no reduction in moment capacity of the section is necessary as long or the cross section is not subjected to high shear force. High shear force is define as $V > 0.6\ V_s$.

419. Lacing bars shall be inclined at an angle not less than ..... and not more than ..... to the axis of the built-up member.

(a) 70º, 40º respectively
(b) 40º, 70º respectively
(c) 45º, 45º respectively
(d) 30º, 40º respectively

HPPSC Poly. Lect. 2016

Ans : (b) Lacing bars shall be inclined at an angle of 40° to 70° to axis of built-up member.

420. Lacing bars and battens is a compound steel columns are designed to resist a transverse shear force of:

(a) 2.0% of the axial load
(b) 1.5% of the axial load
(c) 2.5% of the axial load
(d) 4.0% of the axial load

GPSC AE June 2019
JUVNL AE 2016

Ans. (c) : According to IS 700 : 2008.
Design of batten and lacing
Shear force on lacing and batten = 2.5% of axial load on column.

421. In a single lacing system, the thickness of the lacing bar may be taken as:

(a) 1/60th of the length between inner end rivets
(b) 1/5th of the length between inner end rivets
(c) 1/40th of the length between inner end rivets
(d) 1/30th of the length between inner end rivets

JUVNL AE 2016

Ans. (c) : For single lacing– $t = \frac{L}{40}$

For Double lacing– $t = \frac{L}{60}$

L = length between inner end rivets.

422. Batten shall be designed to carry bending moment and shear force arising from transverse shear force V which is .....% of total axis load on column

(a) 25 (b) 2.5
(c) .25 (d) 3

WBPSC AE 2014

Ans. (b) : As per IS 800 : 1984, battens shall be designed to carry the bending moment and shear arising from transverse shear force of 2.5% of the total axial force on the whole compression member.

423. A compression member tends to buckle in the direction of

(a) Axis of load
(b) Perpendicular to the axis of load
(c) Minimum cross section
(d) Least radius of gyration

WBPSC AE 2001

Ans. (d) : Minimum radius side has low bending stresses and hence the member tries to buckle towards the side which provider less resistance to it.

$\frac{l}{r} > 97$ (for long column)

So, least r required, the radius of gyration created.

424. For single lacing bars, the thickness of flat bracing bare shall not be less than

(a) 1/30 (length between inner end rivets or welds)

Search on Telegram @apna_pdf

(b) 1/40 (length between inner end rivets or welds)
(c) 1/50 (length between inner end rivets or welds)
(d) 1/60 (length between inner end rivets or welds)

WBPSC AE (PHE) 1998

Ans. (b) : Thickness of lacing (t) –

- for single lacing (t) $> \frac{1}{40}$ ×length b/w inner end rivet.
- for double lacing (t) $> \frac{1}{60}$ ×length b/w inner end rivet.

425. Maximum permitted slenderness ratio for a structural member carrying compressive load due to D.L. and L.L. is

(a) 180 (b) 250
(c) 300 (d) 350

WBPSC AE (PHE) 1998
WBPSC AE (Common) 1998

Ans. (a) :

Type of member	λ_{max}
a) A member carrying compressive loads resulting from dead load and imposed load.	**180**
b) A tension member in which a reversed of direct stress occurs due to loads other than wind or seismic force	**180**
c) Compression flange of a beam restrained against lateral torsional buckling	**300**
d) A member normally acting as a tie in a roof truss or a bracing system not considered effective when subjected to possible reversal of stresses resulting from the action of wind or earthquake forces.	**350**

426. A compression member is subjected to an axial force of 2000 kN. The lacings shall be designed to resist a transverse shear of

(a) 50 kN (b) 40 kN
(c) 30 kN (d) 20 kN

TSPSC AEE 2017

Ans. (a) : Lacing can be designed to resist a total transverse shear at any point in the member equal to 2.5% of axial force in member.

So, Axial force 2000 kN

Resist transverse shear force = 2.5% of axial force

$= 2.5\% \times 2000$

$= \frac{2.5}{100} \times 2000 = 50$ kN

427. As per IS 800 : 2007, under working stress design, the condition to be satisfied for members subjected to both axial tension and bending is : $\frac{f_t}{f_{at}} + \frac{f_{bty}}{f_{abty}} + \frac{f_{bt}}{f_{abt}}$ (where notations f_t and f_{at} : actual and permissible tensile stress : f_{bt} : actual bending stress ; f_{abt} : permissible tensile stress under bending only; y and z major and minor axis)

(a) Greater than 1.5
(b) Greater than 1
(c) Less than or equal to 1
(d) Greater than 1 and less than 1.5

CIL MT 2020

Ans. (c) : As per IS 800 : 2007

$$\frac{f_t}{f_{at}} + \frac{f_{bty}}{f_{abty}} + \frac{f_{bt}}{f_{abt}} \le 1$$

Where,
f_t & f_{at} = actual and permissible tensile stresses
f_{bt} = actual bending stresses
f_{abt}= permissible tensile stresses under bending only.

428. In an angle section of size ISA-150×100×6, the thickness in mm is

(a) 6
(b) 150
(c) 1/10th of any side which is higher
(d) 100

Rajasthan AE (Nagar Nigam) 2016

Ans. (a) : ISA-150×100×6
ISA –Indian standard angle section
150 – length of long leg
100 – length of short leg
6 – thickness of leg
150×100×6 is a unequal angle section.

429. The thickness "t" of a single flat lacing should not be less than

(a) $1/30^{th}$ length between inner end rivets
(b) $1/40^{th}$ length between inner end rivets
(c) $1/50^{th}$ length between inner end rivets
(d) $1/60^{th}$ length between inner end rivets

ISRO Scientist/Engineer 2015

Ans : (b) : Thickness of lacing (t) –

For single lacing $t > \frac{1}{40}$ of length between inner end rivet.

For double lacing $t > \frac{1}{60}$ of length between inner end rivet.

430. Battens in compound steel columns are mainly provided

(a) To ensure unified behaviour
(b) To increase the column capacity
(c) To decrease the buckling in members
(d) To prevent buckling

WBPSC AE 2003

Ans. (a) : Battens in compound steel columns are mainly provided to ensure unified behaviour.
Thick thickness of batten plate shall not be less than one fiftieth of the distance between the inner most connecting lines of rivets or welds.
This requirement eliminates lateral buckling of the batten.

Search on Telegram @apna_pdf

5. Steel Beams, Plate Girders

431. Considering the nature of loading on gantry girders, which type of loadings are gantry girders usually designed to resist?

(Chhattisgarh professional exam. board 2016)

OR

Gantry girders are designed to resist–

(UTTRAKHAND AE 2013)

OR

Which of the following loads are to be considered in designing a gantry girder ?

(i) Gantry load
(ii) Lateral loads
(iii) Longitudinal loads
(iv) Wind loads

Select the correct answer using the codes given below :

(a) (i) and (ii) (b) (i), (ii) and (iii)
(c) (i) and (iii) (d) (ii), (iii) and (ii)

UKPSC AE (Paper-I) 2007
ESE 2001

Ans : (b) In design of gantry girder we consider gantry load, lateral load and longitudinal loads.

432. The flange splice in plate girders be placed preferably near about :

(a) maximum shear location
(b) maximum moment location
(c) minimum moment location
(d) minimum shear location

UKPSC AE (Paper-I) 2007

Ans : (c) Flange splices are used to transfer tensile or compressive forces at joint. They should be placed at minimum moment location as they are designed for shear only.

433. In plate girders horizontal stiffeners are needed if the thickness of web is :

(a) less than 6mm
(b) less than $\frac{d}{200}$
(c) less than $\frac{L}{500}$
(d) nearly equal to flange thickness

Where d = distance between flanges
L = span of girder

UKPSC AE (Paper-I) 2007
(ESE 2007)

Ans : (b) Horizontal stiffeners are provided in plate girders if the ratio of D/t_w is greater than 200. They are provided at a distance of $\frac{2}{5}d$. Vertical stiffeners are provided at distance between 0.33 to 1.5d.

434. If 'M' is maximum moment in the plate girder, 'P' is allowable bending stress and 't_w, is the thickness of web, Economical depth for a plate girder is given by–

(a) $\frac{\sqrt{M/P}}{t_w}$ (b) $\frac{1.2\sqrt{M/P}}{t_w}$
(c) $1.1\sqrt{\frac{M}{P.t_w}}$ (d) $\frac{1.3\sqrt{M/P}}{t_w}$

(Uttrakhand AE 2013)

Ans : (c) Depth for a plate girder = $1.1\sqrt{\frac{M}{P.t_w}}$

Depth of the plate girder are generally taken 1/10 to 1/5 of the span. Normally we take 1/12 of span.

435. In an I-section, shear force is shared

(a) Mostly by web
(b) Mostly by flanges
(c) Uniformly by entire section
(d) Proportional to the respective areas of web and flanges

MPPSC AE 2014

Ans. (a) : In I section, shear force is shared mostly by web.

436. What is provided to make connections at place where more than one member is to be joined?

(a) Splices (b) Lug angle
(c) Gusset plate (d) Battens

Rajasthan Nagar Nigam AE Shift-2, 2016

Ans. (c) : A gusset plate is plate provided at ends of tension members through which forces are transferred to main member.
Gusset plates are used to join more than one member at a joint.

437. Which of the following statement is correct for reducing web buckling due to diagonal compression?

(a) Not proving web stiffners to increase shear strength
(b) Providing web stiffner to reduce shear strength
(c) Increasing depth to thickness ratio
(d) Reducing depth to thickness ratio

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (d) : For reducing web buckling due to diagonal compression reducing depth to thickness ratio.

438. For members subjected to bending, the stiffener provided to provide local reinforced to a web under shear and bearing is called as

(a) Intermediate transverse web stiffener
(b) Load carrying stiffener
(c) Bearing stiffener
(d) Torsion stiffener
(e) Diagonal stiffener

CGPSC AE 2014 Shift–I

Ans. (e) : As per IS 800- 2007, (Cl .7.1.1)
Diagonal stiffener : To provide local reinforcement to a web under shear and bearing.

439. In a plate girder, the web plate is connected to the flange plates by fillet welding. The size of the fillet welds is designed to safely resist

(a) The bending stresses in the flange
(b) The vertical shear force at the section


Search on Telegram @apna_pdf

(c) The horizontal shear force between the flanges and the web plate
(d) The forces causing buckling in the web

ESE 2012, 2017

Ans. (c)

- Fillet weld is good in resisting shear and hence it resists horizontal shear force between the flanges and the web plate.



A continuous or intermittent fillet weld is provided between flange plate and web plate of a plate girder as they are meeting in two different planes and they are to be designed for shear stresses.

440. In the case of heavily loaded girders where large, curved cables have to pass through the webs, a minimum thickness of _____ is mandatory to accommodate the cables with adequate cover.

(a) 40 mm to 60 mm (b) 200 mm
(c) 200 mm to 250 mm (d) 120mm to 150mm

TNPSC AE 2019

Ans. (d) Minimum thickness of 120 to 150 mm is mandatory to accommodate the cables with a adequate cover

441. In a beam of I section, the maximum shear force is carried by

(a) the upper flange (b) the web
(c) the lower flange (d) Any of these

APPSC (PHE) AE Paper-2 2012

Ans. (b) : In a beam of I-section, the maximum shear force is carried by the web.
In a I-section of a beam subjected to transverse shear force the maximum shear stress is developed at the centre of the web.

442. Web crippling generally occurs at the point where

(a) Concentrated load act
(b) Shearing force is minimum
(c) Bending moment is maximum
(d) Deflection is maximum

ISRO Scientist/Engineer 2015

Ans : (a) : Web crippling generally occurs at the point where concentrated load act.
Web crippling occurs due to bending stress.

443. According to IS 800 : 2007, allowable vertical deflection for gantry girder with crane load (electronically operated up to 50 tons) is-

(a) $\frac{\text{span}}{500}$ (b) $\frac{\text{span}}{750}$
(c) $\frac{\text{span}}{1000}$ (d) $\frac{\text{span}}{300}$

Maharashtra PSC (Mains) 2017 Paper–I
APPSC Poly. Tech. Lect. 2020

Ans. (b) : For an electrically-operated cranes upto 50 ton capacity, the maximum permissible deflection is given by Span/750.

Deflection limit on gantry girder-


category	maximum deflection
Manually operated crane	Span/500
Electrically operated crane upto 500kN capacity	Span/750
Electrically operated crane more than 500 kN capacity	Span/1000

444. An ISMB 300 has section modulus value of 600×10^3 mm^3, Plates of dimensions 200×10mm are welded over an each flange of width 320mm. What is section modulus of the plated section?

(a) $462\times10^3\,mm^3$ (b) $550\times10^3\,mm^3$
(c) $710\times10^3\,mm^3$ (d) $1220\times10^3\,mm^3$

APPSC Poly. Tech. Lect. 2020

Ans. (d) :



Section modulus due to plates about

$$x\text{-}x = \frac{I}{y}$$

$$I = 2\times\left(\frac{200\times10^3}{12} + 200\times10\times165^2\right)$$

$$= 108933333.3$$

$$y = 170$$

$$z_{plates} = \frac{I}{y} = \frac{108933333.3}{170}$$

$$= 640.782\times10^3\ mm^3$$

section modulus of built-up section = $Z_{plates} + Z_I$

$$= (640.78+600)\,10^3\ mm^3$$

$$= 1240.78\times10^3\,mm^3$$

445. Stiffeners are used in a plate girder

(a) to avoid buckling of web plate
(b) to reduce the compressive stress
(c) to reduce the shear stress
(d) to take the bearing stress

TNPSC AE 2019
ISRO Scientist/Engineer 2015
RRB SSE Bilaspur : 21.12.2014

Ans. (a) Stiffeners provide horizontal and vertical stiffness to avoid buckling of web in plate girder.

Search on Telegram @apna_pdf

446. For interior stiffeners, the effective width of web acting together with the stiffener in each side of the centre line of stiffener is taken as
(a) 10 times the web thickness
(b) 15 times the web thickness
(c) 20 times the web thickness
(d) 25 times the web thickness

TNPSC AE 2019

Ans. (b) For interior stiffeners to avoid buckling of web, the effective width of web acting together with the stiffener in each side of centre line is taken 15 times the web thickness.

447. The most efficient steel section for a beam is
(a) Channel section
(b) Rectangular section
(c) Angle section
(d) I section

TNPSC AE 2019
UPPCL AE 2015

Ans. (d) I-section is more efficient as it has larger section modulus i.e., $z = \frac{I}{y}$ is greater than others.

448. Gantry girders are designed to resist
(a) lateral loads
(b) longitudinal loads and vertical loads
(c) lateral, longitudinal and vertical loads
(d) lateral and longitudinal loads

Gujarat PSC AE 2017
MPPSC AE 2014
ESE 2013
RPSC ACF 2011

Ans : (c) Gantry girders are designed to resist lateral, longitudinal and vertical loads.
– Gantry girders are laterally unsupported beams to carry heavy loads from place to place at the construction site, mostly these are of steel material.

449. Economical depth of plate girder corresponds to
(a) minimum weight
(b) minimum depth
(c) maximum weight
(d) minimum thickness of web

Gujarat PSC AE 2017
UPPCL AE 2015

Ans : (a) Economical depth of plate girder corresponds to minimum weight.

450. In a plate girder, the web plate is connected to the flange plates by fillet welding. The size of the fillet welds is designed to safely resist :
(a) bending stresses in the flanges
(b) vertical shear force at the section
(c) horizontal shear force between the flanges and the web plate
(d) forces causing buckling in the web
(e) warping in the flange plates

CGPSC AE 2014 Shift–I

Ans. (c) : The weld connecting flange plate with the web plate is designed to take up horizontal shear at that level.

451. Intermediate vertical stiffeners are required in plate girder when d/t_w ratio of the web exceeds
(a) 85 (b) 80
(c) 90 (d) 75

Maharashtra PSC AE (Mains) 2012 Paper–I
UKPSC(Urban engineering)-2011

Ans : (a) Intermediate vertical stiffeners are required in plate girder when d/t_w ratio of the web exceeds 85.

452. In plate girder, flanges are designed to resist
(a) Shear force
(b) Bending moment
(c) Axial force
(d) Torsional moment

GPSC Poly. Tech. Lect. 2016
Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (b) In plate girder, flanges are designed to resist bending moment.

453. The flange splice in plate girder should be selected at
(a) maximum shear location
(b) minimum shear location
(c) maximum moment location
(d) minimum moment location

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (d) The flange splice in plate girder should be selected at minimum moment location.

454. In case of statically indeterminate beam, what is the limiting value of redistribution of moments(%) as per IS 456, while using limit state method?
(a) 10 (b) 30
(c) 40 (d) 20

CIL MT 2017

Ans. (b) : In case of statically indeterminate beam, 30 is the limiting value of redistribution of moments(%) as per IS 456, while using limit state method.

455. Cable, as a structural element, resists load by :
(a) bending (b) torsion
(c) tension (d) compression

CIL MT 2017

Ans. (c) : Cable, as a structural element, resists load by tension.

456. In a plate girder bridge, the thickness of web is less than d/200 where d is the unsupported depth of web. The web plate should be provided with–
(a) Vertical stiffeners
(b) Horizontal stiffeners
(c) End stiffeners
(d) Both vertical and horizontal stiffeners

Gujarat PSC AE (N.W.R.) 2020
ESE 2001

Ans. (d) : In a plate girder bridge the thickness of web is less than d/200 where d is the unsupported depth of web, the plate should be provided with both vertical and horizontal stiffeners.

457. The allowable shear stress in stiffened webs of mild steel beams decreases with-
(a) Decrease in spacing of the stiffeners
(b) Increase in spacing of the stiffeners

Search on Telegram @apna_pdf

(c) Decreases in the effective depth
(d) Increase in the effective depth

Gujarat PSC AE (N.W.R.) 2020
ESE 1997

Ans. (b) : The allowable shear stress in stiffened, webs of mild steel beams decreases with increase in spacing of the stiffeners.

458. As per IS:800-2007, what is the permissible bearing pressure between the base plate and the support below?
(a) 0.40 f_{ck} (b) 0.45 f_{ck}
(c) 0.50 f_{ck} (d) 0.60 f_{ck}

Gujarat PSC AE (N.W.R.) 2020

Ans. (d) : As per IS:800-2007, $0.6f_{ck}$ is the permissible bearing pressure between the base plate and the support below.

459. In a steel girder, where would you expect tongue plates to be provided?
(a) The upper flange
(b) The lower flange
(c) The upper and lower ends of the web
(d) None of the above

GESCOM (KARNATAKA) AE 2011

Ans : (c) In a steel girder, where would you expect tongue plates to be provided at the upper and lower ends of the web.

460. In construction terminology, what does RSA stand for?
(a) Rolled Steel Angle
(b) Right Steel Angle
(c) Rolled Strong Angle
(d) Right Skewed Angle

GESCOM (KARNATAKA) AE 2011

Ans : (a) : RSA stands for Rolled Steel Angle.

461. A beam consisting of two or more materials rigidly connected to each other preventing any slip between them during bending is called :
(a) non composite beam (b) non uniform beam
(c) flitched beam (d) timber beam

Rajasthan AE (Nagar Nigam) 2016


Ans. (c) : A beam consisting of two or more materials rigidly connected to each other preventing any slip between them during bending is called flitched beam .
A flitch beam is a compound beam used in the construction of houses, decks and other primarily wood frame structure.

462. The forces acting on the web splice of a plate girder are :
(a) Axial forces
(b) Shear & axial forces
(c) Axial and bending forces
(d) Shear and bending forces

Nagaland PSC CTSE 2017 Paper–I
TSGENCO_2015

Ans. (d) : The forces Acting on web splices of a plate girder are shear and Bending forces.

463. What is the failure of a section in the given figure ?




(i) Web buckling
(ii) Web crippling
(iii) Web crimpling
(iv) Column buckling

Select the correct answer using the codes given below :
(a) (i) and (ii) (b) (ii) and (iii)
(c) (i) and (iv) (d) (ii) and (iv)

Nagaland PSC CTSE 2017 Paper–I

Ans. (b) :



→ The failure of web in direct Crushing under concentrated load is known as web crippling or web crimpling.

464. Out of the available rolled steel sections the more commonly used section as beam is :
(a) T-section (b) L-section
(c) I-section (d) channel section

Nagaland PSC CTSE 2017 Paper–I

Ans. (c) : For Beam best option is I section. I section is very efficient form for carrying both bending and shear loads in the plane of web.

465. The allowable shear stress in the web of mild steel beams decreases with :
(a) Decreases in h/t ratio
(b) Decrease in thickness
(c) Increase in height
(d) Increase in h/t ratio

Nagaland PSC CTSE 2017 Paper–I

Ans. (d) : According to IS 800–1984 the permissible Average shear stress in a beam whose web thickness is more than $\frac{h}{85}$ is 0.40 f_y
Allowable shear stress in Beam with stiffness is given by
(1) when the distance between the vertical stiffeners is less than h

$$\tau_{va} = 0.4\left[1.3 - \frac{\sqrt{f_y}\,\frac{c}{t_w}}{4000\left(1+\frac{1}{2}\left(\frac{c}{b}\right)^2\right)}\right]$$

(2) Where distance b/w the vertical stiffener is more than h

Search on Telegram @apna_pdf

$$\tau_{va} = 0.4 f_y \left[1.3 - \frac{\sqrt{f_y}\frac{h}{t_w}}{4000\left(1+\frac{1}{2}\left(\frac{b}{c}\right)^2\right)} \right]$$

Hence τ_{va} decreases with increase in $\left(\frac{b}{t_w}\right)$ ratio.

466. As per IS 800-1971, for rolled I-beams and channels the allowable stress in axial tension is:

(a) 1400 kg/cm^2 (b) 1000 kg/cm^2
(c) 1500 kg/cm^2 (d) 1200 kg/cm^2

Nagaland PSC CTSE 2017 Paper–I

Ans. (c) : As per IS 800–1971,
For Rolled I–Beam & channel section permissible stress in
Axial tension = 1500 kg/cm^2

467. Generally in bridges, rivets used are of the diameter ranging in between

(a) 12 to 16 mm (b) 16 to 22 mm
(c) 22 to 25 mm (d) 25 to 40 mm

Nagaland PSC CTSE 2017 Paper–I

Ans. (c) : Generally in bridges, rivets used are of the diameter ranging in between 22–25 mm


468. If 'I_b' is moment of inertia of the rolled beam section, 'A_p' is the area of cover plates in one flange and 'h' is the distance between the centroid of the top and bottom flange plates, moment of inertia of built-up plate girder is given by–

(a) $I = \left[I_b + 2A_p \left(\frac{h}{2}\right)^2 \right]$ (b) $I = \left[I_b + 2A_p \left(\frac{h}{2}\right)^3 \right]$

(c) $I = \left[I_b + 2A_p \left(\frac{h}{2}\right) \right]$ (d) $I = \left[I_b + 3A_p \left(\frac{h}{2}\right)^2 \right]$

(UTTRAKHAND AE 2013)

Ans : (a) Cover plate area = A_p; $I_b \rightarrow$ MOI of built up column



$$I_{xx} = I_b + 2 \times A_p \times \left(\frac{h}{2}\right)^2$$

469. The heaviest I-section for same depth is

(a) ISMB (b) ISLB
(c) ISHB (d) ISWB

Nagaland PSC CTSE 2017 Paper–I
(UTTRAKHAND AE 2013)
RPSC A En. 2013

Ans : (c) Rolled steel sections of type I are classified as follows:–
(i) ISJB – Indian Standard Junior Beam
(ii) ISLB – Indian Standard Light Beam
(iii) ISMB – Indian Standard Medium Beam
(iv) ISWB – Indian Standard Wide Beam
(v) ISHB – Indian Standard Heavy Beam

470. Where the imposed load is variable and exceeds three-quarters of the dead load, arrangements of live load acting on the floor under consideration shall not include which of the following case?

(a) Imposed load on all spans
(b) Imposed load on two adjacent spans
(c) Imposed load on alternate spans
(d) Imposed load on spans under consideration

Ans : (a) When imposed load is variable and exceeds three quarters of the dead load, arrangement of the live loads acting on the floor shall not include imposed load on all the spans.

471. The maximum width of a covered steel building section should preferably be restricted to X m beyond which suitable provisions for the expansion joint may be made, where is :

(a) 50 (b) 90
(c) 150 (d) 200

(UP RVNL AE 2016)

Ans : (c) The maximum width of a covered steel building section is limited to 150 m, beyond this suitable provisions for the expansion joints must be made.

472. In general the depth of Plate girder is kept as _____ of span

(a) 1/5 to 1/8 (b) 1/8 to 1/10
(c) 1/10 to 1/12 (d) 1/12 to 1/16

(UKPSC AE Paper I 2007)

Ans : (c) In general the depth of plate girder is kept between $\frac{1}{10}$ to $\frac{1}{12}$ of span length

depth, $d = 1.1\sqrt{\frac{M}{\sigma_b . t_w}}$

t_w = thickness of web plate
σ_b = effective stress

473. In plate girders, the web plate is provided with stiffeners when the ratio of clear depth to thickness of web greater than–

(a) 35 (b) 50
(c) 60 (d) 85

(UTTRAKHAND AE 2013)

Ans : (d) Thickness of web plate in plate girder depends upon bending moment and bending moment depend upon shear stress. When ratio of clear depth to thickness is less than 85, then it is known as rigid girder. At this ratio stiffeners are not required. Minimum thickness of web plate should be 6 mm.

Search on Telegram @apna_pdf

474. While designing electricity operated Gantry girders, additional load of.....of maximum static wheel load should be used to calculate the vertical load transferred to rails.

(a) 25% addition (b) 10% addition
(c) 5% reduction (d) 10% reduction

UKPSC AE 2012 Paper–I

Ans : (a) While designing electrically operated gantry girder, additional load of 25% is added to maximum static wheel load.

475. Steel beam should be designed for

(a) flexural strength (b) stiffness
(c) buckling (d) All the above

(UKPSC AE 2012 Paper–I)

Ans : (d) Steel beams are designed for flexural strength, stiffness and buckling.

476. In beams according to IS : 800 – 1984 permissible average shear stress is calculated by the formula :

(a) $\tau_{va} = 0.40\ f_y$ (b) $\tau_{va} = 0.45\ f_y$
(c) $\tau_{va} = 0.35\ f_y$ (d) $\tau_{va} = 0.3\ f_y$

UKPSC AE (Paper-I) 2007

Ans : (a) IS : 800 – 1984, according to it permissible average shear stress is limited to 0.4 f_y

$$\tau_{av} \not> 0.4 f_y \not> 100\ N/mm^2$$

shear stress $(\tau_v) \not> \dfrac{V}{D \times t_w} = 112.5\ N/mm^2$

477. Bearing stiffener in a plate girder is used to

(a) Transfer the load from the top flange to the bottom one
(b) Prevent buckling of web
(c) Decrease the effective depth of web
(d) prevent excessive deflection

RPSC A En. 2013

Ans (a) Bearing stiffeners are used to transfer concentrated loads on the girder and heavy reactions at supports to the face full of the web.

478. The average shear stress in a member calculated on the cross section of unstiffened web shall not exceed

(a) $0.45 f_y$ (b) $0.40\ f_y$
(c) $0.65\ f_y$ (d) $0.60\ f_y$

RPSC ACF 2011

Ans : (b) Maximum stress in steel is as follows–
(i) Axial tension – $0.60\ f_y$
(ii) Bending stress – $0.66\ f_y$
(iii) Bearing stress – $0.75\ f_y$
(iv) Shear stress,
(a) Maximum – $0.45\ f_y$
(b) Average – 0.40 fy

479. The yield stress of mild steel of normally rolled structural steel is about (in N/mm^2)

(a) 240 to 260 (b) 330 to 360
(c) 420 (d) 550

RPSC ACF 2011

Ans : (a) In steel, percentage of carbon is in between 0.15% to 0.30%. Mild steel is rolled in parts due to its ductile nature. The yield strength of mild steel of normally rolled structural steel is about 240 to 260 N/mm^2.

480. Intermediate vertical stiffeners are provided in plate girders to

(a) eliminate the web bucking
(b) eliminate the local bucking
(c) transfer the vertical loads
(d) prevent the excessive deflection

(JPSC Combined AE Paper V 2013)
[UPPSC State Eng. A.E. 2007(II)]
[UPPSC State Eng. A.E. 2008]
[UPPSC AE 12.04.2016 Paper–I]
ESE 1995

Ans : (a) The element provided to stiffen the web against buckling are called intermediate stiffeners. Intermediate stiffeners are of two types.
(a) Vertical stiffeners : Vertical stiffener is mainly supposed to resist shear buckling but little as bending buckling.
(b) Horizontal stiffeners : Horizontal stiffeners primarily safeguard against buckling due to bending compression.

481. Limiting deflection for steel becomes supporting floor and false ceiling should be

(a) span/600 (b) span/500
(c) span/325 (d) span/200

BPSC AE 2012 Paper–V
ESE 2007

Ans : (c) Limiting deflection for false ceiling and supporting floor should be $\dfrac{span}{325}$ or less.


In reinforced concrete structures, it is limited to $\dfrac{span}{250}$ for working stress and $\dfrac{span}{360}$ for limit state method.

482. The junction between flange and web of an I-section is called :

(a) Lap joint (b) Butt joint
(c) Fillet joint (d) Shear joint

[UPPSC State Eng. A.E. 2008]
[UPPSC AE 12.04.2016 Paper–I]

Ans : (d) Shear joint – The junction between flange and web of an I - section is called shear joint.
Butt joint – A butt joint is a technique in which two pieces of material are joined by simply placing their ends together without any special shaping.
Fillet welding– refers to the process of jointing two pieces of metal together when they are perpendicular or at an angle.
A lap joint – A lap joint or overlap joint is a joint in which the members overlap. Lap joints can be used to join wood, plastic or metal.



Search on Telegram @apna_pdf

483. In case of I-section steel beam:

(a) Shear capacity of flange is neglected.
(b) Shear capacity of web is neglected.
(c) Shear capacity of both flange and web is neglected.
(d) None of the above.

[UPPSC State Eng. A.E. 2008]
[UPPSC AE 12.04.2016 Paper–I]

Ans : (a) In case of I-section steel beam shear capacity of flange is neglected.

484. As per the Indian Standard (IS) 800:2007, with respect to serviceability and when transverse stiffeners are not provided, the $\frac{d}{t_w}$ ratio of the web should be less than or equal to (depth of web = d; thickness of web = t_w; and yield stress ratio of web = ε_w)

(a) $400\ \varepsilon_w$ (b) $250\ \varepsilon_w$
(c) $200\ \varepsilon_w$ (d) $150\ \varepsilon_w$

[MPPSC AE 2016]

Ans : (c) According to IS Code 800:2007, the $\frac{d}{t_w}$ ratio should be less than or equal to $200\ \varepsilon_w$ when transverse stiffeners are not provided.

485. Horizontal web stiffener are used in plate girders, if depth to thickness of web ratio is more than

(a) 100 (b) 180
(c) 200 (d) 300

[UPPSC State Eng. A.E. 2011]

Ans : (c) If $\frac{d_1}{t_w} > 200$, Horizontal stiffeners are provided above neutral axis at a distance of $0.2\ t_w$ from the compression flange. They prevent buckling of web due to bending compressive stress.

486. The ratio of elastic modulus to plastic modulus for a rectangular section of steel is

(a) 1.5 (b) 0.66
(c) 1.70 (d) 0.25

[UPPSC State Eng. A.E. 2003]
[UPPSC State Eng. A.E. 2007(I)]

Ans : (b) **The ratio of elastic modulus to plastic modulus for rectangular section of steel is 0.66**

$$\frac{M_y}{M_p} = R = \frac{1}{\left(M_p / M_y\right)}$$

since $\frac{M_p}{M_y}$ = shape factor for rectangular section is 1.5

$$R = \frac{1}{3/2} = 0.66$$

487. In a plate girder design, the web contribution to the compression flange area is

[UPPSC State Eng. A.E. 2007(I)]
ESE 2002

Or

The effective flange area in tension of a plate girder is equal to

(a) A_W (b) $\frac{A_W}{8}$
(c) $\frac{A_W}{6}$ (d) $\frac{A_W}{50}$

A_w = area of web plate

ESE 2004

Ans : (c) In plate girder design, the web contribution to the compression flange area is $\frac{A_W}{6}$.

effective flange area $= A_f + \frac{A_w}{6}$

A_f = Area of flange plate , A_w = web area

$\frac{A_W}{6}$ = web contribution to compression flange area.

488. Horizontal stiffeners in the plate girders are used to

(a) Increase the bending strength of the web
(b) Increase the shear capacity of the web
(c) Prevent local buckling of flange
(d) Prevent local buckling of web

[UPPSC State Eng. A.E. 2007]

Ans : (d) Horizontal stiffeners in the plate girders are used to increase buckling strength of web.

489. As per IS : 800 the maximum deflection in a beam should not exceed

(a) $\frac{L}{180}$ (b) $\frac{L}{250}$
(c) $\frac{L}{325}$ (d) $\frac{L}{360}$

Where, L = Length of span

[UPPSC State Eng. A.E. 2004 (I)]
MPPSC AE 2014

Ans : (c) **As per IS : 800 the maximum permissible deflection in Working Stress Method (WSM) is** $\frac{\text{span}}{325}$.

490. For an I-beam, shape factor is 1.12. The factor of safety in bending is 1.5. If the allowable stress is increased by 20% for wind and earthquake load, then the load factor is

(a) 1.10 (b) 1.25
(c) 1.35 (d) 1.40

[UPPSC State Eng. A.E. 2003]

Ans : (d)

$$\text{Factor of safety} = \frac{\text{Yield stress}}{\text{Allowable stress}}$$

With increase in allowable stress, the factor of safety will reduce to $= \frac{1.5}{1.2} = 1.25$

$\therefore$ Load factor = fos × shape factor
$= 1.25 \times 1.12 = 1.40$


Search on Telegram @apna_pdf

491. A simply supported beam of span L supports a connection load W at its midspan. If the cross-section of the beam is an I-Section, then the length of elastic-plastic zone of the plastic hinge will be

(a) L/8 (b) L/4
(c) L/2 (d) 3L/4

[UPPSC State Eng. A.E. 2003]
ESE 1995

Ans : (a) For I-section shape factor = $\frac{M_p}{M_y} = 1.1$ to 1.2



From the bending moment diagram

$$\frac{\frac{WL}{4}}{\frac{L}{2}} = \frac{M_y}{\frac{L}{2} - \frac{\ell}{2}}$$

$$\frac{W}{2}\left[\frac{L}{2} - \frac{\ell}{2}\right] = M_y$$

taking $M_p = \frac{WL}{4}$ and $M_y = \frac{M_p}{1.1}$

$$\ell = 0.09L = \frac{L}{11}$$

taking $M_y = \frac{M_p}{1.2}$

$$\ell = \frac{L}{6}$$

So ℓ varies between $\frac{L}{6}$ to $\frac{L}{11}$

Therefore $\frac{L}{8}$ is suitable choice.

492. A ductile structure is defined as one for which the plastic deformation before fracture

(a) is smaller than the elastic deformation
(b) vanishes
(c) is equal to the elastic deformation
(d) is much larger than the elastic deformation

[UPPSC State Eng. A.E. 2003]

Ans : (d) Ductile failure when we apply a tensile force on a body made up of the malleable material, the material shows a plastic deformation (necking) which is called ductile failure. Ductile materials can sustain very large deformation nearly about 50-100% or more strain before the fracture.

493. As per Indian Standards rolled steel I-sections are classified into

(a) four series (b) five series
(c) six series (d) seven series

[UPPSC State Eng. A.E. 2003, 2011]

Ans : (b) As per Indian standards rolled steel I-section are classified into five series.
(i) ISWB - Indian standard wide flange beam has high moment of inertia about y-axis as compared to other beam sections.
(ii) ISLB - Indian standard light beams are generally used as purlins in roof or as secondary beams where loading is less.
(iii) ISMB - Indian standard medium weight in frames, floor beams etc with high moment of inertia about x-axis.
(iv) ISJB - Indian standard Junior beam.
(v) ISCS - Indian standard column section

494. Web crippling generally occurs at the point, where-

(a) deflection is maximum
(b) shearing stress is maximum
(c) bending stress is maximum
(d) concentrated load act

(BPSC AE 2012 Paper–V)


Ans : (d) Web crippling generally occurs at the point, where concentrated load act. To keep bearing stress within permissible limits, the concentrated loads should be transferred from flanges to the web on sufficiently large bearing areas.

495. Lateral stability of steel beam increases

(a) axial compressive stress in beam
(b) shear stress in beam
(c) bending tensile stress in beam
(d) bending compressive stress in beam

(BPSC AE 2012 Paper–V)

Ans : (d) Lateral stability of steel beam increase bending compressive strength in beam. To provide lateral stability compression flange is embedded in concrete as shown in figure.



496. In ISMB– 400, 400 represents the.....of the section.

(a) flange width (b) depth
(c) weight (d) none of these

(BPSC AE Paper V 2001)

Ans : (b) A rolled section is designated by its depth and weight. For example ISMB – 400 @ 250 means, depth of member is 400 mm and its weight is 250 N per metre.

497. The minimum thickness of web in plate girder is....mm.

(a) 6 mm (b) 8 mm
(c) 10 mm (d) 12 mm

(BPSC AE Paper V 2001)

Ans : (a) Minimum thickness of web in plate girder is taken 6 mm. If it is not in direct contact of atmosphere and can be painted. If member is in contact with atmosphere and cannot be painted after assembling then minimum thickness is 8 mm.

Search on Telegram @apna_pdf

498. In I-section usually flanges resist

(a) tension (b) compression
(c) shear (d) bending moment

(BPSC AE Paper V 2001)

Ans : (d) In I-section flange resist bending moment and web resist shear.

499. When the effect of the wind or earthquake load is taken into account, the permissible stresses specified for Rivets, bolts and tension rods may be exceeded by

(a) $33\frac{1}{3}\%$ Percent (b) 25 percent
(c) 15 percent (d) 1.5 times normal value

(BPSC AE Paper V 2006)


Ans : (b) When effect of wind and earthquake is taken in consideration for design of rivet, bolts and tension rods, then permissible stress is increased by 25%.

500. Spacing of the vertical stiffener in plate girder shall be

(a) Not greater than d nor less than 0.25d
(b) Not greater than 2d nor less than 0.25d
(c) Not greater than 1.5d nor less than 0.33d
(d) Not greater than 1.2d nor less than 0.33d

(BPSC AE Paper V 2006)

Ans : (c) When ratio of depth (d) to thickness (t_w) is greater than 85, then vertical stiffeners are used.
Spacing of stiffener is between 0.33d to 1.5d.
Where, d is depth of web plate.




501. In case of laterally unrestrained beams-

(a) the compression flange deflects laterally/
(b) the tension flange deflects laterally/
(c) the web deflects laterally
(d) None of the above

(JPSC Combined AE Paper V 2013)

Ans : (a) In case of laterally unrestrained beam the compression flange deflects laterally. To provide lateral stability compression flange is embedded in concrete.



502. The maximum permissible bearing stress in any part of the beam when calculated on the net area of contact shall not exceed

(a) 0.50 f_y (b) 0.85 f_y
(c) 0.75 f_y (d) 0.25 f_y

When, f_y= yield stress of steel.

(BPSC AE Paper V 2006)

Ans : (c) Maximum permissible bearing stress in any part of beam should not exceed 0.75 f_y. Bending stress should not exceed 0.66 f_y, and axial tension should not exceed 0.60 f_y.

503. In the design of a plate girder, the outstand of web stiffener from the face of the web is restricted to (thickness of stiffener = t_q, and yield stress ratio = ε)

(a) 12 $t_q\varepsilon$ (b) 14 $t_q\varepsilon$
(c) 16 $t_q\varepsilon$ (d) 20 $t_q\varepsilon$


MPPSC AE 2017

Ans. (d) : Thickness of stiffeners is kept such that the outstand from the face of the web is not more than $20t_q\varepsilon$,

where t_q is the thickness of stiffener and $\varepsilon = \sqrt{\frac{250}{f_y}}$.

When the outstand is between $14t_q\varepsilon$ and $20t_q\varepsilon$, the stiffener design is on the basis of a core section with an outstand of $14t_q\varepsilon$.

504. For plate girder shown in figure below by using what action is Panel A designed?



(a) Simple post critical action
(b) Tension field action
(c) Bearing force action
(d) None of the above

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (b) :
⇒ If end and intermediate transverse stiffeners are provided, then tension field method of finding shear buckling strength of web may be used.
⇒ It accounts for post buckling strength provided by the stiffeners.

505. The maximum permissible vertical deflection of a simply supported beam in non industrial buildings if the element is susceptible for cracking is-

(a) $\frac{\text{span}}{360}$ (b) $\frac{\text{span}}{350}$
(c) $\frac{\text{span}}{325}$ (d) $\frac{\text{span}}{300}$

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (a) : Deflection limits are given in table no. 6 of IS 800 : 2007.
Simply supported beam non industrial building maximum vertical deflection is L/360.

506. The partial safety factors for dead load and leading live load in calculation of vertical deflection in a steel beam are-

(a) 1.0 and 1.0 (b) 1.0 and 1.2
(c) 1.2 and 1.0 (d) 1.2 and 1.2

Maharashtra PSC (Mains) 2015 Paper–I

Search on Telegram @apna_pdf

Ans. (a) :

⇒ Vertical deflection comes under limit state of serviceability criteria.

⇒ For serviceability criteria, partial safety factors for dead and live loads are 1 and 1 respectively. Whereas for limit state of strength criteria, they are 1.5 and 1.5 respectively.

507. The design bending strength of a laterally supported beam is given by $M_d = (\beta_b.Z_p.f_y)/\gamma_{m0}$, meaning. β_b for plastic and compact sections are given by-

(a) 1.0, 0.8 (b) 0.8, 1.0

(c) 1, Z_e/Z_p (d) 1, 1

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (d) : According to IS code 800 : 2007 value of β_b plastic and compact sections is 1 for semi-compact it is $\frac{Z_e}{Z_p}$.

508. The optimum thickness of web, t_w, of a plate girder is given by-

(a) $t_W = \left(\frac{M_Z}{f_y.k^2}\right)^{0.33}$ (b) $t_W = \left(\frac{f_y.k^2}{M_Z}\right)^{0.33}$

(c) $t_W = \left(\frac{M_Z}{f_y.k^2}\right)$ (d) $t_W = \left(\frac{f_y.k^2}{M_Z}\right)$

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (a) : $M = \frac{f_y b_f t_f}{\gamma_{m0}}$

assuming M is carried out by flanges only

$$b_f t_f = \frac{M\gamma_{m0}}{f_y d}$$

$$\gamma_{m0} = 1.1$$

$$A = 2b_f t_f + dt_W = \frac{2M\gamma_0}{f_y d} + dt_W$$

Take, $\frac{d}{t_W} = K$

$$A = \frac{2M\gamma_{m0}}{f_y d} + \frac{1}{K}d^2$$

For minimum value of A, $\frac{dA}{dd} = 0$

$$0 = -\frac{2M\gamma_{m0}}{f_y d^2} + \frac{2}{K}d$$

$$d^3 = \frac{MK\gamma_{m0}}{f_y}$$

$$d = 3\sqrt{\frac{MK\gamma_{m0}}{f_y}} = kt_W$$

$$t_W = \left(\frac{M}{f_y K^2}\right)^{0.33}$$

509. The deep structural members subjected to transverse loads are called-

(a) Beam (b) Columns

(c) Plate girders (d) Trusses

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (c) Plate girders are deep structural members, subjected to transverse load.

510. The minimum thickness of a base plate, t_s in case of slab base can be calculated by the formula-

(a) $t_s = \sqrt{2.5W\left(b^2 - 0.3a^2\right)f_y/\gamma_{m0}}$

(b) $t_s = \sqrt{2.5W\left(b^2 - 0.3a^2\right)\gamma_{m0}/f_y}$

(c) $t_s = \sqrt{2.5W\left(a^2 - 0.3b^2\right)\gamma_{m0}/f_y}$

(d) $t_s = \sqrt{2.5W\left(a^2 - 0.3b^2\right)f_y/\gamma_{m0}}$

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (c) :

Moment at section (1) - (1)

$Z_l = \frac{1\times t^2}{6}, M_{11} = \frac{wa^2}{2}$ For 1 mm width

$$M_{22} = \frac{Wb^2}{2}$$

Design, $BM = M_{11} - \mu M_{22} < \frac{1.2Z_l f_y}{\gamma_{mo}}$

$$\frac{M_{11}}{Z_l} - \mu\frac{M_{22}}{Z_l} \le \frac{1.2f_y}{\gamma_{mo}}$$

$$f_{11} - \mu f_{22} \le \frac{1.2f_y}{\gamma_{mo}}$$

$$\frac{w}{2Zl}\left(a^2 - \mu b^2\right) < \frac{1.2f_y}{\gamma_{mo}}$$

$$\frac{w\left(a^2 - \mu b^2\right)}{2\times 1\times\frac{t^2}{6}} \le \frac{1.2fy}{\gamma_{m0}}$$

$$\frac{w\left(a^2 - \mu b^2\right)}{2\times 1\times\frac{t^2}{6}} \le \frac{1.2fy}{\gamma_{m0}}$$

$$\frac{w\left(a^2 - 0.3b^2\right)6}{2\times t^2} < \frac{1.2f_y}{\gamma_{m0}}$$

$$\frac{w\left(a^2 - 0.3b^2\right)6\times\gamma_{mo}}{2\times 1.2\ f_y} \le t^2$$

$$\frac{2.5\times w\left(a^2 - 0.3b^2\right)\gamma_{mo}}{f_y} \le t^2$$

$$\sqrt{\frac{2.5w\left(a^2 - 0.3b^2\right)\gamma_{mo}}{f_y}} \le t$$

Search on Telegram @apna_pdf

511. The average shear stress in a member calculated on the cross section of unstiffened web shall not exceed–

(a) $0.45\ f_y$ (b) $0.40\ f_y$
(c) $0.65\ f_y$ (d) $0.66\ f_y$

OPSC AEE 2015 PAPER–I

Ans. (b) :

	Cases	Permissible stress
1.	Axial tension and compression	$0.6\ f_y$
3.	In bearing (e.g-at support)	$0.75\ f_y$
2.	In bending	$0.66\ f_y$
4.	In shear	Maximum permissible avg stress= $0.40\ f_y$ Maximum permissible stress = $0.45\ f_y$

512. The maximum deflection for a steel beam as per IS code should not exceed-

(a) $\frac{1}{150}$ of span (b) $\frac{1}{250}$ of span
(c) $\frac{1}{325}$ of span (d) $\frac{1}{350}$ of span

OPSC AEE 2015 PAPER–I
UPPCL AE 2014

Ans. (c) : Maximum deflection shall not exceed 1/325 of the span.

513. The angle dispersion of a concentrated load on the flange to the web plate of a steel beam is

(a) 90 degree with the horizontal
(b) 60 degree with the vertical
(c) 45 degree with the horizontal
(d) 30 degree with the vertical

BPSC AE 2019 Paper (V) Section-I

Ans. (c) : The angle dispersion of a concentrated load on the flange to the web plate of a steel beam is 45 degree with the horizontal.

514. A welded steel plate girder consisting of two flange plates of 350 mm × 16 mm and web plate of 1000 mm × 6 mm requires

(a) no stiffeners
(b) vertical stiffeners
(c) immediate vertical stiffeners
(d) vertical and horizontal stiffeners

BPSC AE 2019 Paper (V) Section-I

Ans. (b) : We know that,

if $250 > \frac{d}{t_w} > 90$, then only vertical stiffeners are provided.

Now, $\frac{d}{t_w} = \frac{1000}{6} = 166.67$

So, only vertical stiffeners are provided.

515. The minimum thickness of web plate from corrosion point of view should be

(a) 12 mm (b) 6 mm
(c) 3 mm (d) 20 mm

APPSC AE 2016 (Mains)

Ans. (b) : The minimum thickness of web plate from corrosion point of view should be 6 mm.

516. A steel column in a multi-storeyed structure carries a load of 125 kN. It is builtup of 2 ISMC 350 channels connected by lacing. The lacing carries a load of

(a) 125 kN (b) 12.5 kN
(c) 3.125 kN (d) Zero

APPSC AE 2016 (Mains)

Ans. (c) : Load carried by lacing = 2.5% of structure load.

$$= \frac{2.5}{100} \times 125 = 3.125 KN$$

517. Which one of the following solid sections will have minimum shape factor?

(a) Circular (b) Rectangular
(c) Triangular (d) Diamond

[HPPSC 2016-II]

Ans. (b) : Shape factor is defined as ratio of plastic moment to the yield moment of a member.

$$S = \frac{M_P}{M_Y} = \frac{Z_P}{Z_Y}$$

Shape factor for different sections:-
Rectangular= 1.5; circular = 1.69, Triangular = 2.34
Diamond = 2.34

518. In the plate girders, shear force is mainly resisted by :

(a) Top flange (b) Bottom flange
(c) Web (d) Horizontal stiffener

[HPPSC 2016-II]

Ans. (c) : In plate girder web will bear the majority shear force. The shear strength of web plate girder depends upon depth to thickness ratio of web.

519. A steel member 'M' has reversal of stress due to live loads, whereas another member 'N' has reversal of stress due to wind load. As per IS 800 : 2007, the maximum slenderness ratio permitted is :

(a) less for member 'M' than that of member 'N'
(b) more for member 'M' than for member 'N'
(c) same for both the members
(d) not specified in the code

JPSC AE (Pre) 2019

Ans. (a) :
M = reversal of stress is due to live load
N = reversal of stress is due to wind load as per IS 800 : 2007
for M, the max. slenderness ratio = 180
and, for N, the max. slenderness ratio = 350

520. The lighter sections of structural members subject to transverse loading are called as :

(a) Struts (b) Tie
(c) joist (d) Stanchions

GPSC AE Class (1&2) Paper - 2 2017

Ans. (c) The lighter sections of structural members subject to transverse loading are called as joist.

Search on Telegram @apna_pdf

521. Intermediate vertical stiffeners are provided in plate girders to :

(a) eliminate web buckling
(b) eliminate local buckling
(c) prevent excessive deflection
(d) to transfer concentrated loads

GPSC AE Class (1&2) Paper-2, 2017

Ans. (a) To eliminate web buckling intermediate vertical stiffeners are provided in plate girders.

522. Most appropriate hot rolled Indian standard section for steel girder is :

(a) ISHB (b) ISLB
(c) ISMB (d) ISWB

Rajasthan JEn (Degree) 2016

Ans. (c) ISMB is used for steel girder.

523. Gantry girders are designed for which of the following types of loads?

(i) Gravity loads (ii) Lateral Loads
(iii) Wind loads (iv) Longitudinal Loads
(a) (i) and (ii) (b) (i), (ii), and (iv)
(c) (i), (iii) and (iv) (d) (i), (ii), (iii) and (iv)

GPSC AE (CLASS 1 & 2) 2019

Ans : (b) Gantry girder are designed for three perpendicular direct load, gravity load, lateral load and longitudinal load.

524. lateral load acting at the level of compressing flange of gantry girder is resisted by

(a) Tension flange (b) Compression flange
(c) Web (d) Lateral supports

GPSC AE (CLASS 1 & 2) 2019

Ans : (b) : Lateral load i.e., transverse load is resisted by flange section only, web section resist shear.

525. In case of laterally supported beam, the design bending stress is governed by

(a) Lateral torsional buckling
(b) Shear lag
(c) Yield stress
(d) None of the above

GPSC AE (CLASS 1 & 2) 2019

Ans : (c) : In case of laterally supported beam, the designed bending stress is governed by yield stress.

526. For what purpose stiffeners are used in a plate girder?

(a) to connect the flange plates to the web
(b) to provide web splice
(c) to prevent buckling of web
(d) to provide splice for flange plates and cover plates

Kerala PSC AE 2015


Ans. (c) Stiffeners are used in a plate girder to prevent buckling of web.

527. Web crippling generally occurs at the point where

(a) bending moment is maximum
(b) shearing force is minimum
(c) heavy concentrated loads act
(d) deflection is maximum

TNPSC AE 2018
UPPCL AE 2014

Ans. (c) : Web crippling is buckling of the web caused by the compressive force delivered through the flange. To keep the bearing stress in permissible limits, the concentrated load should be transferred from flanges to the web on sufficiently large bearing areas.




Web failure by local crippling

IS 800 : 2007 has accepted the following formula to find crippling of web.

$$F_W = (b_1 + n_C)t_W \times \frac{f_{yw}}{\gamma_{m_0}}$$

where b_1 = stiff bearing length
n_c = length obtained by dispersion through the flange to the web junction at a slope of 1 : 2.5 to the plane of flange.

$n_c = 2.5\ t_f$
f_{vw} = yield stress of the web



528. The problem of web-crippling in beams is significant when

(i) Web is weak under concentrated loads
(ii) There is too much flexural moment
(iii) Compression flange is weak
(a) Only (i) (b) Only (ii)
(c) (i), (ii) (d) (i), (ii) and (iii)

GPSC AE (CLASS 1 & 2) 2019

Ans : (a) : The web crippling in beam happens due to the web is weak under concentrated load. It happens due to the large concentrated load applied over the beam.

529. Which of the following types of failure is more prone to take place when web of the plate girder is made too thick?

(a) Local buckling (b) Shear buckling
(c) Flexural buckling (d) Shear yielding

GPSC AE (CLASS 1 & 2) 2019

Ans : (d) : When the web of plate girder is too thick the failure is to take place shear yielding in steel plate girder.

530. A welded plate girder of span 25 m is laterally restrained throughout its length. It has to carry a load of 80 kN/m over the whole span besides its weight. If K = 200 and f_y = 250 MPa, the thickness of web will be nearly


(a) 10 mm (b) 14 mm

Search on Telegram @apna_pdf

(c) 16 mm (d) 20 mm

ESE 2019

Ans. (a)



Span of girder L = 25m

f_y = 250 MPa

$k = \frac{d}{t_w} =$

Total load 'P' = 80 kN/m

Factored load = 1.5 × 80 = 120 kN/m

Self weight of welded plate girder

$$= \frac{W}{400} = \frac{80 \times 25}{400} = 5 kN/m$$

Factored self weight = 1.5×5 = 7.5 kN/m

Total factored load inclusive of self weight

W = 120 + 7.5

[W = 127.5kN/m]

Maximum factored bending moment $\left[M_{zz} = \frac{WL^2}{8}\right]$

$$M_{zz} = \frac{127.5 \times 25^2}{8}$$

[M_{zz}= 9960.9375kN-m]

Optimum thickness of web plate

$$t_w = \left[\frac{M_{zz}}{f_y \times k^2}\right]^{1/3}$$

$$t_w = \left[\frac{9960.9375 \times 10^6}{250 \times 200^2}\right]^{1/3}$$

$$\boxed{t_w = 9.99mm \simeq 10mm}$$


531. In which one of the following industrial roofing contexts, is the loading carried by the combination of pure flexure and flexure due to shear induced by the relative deformation between the ends of the top and bottom chord members?

(a) Vierendeel girders (b) Scissors girders

(c) Lenticular girders (d) Mansard girders

ESE 2019

Ans. (a)



An open web truss having verticals which are rigidly connected to the top and bottom chords but without diagonals.

Vierendeel girder is a series of rectangular frames, which achieves stability by the rigid connections of vertical web members to the top and bottom chord.

In Vierendeel girder the loading is carried by a combination of pure flexure and flexure due to shear induced by the relative deformation between the ends of the top and bottom chord members, similar to that found in castellated beams.

532. Which of the following assumptions are correct for ideal beam behaviour?

1. The compression flange of the beam is restrained from moving laterally.
2. The tension flange of the beam is restrained from moving laterally.
3. Any form of local buckling is prevented.

(a) 2 and 3 only (b) 1 and 3 only

(c) 1 only (d) 3 only

ESE 2019

Ans. (b) : Two important assumptions have been made therein to achieve the ideal beam behavior :

→ The compression flange of the beam is restrained from moving laterally.

→ Any form of local buckling is prevented.

A beam experiencing bending about major axis and its compression flange not restrained against buckling may not attain its material capacity.

533. Buckling of the compression flange of a girder, without transverse stiffeners, can be avoided if (with standard notations)

(a) $\frac{d}{t_w} \le 345\varepsilon_f^2$ (b) $\frac{d}{t_w} \le 270\varepsilon_f^2$

(c) $\frac{d}{t_w} \le 270\varepsilon_w$ (d) $\frac{d}{t_w} \le 250\varepsilon_w$

ESE 2018

Ans. (a)

- In order to avoid buckling of compression flange into web, the web thickness without transverse stiffener shall satisfy (clause 8.6.1.2 of IS 800 : 2007)
- $\left[\frac{d}{t_w} \le 345\varepsilon_f^2\right]$
- $\left.\begin{array}{l}\frac{d}{t_w} \le 345\varepsilon_f^2 \text{ for } c \ge 1.5d \\ \frac{d}{t_w} \le 345\varepsilon_f \text{ for } c < 1.5d\end{array}\right\}$ When only transverse stiffeners are provided

Where c = clear distance between transverse stiffener.

534. A simply supported steel beam of rectangular section and of span L is subjected to a uniformly distributed load. The length of the plastic hinge by considering moment ratio of 1.5 will be nearly


(a) 0.27 L (b) 0.39 L

(c) 0.45 L (d) 0.58 L

ESE 2018

Ans. (d) : Simply supported steel beam subjected to uniformly distributed load.

Search on Telegram @apna_pdf



- For rectangular beam, shape factor is

$$\left[S.F = \frac{M_P}{M_Y} = 1.5\right]$$

- So, the length of plastic hinge

$$\left[L_P = L\sqrt{1-\frac{1}{SF}}\right]$$

$$\Rightarrow L_P = L\sqrt{1-\frac{1}{1.5}}$$

$$L_P = 0.577L$$


$$\boxed{L_P = 0.58L}$$

535. A beam-column is alternately bent either (1) in single curvature, or (2) in double curvature. The secondary moments induced are to be compared. These are indicated SM_1 and SM_2 as per the conditions (1) and (2) respectively

(a) $SM_1 > SM_2$ (b) $SM_1 < SM_2$
(c) $SM_1 = SM_2$ (d) Cannot be ascertained

ESE 2017

Ans. (a)



- A beam column is a member which carrying bending moment.
- Due to bending, deflection (Δ), the axial force 'P' induces additional moment = P × Δ
- In single curvature, P. Δ moment will be more than that in double curvature because of lower 'Δ' in double curvature.
- It is observed that, higher effective length is in case (1). It has less capacity. For a given condition, moment developed in a weaker member is high.

536. Gantry girders can be designed

(a) As laterally supported beams.
(b) As laterally unsupported beams
(c) By using channel sections.

Select the *correct* answer using the codes given below.

(a) 1, 2 and 3 (b) 1 and 2 only
(c) 2 and 3 only (d) 1 and 3 only

ESE 2017

Ans. (a) Gantry girders are laterally unsupported beams to carry heavy loads from place to place at the construction sites. As a beam or a girder the most efficient section is I section but gantry girder under various loads, to enhance lateral stability or lateral bending strength to withstand lateral loads, normally a channel section is reinforced to the compression flange of I-section.

537. Load carrying stiffeners are provided in a plate girder in order to?

(a) Prevent local buckling of the web due to concentrated loading
(b) Provide local reinforcement to a web under shear ad bearing
(c) improve the buckling strength of a slender web due to shear
(d) Prevent local crushing of the web due to concentrated loading

DSSSB AE 2019

Ans. (a) Load carrying stiffeners are provided in a plate girder in order to prevent local buckling of the web due to concentrated loading.
As in case of rolled sections, the webs are proportioned that it will stably carry load without buckling or crippling of the web.
But in plate girders to achieve economy, webs are made thin. In such cases the stiffeners are required at the ends, at the location of heavy point load and along longitudinal axis to prevent web buckling.


538. Web crippling of a structural steel beam occurs due to

(a) Failure of the web under concentrated load
(b) Excessive bending moment
(c) Minimum shear force
(d) Secondary bending moment

ISRO Scientist/Engineer 2019

Ans : (a) :

- The failure of web in direct crushing under concentrated load is known as web crippling or web crippling. The web crippling may occur if the in-place compressive stress in the web is too large.
- The web crippling may also occur if the uniformly distributed load on the flange is too large for web thickness.
- The web crippling means the stress concentration due to bottleneck condition at the web toe of the fillet under or over heavy load concentrations.
- In web crippling, local buckling of the web occurs immediately adjacent to a concentration of stress.



539. Which of the following is a best compression member section?

(a) Single angle section

Search on Telegram @apna_pdf

(b) Tubular section
(c) Double angle section
(d) I section

ISRO Scientist/Engineer 2017


Ans : (b) Tubular section is a best compression member.

540. Junction between the flange and web of a beam is known as

(a) Lap joint (b) Butt joint
(c) Fillet (d) Shear joint

ISRO Scientist/Engineer 2017

Ans : (c)



Junction between the flange and web of a beam is known as Fillet.

541. Rolled steel equal and unequal sections are designated as ISA followed by

(a) Length and thickness of legs
(b) Width of flange and depth of web
(c) Depth of section
(d) Weight per meter length

ISRO Scientist/Engineer 2017

Ans : (a) Rolled steel equal and unequal sections are designated as ISA followed by length and thickness of legs.

542. The stability of the beam depends on

(a) Torsional stiffness (b) Flexural stiffness
(c) Axial stiffness (d) Serviceability

APTRANSCO AE 2017

Ans : (a) The stability of the beam depends on torsional stiffness.

543. The deflections under working loads are computed using

(a) elastic theory
(b) plastic theory
(c) ultimate strength theory
(d) fracture mechanics

APTRANSCO AE 2017

Ans : (a) The deflections under working loads are computed using elastic theory.

544. The connections subject to reversal of stresses due to passage of live load in case of bridges are designed for the

(a) sum of minimum forces and reversal of forces
(b) sum of maximum forces and reversal of forces
(c) difference of maximum force and reversal of forces
(d) impact factor times the difference of maximum forces and reversal of forces

APTRANSCO AE 2017

Ans : (b) The connections subject to reversal of stresses due to passage of live load in case of bridges are designed for the sum of maximum forces and reversal of forces .

545. The surge loads in gantry girder are

(a) Longitudinal loads (b) Transverse
(c) Lateral loads (d) Wind loads

APTRANSCO AE 2017

Ans : (c) The surge loads in gantry girder are lateral loads.

546. The depth of plate girder is given by

(a) $(Mk^2/F_y)^{0.33}$ (b) $(M/F_yk^2)^{0.33}$
(c) $(Mk^2/F_y)^{0.5}$ (d) (Mk^2/F_y)

Where M, k, F_y have their usual meanings.

APTRANSCO AE 2017

Ans : (a) The depth of plate girder is given by $(Mk^2/F_y)^{0.33}$

547. Intermediate vertical stiffeners are provided in plate girders to:

(a) eliminate web buckling.
(b) eliminate local buckling.
(c) transfer concentrated load.
(d) eliminate excessive deflection.

WBPSC Poly Lect. 2019
UPPCL AE 2019
ESE 2007

Ans. (a) : Intermediate vertical stiffeners are provided in plate girders to eliminate web buckling.

548. Horizontal stiffener in a plate girder is provided to safeguard against :

(a) Shear buckling of web plate
(b) Compression buckling of web plate
(c) Yielding
(d) All of these

OPSC AEE 2019 Paper–I

Ans. (b) : Horizontal stiffeners in a plate girder is provided to safe guard against compression buckling of web plate. Horizontal stiffeners are also called longitudinal stiffeners.

549. Bearing stiffener in a plate girder is used to :

(a) Transfer the load from the top flange to the bottom one.
(b) Prevent buckling of web
(c) Decrease the effective depth of web
(d) Prevent excessive deflection

OPSC AEE 2019 Paper–I
Rajasthan Nagar Nigam AE Shift-2, 2016
ESE 2013, 2005

Ans. (b) : Bearing stiffeners are provided at the points of concentrated loads and at support to resist reactions, local bending failure of the flange, web crippling and buckling of web.
If beaming stiffeners are the only means of providing torsional restrain then they are also called torsional stiffeners

550. Economical depth of a plate girder is given by :

(a) $\sqrt{\left(\frac{M}{\sigma t_w}\right)}$ (b) $1.1\sqrt{\left(\frac{M}{\sigma t_w}\right)}$

Search on Telegram @apna_pdf

(c) $1.2\sqrt{\left(\frac{M}{\sigma t_w}\right)}$ (d) $1.3\sqrt{\left(\frac{M}{\sigma t_w}\right)}$

OPSC AEE 2019 Paper–I

Ans. (b) : Economical depth of plate girder (d) (the depth at which weight of girder is minimum)

for riveted plate girder, $D = 1.1\sqrt{\frac{M}{\sigma.t_w}}$

551. Shear buckling of web in a plate girder is prevented by using :

(a) Vertical intermediate stiffener
(b) Horizontal stiffener along the neutral axis
(c) Bearing stiffener
(d) None of these

OPSC AEE 2019 Paper–I
UP Jal Nigam AE 2016

Ans. (a) : In plate girders, intermediate transverse stiffeners are provided to increase buckling resistance of web in diagonal or shear buckling.

552. Intermediate vertical stiffeners in a plate girder need to be provided, if the depth of web exceeds ("t" is thickness of web) :

(a) 50t (b) 85t
(c) 200t (d) 250t

OPSC AEE 2019 Paper–I

Ans. (b) : Intermediate vertical stiffeners in a plate girder are needed when the depth of web exceeds 85t.

553. The range of economical spacing of trusses varies from (where L is span) :

(a) $\frac{L}{3}$ to $\frac{L}{5}$ (b) $\frac{L}{4}$ to $\frac{2L}{5}$
(c) $\frac{L}{3}$ to $\frac{L}{2}$ (d) $\frac{2L}{5}$ to $\frac{3L}{5}$

OPSC AEE 2019 Paper–I

Ans. (a) : The spacing of the truss depends on the type truss used, the truss span, the function of building, the subsoil conditions etc.

A good thumb rule for the truss spacing is $\frac{1}{5}$ to $\frac{1}{3}$ of their span.

554. As per IS : 800, the maximum bending moment for design of purlins can be taken as (where W is total distributed load on the purlins and L is centre distance of support) :

(a) $\frac{WL}{6}$ (b) $\frac{WL}{8}$
(c) $\frac{WL}{10}$ (d) $\frac{WL}{12}$

OPSC AEE 2019 Paper–I
WBPSC AE 2007

Ans. (c) : As per IS 800–1984 clause 6.9.2. The maximum bending moment in a purlin may be taken as $\frac{WL}{10}$ when W is the total distributed load on the purlin including wind load.

555. The number of seismic zones in which the country has been divided are :

(a) 3 (b) 5
(c) 6 (d) 7

OPSC AEE 2019 Paper–I

Ans. (b) : As per IS 1893 (Part)–1970. Based on the levels of intensities sustained during damaging past earthquake, the zone map subdivided India into 5 zone.

556. As per IS:875, for the purposes of specifying basic wind velocity, the country has been divided into :

(a) 4 zones (b) 5 zones
(c) 6 zones (d) 7 zones

OPSC AEE 2019 Paper–I

Ans. (c) : As per IS 815 (Part 3) for the purposes of specifying. Basic wind velocity the country has been divided into 6 zones.

557. The thickness of web for unstiffened plate girder with clear distance "d" between the flanges shall not be less than :

(a) $\frac{d}{200}$ (b) $\frac{d}{85}$
(c) $\frac{d}{100}$ (d) $\frac{d}{160}$

OPSC AEE 2019 Paper–I
[UPPSC State Eng. A.E. 2003]
GPSC AE June 2019
ESE 1996, 2011

Ans. (b) : As per IS 800 : 1984 clause 67.3.1 the thickness of the web plate shall be not less than the greater of $\frac{d\sqrt{\tau_{va}.cal}}{816}$ & $d\sqrt{6y}/1344$ but not less than $\frac{d}{85}$ for unstiffened webs where d is depth of web.

$\frac{d}{t_w} \le 85$ then no stiffeners are required.

558. Which of the following assumptions are correct for the lateral torsional buckling of an I-section beam ?

1. The beam is initially distorted
2. Its behaviour is elastic
3. It is loaded by equal and opposite end moments in the plane of the web

(a) 1 and 2 only (b) 2 and 3 only
(c) 1 and 3 only (d) 1, 2 and 3

ESE 2020

Ans. (b) : The lateral torsional buckling of an I-section is considered with the following assumption–

(1) The beam is initially undistorted.
(2) Its behaviour is elastic (no yielding).
(3) It is loaded by equal and opposite end moments in the plane of web.
(4) The beam does not have residual stress.
(5) The land acts in the plane of web only (no external applied lateral (or) torsional loads).
(6) Its ends are simply supported vertically and laterally.

Search on Telegram @apna_pdf


559. At a section along the span of a welded plate girder, where the web is spliced, the bending moment is M. If the girder has top flange, web and bottom flange plates of equal area, then the share of the bending moment which would be taken by the splice plates would be

(a) M (b) $\frac{M}{3}$

(c) $\frac{M}{7}$ (d) $\frac{M}{13}$

OPSC AEE 2019 Paper–I
APTRANSCO 2017
ESE 2010

Ans. (c) : Moment taken by splice plate = moment taken by web plate



$$\frac{M_W}{I_W} = \frac{M}{I}$$

$$\therefore I_W = \frac{t.B^3}{12}$$

I = M . I of entire plate

$$I = \left[\frac{Bt^3}{12} + Bt \times \left(\frac{B+2t}{2}\right)^2\right] + \left[\frac{t \times B^3}{12}\right]$$

$$I = \frac{7tB^3}{12}$$

$$M_w = \frac{I_w}{I} \times M$$

$$M_w = \frac{\frac{tB^3}{12}}{\frac{7tB^3}{12}} \times M = \frac{M}{7}$$

560. In a design of beam columns, the values of plastic section ratio $\beta_b = 1$, the plastic sectional modulus $Z_{pz} = 3948812\ mm^3$, the yield stress $f_y = 250\ N/mm^2$ and critical moment of $M_{cr} = 16866 \times 10^6$ N.mm. The non-dimensional lateral torsional slenderness ratio will be nearly.

(a) 0.141 (b) 0.242

(c) 0.323 (d) 0.424

ESE 2020

Ans. (b) : Given,

$\beta_b = 1$, $Z_{pz} = 3948812\ mm^3$, $f_y = 250\ N/mm^2$

$M_{cr} = 16866 \times 10^6$ N-mm.

Non dimensional lateral torsional slenderness ratio,

$$\lambda_{LT} = \sqrt{\frac{\beta_b \times Z_{pz} \times f_y}{M_{cr}}}$$

$$\lambda_{LT} = \sqrt{\frac{1 \times 3948812 \times 250}{16866 \times 10^6}} = 0.2419 \simeq 0.242$$

561. In a cantilever plate girder to prevent web buckling, horizontal stiffeners are provided running along the span. They are provided

(a) below the neutral axis

(b) over the entire cross-section (above as well as below neutral axis)

(c) above the neutral axis

(d) None of the above

Maharashtra PSC Mains 2018 Paper-1

Ans. (c) : Horizontal stiffeners are also called longitudinal stiffeners. These increase the buckling resistance and the provided in the compression zone of the web. So, for a cantilever plate girder horizontal stiffeners are provided above the neutral axis.

Horizontal stiffeners are provided above neutral axis at a distance of 0.2 t_w from the compression flange.

562. An example of light moment connection is

(a) framed connection

(b) unstiffened seat connection

(c) clip angle connection

(d) split beam connection

GPSC AE March 2018

Ans. (c) : A moment connection transfer bending moment from a beam to a column.

Clip angle connection is an example of light moment connection. Clip angle connections are used for connecting a floor beam to another beam or a column to beam.

563. To transfer large shear force through connection, which of the following option is most suitable ?

(a) clip angle connection

(b) bracket connection

(c) stiffened seated connection

(d) framed connection

GPSC AE March 2018

Ans. (c) Stiffened seated connection-In addition to the seat angle a web cleat is provided when the beam is connected to a beam and a flange cleat is used when the beam is connected to a stanchion.

564. As per IS : 800 in the case of a plate girder with vertical and horizontal stiffeners, the greater and lesser unsupported clear dimension of a web panel in term of web thickness t_w should not exceed respectively

(a) 180 t_w and 85 t_w (b) 270 t_w and 180 t_w

(c) 270 t_w and 200 t_w (d) 400 t_w and 250 t_w

GPSC AE March 2018
ESE 2000

Ans. (c) : As per IS 800:2007 in the case of plate girder with vertical and horizontal stiffeners, the greater and lesser thickness should not exceed 270 t_w and 200 t_w.

$t_w \rightarrow$ web thickness

565. Vertical deflection of gantry girder for electrically operated cranes over 500 kN is

(a) span/400 (b) span/500

(c) span/750 (d) span/1000

GPSC AE March 2018

Search on Telegram @apna_pdf

Ans. (d) : Limiting deflection of gantry girders
Vertical deflection

(1) Manually operated $= \frac{L}{500}$

(2) EOT cranes with a capacity < 500 kN = $\frac{L}{750}$

(3) EOT cranes with a capacity > 500 kN = $\frac{L}{1000}$

566. Economical depth of gantry girder is about

(a) $1/8^{th}$ span (b) $1/12^{th}$ span
(c) $1/16^{th}$ span (d) $1/20^{th}$ span

GPSC AE March 2018


Ans. (b) : Economical depth of gantry girder is about 1/12th of the span. The width of flange 1/40 and 1/30th of the span to prevent excessive lateral deflection.

567. A steel beam having I cross-section has an overall depth of 300 mm. The top and bottom flange widths are 120 mm each. If the flange stresses at the top and bottom are 120 N/mm^2 and 30 N/mm^2, respectively, the depth of the neutral axis from the top of the beam would be:

(a) 60 mm (b) 120 mm
(c) 180 mm (d) 240 mm

UPSC JWM 2017

Ans. (d) :



$\frac{120}{x} = \frac{30}{300 - x}$

x = 240 mm

568. Pick up the correct statement from the following:

(a) In a loaded beam, the moment at which the first yield occurs is called yield moment
(b) In a loaded beam, the moment at which the entire section of the beam becomes fully plastic, is called plastic moment
(c) In a fully plastic stage of the beam, the neutral axis divides the section in two sections of equal area
(d) All of the above

KPTCL AE 2016

Ans. (d)

569. In a two hinged stiffening girder of span '*l*' the maximum positive or negative moment due to a moving concentrated load W is :

(a) $\frac{Wl}{4}$ (b) $\frac{Wl}{8}$
(c) $\frac{Wl}{16}$ (d) $\frac{Wl}{24}$

OPSC Civil Services Pre 2011

Ans. (b) : In a two hinged stiffening girder of span '*l*' the maximum positive or negative moment due to a moving concentrated load W is $\frac{Wl}{8}$

570. Which of the following sections is the most efficient for a simply supported gantry girder?

(a) I-section with a wide bottom flange
(b) I-section with a heavy plate connected to the bottom flange
(c) I-section with equal flanges
(d) I-section with a channel attached to the top flange

Rajasthan Nagar Nigam AE Shift-2, 2016

Ans. (d) : I-section with a channel attached to the top flange.
The reinforcement of channel section to the compression flange of I-section will increase lateral buckling strength.

571. In the plate, girder stiffeners are used

(a) to take bearing stress
(b) to reduce the compressive stress
(c) to avoid buckling of web plate
(d) to reduce the shear stress

Maharashtra PSC (Mains) 2019 Paper–I
Rajasthan AE Nagar Nigam Shift-3, 2016

Ans. (c) : Stiffeners are provided to support to other member and when attached to beam then avoid buckling of web plate.

572. As per IS 800-2007 the maximum deflection in a beam of length 'L' should not exceed

(a) L/250 (b) L/80
(c) L/325 (d) L/360

Rajasthan AE Nagar Nigam Shift-3, 2016
LMRC AM 2015

Ans. (c) : According to IS 800-2007

maximum deflection in beam $\leq \frac{\text{span length}}{325}$

$\Delta \leq \frac{L}{325}$

When span 5m then deflection of beam 20 mm.

573. Allowable bending stress in grillage beam encased in concrete is increased from that specified in code by

(a) 25% (b) $33\frac{1}{3}\%$
(c) $16\frac{2}{3}\%$ (d) 10%

TANGEDCO AE 2018

Ans. (b) : Allowable bending stress in grillage beam encased in concrete is increased by 33.33%.

574. For long shallow girders with low warping stiffness the critical moment is expressed as

(a) $\sqrt{EI_y GJ}$ (b) $\frac{\pi}{L}\sqrt{EI_y GJ}$
(c) $\frac{\pi}{L}\sqrt{EI_y GJ}$ (d) $EI_y GJ$

TRB Poly. Tech. Lect. 2012

Search on Telegram @apna_pdf

Ans. (b) : For long shallow girders with low warping stiffness the critical moment $= \frac{\pi}{L}\sqrt{EI_y GJ}$

575. When the depth of a plate girder is less than 75 cm, then such a plate girder is known as

(a) deep plate girder
(b) shallow plate girder
(c) economical plate girder
(d) none of the above

UKPSC(Urban engineering)-2011

Ans. (b) : When the depth of plate girder is less than 750 mm. Then such girders known as 'Shallow plate Girders'.

576. In a plate girder, the web is primarily designed to resist

(a) Torsional moment (b) Bending moment
(c) Diagonal buckling (d) Shear force

TSGENCO_2015
ESE 2014

Ans. (d) : In a plate girder, the web is primarily designed to resist shear force.

577. Web crippling occurs due to.

(a) Column action of web
(b) Excessive bending moment
(c) Failure of web under point load
(d) Secondary bending moment

UJVNL AE 2016

Ans. (c) : Web crippling occurs when the web is slender i.e. h/t_w is large.
h = length of web. t_w = thickness of web and a point loads acted on it web crippling occurs due to secondary bending moment.

578. The most efficient section for a given beam for a given cross-sectional area is.

(a) Circular (b) Channel
(c) Hollow circular (d) I- section

UJVNL AE 2016

Ans. (d) : In case of I section, the web resists shear forces, while the flange resist most of the building moment.
That is why I-section is a very efficient for carrying both bending and shear load in the plane of the web.

579. If W and L are the total superimposed load and the span of a plate girder in meters, the approximate self weight of the girder, is taken as

(a) $M = \frac{WL}{300}$ (b) $M = \frac{WL}{100}$
(c) $M = \frac{WL}{400}$ (d) $M = \frac{WL}{200}$

APPSC AEE 2012

Ans. (a) : Self weight of girder $(M) = \frac{WL}{300}$
W = total superimposed load
L = span

580. According to IS 800–2007, the minimum thickness of vertically stiffened web plate shall not be less than

(a) $\frac{d}{95}$ (b) $\frac{d}{250}$
(c) $\frac{d}{225}$ (d) $\frac{d}{200}$

APPSC AEE 2012

Ans. (a) : If $\frac{d_1}{t_w} > 90$, vertical stiffeners are provided to prevent buckling of web due to diagonal compression.

581. Stiffeners are used in a plate girder

(a) To reduce compressive strength
(b) To reduce the shear stress
(c) To avoid the buckling of web plate
(d) To take the bearing stress

APPSC AEE 2012

Ans. (c) : Stiffeners are used in plate girders to avoid the buckling of web plates by providing resistance to longitudinal and transverse shear.

582. As per ISI, rolled steel beam sections are classified into

(a) Three series (b) Four series
(c) Five series (d) Six series

APPSC AEE 2012

Ans. (c) :

Beam
- ISJB (Indian Standard Junior Beams)
- ISLB (Indian Standard Light weight Beams)
- ISMB (Indian Standard Medium weight Beams)
- ISWB (Indian Standard Wide flange Beams)
- ISHB (Indian Standard Heavy weight Beams)

583. Determine the economical depth of the welded plate girder of span 24m to carry super imposed load of 35 kN/m. Avoid stiffeners and use Fe 415 steel :

(a) 1000 mm (b) 800 mm
(c) 1400 mm (d) 1200 mm

TRB Poly. Lect. Tech. 2017

Ans. (a) :

584. The web crippling strength is calculated as :

(a) $(b_1 + n_2)\ t_w \frac{f_y w}{\gamma_{mo}}$
(b) $f_y w t_w$
(c) $\frac{n_2 t_w}{\gamma_{mo}}$
(d) None of the above

TRB Poly. Lect. Tech. 2017

Ans. (a) : The web crippling strength is calculated as $(b_1 + n_2)\ t_w \frac{f_y w}{\gamma_{mo}}$.

Search on Telegram @apna_pdf

585. The economical depth (d) of the plate girder is :

(a) $\left(\frac{MK}{f_y}\right)^{1/5}$ (b) $\left(\frac{MK}{f_y}\right)^{1/3}$

(c) $\left(\frac{Mf_y}{k}\right)^{1/5}$ (d) $\left(\frac{f_yK}{M}\right)^{1/3}$

TRB Poly. Lect. Tech. 2017

Ans. (a) : The economical depth (d) of the plate girder is $\left(\frac{MK}{f_y}\right)^{1/5}$


586. A steel beam is carrying just its self load. It needs to be so supported on two columns (span length, *l*) with equal overhangs (y) on both the sides such that the bending moment at the mid-span is zero. The ratio of *l*/y should be:

(a) 0.25 (b) 0.5

(c) 1.00 (d) 2.00

UPRVUNL AE 2016

Ans. : (d) Let the beam carry w kN/m its self load at point C, BM = 0 for this



$\frac{\ell}{y} = 2$

$\ell = 2y$

When a steel beam is carrying its self load, it needs to be support on two columns (span length, *l*) with equal overhangs (y) on both the sides such that the bending moment at the mid-span is zero. The ratio of *l* /y should be 2.

587. In rolled steel beams, shear force is mostly resisted by :-

(a) Web only


(b) Web and flanges together

(c) Flanges only

(d) Neutral axis

GPSC AE January 2018
UPPCL AE 2014

Ans. (a) : In rolled steel beam, shear force mostly resisted by web only.



588. A diagram which shows the variation of the axial load at all sections along the span of a beam is –

(a) Thrust diagram

(b) Bending moment diagram

(c) Stress diagram

(d) Shear force diagram

UPPCL AE 2014

Ans. (a) : A diagram which shows the variation of the axial load at all sections along the span of a beam is thrust diagram.

589. If 't' is the thickness of web of plate girder which is stiffened vertical then, the smallest clear dimension of a panel should not exceed:-

(a) 85 t (b) 180 t

(c) 250 t (d) 200 t

UPPCL AE 2014

Ans. (b) : The thickness (t) of web of plate girder which is stiffened vertical, then smallest clear distance of panel should not exceed 180 t.

590. In rolled steel beams, major part of bending moment is resisted by

(a) Flanges

(b) Web

(c) Flanges and web

(d) Flanges, web and fillets

APPSC AEE 2016

Ans. (a) : In beam element I or H shaped the web resists the shear forces while the flanges resisted most of the bending moment experienced by the beam.

591. In case of hot rolled steel section, a beam with a series of regular openings in its web is called .....

(a) Tapered Beam (b) Hybrid Beam

(c) Castellated Beam (d) Latticed Beam

GPSC AE January 2018

Ans. (c) : A Castellated Beam is a beam style where on I-beam is subjected to a longitudinal cut along its web (a series of regular opening) following a specific pattern. The purpose is to divide and reassemble the beam with a deeper web by taking advantage of the cutting pattern.

592. The design bending strength of laterally unsupported beam is governed by .....

(a) Lateral torsional buckling strength

(b) Yield stress of material

(c) Type of loading

(d) Type of support

GPSC AE January 2018

Ans. (a) : Design strength in bending (flexure) of laterally unsupported beam is governed by lateral torsional buckling strength.
Beams with major axis bending and compression flange not restrained against lateral bending fail by lateral torsional buckling before attaining their bending strength.

593. The heaviest section for same depth as per Indian Standard hot rolled steel sections is.

(a) ISHB (b) ISMB

(c) ISWB (d) ISLB

GPSC AE January 2018

Ans. (a) : For same depth, as per Indian Standard heavier hot rolled steel section is ISHB.
ISHB = Indian standard Heavy Beam.

594. For hot rolled steel section design of beams, as per Indian Standard code a laterally supported beam means.

(a) Web is restrained

(b) Compression flange is restrained

(c) Tension flange is restrained

(d) Web thickness is more than 10 mm

GPSC AE January 2018

Search on Telegram @apna_pdf

Ans. (b) : For hot rolled steel section design of beams, as per Indian Standard code a laterally supported beam refers to restrain the movement of the compression section of a beam.

595. Minimum spacing of vertical stiffeners in plate girder of depth d is limited to .....

(a) d/4 (b) d/3
(c) d/2 (d) 2d/3

GPSC AE January 2018

Ans. (b) : Vertical stiffeners are provided in a spacing of 0.33d to 1.5 d, where d is the distance between the flanges ignoring the fillets.

596. To prevent local crushing of the web due to concentrated loading, which type of stiffeners are provided?

(a) Torsion stiffeners
(b) Diagonal stiffeners
(c) Load carrying stiffeners
(d) Bearing stiffeners

GPSC AE January 2018

Ans. (d) : Bearing stiffeners are the additional stiffeners required at the top of concentrated loads for the purpose of protecting the web from compressive loads or local crushing.

597. Match List-I with List-II and select the correct answer using the loads given below the list :

List-I (Type of stresses)	List-II (Allowable value of stress)
A. Axial tension	1. 0.75 f_y
B. Bending tension	2. 0.66 f_y
C. Maximum shear stress	3. 0.60 f_y
D. Bearing stress	4. 0.40 f_y

(f_y=minimum field stress of steel)

Code :

	A	B	C	D
(a)	2	3	1	4
(b)	3	2	4	1
(c)	2	3	4	1
(d)	3	2	1	4

MPPSC AE 2014

Ans. (b)

List-I (Types of stress)	List-II (Allowable value of stress)
A. Axial tension	1. 0.60 f_y
B. Bending tension	2. 0.66 f_y
C. Maximum shear stress	3. 0.40 f_y
D. Bearing stress	4. 0.75 f_y

598. Gusset plates are designed to resist

(a) Torsion & bending
(b) Only shear
(c) Shear & bending
(d) Shear, bending & torsion

GPSC AE June 2019

Ans. (c) : Gusset plates are designed to resist shear and Bending.
Gusset plate is a plate for connecting beams and girders to columns. They are used in bridges and buildings, as well as other structures.

599. Which one of the sections is most efficient for gantry girder

(a) I section with equal flanges
(b) I section with channel attached to the top flange
(c) I section with a wide bottom flange
(d) I section with a heavy connected bottom flange

GPSC AE June 2019
ESE 2006

Ans. (b) : I-section with a channel attached to the top flange is the most efficient for a simply supported gantry girder. The reinforcement of channel section to compression flange of I-section will increase lateral buckling strength.

600. The imperfection factor for lateral torsional buckling of beams for welded steel sections is

(a) 0.65 (b) 0.21
(c) 0.45 (d) 0.49

GPSC AE Dec 2018

Ans. (d) : The imperfection factor for lateral torsional buckling of beams for welded steel sections is 0.49.
And for rolled steel section is 0.21

601. The shear lag effect in beam flanges is disregarded when the width of flange with outstand supported along one edge is less than or equal to (Here L_0 is the length between points of zero moment in the span)

(a) $\frac{L_0}{10}$ (b) $\frac{L_0}{15}$
(c) $\frac{L_0}{20}$ (d) L_0

GPSC AE Dec 2018

Ans. (c) The shear lag effect in beam flange is disregarded when, $b \le \frac{L_0}{20}$

602. In the plate girder the vertical stiffeners are provided when the ratio of clear depth of the thickness of web exceed:

(a) 50 (b) 65
(c) 75 (d) 85

PTCUL AE 2016

Ans. (d) : As per IS 800 : 2007, in plate girder the vertical stiffeners are provided when ratio of clear depth to thickness of web exceed 85.

603. The maximum shear stress of steel member in flexure shall not exceed:

(a) 0.45 f_y (b) 0.66 f_y
(c) 0.40 f_y (d) 0.87 f_y

PTCUL AE 2016

Ans. (a) : As per IS 800 : 2007, the maximum shear stress of steel member in flexure or bending shall not be exceed 0.45 f_y.

604. The problem of lateral buckling can arise only in those steel beams which have

(a) Moment of inertia about the bending axis larger than the other

Search on Telegram @apna_pdf

(b) Moment of inertia about the bending axis smaller than the other
(c) Fully supported compression flange
(d) None of the above

UJVNL AE 2016
ESE 2014

Ans. (b) The problem of lateral buckling can arise only in those steel beams which have moment of inertia about the bending axis smaller than the other.

605. Which of the following is a correct match ?
(a) Castellated girder -ISA
(b) Purlin - ISLC
(c) Joist - ISF
(d) Girder - ISHB

UPPCL AE 2019

Ans. (b) : For purlin ISLC (Indian Standard Light Channel is used.
There are mainly 4 types of channels :
ISLC - IS Light channel
ISMC - IS medium channel
ISSC - IS special channel

606. A beam section is classified as low shear case when the factored shear force is less than:
(a) $0.4\ V_d$ (b) $0.6\ V_d$
(c) $0.8\ V_d$ (d) V_d

LMRC AM 2018

Ans. (b) : For low shear case –
$V \le 0.6\ (V_d)$
Where
V= Shear force
V_d = design shear capacity

607. As per IS 800 : 1984, when cranes are manually operated, the vertical deflection of gantry girder under dead and imposed load should not exceed (where, L = span of crane runway girder)
(a) $\frac{L}{650}$ (b) $\frac{L}{500}$
(c) $\frac{L}{750}$ (d) $\frac{L}{1000}$

DMRC AM 2020
Rajasthan VP ITI 2018

Ans. (b) : As per IS 800 : 1984 when cranes are manually operated the vertical deflection of gantry girder under dead an imposed load should not exceed $\frac{L}{500}$.

608. The maximum lateral deflection of a gantry girder between rail as is :
(a) L/400 (b) L/500
(c) L/700 (d) L/600
(e) L/800

CGPSC AE 2017

Ans. (a) The maximum lateral deflection of a gantry girder between rail as is L/400.

609. As per IS 800 : 2007, the resistance to shear buckling shall be verified when.....for a unstiffened web.
(a) $\frac{d}{t_w} > 67\varepsilon$ (b) $\frac{d}{t_w} > 80\varepsilon$
(c) $\frac{d}{t_w} > 75\varepsilon$ (d) $\frac{d}{t_w} > 90\varepsilon$
(e) $\frac{d}{t_w} > 100\varepsilon$

CGPSC AE 2017

Ans. (a) As per IS 800 : 2007, the resistance to shear buckling shall be verified when $\frac{d}{t_w} > 67\varepsilon$ for a unstiffened web.

610. The outstand of the flange of build-up beams from the line of connection should not extend beyond.
(a) 10 t (b) 85 t
(c) $256t/\sqrt{f_y}$ (d) 180 t_w

Haryana PSC AE 2017

Ans. (c) : Out stand length = $\frac{256t}{\sqrt{f_y}}$ or 16t which ever is less will be taken.

611. Economical depth of a plate girder corresponds to -
(a) Minimum weight
(b) Minimum depth
(c) Maximum weight
(d) Minimum thickness of web

Rajasthan VP ITI 2018

Ans. (a)

612. The web crippling due to excessive bearing stress - can be avoided by :
(a) Increasing the web thickness
(b) Providing suitable stiffeners
(c) Increasing the length of the bearing plates
(d) None of the above

UP Jal Nigam AE 2016

Ans. (b) : The web crippling due to excessive bearing stress - can be avoided by providing suitable stiffeners.

613. Consider the following statements about plate girder
(a) Deep structural member subjected to transverse load
(b) They are economically used for span upto 30m
(c) Element of plate girder are web plate, flange angle and flange plate
(d) Depth of plate girder is less than 750 mm is known as below plate girder.

UP Jal Nigam AE 2016

Ans. (d) : Assumption of plate girder :
- Deep structural member subjected to transverse load.
- They are economically used for span upto 30m.
- Element of plate girder are web plate, flange angle and flange plate.
- Depth of plate girder is less than 750 mm is known as below plate girder or shallow plate girder.

Search on Telegram @apna_pdf

614. Most suitable section for gantry girder is :
(a) I beams
(b) Channel section
(c) Beam with channel at the top flange
(d) I beam with channel at the top flange

UP Jal Nigam AE 2016

Ans. (c) : Most suitable section for gantry girder is beam with channel at the top flange.

615. The strength rolled steel beams is increased by adding plates to its flange such beams is/are known as :
(i) Built up beams
(ii) Compound beams
(iii) Compound girder
Which of the above statements is/are correct?
(a) (i) (ii) (b) (i) (iii)
(c) (ii) (iii) (d) (i) (ii) (iii)

UP Jal Nigam AE 2016

Ans. (d) : The strength rolled steel beams is increased by adding plates to its flange such beams is/are known as Built up beams, Compound beams and Compound girder .

616. Which of the following plates is used for connecting two or more structural members intersecting each other?
(a) Template (b) Base plate
(c) Gusset plate (d) Shoe plate


UPRVUNL AE 2014

Ans. (c) : Gusset plates is used for connecting two or more structured members intersecting each.

617. The distance between C.G. of compression and C.G. of Tension Flanges of a Plate Girder is known as:
(a) Clear depth (b) Effective depth
(c) Overall depth (d) None of these

RRB SSE Bilaspur : 21.12.2014

Ans : (b)



In general depth of the plate girder is kept 1/10 th to 1/12 th of the span the distance between C.G. of compression flange and C.G. of tension flange is known as effective depth of plate girder.

618. For a simply supported span supporting brittle cladding in industrial building, the maximum vertical deflection as per IS : 800-2007 is restricted to ..... .
(a) span/150 (b) span/300
(c) span/120 (d) span/240

HPPSC Poly. Lect. 2016

Ans : (b) The maximum lateral deflection in other buildings subjected to wind load and for brittle cladding is L/500 and for elastic cladding is L/300.

619. Stiffener is provided for different requirements in steel structures. Which of the following stiffener is not under the requirements?
(a) Tension Stiffener (b) Torsional Stiffener
(c) Bearing Stiffener (d) Wearing Stiffener

IRCON AE 2017

Ans. (d) : Stiffener are secondary plates or sections which are attached to beam webs or flanges to stiffen them against out of plane deformation and wearing stiffener is not used in steel structure.

620. What will be the stiffness of a member with flexural displacement with its far end fixed?
(a) $\frac{3EI}{L}$ (b) $\frac{6EI}{L}$
(c) $\frac{4EI}{L}$ (d) $\frac{2EI}{L}$

IRCON AE 2017

Ans. (c) : When far end is simply supported.
stiffness $K = \frac{3EI}{L}$
for far end as fixed $\boxed{K = \frac{4EI}{L}}$
K = Stiffness, E = Young's modulus of elasticity.
I = moment of inertia of beam
L = beam length

621. In an I shaped section of equal flange width, the maximum resistance to shear is taken at which of the following positions?
(a) Middle of top flange
(b) Both top and bottom fibres
(c) Middle of bottom flange
(d) Mid point of web

JUVNL AE 2016

Ans. (d) : Maximum shear is considered at the mid (C.G.) point of section, if the section is symmetric. Here, I beam is symmetric and CG is at mid of web.

622. Intermediate vertical stiffeners are provided in plate girder to
(a) Eliminate web buckling
(b) Eliminate local buckling
(c) Transfer concentrated load
(d) Prevent increasing deflection

WBPSC AE 2012

Ans. (a) : When the thickness of the web is very less (less than 1/85th of the depth of the web) the web may buckle due to shear. In that scenario. Inter mediate vertical stiffeners are provided in order to improve the buckling strength of the web.

623. For unstiffened web, the slenderness ratio adopted to check web bucking is
(a) $\frac{h_1}{t_u}$ (b) $\frac{h_1\sqrt{3}}{t_u}$
(c) $\frac{t_w\sqrt{2}}{h_1}$ (d) $\frac{h_1\sqrt{2}}{t_w}$

WBPSC AE 2007

Ans. (b) :

Search on Telegram @apna_pdf

624. In a plate girder the flange splicing is done at
(a) Minimum shear location
(b) Minimum moment location
(c) Maximum shear location
(d) Maximum moment location

WBPSC AE 2003

Ans. (b) : Splices in the web of the plate girder are designed to resist the minimum shear moment at the spliced section.

625. The purpose of stiffeners in a plate girder is to
(a) Prevent buckling of web plate
(b) Increase the moment carrying capacity of the girder
(c) Reduce the shear stress
(d) Take care of bearing stress

WBPSC AE 2003

Ans. (a) : Stiffener are provided in the plate girder to prevent the buckling of the web plate if –

$\frac{d}{t_w} \le 85$ – No stiffeners are required.

$85 < \frac{d}{t_w} \le 200$ – Only vertical stiffeners are provided.

$200 < \frac{d}{t_w} \le 250$ – One horizontal stiffeners with Vertical stiffeners is provided [2/5th distance from N.A. is compression side.]

626. Horizontal stiffness are generally provided when the ratio of clear depth to the thickness of web exceeds
(a) 50 (b) 150
(c) 100 (d) 200

WBPSC AE 2001

Ans. (d) : If $\frac{d}{t_w} > 200$, Horizontal stiffeners are provided above neutral axis at distance of 0.2 t_w from the compression flange.

627. The greatest permissible dimension of the web is panel of a plate girder is restricted to
(a) 230 t (b) 260 t
(c) 270 t (d) 25 t
Where t is the thickness of the web

WBPSC AE (MCD) 1998

Ans. (c) : A plate girder is type of beam built from plates of steel that are either bolted or welded together the web is panel of a plate girder is restricted to 270t.

628. Impact allowance for crane girders and supporting columns for electrically operated heavy duty cranes is
(a) 10% (b) 25%
(c) 30% (d) 50%

WBPSC AE (PHE) 1998

Ans. (a) : For manually operated cranes, 10% of the static wheel load is taken as impact load because they move slowly.

629. Transverse surge force on the rail head from on EOT crane girder, when compared with combined weight of crab and weight lifted is
(a) 5% (b) 10%
(c) 15% (d) 20%

WBPSC AE (PHE) 1998

Ans. (a) : Additional loads to be considered for structures subjected to impact loads.

Type of load	Additional load
(a) Vertical force transferred to the Rail (i) for electric overhead cranes	25% of maximum static wheel load
(b) Horizontal force transferred to the rail (i) for hand operated cranes	5% of the weight of the rail and the weight on the crane
(c) Horizontal forces along the rail	5% of the static wheel load.

630. Intermediate vertical stiffeners are provided in a plate thickness is less than
(a) d/45 (b) d/85
(c) d/100 (d) d/200

WBPSC AE (PHE) 1998

Ans. (b) : When the thickness of the web is very less (less than 1/85th of the depth of the web) the web may buckle due to shear. In that scenario. Inter mediate vertical stiffeners are provided in order to improve the buckling strength of the web.

631. Maximum deflection in a steel beam should not generally exceed
(a) 0.002 mm (b) 0.02 mm
(c) 0.06 mm (d) 0.2 mm

WBPSC AE (Common) 1998

Ans. (a) : The maximum deflection for a beam shall not exceed $\frac{1}{325}$ (0.0030 ≈ 0.002 mm) of the span.

632. The maximum deflection in a steel beam should be generally exceed
(a) span/325 (b) span/300
(c) span/250 (d) span/400

WBPSC AE (Common) 1998

Ans. (a) : The maximum deflection in a steel beam should be generally span/325.

633. The vertical stiffener of a plate girder is provided is d/tv exceeds-
(a) 200 (b) 85
(c) 250 (d) 400

WBPSC AE (Common) 1998

Ans. (b) : When the thickness of the web is less than 1/85 th of the depth of the web then vertical stiffeners of a plate girder are provided.

634. The list of principal components of a plate girder is _____.
i. Top and bottom flange plates and web plates.
ii. Horizontal stiffeners, Intermediate and bearing stiffeners.
iii. Cleat angles and seat angles.
iv. Web splicing and flange splicing.

Search on Telegram @apna_pdf

(a) i, iii, iv (b) i, ii, iii
(c) i, ii, iv (d) ii, iii, iv

TSPSC Deputy Engineer 2015

Ans. (c) : The list of principal components of a plate girder is–
- Top and bottom flange plates and web plates.
- Horizontal stiffeners, Intermediate and bearing stiffeners.
- Web splicing and flange splicing.

635. The requirements to be satisfied in the design of a gantry girder are that it has to withstand effects due to _____.
(a) Moving loads, impact effects and fatigue.
(b) Moving loads, longitudinal loads, lateral loads, impact effects and fatigue.
(c) Lateral loads, longitudinal loads, impact effects and fatigue.
(d) Dynamic loads, longitudinal loads, impact effects and fatigue.

TSPSC Deputy Engineer 2015

Ans. (b) : Gantry girder are subjected to gravity load (D.L. + weight of crab + weight of truss etc.), lateral loads and longitudinal load these load acts manually.

636. The principal reason for adding stiffness to the web of a steel beam is to _____.
(a) Increase its moment carrying capacity.
(b) Reduce the deflection of the beam.
(c) Increase the stiffness of the web.
(d) Improve aesthetics.

TSPSC Deputy Engineer 2015

Ans. (c) : The main reason for adding stiffeners to the web of a steel beam is to increase the stiffeners of the web.

637. A simply supported girder of span 10m is traversed by a 5m long UDL segment of intensity 10 kN/m. The magnitude of absolute maximum moment in the beam is ____.
(a) 93.75 kN.m (b) 98.75 kN.m
(c) 90.25 kN.m (d) 88.75 kN.m

TSPSC Deputy Engineer 2015

Ans. (a) :

638. For a simply supported girder, EUDLL is defined as the intensity of the UDL acting on full span whose _____.
(a) intensity is larger than all other loads acting on the span.
(b) moment diagram is above the bending moment caused by all loads on the span.
(c) bending moment diagram just envelops bending moment caused by all loads on the span.
(d) intensity is larger than the sum of intensities of all loads on the span.

TSPSC Deputy Engineer 2015

Ans. (c) :

639. The stiffener which prevents local crushing of the web of plate girder due to concentrated loading is:
(a) Diagonal stiffener
(b) Intermediate transverse stiffener
(c) Load carrying stiffener
(d) Bearing stiffener

TSPSC AEE 2017

Ans. (d) : Bearing stiffeners are placed over the end bearing of welded plate girder and over intermediate bearing of continuous welded plate girders. They consist of two or more plates placed on both sides of the web.

640. The recommended limit of vertical deflection for gantry girder carrying EOT crane of capacity 50 tons is
(a) Span/750 (b) Span/500
(c) Span/300 (d) Span/240

TSPSC AEE 2017

Ans. (a) : Where electric overhead travelling crane are operated upto 50t $\Rightarrow \frac{L}{750}$

Where electric overhead travelling cranes are operated, over 50t $\Rightarrow \frac{L}{1000}$

641. Why are intermediate vertical stiffeners provided in plate girders?
(a) To eliminate web buckling
(b) To eliminate local buckling
(c) To transfer concentrated loads
(d) To prevent excessive deflection

Chandigarh AE 2017

Ans. (a) : Intermediate vertical stiffeners provided in plate girder to eliminated web buckling.

642. A beam is made of two identical metal flats soldered together. What is the ratio of stiffness of this beam to the stiffness of a beam in which the two flats are not soldered and which acts independently?
(a) 2 (b) 4
(c) 6 (d) 8

Chandigarh SDE 2017

Ans. (b) : Stiffeners of a beam is directly proportional to the moment of inertia of the cross section about its centroidal axis

$$\frac{\text{stiffeners soldered beam}}{\text{stiffeners unsoldered beam}} = \frac{\frac{b(2d)^3}{12}}{2\times\frac{bd^3}{12}} = 4$$

643. It is recommended that the reinforcement splicing for members should not be done at locations where the bending moment is more than P% where P is :
(a) 33 (b) 75
(c) 50 (d) 67

UPPCL AE 2015

Ans. (c) : According to IS 800 – 2007.
For the bending moment is more than P% (as P = 50) so that the reinforcement splicing for member should not be done at location.

Search on Telegram @apna_pdf

6. Column Base & Foundation

644. Web buckling occurs in a beam due to excessive
(a) Direct tensile stress in the web
(b) Bending tensile stress in the web
(c) Torsional shear stress in the web
(d) Compressive stress in the web

ISRO Scientist/Engineer 2020
ESE 2015

Ans. (d) : Web buckling occurs when the vertical compressive stress in the web at mid height reaches the critical buckling stress, as the thing web acts as a long slender column due to the action of heavy concentrated load on a beam a reason of high compressive stress is formed directly under the loads.

645. As per IS 800 : 1984, the thickness of slab base is
(a) $\frac{3w}{\sigma_{bs}}\left(a^2-\frac{b^2}{4}\right)$ (b) $\frac{3w}{\sigma_{bs}}\left(\frac{a^2-b^2}{4}\right)$
(c) $\sqrt{\frac{3w}{\sigma_{bs}}\left(a^2-\frac{b^2}{4}\right)}$ (d) $\sqrt{\frac{3w}{\sigma_{bs}}\left(\frac{a^2-b^2}{4}\right)}$

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (c) As per IS 800 : 1984, the thickness of slab base is $\sqrt{\frac{3w}{\sigma_{bs}}\left(a^2-\frac{b^2}{4}\right)}$

646. The depth of footing shall be calculated for
(a) bending moment
(b) bending moment and checked for shear
(c) shear and checked for bending moment
(d) shear

TRB Poly. Tech. Lect. 2012

Ans. (c) : The depth of footing shall be calculated for shear and checked for Bending moment.

647. The maximum admissible slenderness ratio of a steel column in which the design is governed wind load combination is :
(a) 120 (b) 180
(c) 250 (d) 350

(UKPSC AE (Paper-I) 2007)

Ans : (c) Compression member in which stress due to wind load and earthquake is considered should have slenderness ratio less than 250.

648. In column Analogy method, the area of an analogous column for fixed beam of span 'L' and flexural rigidity 'EI' is taken as–
(a) L/EI (b) L/2EI
(c) L/3EI (d) L/4EI

(UTTRAKHAND AE 2013)

Ans : (a) In column analogy method, the area of an analogous columns for fixed beam of span 'L' and flexural rigidity 'EI' is taken as L/EI.

649. The design of eccentrically loaded steel column needs revision if
(a) $\frac{f'_c}{f_c}+\frac{f'_b}{f_b}=1$ (b) $\frac{f'_c}{f_c}-\frac{f'_b}{f_b}<1$
(c) $\frac{f'_c}{f_c}+\frac{f'_b}{f_b}<1$ (d) $\frac{f'_c}{f_c}+\frac{f'_b}{f_b}>1$

(UKPSC AE 2012 Paper–I)

Ans : (d) If a member is eccentrically loaded, then, it is subjected to both direct and torsional stress and $\frac{f'_c}{f_c}+\frac{f'_b}{f_b}<1$; if $\frac{f_c'}{f_c}+\frac{f_b'}{f_b}>1$, then member should be redesigned.

650. Which one of the following is most suitable section for steel column section ?
(a) ISWB (b) ISMB
(c) ISHB (d) ISLB

Rajasthan JEN (Degree) Shift - II 2016

Ans. (c) ISHB (Indian Standard Heavy Beam) is best suitable section for steel column.

651. Column splice is used to increase
(a) Cross-sectional area
(b) Width of the column
(c) Length of the column
(d) Strength of the column


ISRO Scientist/Engineer 2020
Rajasthan Nagar Nigam AE Shift-2, 2016

Ans. (c) : A column splice means the joining of two parts of column where as a column base transfer forces and moment at the lower end of a column to a foundation.

652. Effective length of a column fixed at one end and pinned at the other end is
(a) $2l$ (b) l
(c) $\frac{l}{\sqrt{2}}$ (d) $\frac{l}{2}$

TNPSC AE 2019

Ans. (c)



653. In the design of steel columns, the shear resistance at the proper contact surface between steel base and concrete/grout may be calculated using a friction coefficient of
(a) 0.25 (b) 0.35
(c) 0.65 (d) 0.55
(e) 0.45

HPPSC 2016-II
CGPSC AE 2014 Shift–I

Ans. (e) : As per IS - 800 - 2007 (C 7.4.1), shear resistance at the proper contact surface between steel base & concrete grout may be calculated using a friction coefficient of 0.45.

Search on Telegram @apna_pdf

654. In order to account for the shear deformation and associated effects, the effective slenderness ratio of laced columns shall be taken as k times, the actual maximum slenderness ratio. The value of k specified in IS 800 is

(a) 0.95 (b) 0.85
(c) 1.15 (d) 1.1
(e) 1.05

CGPSC AE 2014 Shift–I

Ans. (e) : As per IS 800 - 2000, (Cl 7.6.15) the effective slenderness ratio $(KL/r)_e$, of load columns shall be taken as 1.05 times the $(Kl/r)_0$, the actual maximum slenderness ratio, in order to account for shear deformation effects.

655. Choose the wrong statement:

(a) Column is a vertical member of a structure which carries an axial compressive force.
(b) The ratio of length of a column to its minimum radius of gyration is called slenderness ratio.
(c) A column tends to buckle in the direction of the minimum moment of inertia.
(d) The equivalent length of a column with one end fixed and other end free, is half of its actual length.

TNPSC AE 2012


Ans. (d) The equivalent length of a column with one end fixed and other end free, is twice of its actual length $\boxed{l_{eff} = 2l}$.

656. For a circular column section to avoid tension, the limit of eccentricity "e" is (where D is diameter of the column)

(a) $\frac{D}{3}$ (b) $\frac{D}{8}$
(c) $\frac{D}{5}$ (d) $\frac{D}{6}$

TNPSC AE 2012

Ans. (b)



For a circular column section to avoid tension, the limit of eccentricity "e" is $\frac{D}{8}$

657. Web stiffeners are to be provided where a concentrated load, which exceeds x percent of the shear capacity of the member, is applied within D2 of a plastic hinge location. What is x?

(a) 10 (b) 20
(c) 15 (d) 25

CIL MT 2017

Ans. (a) :

658. Columns are

(a) Structural members subjected to compressive stress in a direction parallel to its longitudinal axis
(b) Structural members subjected to compressive stress in a direction not parallel to its longitudinal axis
(c) Structural members subjected to compressive stress in a direction parallel to both its axes
(d) None of the above

GESCOM (KARNATAKA) AE 2011

Ans : (a) Columns are structural members subjected to compressive stress in a direction parallel to its longitudinal axis.

659. The foundation provided below a heavily loaded steel column on a soil of low bearing capacity is :

(a) Isolated column footing
(b) Grillage foundation
(c) Raft foundation
(d) Strip footing

KPSC AE 2020

Ans. (b) : The foundation provided below a heavily loaded steel column on a soil of low bearing capacity is Grillage foundation.

660. The bracing provided in the plane of end posts is called :

(a) Sway bracing
(b) Portal bracing
(c) Top lateral bracing
(d) Bottom lateral bracing

Nagaland PSC CTSE 2017 Paper–I

Ans. (b) : End post → Portal Bracing is provided in plane of end post, they are designed to transfer 50% of the top Panel wind load to Bottom bracing.

661. The effective length of a battened column increased :

(a) 5% (b) 15%
(c) 10% (d) 25%

Nagaland PSC CTSE 2017 Paper–I

Ans. (c) : As per IS-800-2007 (Cl 7.7.1.4)
the effective slenderness ratio $\left(\frac{KL}{r}\right)_e$ of battened columns, shall be taken as 1.1 times the $\left(\frac{KL}{r}\right)_0$ the maximum actual slenderness ratio of the column, to account for shear deformation effect.

662. The lighter sections of structural member subjected to transverse loading are called as :

(a) Struts (b) tie
(c) Joists (d) Stanchions

Nagaland PSC CTSE 2017 Paper–I

Ans. (c) : Strut & stanchions → axial compression
Tie → axial tension
Joist subjected to transverse loading not axial loading

663. Slenderness ratio of a compression member is the ratio of effective length of member to the :

(a) Critical load

Search on Telegram @apna_pdf

(b) Radius of gyration
(c) Area of cross-section
(d) Weight of section

Nagaland PSC CTSE 2017 Paper–I

Ans. (b) : Slenderness ratio of compression member :
→ The tendency of member to buckle is usually measured by its slenderness ratio.

$$\text{slenderness Ratio of member}(\lambda) = \frac{\text{effective length}}{\text{Radius of gyration}}$$

664. The torsional stiffness of a member can be defined as :
(a) Torque for unit moment
(b) Moment for unit twist
(c) Torque for unit twist
(d) Torsion for unit twist

Nagaland PSC CTSE 2017 Paper–I

Ans. (c) Torsional stiffness : The measure of torsional stiffness is the Angle of twist of one part of shaft relative to another part when a certain torque is applied.
Torsional stiffeners C_T is calculated as the ratio between applied torque T and angle of deformation

$$C_T = \frac{T}{\alpha}\ \text{Nm/deg}$$

665. Unequal settlements in the supports of a statically indeterminate structure develop.
(a) Member forces
(b) Reactions from supports
(c) No reactions
(d) Strains in some members only

Nagaland PSC CTSE 2017 Paper–I

Ans. (b) : Unequal settlements in the supports of a statically indeterminate structure develop reactions from support.

666. The correct maximum shear capacity of a prismatic beam under plastic design of steel structures is :
(a) $0.60\ Af_y$ (b) $0.75\ Af_y$
(c) $0.55\ Af_y$ (d) $0.50\ Af_y$
Where symbols have their usual meaning.

UKPSC AE (Paper-I) 2007
ESE 2006

Ans : (c) For prismatic steel section maximum permissible stresses are as follows–
Axial tension and compressive stress → $0.60\ f_y$
Bending stress → $0.66\ f_y$
Bearing stress → $0.75\ f_y$
Shear stress, (a) maximum → $0.45\ f_y$
(b) Average → $0.4\ f_y$
For plastic design, maximum shear stress is $0.55\ f_y$.

667. A steel member is designed with a consideration for failure governed by buckling. What should be the partial factor of safety for materials to be considered?
(a) 0.90 (b) 1.00
(c) 1.10 (d) 1.25

(UP RVNL AE 2016)

Ans : (c) Partial safety factor for a material when failure is governed by buckling is taken as 1.1.

668. The width (thickness) of a gusset plate for the base of the pillar should not be less than :
(a) 6 mm (b) 8 mm
(c) 12 mm (d) 40 mm

UKPSC AE 2012 Paper–I

Ans : (b) Gusset plate is used to join different members of a structure such as roof, columns etc, to one another by riveting, welding. Thickness of gusset plates in pillars is taken from 8 mm to 16 mm and rivet of diameter 22 mm or more is used.

669. Where should splices in column be provided ?
(a) At the floor level
(b) At the mid height of column
(c) At the beam column joint
(d) At one–fourth height of column

UKPSC AE (Paper-I) 2007

Ans : (d) A splice plate should be located at the point of contraflexure of the column. If column ends are restrained in direction and position, contraflexure point will be at the middle of the column due to wind stresses.
In case of typical column splices are always given 1/4th of the column height.
However, due to direct load there will be two points of contraflexure varying from middle to the point above and below middle. For column of two storey length, splice it at about 30-150 cm above floor level.

670. Effective length of a column is the length between the points of :
(a) maximum moments
(b) zero shear
(c) zero moment
(d) none of the above

UKPSC AE (Paper-I) 2007

Ans : (c) Effective length of column is the length between point of zero moments.


671. The thickness of the base plate provided for a steel column is determined from
(a) flexural strength of plate
(b) shear strength of plate
(c) bearing strength of the concrete pedestal
(d) punching criteria

GPSC AE (CLASS 1 & 2) 2019
Maharashtra PSC (Mains) 2019 Paper–I
UKPSC AE 2012 Paper–I

Ans : (a) Thickness of base plate provided for steel column is determined from flexural strength of plate

$$f = \sqrt{\frac{3w}{\sigma_{bs}}\left(a^2 - \frac{b^2}{4}\right)}$$

t = thickness of the base plate



672. Rotation of Machine foundation about Y, Z and X axes are respectively known as–
(a) Yawing, Pitching and Rocking

Search on Telegram @apna_pdf

(b) Pitching, Yawing and Rocking
(c) Rocking, Pitching and Yawing
(d) Rocking, Yawing and Pitching

(UTTRAKHAND AE 2013)

Ans : (d) For machine foundation rotation about x, y and z plane is known as pitching, rocking and yawning respectively.

673. The permissible bending stress in the slab base of columns for all grades of steel is limited to–

(a) 185 N/mm^2 (b) 165 N/mm^2
(c) 175 N/mm^2 (d) 200 N/mm^2

(UTTRAKHAND AE 2013)
RPSC ACF 2011

Ans : (a) Permissible bending stress in slab base is limited to 185 N/mm^2.
Stress in plate from concrete is limited from 0.45 f_{ck} to 0.6 f_{ck}.

674. In a grillage footing the beams in each tier are spaced such that the minimum spacing between the flanges of the two consecutive beams is not less than

(a) 50 mm (b) 75 mm
(c) 100 mm (d) 150 mm

RPSC A En.– 2013

Ans : (b) When the soil has low bearing capacity, large concrete blocks may become uneconomical and in such cases grillage footing is provided. The minimum spacing between flanges of two consecutive beams should not be less than 75 mm.

675. The effective length of compression steel column of length 'L' which is effectively held in position at both ends but not restrained against rotation is

(a) 0.65 L (b) 0.8 L
(c) L (d) 1.5 L

Maharashtra PSC AE (Mains) 2012 Paper–I
ESE 1999

Ans : (c) • Effectively held in position at both end but not restrained against rotation

$\boxed{l = L}$

• Effectively held in position and restrained against rotation at both ends $\boxed{l = 0.65L}$

• Effectively held in position at both ends, restrained against rotation at one end. $\boxed{l = 0.8\ L}$

• Effective held in position and restrained against rotation at one end and at the other and restrained against rotation but not held in position $\boxed{l = 1.2L}$

676. In a simply supported beam of span L each end is restrained against torsion, compression flange being unrestrained. According to IS : 800, the effective length of the compression flange will be equal to

(a) L (b) 0.85L
(c) 0.75L (d) 0.70L

UPPSC State Eng. A.E. 2003

Ans : (a)

Type of member	End condition of bracing	Effective length, *l*
simply supported beams	Restrained against torsion and (i) unrestrained against lateral bending (ii) Partially restrained against lateral bending (iii) Fully restrained against lateral bending	 L 0.85 0.7
All members	Effective lateral bracing at intervals along the length	Distance b/w intersections of bracings with member

677. In the design of a base plate, the bearing strength of concrete as per the Indian Standard (IS) 800:2007, is taken as (f_{ck} is characteristic strength of concrete)

(a) 0.4 f_{ck} (b) 0.45 f_{ck}
(c) 0.5 f_{ck} (d) 0.60 f_{ck}

[MPPSC AE 2016]

Ans : (b) In design of base plate bearing strength of concrete is taken 0.45 f_{ck} and maximum bearing pressure should not exceed 0.6 f_{ck}.

678. When wind or seismic forces and considered for structural design, allowable stress in material are generally increased by

[UPPSC State Eng. A.E. 2011]

OR

Whenever the earthquake or wind loading is considered in design of member, the permissible stresses may increased by

(a) 20% (b) 25%
(c) $33\frac{1}{3}\%$ (d) 50%

[RPSC ACF 2011]
ESE 2001

Ans : (c) When wind or seismic forces and considered for structural design, allowable stress in material are generally increased by $33\frac{1}{3}\%$

679. Yield line theory results in

(a) elastic solution
(b) lower bound solution
(c) Upper bound solution
(d) unique solution

UPPSC State Eng. A.E. 2003
ESE 1995

Ans : (c) The yield line theory is the ultimate load theory. Both the virtual work method as well as equilibrium method give the upper bound solution, i.e. the computed collapse load on the basis of an assumed yield line pattern is bound to be larger than the actual collapse load.

Search on Telegram @apna_pdf

680. To prevent buckling of the top edge of a gusset plate due to bending compression, the outstand of the gusset plate from the edge of column should be limited to (thickness of plate = t; yield stress ratio = $t_q\varepsilon$)

(a) 9.40 $t\varepsilon$ (b) 8.40 $t\varepsilon$
(c) 13.6 $t\varepsilon$ (d) 29.3 $t\varepsilon$

MPPSC AE 2017

Ans. (c) : According to IS 800 : 2007, to prevent buckling of top edge of a gusset plate due to bending compression, the outstand of the gusset plate from the edge of column should be limited to 13.6 $t_q\varepsilon$.

681. A steel plate of size 250 mm × 150 mm × 10 mm with holes for two number of 16 mm diameter bolts having ultimate strength of 410 MPa, the design strength of plate in rupture of critical section is-

(a) 336 kN (b) 382 kN
(c) 365 kN (d) 280 kN

MPPSC AE 2017

Ans. (a) : Nominal diameter = 16 mm
Gross diameter = 16 + 2 = 18 mm

$$\text{Design strength} = \frac{0.9 f_u}{\gamma_{m1}} \times A_{net}$$

$$\text{So, Design strength} = \frac{0.9\times 410}{1.25}\times(B-2d_0)\times 10$$

$$= \frac{0.9\times 410}{1.25}\times(150-2\times 18)\times 10$$

$$= 336.528 \text{ kN}$$

Design strength = 336 kN

682. A square base plate of 1200 mm × 1200 mm is provided under a column 15 mb 400, which is carrying an axial force of 1440 kN along with bending moments of 288 kNm and 144 kNm about its Major and Minor axis respectively. The maximum pressure (neglecting Poisson's effect) anywhere on the base plate is-

(a) 2.5 N/mm^2 (b) 2.6 N/mm^2
(c) 2.75 N/mm^2 (d) 3.0 N/mm^2

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (a) :

$$\sigma_{max} = \frac{P}{A} + \frac{M_x y_y}{I_{yy}} + \frac{M_y y_x}{I_{xx}}$$

$$= \frac{1440\times 10^3}{1200\times 1200} + \frac{288\times 10^6\times 600\times 12}{(1200)^4}$$

$$+ \frac{144\times 10^6\times 600\times 12}{(1200)^4}$$

$$= 1+1+0.5 \text{ N/mm}^2 = 2.5 \text{ N/mm}^2$$

683. A solid steel plate having ultimate strength of 410 MPa, the design strength in rupture (N/mm^2) is-

(a) 250 (b) 295.2
(c) 335.45 (d) 410

MPPSC AE 2017

Ans. (b) : For Fe 410 plate, design strength in rupture is given as

$$\frac{0.9 f_u}{\gamma_{m1}} \text{ (Where, } f_u = 410 \text{ N/mm2 } \gamma_{ml} = 1.25)$$

$$\frac{0.9\times 410}{1.25} = 295.2 \; MPa$$

684. In a plate girder, bending is primarily resisted by-

(a) Web plate
(b) Flange plate only
(c) Flange angle only
(d) Flange plate and flange angle

OPSC AEE 2015 PAPER–I


Ans. (b) : The components of typical plate girder are as follows :
1. Web
2. flanges
3.stiffeners
In a plate girder, bending is primarily resisted by flange plates and shear by web.

685. The effective length of a steel compression member which is effectively held in position at both ends but restrained in direction at one end only-

(a) L (b) 0.8 L
(c) 1.2 L (d) 1.5 L

OPSC AEE 2015 PAPER–I

Ans. (b) : 0.8 L is effective length of a steel compression member which is effectively held in position at both ends but restrained in direction at one end only.



686. In a footing, it is usual to assume that the maximum value of transverse bending will occur at a distance, equal to (measured from the of the column)

(a) Half the effective depth
(b) Effective depth
(c) Twice the effective depth
(d) None of the given answers

APPSC AE 2016 (Mains)

Ans. (d) : As per IS code 456 : 2000 clause 34.2
The critical section of maximum bending moment for the purpose of designing an isolated concrete footing which supports a column, pedestal or wall shall be :
(i) Halfway between the centre line and the edge of the wall, for footing under masonry.

Search on Telegram @apna_pdf

687. The code advocates that for the determination of stress in a column section, the beam reactions can be assumed to be applied at an eccentricity of _____ from the face of section or at the centre of bearing.

(a) 200 mm (b) 5d or 450 mm
(c) 100 mm (d) 3d or 300 mm

[HPPSC 2016-II]

Ans. (c) : As per IS 800 : 2007
For the purpose of determining the stress in a stanchion or column section, the beam reactions or similar loads shall be assumed to be applied at an eccentricity of 100 mm from the face of the section or at the center of the bearing whichever dimension gives the greater eccentricity.

688. In case of bolted plate, the angle section that is used should be:

(a) Unequal with long leg connected
(b) Unequal with short leg connected
(c) Equal angle
(d) Equal angle connected back to back

GPSC AE (CLASS 1 & 2) 2019

Ans : (b) : In case of bolted plate the angle section that is used should be unequal with short leg connected.

689. The purpose of anchor bolts in column base is to

(i) Act as reinforcement in the concrete pedestal
(ii) To resist tension force
(iii) To keep the column in place

The correct purposes are

(a) (i) and (ii) (b) (ii) and (iii)
(c) (i) and (iii) (d) None of the above

GPSC AE (CLASS 1 & 2) 2019

Ans : (b) : The purpose of anchor bolt in column base is to resist tension force & to keep the column in place in vertical axis so that the load can be distributed to the footing to the base of plate and then to the soil surface. All the shear force will be resisted by web only, mainly any bending will be resisted by flange only.

690. The fasteners in gusseted base plate are designed for

(a) 25% (b) 50% column load
(c) 75% column load (d) 100% column load

GPSC AE (CLASS 1 & 2) 2019

Ans : (b) : In a gusset base, when the end of the column is machine smooth for complete bearing the axial load is transferred to base slab 50% by direct bearing and 50% through fastening.

691. Which among the following is also known as rolled steel joist?

(a) rolled steel T-section
(b) rolled steel channel section
(c) rolled steel I-section
(d) rolled steel angle section

Kerala PSC AE 2015


Ans. (c) : A Rolled Steel Joist (RJT) is a common type of beam used for structural steel work. It is also known as I-beam.
An RSJ is a beam with an 'I' or 'H' shaped cross section that comes in a variety of standard size. It is very efficient from for carrying bending and shear loads in the plane of the web (the vertical element).

692. A grillage foundation is essentially a:

(a) Shallow foundation (b) Deep foundation
(c) Spread foundation (d) Pile foundation

GPSC AE Class (1&2) Paper - 2 2017
KPSC AE 2016

Ans. (c) : A spread footing also called as isolated footing, pad footing and individual footing is provided to support an individual column.
Grillage Foundation – A foundation which consists of one, two or more tiers of beams (typically steel) superimposed on a layer of concrete to disperse load over an extensive area is grillage foundation. Grillage foundation is a type of spread foundation often used at the base of a column.



693. Bearing stiffeners are provided

(a) At the ends of plate girders
(b) At the ends of plate girder and on both faces of the web
(c) At the ends of plate girder and only on one face of the web
(d) At the points of concentrated loads, to protect the web from the direct compressive loads

ESE 2019

Ans. (d) : The bearing stiffeners are provided to prevent the web from crushing and buckling side way, under the action of concentrated load.
Bearing stiffeners are provided at the supports and the points of application of concentrated loads, to protect the web form the direct compressive loads.

694. Effective buckling length of a steel angle connected by double rivets is:

(a) 0.7 L (b) 0.85 L
(c) L (d) 1.3 L

ISRO Scientist/Engineer 2020

Ans. (b) Effective buckling length of a steel angle connected by double rivets is 0.85 L

695. Consider the following two statements regarding Bearing stiffness provided at the location of a concentrated load.

(1) Bearing stiffeners have to resist bearing and buckling loads.
(2) Bearing area and the area resisting buckling load are the same.

Search on Telegram @apna_pdf

Which of the above statements is/are *correct?*

(a) 2 only (b) 1 only
(c) Both 1 and 2 (d) Neither 1 nor 2

ESE 2017

Ans. (b)

- Bearing stiffeners have to resist direct bearing of support reaction and also resist the buckling of web of girders.
- Bearing stiffeners are provided at locations of support reactions and concentrated load.
- Bearing area and buckling area are not same.
- Bearing area is calculated at root of web by dispersion at a slope 1 : 2.5.
- Buckling area is calculated at neutral axis by dispersion at 45^0. Under concentrated load (or buckling load) and near support due to support reaction, the web behaves as a thin compression member.

696. The thickness of the column base plate is determined from

(a) Shear strength of the plate
(b) Flexural strength of the plate
(c) Punching shear strength
(d) Bearing strength of the plate

APTRANSCO AE 2017

Ans : (b) Thickness of base plate provided for steel column is determined from flexural strength of plate

$t = \sqrt{\frac{3w}{\sigma_{bs}}\left(a^2 - \frac{b^2}{4}\right)}$ t = thickness of the base plate.

697. The effective length, L, of a column having actual length, *l*, with one end fixed and other end free, is given by:

(a) $L = 2l$ (b) $L = \frac{l}{2}$

(c) $L = \frac{l}{\sqrt{2}}$ (d) $L = l$

WBPSC Poly Lect. 2019

Ans. (a) :

Description	Effective length
1. One en fixed and other hinged	$\frac{l}{\sqrt{2}}$
2. Both ends fixed	$\frac{l}{2}$
3. Both ends hinged	l
4. One ends fixed and other free	$2l$

698. The best arrangement to provide unified behaviour in built up column is by:

(a) lacing
(b) battening
(c) tie plate
(d) perforated cover plate

WBPSC Poly Lect. 2019

Ans. (a) : Slenderness ratio of lacing bar should be 145. The best arrangement to possible unified behaviour in built up column is by lacing.

699. An ISHB 300 with plastic section modulus of 921.68×10^3 mm^3, flange width of 250 mm, the yield stress of 250 N/mm^2 is embedded in a pocket base to develop its strength with M 25 concrete in design of beam-column. The required depth will be nearly.

(a) 475 mm (b) 425 mm
(c) 375 mm (d) 325 mm

ESE 2020


Ans. (a) : Given,

Yield stress (f_y) = 250 N/mm^2

plastic section modulus (Z_{pz}) = 921.68×10^3 mm^3

flange width (b_f) = 250 mm

f_{ck} = 25 N/mm^2



The required depth of section,

$$d = \sqrt{\frac{f_y . z_{pz}}{0.164 \times f_{ck} \times b_f}}$$

$$d = \sqrt{\frac{250 \times 921.68 \times 10^3}{0.164 \times 25 \times 250}}$$

$d = 474.13$ mm

or $\boxed{d \simeq 475\text{mm}}$

700. The splicing of a column becomes necessary, where :

(a) The available length of structural steel section is less than the required length of the column
(b) Section remains same throughout at all floors
(c) Only riveted columns are to be designed
(d) Splices should be designed to carry axial loads only

ESE 2020

Ans. (a) : When a joint is provided in the length of member is called splice.

Column section can be spliced in the following cases :

(i) When the length of column is more than the length of column section available.
(ii) In case of multi-storey building where the columns are provided along its height.
(iii) Splice is provided when real column has to resist the bending due to eccentricity of the load.


701. A hollow steel column has an external diameter of 250 mm and an internal diameter of 200 mm. If the safe compressive stress is 120 N/mm^2, the safe axial compressive load for the column is, nearly-

(a) 2210 kN (b) 2120 kN
(c) 2000 kN (d) 1500 kN

UPSC JWM 2017

Search on Telegram @apna_pdf

Ans. (b) :



Given, D = 250 mm
d = 200 mm
σ_c = 120 N/mm^2

Cross - section area = $\frac{\pi}{4}\left(250^2 - 200^2\right)$
= 17671.45 mm^2
force = σ.A = 120.0 × 17671.45
Load = 2120.57 kN

702. What is the minimum number of anchor bolts provided even if the steel column is subjected to only axial loads:
(a) 2 (b) 4
(c) 6 (d) 9

GOA PSC Assistant Prof. 2020

Ans. (a) : A minimum two anchor bolts are to be provided even if the steel column is subjected to only axial load.

703. In the foundation bolts fixing a column to its footing, the type of stress induced is
(a) pure compression (b) bearing
(c) pure tension (d) bending

Rajasthan Nagar Nigam AE Shift-2, 2016

Ans. (c) : The foundation bolts fixing a column to its footing, the type of stress induced is pure tension.

704. A plate used for connecting two or more structure members intersecting each other is
(a) Template (b) Base plate
(c) Gusset plate (d) Shoe plate

TSGENCO_2015

Ans. (c) : Gusset plate is used for connecting two or more structure members intersecting each other.

705. In a steel structure, the wires/cables are generally used as
(a) compression members
(b) tension members
(c) members for resisting shear
(d) Either (A) or (B)

BPSC AE Aug. 2019 Paper-V

Ans. (b) : In structural applications, cable or wire is generally used as a flexible tension member. There are several types of cables available for use in cable supported bridges.

706. While designing the foundations of a steel building, the strength and rigidity of the foundation relative to the superstructure will be :
(a) Lower than the superstructure
(b) Equal to superstructure
(c) Higher than superstructure
(d) Does not have to be in proportion to superstructure

UPRVUNL AE 2016

Ans.: (b) While designing the foundations of a steel building, the strength and rigidity of the foundation relative to the superstructure will be equal to superstructure.

707. A steel member is designed with a consideration for failure governed by buckling. What should be the partial factor of safety for materials to be considered?
(a) 0.90 (b) 1.00
(c) 1.10 (d) 1.25

UPRVUNL AE 2016

Ans.: (c) When a steel member is designed with a consideration for failure governed by buckling 1.10 should be the partial factor of safety for material to be considered.

708. To get the effective length of a prismatic steel compression member of length L fully restrained at both the ends, L is usually multiplied by what factor?
(a) 0.65 (b) 0.80
(c) 1.00 (d) 1.20

UPRVUNL AE 2016

Ans.: (a) L = Original length , L_e = effective length

End conditions	**Effective length**
1. 	$\ell = 0.65L$

709. The anchor bolts are provided to check the:
(a) settlement of foundation
(b) punching shear of base plate
(c) uplift of base plate
(d) moment of base plate

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (c) : The anchor bolts are provided to check the uplift or base plate.

710. Critical stress for elastic buckling of an Euler column will be
(a) $\pi^2\lambda / E^2$ (b) $\pi^2 E / \lambda^2$
(c) $\pi\lambda^2 / E^2$ (d) $\pi E^2 / \lambda$

GPSC AE Dec 2018

Ans. (b) : Critical stress for elastic buckling of an Euler column,

$$\sigma_c = \frac{\pi^2 E}{\lambda^2}$$

λ = slenderness ratio
E = Young's modulus

711. A steel column base is subjected to a moment. If the intensity of bearing pressure due to axial load is equal to stress due to moment , then the bearing pressure between the base and concrete is :
(a) Tension at one end and compression at other end
(b) Zero at one end and compression at other end
(c) Uniform compression throughout
(d) Uniform tension throughout

CIL MT 2020

Search on Telegram @apna_pdf

Ans. (b) : Zero at one end and compression at other end.
A steel column base is subjected to moment if the intensity of bearing present due to axial load is equal to stress due to moment, then the bearing pressure between the base and concrete is zone at one end and compression at other end.

712. In a gusseted base, when the end of the column is machined for completed bearing on the base plate, then the axial load is assumed to be transferred to base plate
(a) 100% by direct bearing
(b) 100% through fastenings
(c) 50% by direct bearing and 50% through fastenings
(d) 75% by direct bearing and 25% through fastenings

Haryana PSC AE 2010

Ans. (c) : In a gusset base, when the end of the column is machine smooth for complete bearing the axial load is transferred to base slab 50% by direct bearing and 50% through fastening.

713. In a steel column-base, if the steel plate rests on concrete with characteristics compressive strength of 20 MPa, what is the bearing stress at the interface between the steel plate and concrete surface?
(a) 6.00 N/mm^2 (b) 6.75 N/mm^2
(c) 7.00 N/mm^2 (d) 8.00 N/mm^2
(e) 9.00 N/mm^2

Haryana PSC AE 2018 Paper–I

Ans. (e) : 9.00 N/mm^2

714. The minimum thickness of plates in a steel chimney should be :
(a) 4 mm (b) 5 mm
(c) 6 mm (d) 8 mm

UP Jal Nigam AE 2016

Ans. (c) : The minimum thickness of plates in a steel chimney should be 6 mm.

715. The effective length of a column effectively held in position and restrained in directions at both ends, is equal to
(a) 0.67 L (b) 0.85 L
(c) 1.00 L (d) 1.50 L

WBPSC AE (MCD) 1998

Ans : (a) • Effectively held in position at both end but not restrained against rotation
$\boxed{l = L}$
• Effectively held in position and restrained against rotation at both ends $\boxed{l = 0.65L}$
• Effectively held in position at both ends, restrained against rotation at one end. $\boxed{l = 0.8\ L}$
• Effective held in position and restrained against rotation at one end and at the other and restrained against rotation but not held in position $\boxed{l = 1.2L}$

716. Cross-sectional area being the same, the most economical section for a column is
(a) 1 section (b) L section
(c) Flat shape (d) Tubular section

WBPSC AE (PHE) 1998

Ans. (d) : A tubular section is most efficient and economical for the column free to buckle in any direction. The radius of gyration for the tubular section in all the direction remains same. The tabular section has high local buckling strength.

717. According to IS: 456-2000, in the design of isolated RCC column footing using RCC with an effective depth d, the critical sections to be checked are _____.
(a) Bending moment at the face of the column, one-way shear at d/2 away from the face of column and two-way shear at d around the column.
(b) Bending moment at the face of the column, one-way at d away from the face of column and two-way shear at d around the column.
(c) Bending moment at d/2 away from the column, one-way shear at d away from the face of column and two-way shear at d/2 around the column.
(d) Bending moment at the face of the column, one-way shear at d away from the face of column and two-way shear at d/2 around the column.

TSPSC Deputy Engineer 2015

Ans. (d) : According to IS 456-2000 design of isolated RCC column footing to be check bending moment at the face of the column one-way shear at d away from the face of column and two-way shear at d/2 around the column.

718. The expression working out the thickness of slab base, σ_{bs} = permissible bending stress in slab base, a, b = longer and shorter projections of the slab base edge to the column member, Posions ratio = 0.25.
(a) $t = \left((3w/\sigma_{bs})(a - b/4)\right)^{1/2}$
(b) $t = \left((3w/\sigma_{bs})(a^2 - b^2/4)\right)^{1/2}$
(c) $t = \left((3w/\sigma_{bs})(a^2 - b^2)\right)^{1/2}$
(d) $t = \left((3w/\sigma_{bs})(a - b^2/4)\right)^{1/2}$

TSPSC Deputy Engineer 2015

Ans. (b) : The thickness of rectangular slab base as per IS 800 : 1984

$$t = \sqrt{\frac{3w}{\sigma_{bs}}\left(a^2 - \frac{b^2}{4}\right)}$$

Where,
t = thickness of slab base (mm)
w = the pressure or loading on the under side of the base (MPa)
a = the greater projection of the plate beyond the column (mm) = max (α, β)

Search on Telegram @apna_pdf

b = The lesser projection of the plate beyond the column (mm) = min (α, β)

σ_{bs} = The permissible bending stress in slab bases.
= 165 MPa for flanged beam
= 185 MPa for solid plate

719. In the built-up steel columns, the lacing is provided _____.

i. to keep all individual sections together.
ii. to take-up lateral shear to an extent of 2.5% of axial force.
iii. to increase the bending strength of the section.
iv. to increase the compressive strength of the section.

(a) i, iii (b) ii, iii
(c) iii, iv (d) i, ii

TSPSC Deputy Engineer 2015

Ans. (d) : In the built-up steel columns, the lacing is provided for–
- To keep all individual sections together.
- To take-up lateral shear to an extent of 2.5% of axial force.

720. Slenderness ratio of lacing bars should not exceed

(a) 100 (b) 120
(c) 180 (d) 145

Chandigarh AE 2017

Ans. (d) : Slenderness ratio of lacing bars should not exceed than 145.

721. The diameter of ties in a column should be

(a) more than or equal to one fourth of diameter of main bar
(b) more than or equal to 5 mm
(c) more than 5 mm but less than one-fourth of diameter of main bar
(d) more than 5 mm and also more than one-fourth of diameter of main bar

Chandigarh SDE 2017

Ans. (d) : The minimum diameter of the ties or helical reinforcement shall not less than $1/4^{th}$ the diameter of the largest longitudinal bars an in no case less than 5 mm. The maximum diameter of the dies or helical steel preferably be not more than 12 mm and 25 mm respectively.

7. Industrial Roof Trusses

722. In structural design work, the earthquake forces shall be calculated in accordance with the following IS Code

(a) IS 1904 (b) IS 1893
(c) IS 6909 (d) IS 12330

GPSC Assistant Prof. 2016

Ans. (b) : IS 1893 the earthquake forces shall be calculated in accordance with this code in structural design work.

723. In the equation $V_z = V_b k_1 k_2 k_3 k_4$ which is used for calculating the design wind speed V_z at any height z, which factor(s) is/are denoted by k_1

(a) Topography factor
(b) Terrain, height and structure size factor
(c) Probability factor
(d) Stability factor

GPSC AE Dec 2018

Ans. (c) : $V_z = V_b k_1 k_2 k_3 k_4$
k_1 = Probability factor
k_2 = Terrain roughness and ht. factor
k_3 = Topography factor
k_4 = Importance factor

724. According to IS 1893 (Part-1):2002, the zone factor for seismic zone III is equal to

(a) 0.10 (b) 0.16
(c) 0.24 (d) 0.36

GPSC AE Dec 2018

Ans. (b) : According to IS 1893 (Part-1):2002, the zone factor for seismic zone III is equal to 0.16.

725. Limit state of serviceability for deflection including the effects due to creep, shrinkage and temperature occurring after erection of partitions and application of finishes as applicable to floors and roofs is restricted to :

(a) $\frac{\text{Span}}{150}$ (b) $\frac{\text{Span}}{200}$
(c) $\frac{\text{Span}}{250}$ (d) $\frac{\text{Span}}{350}$

OPSC AEE 2019 Paper–I

Ans. (d) : The deflection including the effects of temperature, creep and shrinkage occurring after erection partitions and application of fine shear should not exceed span/350 (or) 20 mm whichever is smaller.

726. The most efficient cross section in a roof truss is

(a) Angle section (b) Circular section
(c) Rectangular section (d) Tubular section

APTRANSCO AE 2017

Ans : (d) The most efficient cross section in a roof truss is tubular section.

727. The principal rafter of a roof truss with purlins placed at intermediate parts on panel length can be analysed by

(a) method of joints
(b) method of sections
(c) graphical method
(d) moment distribution method

APTRANSCO AE 2017

Ans : (d) The moment distribution method is a structural analysis method for statically indeterminate beam and frames developed by Hardy Cross. It published in 1930 ASCE Journal

728. The members which support covering material of a steel roof truss are–

(a) Rafters (b) Purlins
(c) Struts (d) Battens

(UTTRAKHAND AE 2013)

Ans : (b) Purlins are beams provided over trusses to support the roofing between the adjacent trusses. These are placed in tilted position over the principal rafters of the trusses. They are designed as continuous beams. Distance between purlins is generally 1.5 m to 3 m.

Search on Telegram @apna_pdf

729. In the roof for principal rafter most frequently used section is :

(UKPSC AE (Paper-I) 2007)

(a) two channels placed back to back
(b) one angle and one channel placed back to back
(c) two angles placed back to back
(d) none of the above

Ans : (c) In tension member when member of required length is not available, then we use two different members. Generally members are connected to plates with the help of tension splices and riveted.

730. In a roof truss over an industrial building, purlins are provided to carry dead loads, live loads and wind loads. As per IS 800, the support conditions assumed for these would be

(a) Continuous (b) Fixed
(c) Cantilever (d) Simply supported
(e) Propped cantilever

CGPSC AE 2014 Shift–I

Ans. (a) : IS recommends the purlins to be designed as continuous beam.

731. Which of the following is an incorrect assumption in the analysis of truss?

(a) All joints are pinned
(b) Loads applied at joints only
(c) All members are straight
(d) Weights of members are acting at their centres

Kerala PSC AE 2015


Ans. (d) : Truss- a framework typically supporting a roof and consisting of rafters, post, strut in bridge or any structure.
→ Weight of member are assumed to be acting at joint and not at center.

732. In roof truss purlins, the sag rods are designed as-

(a) Compression members
(b) Laterally supported beams
(c) Laterally unsupported beams
(d) Tension members

MPPSC AE 2017

Ans. (d) :



A sag rod is designed as a tension member to resist the tangential component of the resultant of the roof load and purlin dead load.
At the crown, sag rod provided is termed as tie rod, this resists the tangential components from the two sides of the roof truss.

733. Roof trusses are generally used when the span exceeds:

(a) 3 m (b) 5 m
(c) 10 m (d) 15 m

Kerala PSC AE 2015

Ans. (b) : A triangular structural framework designed to provide support and strength of the roof is known as truss roof truss is generally used for span longer than 5m.

734. The fundamental natural period for vibration of steel frame building is

(a) $0.075\ h^{0.75}$ (b) $0.085\ h^{0.75}$
(c) $0.075\ h^{0.85}$ (d) $0.085\ h^{0.85}$

Gujarat PSC AE 2017

Ans : (b) Fundamental natural period for vibration (T_1 sec) may be approximated by following eqn.–

$$T_1 = C_t (H)^{0.75}$$

Where $C_t = 0.085$ for steel frame
and $C_t = 0.075$ for concrete frame
H is height of building (m)

735. A purlin is a roof beam, usually supported by

(a) Lintels (b) Joist
(c) Girt (d) Roof trusses

TNPSC AE 2019


Ans. (*) Purlins are horizontal beams that are used for structural support in buildings. Most commonly purlins are major components of roof structures. Roof purlins are supported either by rafter or building walls and the roof deck is laid over the purlins.

736. In roof trusses the most frequently used section is

(a) two-angle sections placed back to back
(b) two-channel sections placed back to back
(c) two-channel sections placed at a distance apart
(d) four-angle sections

TNPSC AE 2012

Ans. (a) :



In roof trusses the most frequently used section is two-angle sections placed back to back.

737. Structural members of the truss which are supported on the principal rafter and which run transverse to the truss are called

(a) Rafters (b) Purlins
(c) Sag tie (d) Struts

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (b) Structural members of the truss which are supported on the principal rafter and which run transverse to the truss are called purlins.

738. Which of the following statements are correct, with respect to wind load analysis as per IS:875 (Part 3)?

(i) For a given basic wind speed, the value of Risk Coefficient k_1 decreases if the mean probable design life of structure in years is increased.

Search on Telegram @apna_pdf

(ii) Value of factor k_2 decreases, if the category of structure changes from Category 1 to Category 4.
(iii) When upwind slope is less than 3°, the value of Topography factor k_3 may be taken as 1.
(a) (i) and (ii) (b) (ii) and (iii)
(c) (i) and (iii) (d) (i), (ii) and (iii)

Gujarat PSC AE (N.W.R.) 2020

Ans. (b) : Wind load analysis as per IS:875 (Part 3) :
- Value of factor k_2 decreases, if the category of structure changes from Category 1 to Category 4.
- When upwind slope is less than 3°, the value of Topography factor k_3 may be taken as 1.

739. Which of the following does not belong to the class 'shell roof ' :
(a) Dome (b) Barrel vault
(c) Warped surface (d) Flat slab

KPSC AE 2020

Ans. (d) : Flat slab does not belong to the class 'shell roof'. Flat slab is a reinforced concrete slab supported directly by concrete columns without using beams.

740. Two effective length of an angle member in a riveted truss is equal to which one of the following ?
(a) l (b) 0.85 l
(c) 0.65 l (d) 0.5 l

Nagaland PSC CTSE 2017 Paper–I
ESE 2008

Ans. (b) : Double Angle strut : A double Angle discontinuous strut with angle placed back to back & connected to both sides of a gusset or any rolled steel section by not less than two rivet or bolts or in line along the Angle at each end or by equivalent in welding, can be regarded as an Axially loaded strut. Its effective length is adopted as 0.85 times the distance b/w intersections, depending on the degree of restrained provided.

741. The beams resting on purlins are known as :
(a) Spandrel beams (b) Common rafters
(c) Trimmers (d) Stringers

Nagaland PSC CTSE 2017 Paper–I

Ans. (b) : In roof trusses horizontal beams spanning between the two adjacent trusses are known as purlins, the beam resting on the purlins are known as common rafter or simply rafters.

742. Maximum bending moment in roof purlins is taken as
(a) WL/10 (b) WL/20
(c) WL/40 (d) WL/50

RPSC AE 2018
(UKPSC AE 2012 Paper–I)

Ans : (a) Purlins are supported by principal rafters. Weight of purlin is between 8-15 Kg/m^2 and distance between two purlins is taken 1.5 – 3.0 m, Depth is taken L/45 and width equal L/60. Maximum bending moment is WL/10. Maximum deflection L/200.

743. For roof truss, the member which is used as transverse member between two adjacent trusses is called as
(a) principal rafter (b) common rafter
(c) purlin (d) all the above are true

(UKPSC AE 2012 Paper–I)

Ans : (c) The member between two adjacent trusses is known as purlin.

744. The maximum allowable deflection in roof purlins is :
(a) 10 mm (b) $\frac{L}{200}$
(c) $\frac{L}{325}$ (d) $\frac{L}{400}$
Where L is the length of purlin

(UKPSC AE (Paper-I) 2007)

Ans : (b) Purlins are supported by principal rafters. Weight of purlin is between 8-15 Kg/m^2 and distance between two purlins is taken 1.5 – 3.0 m, Depth is taken L/45 and width equal L/60. Maximum bending moment is WL/10. Maximum deflection L/200.

745. Normally, the pitch of roof truss with asbestos sheets should not be less than–
(a) $\frac{1}{2}$ of span (b) $\frac{1}{4}$ of span
(c) $\frac{1}{7}$ of span (d) $\frac{1}{12}$ of span

(UTTRAKHAND AE 2013)

Ans : (d) For roof truss, ratio of rise to the span length is known as pitch.
For steel roofs pitch is taken between $\frac{1}{3}$ to $\frac{1}{4}$ and for asbestos sheets it should not be less than $\frac{1}{12}$.
Roofs with lesser pitch are subjected to low air pressure.

746. Generally the purlins are placed at the panel points so as to avoid
(a) Axial force in rafter
(b) Shear force in rafter
(c) Deflection of rafter
(d) Bending moment in rafter

(UPRVUNL AE 2015)

Ans : (d) Purlin is a tie member used to support sheets and to connect two truss members. It is placed above main rafter in longitudinal direction. It is parallel to the ridge of truss. It is used for bearing bending stresses in beams.

747. The wind load on a steel truss for an industrial building will depend upon
(a) Location of structure
(b) Shape of structure
(c) Location, shape and height of structure
(d) Shape and height of structure

(UPRVUNL AE 2015)

Ans : (c) The pressure due to wind depends upon size of building, shape of building and its location.
Design wind pressure $P_z = 0.6\ V_z^2$

748. In industrial buildings in northern hemisphere, the advantage of a north-light roof is
(a) Allows sunlight into the building
(b) Fully explains the aurora borealis

Search on Telegram @apna_pdf

(c) Permits diffused daylight into the building and helps avoid glare of direct sunlight
(d) Allows both sunlight and the prevailing northern breeze in the building

(UPRVUNL AE 2015)

Ans : (c) In northern hemisphere, advantage of north light room in industrial building is it provides diffuse day light into the building and helps avoid glare of direct sunlight.

749. Which of the following elements of a pitched roof industrial steel building primarily resists lateral load parallel to the ridge?
(a) Purlins (b) Bracings
(c) Truss (d) Columns

UTTRAKHAND AE 2013)
ESE 2002

Ans : (a) Purlin is a continuous beam purlins are parallel to the ridge of truss. Normally purlins distance are kept 1.50 m to 3.0 m.

750. The Indian Standard code used for Wind load analysis is
(a) IS 875 part–1 (b) IS 875 part–2
(c) IS 875 part – 3 (d) IS 875 part–4

RPSC VPITI 2012

Ans : (c) Is codes for loads are given below-
(i) Live load – IS : 875 (Part – I)
(ii) Dead load – IS : 875 (Part– II)
(iii) Wind load – IS : 875 (Part– III)
(iv) Snow load – IS : 875 (Part – IV)
(v) Special loads – IS : 875 (Part– V)
(vi) Earthquake loads – IS : 1893 (Part – I)

751. The design wind speed depends upon-
(1) risk coefficient
(2) topography of the area
(3) size of the structure
of the above
(a) (1), (2) are correct
(b) (2), (3) are correct
(c) (3), (1) are correct
(d) (1), (2) and (3) are correct

RPSC VPITI 2012

Ans : (d) The pressure exerted due to wind load depends upon size, shape and location of structure. It also depends upon risk coefficient which varies with type of building.

752. For the purpose of determining the seismic forces, India is divided into zones
(a) 4 (b) 5
(c) 6 (d) 7

RPSC ACF 2011

Ans : (a) Zone factor (Z):– Seismic zoning assesses the maximum severity of shaking, that is anticipated in that region. There are four zones:-

Seismic Zone	I	II
Seismic Intensity	Low (0.1)	Moderate 0.16
Seismic Zone	III	IV
Seismic Intensity	Severe (0.24)	very severe (0.36)

753. Generally the purlins are placed at the panel so as to avoid
(a) Axial force in rafter
(b) Shear force in rafter
(c) Deflection if rafter
(d) Bending moment in rafter

RPSC ACF 2011

Ans : (d) Purlin is a tie member used to support sheets and to connect two truss members. It is placed above main rafter in longitudinal direction. It is parallel to the ridge of truss. It is used for bearing bending stresses in beams.

754. The basic wind speed is specified at height 'h' above mean ground level in open terrain, the value of 'h' is
(a) 10 m (b) 20 m
(c) 25 m (d) 50 m

RPSC ACF 2011

Ans : (a) Design wind speed upto 10 m height from the mean ground level is considered constant.

755. To minimize the total cost of a roof truss, the ratio of the cost of truss to the cost of purlin shall be
(a) 1 (b) 2
(c) 3 (d) 4

RPSC AE 2018
Maharashtra PSC (Mains) 2015 Paper–I
RPSC ACF 2011

Ans : (b) Central distance of truss for which sloping roof is minimum is known as economical distance.

$$\boxed{T = 2P + R}$$

T = cost of one truss member
P = cost of purlin
R = cost of roof
if R is ignored

$$T = 2\,P \Rightarrow \boxed{\frac{T}{P} = 2}$$

756. The members which support covering material of a steel roof truss are–
(a) Rafters (b) Purlins
(c) Struts (d) Battens

(UTTRAKHAND AE 2013)
(RPSC ACF 2011)

Ans : (b) Purlin is a tie member used to support sheets and to connect two truss members. It is placed above main rafter in longitudinal direction. It is parallel to the ridge of truss. It is used for bearing bending stresses in beams. It is a continuous type beam.

757. The reversible nature of loads are:
(a) Earthquake loads (b) Wind loads
(c) Both (a) and (b) (d) None of the above

[UPPSC AE 12.04.2016 Paper–I]

Ans : (c) Earthquake loads and wind loads, both are reversible in nature. Fast flowing winds can topple structures. During earthquake, soil looses its bearing strength and structure fails.

758. The Indian Standard (IS) 800:2007 recommends, in taking advantage of reduced design forces, that the purlins be designed as
(a) continuous beams
(b) simply–supported beams
(c) cantilever beams

Search on Telegram @apna_pdf

(d) tension members

[MPPSC AE 2016]
ESE 2005

Ans : (a) According, to IS Code 800:2007 purlin and rail canvas are designed as continuous beam.

759. The live load for a slopping roof with slope 15°, where access is not provided to the roof is taken as:

OR

The principal rafter of roof truss is inclined at an angle of 15^0. No access is provided except maintenance. The roof is subjected to imposed load of 0.75 kN/m², the design imposed load is

(a) 1.50 kN/m² (b) 0.75 kN/m²
(c) 0.65 kN/m² (d) 0.40 kN/m²

Haryana PSC AE 2017
[MPPSC AE 2016]
ESE 2010

Ans : (c) According to IS: 875-1975
Angle of inclination = 15^0
Imposed load = 0.75 kN/m²
By using formula,

$$\text{Live load} = \text{imposed load} - .02(\text{angle of inclination} - 10^\circ)$$

$$= 0.75 - 0.02\ (15-10)$$

Live load = $0.75 - 0.02 \times 5 = 0.65 \text{kN/m}^2$

760. For heavy vibratory loads in industrial building, the roof trusses are provided with

(a) diagonal bracing in the lower chord member
(b) diagonal bracing in the upper chord member
(c) transverse bracing
(d) knee bracing

[UPPSC State Eng. A.E. 2007(I)]
ESE 2012

Ans : (a) Diagonal bracing in the lower chord member is used only when heavy vibration loads are anticipated in the industrial buildings whereas the diagonal bracing in the upper chord member reduces the unsupported length of the diagonal and make them more effective in compression.
A transverse bracing is used to reduce the end moments of the columns.

761. As per IS : 800-1984, an angle section purlin is designed for a bending moment equal to:

(a) $\frac{W\ell^2}{9}$ (b) $\frac{W\ell^2}{10}$
(c) $\frac{W\ell^2}{12}$ (d) None of these

Where B W = load per meter
ℓ = span of purlin

[UPPSC State Eng. A.E. 2004 (I), 2007]

Ans : (b) As per IS 800 : 1984, the maximum bending moment in the purlin.

$$M = \frac{W\ell}{10} \text{ or } \frac{w\ell^2}{10}$$

W = Total load on purlin including wind load.
w = uniformly distributed load on purlin per unit length including wind load.

762. Design of structure should not consider snow load when roof is steeper than:

(a) 60^0 (b) 45^0
(c) 30^0 (d) 15^0

[UPPSC State Eng. A.E. 2007]


Ans : (a) Snow load is not considered when roof is steeper than 60^0.
According to IS 875-1964 Snow load per cm. is considered 2.5 kg/m². If slope of roof is greater than 50^0 then we should not considered the snow load in designing.

763. In a roof truss, the member which supports the purlins is known as:

(a) main strut (b) main tie
(c) sag tie (d) principal rafter

RPSC A. En.- 2013
[UPPSC State Eng. A.E. 2007]

Ans : (d) In roof truss, purlin is supported over principal rafter.



764. When purlins are placed between panel points the principal rafter is to be designed for

(a) axial compression and tension
(b) axial compression
(c) axial compression and bending moment
(d) axial tension and bending moment

(BPSC AE 2012 Paper–V)

Ans : (c) When purlin is placed between panel point the principal rafter is to be designed for axial compression and bending moment.

765. Distance between purlins on sloping roof depends on -

(a) Slope of truss
(b) type of truss
(c) type of roof coverings
(d) spacing of trusses

(BPSC AE 2012 Paper–V)

Ans : (c) Distance between purlins on sloping surface depends on type of roof covering. For supporting roof loads, main rafter is provided. Purlin are provided above the main rafter.

766. In a steel roof truss, if angle iron purlin is used its depth should not be less than

(a) 1/60 × span of purlin
(b) 1/45 × span of purlin
(c) 1/60 × spacing of purlin
(d) 1/45 × spacing of purlin

(BPSC AE 2012 Paper–V)

Search on Telegram @apna_pdf

Ans : (b) Purlins are supported by principal rafters. Weight of purlin is between 8-15 Kg/m^2 and distance between two purlins is taken 1.5 – 3.0 m, depth is taken L/45 and width equal L/60. Maximum bending moment is WL/10. Maximum deflection L/200.

767. Purlins in roof trusses are designed as....members.

(a) bending (b) tension
(c) compression (d) axial

GPSC AE January 2018
(BPSC AE Paper V 2001)

Ans : (a) Purlin is designed for bending stress and axial stress, both but bending forces are primary.

768. Effective length of groove welds in case of butt joint is equal to-

(a) length of continuous full size weld
(b) overall length of weld minus twice the size of weld
(c) overall length of weld minus four times the size of weld
(d) overall length of weld plus twice the size of weld

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (a) :

⇒ Effective length of groove welds in case of butt joint is equal to length of continuous full size weld.
⇒ Effective length of welds in case of fillet joint is equal to overall length of weld minus two times the size of weld.

769. The top chord of roof truss is inclined at an angle of 20°, no access is provided for maintenance. The live load to be considered for the design will be-

(a) Zero (b) 0.4 kN/m^2
(c) 0.75 kN/m^2 (d) 0.55 kN/m^2

Maharashtra PSC (Mains) 2017 Paper–I


Ans. (d) : According to table 2 of IS code 815
live load considered for design
$= 0.75 - 0.02\ (20 - 10)$
$= 0.55$ kN/m^2

770. Generally the purlins are placed at the panel points so as to avoid-

(a) Axial force in rafter
(b) Shear force in rafter
(c) Deflection of rafter
(d) Bending moment in rafter

GOA PSC Assistant Prof. 2020
OPSC AEE 2015 PAPER–I
Rajasthan AE Nagar Nigam Shift-3, 2016
UPRVUNL AE 2015
ESE 2011

Ans. (d) :



In trusses load application purlin is desired at panel points so as to avoid Bending moment.

771. The members of a roof truss which carry axial compression are called

(a) Column (b) Beam
(c) Stanchion (d) Strut

APPSC AE 2016 (Mains)

Ans. (d) :
Column : Column are not part of truss.
Beam : Beam is flexural member.
Stanchion : It's a bar or post forming a support.
Strut : Strut is part of truss that carry compressive load.

772. As per IS-875, where access is not provided except for maintenance, live load on roofs, while designing a truss, in respect of its plan area is adopted as

(a) 100 N/sq.m (b) 400 N/sq.m
(c) 750 N/sq.m (d) 1500 N/sq.m

APPSC AE 2016 (Mains)

Ans. (c) : According to IS code – 875– live load is
• General access provided with roof angle < 10° – 1500 N/m^2.
• Access provided only for maintenance – 750 N/m^2.

773. Consider the following statements -

I- The economic spacing of a roof truss depends on cost of purlins and cost of roof covering.
II- Purlins provided over roof trusses are designed as a continuous as per IS : 800.
III- Bearing stiffeners are provided in a plate girder to prevent web buckling.

The correct statements are -

(a) I, II and III are correct
(b) Only I and II are correct
(c) II and III are correct
(d) I and III are correct

RPSC AE 2018
ESE 2000

Ans. (a) :
• The economic spacing of a roof truss depends on cost of purlins and cost of roof covering.
• Purlins provided over roof trusses are designed as a continuous as per IS : 800.
• Bearing stiffeners are provided in a plate girder to prevent web buckling.

774. A cable subjected to its own weight and free of any other loads will take the form of :

(a) parabolic curve (b) elliptic curve
(c) catenary curve (d) Bernoulli's Lemniscate

GPSC AE Class (1&2) Paper - 2 2017

Ans. (c) : The shape assume by any string or cable suspended freely between two point is said to be catenary cable used in suspension bridge.

775. If the cost of purlins /unit area is p and the cost of roof covering / unit area is r, then cost of trusses / unit area *l* for an economical spacing of the roof trusses will be

(a) p + r (b) 2p + r
(c) p + 2r (d) 2p + 2r

ESE 2019
GPSC AE March 2018

Search on Telegram @apna_pdf

Ans. (b) : Economic spacing of truss depends upon cost of purlins and cost of roof covering.

Where;

t = cost of truss per unit area.

p = cost of purlin per unit area.

r = cost of roof covering per unit area.

Cost of purlins is directly proportional to the square of spacing of trusses.

$$\left[P = K_2S^2\right]$$

Cost of roof covering is directly proportional to the spacing of trusses.

$$\therefore \left[r = KS\right]$$

$$\therefore \left[\ell = \frac{K_1}{S}\right]$$

Total cost = $\ell + p + r$

$$\left[C = \frac{K_1}{S} + K_2S^2 + K_3S\right]$$

For minimum cost, $\frac{dc}{ds} = 0$

$$\therefore \frac{K_1}{S^2} + 2K_2S + K_3 = 0$$

$$\frac{K_1}{S} + 2K_2S^2 + K_3S = 0$$

$$\Rightarrow -\ell + 2p + r = 0$$

$$\boxed{\ell = 2p + r}$$


776. Double pitched roof trusses of span 20 m and rise 2.5 m are paced at 8 m spacing. The maximum live load reaction at the supports is nearly

(a) 35 kN (b) 40 kN

(c) 46 kN (d) 60 kN

ESE 2018

Ans. (d)



- When access not provided live load = 0.75kN/m^2
- Plan area of roof = 20 × 8 = 160m^2
- Total live load on truss = 0.75 × 20 × 8 = 120kN
- [Each support reaction = $R = \frac{120}{2} = 60$kN]

777. According to IS: 875 Part 3, the design wind speed acting on industrial roof is estimated based on the basic wind speed by multiplying it by factors K_1, K_2 and K_3, where K_1 is called

(a) Terrain height factor (b) Structure size factor

(c) Topography factor (d) Risk coefficient

ESE 2014, 2017

Ans. (d) : According to IS–875 (Part 3) wind load on building structure the design wind speed at any height 'z' in m/s can be mathematically expressed as follows

$$\left[V_z = V_bK_1K_2K_3K_4\right]$$

where,

K_1 = Probability factor (Risk coefficient).

K_2 = Terrain roughness and height factor.

K_3 = Topography factor.

K_4 = Importance factor for the cyclonic region.

778. As per IS 875 (part-3) : 2015, while considering the wind load acting in direction normal to the individual structural element or cladding unit, the following is not considered:

(a) Material density coefficient

(b) Internal and external pressure coefficients

(c) Surface area

(d) Design wind pressure

ISRO Scientist/Engineer 2020

Ans. (a) : As per IS 875 (part-3) : 2015, while considering the wind load acting in direction normal to the individual structural element or cladding unit, the following is not considered for material density coefficient.

779. Peak Gust wind speed as per IS 875 (Part 3) – 2015, for design loads is defined as:

(a) Wind speed associated with maximum wave length

(b) Wind speed associated with maximum frequency and velocity

(c) Wind speed associated with maximum amplitude

(d) Wind speed associated with maximum amplitude and wave length

ISRO Scientist/Engineer 2020

Ans. (c) : Peak Gust wind speed as per IS 875 (Part 3) – 2015, for design loads is defined as wind speed associated with maximum amplitude.

780. The self-weight of a steel roof truss in N/m^2 may be computed by: (span = *l*)

(a) $(l/3) + 5$ (b) $[(l/3) + 5] \times 10$

(c) $(l/3) - 5$ (d) $[(l/3) - 5] \times 10$

Ans. (b) The self-weight of a steel roof truss in N/m^2 may be computed by $[(l/3) + 5] \times 10$.

781. Wind load on steel roof truss for an industrial building will depend on-

(a) Location of the structure

(b) Height of the structure

(c) Shape of the structure

(d) All of these

MPPSC AE 2017

Ans. (d) : Wind load $0.6 \times V_Z^2$

V_Z = Design wind speed = $K_1K_2K_3V_b$

V_b = Basic wind speed

K_1 = Risk coefficient, depends on location

K_2 = Factor dependent on height of structure and shape

K_3 = Terrain factor

Search on Telegram @apna_pdf

782. If 'H' is the total height of the building, under transient wind load the lateral sway at the top should not exceed

(a) $\frac{H}{200}$ (b) $\frac{H}{300}$

(c) $\frac{H}{400}$ (d) $\frac{H}{500}$

Maharashtra PSC Mains 2018 Paper-1

Ans. (d) : As per IS 456 : 2000 under transient wind load the lateral sway at top should not exceed $\frac{H}{500}$.

783. Which one of the following is matched correctly ?

(a) Pratt truss : Large span

(b) Warren truss : Small span

(c) Quadrangle : Medium pitch

(d) North light truss : Ventilation

GPSC AE March 2018

Ans. (c) : (1) Pratt truss → Commonly used for short span from 6 to 10 m in span.
(2) Warren truss → Commonly used in long span building (20 to 100m in span).
(3) North light truss → used for short span in industrial work shop type building (20-30m).
(4) Quadrangle → medium pitch.

784. If an industrial building is cover by GI sheet and if no snowfall is expected in that area, then the minimum pitch should be

(a) $1/24^{th}$ of span (b) $1/6^{th}$ of span

(c) $1/12^{th}$ of span (d) $1/4^{th}$ of span

GPSC AE March 2018

Ans. (c) If an industrial building is cover by GI-sheet and if no snowfall is expected in that area then minimum pitch should be 1/12th of span.

785. A structural element is subjected to pure shear of 125 N/mm^2. The yield stresses in tension as well as compression are both 250 N/mm^2. What would be the factor of safety, in tension and compression, according to maximum normal stress theory?

(a) 2.5 and 2 (b) 2 and 2.5

(c) 2.5 and 2.5 (d) 2 and 2

UPSC JWM 2017

Ans. (d) : When structural element subjected pure shear then shear are same in both direction (tension of compression)

$$(FOS)_C = \frac{250\ N/mm^2}{125\ N/mm^2} = 2$$

$$(FOS)_T = \frac{250}{125} = 2$$

786. Purlins are provided in industrial buildings over roof trusses to carry dead loads, live loads and winds. They are assumed as what type of beams as per IS 800: 84 code?

(a) Simply supported (b) Continuous

(c) Fixed (d) Cantilever

Rajasthan AE Nagar Nigam Shift-3, 2016

Ans. (b) : Purlins are provided in industrial buildings over roof trusses to carry dead loads, live loads and winds. They are assumed as continuous beams as per IS 800: 1984 code.

787. The base plate of a roof truss is attached to the concrete pier with the help of 16 mm dia anchor bolts of grade Fe 250 MPa. What is the maximum pull the base can be subjected to if the root dia is 0.75 times the shank dia?

(a) 67.5 kN (b) 28.3 kN

(c) 56.55 kN (d) 33.75 kN

TRB Poly. Tech. Lect. 2012

Ans. (b) Root Area of Anchor bolt $= 0.75 \times \frac{\pi}{4} \times 16^2$

$= 150.8\ mm^2$

Permissible stress in tension for mild Steel anchor bolt = 100 MPa

Tensile capacity of

One bolt $= \frac{150.8 \times 100\ kN}{1000} = 15.08\ kN$

Let two bolts are in tension than the maximum pull at base $= 15.08 \times 2$

$= 30.16\ kN \simeq 28.3\ kN$ (approximately)

788. In a roof truss, which component of the truss may be subjected to unsymmetrical bending

(a) Principal rafters (b) Struts

(c) Ties (d) Purlin

TSGENCO_2015

Ans. (d) : In a roof truss, Purlin may be subjected to unsymmetrical bending.


789. The sliding end of a roof truss rests on brick wall through a concrete pad. The maximum normal reaction on the bearing is 125 kN. The principal rafter is inclined at 30^0 to the main tie which one is horizontal. What will be the factored force in the principal rafter?

(a) 250 kN (b) 375 kN

(c) 62.5 kN (d) 216.5 kN

TRB Poly. Lect. Tech. 2017

Ans. (a) :



F sin 30 = 125

$F = \frac{125}{0.5} = 250\ kN$

790. The live load for the design of staircases are per IS 875 (1964) for public buildings liable overcrowding is :

(a) 2 kN/m^2 (b) 3 kN/m^2

(c) 4 kN/m^2 (d) 5 kN/m^2

TRB Poly. Lect. Tech. 2017

Ans. (d) : The live load for the design of staircases are per IS 875 (1964) for public buildings liable overcrowding is 5 kN/m^2

Search on Telegram @apna_pdf

791. In an industrial steel building, which of the following elements of a pitched roof primarily resist loads parallel to the ridge ?

(a) Bracings (b) Purlins
(c) Columns (d) Trusses

AP TRANSCO AEE 2017
APTRANSCO 2017

Ans. (a) : In an industrial steel building, bracing elements of a pitched roof primary resists loads parallel to ridge.
The purlin transmit the load into the roof bracing and them through the eave purlin to the wall, diagonal bracing on the adjacent wall and finally to the building foundation.

792. In case of industrial steel structure, sag rods are designed as .....

(a) Torsional member
(b) Compression member
(c) Bending member
(d) Tension member

GPSC AE January 2018

Ans. (d) : Sag rods are provided midway or at one-third point between roof trusses to take up the sag in direction of sloping roof by purlins as a tension member.

793. In industrial buildings in northern hemisphere, the advantage of a north-light roof is

(a) Allows sunlight into the building
(b) Fully explains the aurora borealis
(c) Permits diffused daylight into the building and helps avoid glare of direct sunlight
(d) Allows both sunlight and the prevailing northern breeze in the building

UPRVUNL AE 2015

Ans. (c) : In the northern hemisphere the north light is an even light all day and considered good indirect lighting. There is no glare of direct sunlight moving across the industrial workspace.


794. The wind load on a steel truss for an industrial building will depend upon

(a) Location of structure
(b) Shape of structure
(c) Location, shape and height of structure
(d) Shape and height of structure

UPRVUNL AE 2015

Ans. (c) : IS. 800. 2007
economical spacing of roof truss =

$\left[\frac{1}{3}+\frac{1}{5}\right]$



$\text{Pitch} = \frac{\text{Rise}}{\text{Span}}$

Slope = 2 (Pitch)
for live load
Side Slope $\not>$ 30º

795. The plate used as a connecting piece at the intersection of two or more members in a roof truss is called as:

(a) Template (b) Gusset plate
(c) Base plate (d) Shoe plate

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (b) : The plate used as a connecting piece at the intersection of two or more members in a sag truss called as gusset plate.

796. The economical range of spacing of roof trusses is:

(a) $\frac{1}{2}$ to $\frac{1}{3}$ of span (b) $\frac{1}{2}$ to $\frac{1}{4}$ of span
(c) $\frac{1}{4}$ to $\frac{1}{6}$ of span (d) $\frac{1}{3}$ to $\frac{1}{5}$ of span

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (d) The economical range of spacing of roof trusses is $\frac{1}{3}$ to $\frac{1}{5}$ of span.

797. An angle section can be used as purlin when slope of the roof truss is:

(a) between 40º and 70º (b) less than 30º
(c) greater than 30º (d) less than 45º

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (b) : An angle section can be used as purlin when slope of the sag truss is less than 30^0

798. In a collar beam roof

(a) there is no horizontal tie beam
(b) there is a horizontal tie at the feet of rafters only
(c) there is a horizontal tie at almost the middle of rafters only
(d) there are two horizontal ties, one at the feet and other at the middle of rafters

GPSC AE Dec 2018

Ans. (c) : In a collar beam roof, there is a horizontal tie at almost the middle of rafters only.

799. As per IS: 800, the splice connection should be desgined for a force of at least k times the member design capacity in tension. Here the value of k is

(a) 0.3 (b) 0.4
(c) 0.5 (d) 0.6

GPSC AE Dec 2018

Ans. (a) : As per IS: 800, the splice connection should be desgined for a force of at least 0.3 times the member design capacity in tension.

800. The maximum slenderness ratio of connection members normally acting as a tie in a roof truss or a bracing system but subjected to possible reversal of stress resulting from the action of wind or seismic force is

(a) 180 (b) 250
(c) 300 (d) 350

GPSC AE Dec 2018

Search on Telegram @apna_pdf

Ans. (d) : A members normally acting as a tie in a roof truss or a bracing system and considered effective when subjected to possible reversal of stress into compression resulting from the action of wind or earthquake forces. For such case slenderness ratio $\left(\frac{KL}{r}\right) = 350$.

801. A beam supporting floor construction but not a major beam is called as :

(a) rafter (b) spandrel
(c) girt (d) joist
(e) strut

CGPSC AE 2017

Ans. (d) A beam supporting floor construction but not a major beam is called as joist.

802. Minimum imposed load considered for sloping roof with slope greater than 10^0 should not be less than -

(a) 1.5 kN/m^2 (b) 0.75 kN/m^2
(c) 0.40 kN/m^2 (d) 0.10 kN/m^2

Rajasthan VP ITI 2018

Ans. (c) : As per IS : 875, the minimum imposed load on the roof truss should be 0.4 kN/m^2 for sloping roof upto 10^0, the imposed load is taken as 0.5 kN/m^2 if access is not provided and 0.75 kN/m^2 is access is provided.

803. Consider the following statements about Roof truss, Find the incorrect one :

(i) Purlins rest on top chord of roof truss
(ii) Rafter rest on purlin and support the sheathing
(iii) Principal rafter is defined as top chord member carries tensile force
(iv) Bay is defined as distance between the adjacent purlin

Which of the above statements is/are correct?

(a) (i) (ii) (iii) (b) (i) (ii) (iv)
(c) (ii) (iii) (iv) (d) (i) (ii) (iii) (iv)

UP Jal Nigam AE 2016

Ans. (b) : About roof truss correct statement are :
(i) Purlins rest on top chord of roof truss
(ii) Rafter rest on purlin and support the sheathing
(iii) Bay is defined as distance between the adjacent purlin.

804. Consider the following statements about availability of Asbestos cement sheets used on Roof truss.

(i) Asbestos cement sheets are available in length of 1.5-3.0 m
(ii) Overall width = 1.05 m effective width 1.01 m
(iii) Thickness = 6.7 mm
(iv) Asbestos cement sheets are used for slope 30 and less

Which of the above statements is/are correct?

(a) (i) (ii) (iii) (b) (i) (ii) (iv)
(c) (ii) (iii) (iv) (d) (i) (ii) (iii) (iv)

UP Jal Nigam AE 2016

Ans. (a) Correct statements about availability of Asbestos cement sheets used on Roof truss :
(i) Asbestos cement sheets are available in length of 1.5-3.0 m.
(ii) Overall width = 1.05 m effective width 1.01 m.
(iii) Thickness = 6.7 mm.

805. Sag roads in a roof truss are used for connecting

(a) main tie (b) Purlin
(c) Sling (d) Rafter

WBPSC AE 2014

Ans. (b) : Sag rods in a roof truss are used for connecting two purlins sag rod used as tension member.

806. The slenderness ratio of single angle discontinuous strut shall not exceed

(a) 120 (b) 180
(c) 150 (d) 200

WBPSC AE 2014

Ans. (b) : The slenderness ratio of single angle discontinuous strut shall not exceed than 180.

807. If the total distributed load on purlin is W including wind load, the maximum bending moment is

(a) W/4 (b) Wl/8
(c) Wl/2 (d) Wl/10

WBPSC AE 2014

Ans. (d) : Maximum bending moment in purlin is

$M_{max} = \frac{WL}{10}$ as per IS : 800


809. The maximum economical spacing of trusses is recommended as

(a) $\frac{L}{5}$ (b) $\frac{2L}{5}$
(c) $\frac{L}{3}$ (d) $\frac{3L}{5}$

WBPSC AE 2007

Ans. (c) : The maximum economical spacing of trusses is 1/3rd to 1/5th of the span.

810. The force in the member AB of the loaded truss shown in figure, is



(a) 3000 N (Tensile)
(b) 3000 N (compressive)
(c) 6000 N (Tensile)
(d) 60000 N (compressive)

WBPSC AE 2001

Ans. (d) :

Search on Telegram @apna_pdf

811. In a steel roof truss, tension number consists of single angle connected by rivets to gusset plates, cross sectional area to be considered for design is

(a) net area of both the legs of the section
(b) net area of the connected leg plus a fraction of the other leg area
(c) net area of the connected leg only
(d) mean of the areas of connected and unconnected legs

WBPSC AE (PHE) 1998

Ans. (c) : In a steel roof truss, tension number consists of single angle connected by rivets to gusset plates, cross sectional area to be considered for design is net area of the connected leg only.


8. Plastic analysis

812. The shape factor of a rectangular section is

(a) 0.5 (b) 1.0
(c) 1.5 (d) 2.0

UPSC JWM 2017

Ans. (c) :



$M_Y = \sigma_Y Z_y$

$M_P = \sigma_Y Z_p$

$M_Y = \sigma_Y \frac{bd^2}{6}$

$M_P = \sigma_Y Z_P = \sigma_Y \frac{A}{2}(Y_1 + Y_2)$

$= \frac{\sigma_Y A}{2} \times \frac{d}{2}$

$M_P = \sigma_Y Z_p = \frac{\sigma bd^2}{4}$

$\delta = \frac{M_P}{M_y} = \frac{\sigma_Y bd^2 6}{L\sigma_Y bd^2}$

$\delta = 1.5$

813. Of the following four sections, which section has the maximum Plastic Modulus?

(a) ISMB250 (b) ISHB250
(c) ISWB250 (d) ISLB250

Gujarat PSC AE (N.W.R.) 2020

Ans. (b) : ISHB250 section has the maximum Plastic Modulus.

814. The shape factor of a rectangular section is

(a) 1.0 (b) 1.5
(c) 2.0 (d) 3.6

(UPRVUNL AE 2015)
ESE 2008

Ans : (b) Shape factor is ratio of maximum resistance of plastic moment (M_p) to the maximum resistance of yield moment (M_y).

Shape factor for different type of sections–


Sections	shape factor (M_p/M_y)
Rectangular	1.5
Square	1.5
Triangular	2.3
Circular	1.7
T–shape	1.8
Diamond	2

815. Which of the following section will have largest shape factor?

(a) Rectangle (b) I-section
(c) Solid circular section (d) Diamond section

(UTTRAKHAND AE 2013)
[UPPSC State Eng. A.E. 2004 (I)]

Ans : (d) Among the given option diamond section have largest shape factor, which is equals to 2.




816. The ratio of plastic moment capacity to yield moment capacity of a MS beam section is taken as about:

(a) 0.85 (b) 0.15
(c) 1.50 (d) 1.70

[UPPSC State Eng. A.E. 2007]

Ans : (c)



817. The plastic modulus of rectangular beam of width 200 mm and depth 400 mm is

(a) 2×10^6 mm^3 (b) 5.33×10^6 mm^3
(c) 8×10^6 mm^3 (d) 1.07×10^6 mm^3

[MPPSC AE 2016]


Ans : (c) Plastic modulus of a beam is moment of area about neutral area axis

for, rectangle, plastic section modulus is

$$Z_p = \frac{A}{2}(\bar{y}_1 + \bar{y}_2)$$

$$\frac{200\times400}{2}\times(100+100) = 8\times10^6\ mm^3$$

Search on Telegram @apna_pdf



$Z_p = 8\times10^6\,mm^3$

818. In plastic analysis of steel structures, at the location of plastic hinge

(a) Curvature is zero
(b) Curvature is infinite
(c) Moment is infinite
(d) Moment is zero

RPSC VPITI 2012
ESE 2010

Ans : **(b)** In plastic analysis of steel structures, at the location of plastic hinge curvature is infinite as at that point beam is free to rotate in any direction.

819. The section modulus and the plastic modulus of a section are Z and S respectively. Then its shape factor is :

(a) $\frac{S-Z}{Z}$ (b) $\frac{S-Z}{S}$
(c) $\frac{Z}{S}$ (d) $\frac{S}{Z}$

(UKPSC AE (Paper–I) 2007)

Ans : **(d)** Shape factor is ratio of plastic moment of resistance to the yield moment of resistance

$$\text{Shape factor} = \frac{M_P}{M_y} = \frac{\sigma_y.Z_P}{\sigma_y.Z_y} = \frac{Z_P}{Z_y};$$

Z_P is plastic modulus
Z_y is section modulus

$\therefore$ Shape factor $\frac{S}{Z}$

820. Shape factor is given by

(a) M_y/M_p (b) Z/Z_p
(c) both of (a) & (b) (d) None of the above

UKPSC AE 2012 Paper–I

Ans : (d) Shape factor is ratio of plastic moment of resistance (M_p) to the yield moment of resistance (M_y).

$$S = \frac{M_p}{M_y} = \frac{\sigma_y.Z_p}{\sigma_y.Z} = \frac{Z_p}{Z}$$

821. In plastic analysis, the shape factor for a triangular section is

(a) 1.5 (b) 2.34
(c) 1.7 (d) 2.5


TNPSC AE 2018
Haryana PSC AE 2018 Paper–I

Ans. (b) :

$$\text{Shape factor} = \frac{M_p}{M_y} = \frac{\sigma_y.Z_p}{\sigma_y.Z_y} = \frac{Z_p}{Z_y} = \frac{Plastic\ \text{section modulus}}{\text{Elastic section modulus}}$$

$$= \frac{0.0963bh^2}{\frac{bh^2}{24}} = 2.34$$

822. Consider a triangular section with base b and height h as shown in the figure.



The shape factor will be nearly

(a) 2.3 (b) 3.2
(c) 4.1 (d) 5.0


ESE 2019

Ans. (a) : Shape factor for triangular section :–

$$\left[\text{Shape factor} = \frac{\text{Plastic Modulus}}{\text{Section Modulus}}\right]$$

$$\text{Plastic Modulus 'Zp'} = \frac{A}{2}(y_c + y_t)$$

$$\text{Section Modulus 'Z'} = \frac{\frac{bh^3}{36}}{\frac{2h}{3}} = \frac{bh^2}{24}$$



$$S = \frac{Z_p}{Z} = \frac{\frac{A}{2}(y_c + y_t)}{\frac{bh^2}{24}}$$

$S = 2.346$

■ Shape factor of various section–
→ Rectangular 'S' = 1.5
→ Circular 'S' = 1.7
→ I–section 'S' = 1.132

823. The shape factor of an I–section is–

(a) 1.04 (b) 1.14
(c) 1.70 (d) 2.00

(UTTRAKHAND AE 2013)

Ans : (b) Shape factor for different type of sections:-

(i) Rectangular/square section → 1.5
(ii) Circular → 1.698
(iii) Diamond → 2
(iv) I-section → Between 1.12 to 1.15
(v) T-section → 1.9 to 1.95

Search on Telegram @apna_pdf

824. Which of the following represents the increasing order of shape factor?

(a) Rectangle, I-section, solid-circular section, diamond
(b) I-section, rectangle, solid-circular section, diamond
(c) Diamond, solid-circular section, rectangle, I-section
(d) Diamond, solid-circular section, I-section, rectangle

(JPSC Combined AE Paper V 2013)

Ans : (b) Shape factor for different type of sections;-

1 -	Rectangular	-	1.50
2 -	I - section	-	1.12 to 1.15
3 -	Solid circular	-	1.7
4-	Diamond	-	2.0
5-	T-section	-	1.90 to 1.95

825. A section has the capacity to develop plastic hinge, but does not have the capacity to form collapse mechanism. Such a section is called:

(a) plastic section (b) compact section
(c) semi-compact section
(d) slender section

APPSC Poly. Tech. Lect. 2020

Ans. (b) : The cross-section, which can develop plastic moment of resistance, but have inadequate plastic hinge rotation capacity for formation of a plastic mechanism before buckling are referred to as compact sections. The stress distribution for these sections is rectangular.

826. The shape factor of structural steel sections primarily depends on :

(a) cross sectional geometry
(b) Poisson's ratio
(c) proof stress of the material
(d) loading conditions

CIL MT 2017


Ans. (a) : The shape factor of structural steel sections primarily depends on cross sectional geometry.

827. For a simply supported steel beam of span L and carrying a point load at the mid-length, at the stage of collapse, what part of the beam is fully elastic

(a) L/3 from each end (b) L/4 from each end
(c) L/5 from each end (d) L/6 from each end
(e) No part of the beam remains elastic at collapse

CGPSC AE 2014 Shift–I

Ans. (a) :



Assume x-section is rectangular

$\therefore$ shape factor (K_S) = 3/2

$$\text{Length of elastic zone} = L\left[1-\frac{1}{K_S}\right]$$


$$= L\left[1-\frac{2}{3}\right] = \frac{L}{3}$$

828. According to Tresca yield locus is?

(a) a rectangle (b) a hexagon
(c) a ellipse (d) a circle

(BPSC AE 2012 Paper–V)

Ans : (b) Tresca proposed a model for the onset of yield in a material under a general applied stress.
The diagram for yield surface for an isotropic material that is a hexagonal.



829. Which one of the following is the correct assumption made in evaluation of fully plastic moment ?

(a) The upper and lower yield stresses and the modulus of elasticity have different values in compression and tension
(b) The material is homogeneous and isotropic in both the elastic and plastic states
(c) There will be resultant axial force on the beam
(d) Some layers of the material are not free to expand and contract longitudinally and laterally under stress

ESE 2020

Ans. (b) : Assumptions made in evaluation of fully plastic moment are–

(1) The material obeys Hooke's law until the stress reaches the upper yield value. On further straining the stress drops to the lower yield value and thereafter remains constant.
(2) The upper and lower yield stresses and 'E' have the same values in compression and in tension.
(3) The material is homogeneous, and isotropic in both elastic and plastic stages.
(4) Plane transverse section remains plane and normal to the longitudinal axis after bending, the effect of shear being neglected.
(5) There is no resultant axis force on the beam.
(6) The cross-section of beam is symmetrical about an axis through its centroid parallel to the plane of bending.
(7) Every layer of material is free to expand and contract.

830. Shape factor is a property which depends :

(a) Only on the ultimate stress of the material
(b) Only on the yield stress of the material
(c) Only on the geometry of the section
(d) Both on the yield stress and ultimate stress of material

UPPCL AE 2019
Nagaland PSC CTSE 2017 Paper–I

Search on Telegram @apna_pdf

Ans. (c) : Shape factor is the ratio of the moment carrying capacity of the plastic section over that of the elastic section when the yielding just start, Shape factor $= \frac{\sigma_y Z_p}{\sigma_y Z_e} = \frac{Z_p}{Z_e}$

$\Rightarrow$ Shape factor depends only on the geometry of the section.

831. The statical method of Plastic analysis satisfies:

(a) Equilibrium and mechanism conditions
(b) Mechanism and plastic moment conditions
(c) Equilibrium conditions only
(d) Equilibrium and plastic moment conditions

Nagaland PSC CTSE 2017 Paper–I

Ans. (b) : Following are the fundamental condition for plastic Analysis.
(1) Mechanism condition : At ultimate collapse load, the number of plastic hinge must be just enough to form a mechanism.
(2) Equilibrium condition : The summation of the forces and moments acting on a structure must be equal to zero.
(3) Plastic moment condition : The Bending moment anywhere must not exceed the fully plastic moment.

832. Which one of the following methods of design is not suitable for structure subjected to impact and fatigue?

(a) Simple design (b) Semi-rigid design
(c) Rigid design (d) Plastic design

[UPPSC State Eng. A.E. 2011]

Ans : (d) Plastic design method of design is not suitable for structure subjected to impact and fatigue.

833. The probability based assessment of safety is ensured by
1. Plastic Analysis
2. statistical Method
3. Reliability Approach
Which are the correct of the above?

(a) 1 and 2 (b) 2 and 3
(c) 1 and 3 (d) 1,2 and 3

[UPPSC State Eng. A.E. 2011]

Ans : (b) The probability based assessment of safety is ensured by –
- Statistical Method
- Reliability Approach

834. When a steel exhibits linear load displacement until fracture occurs suddenly with very little plastic deformation, then the behavior is called as :

(a) Ductile behavior
(b) Newtonian behavior
(c) Elasto-plastic behavior
(d) Brittle behavior
(e) Plastic behavior

CGPSC AE 2014 Shift–I

Ans. (d) When a steel exhibits linear load displacement until fracture occurs suddenly with very little plastic deformation, this is called brittle behaviour.

835. According to IS 800, while using plastic method of analysis, unless adequate ductility and plastic rotation capacity are established for design loading conditions, the yield stress of the grade of the steel used shall not exceed :

(a) 415 MPa (b) 500 MPa
(c) 550 MPa (d) 450 MPa
(e) 380 MPa

CGPSC AE 2014 Shift–I

Ans. (d) : As per IS 800 - 2007, (Cl 4.5.2)
(a) The yield stress of the grade of the steel used shall not exceed 450 MPa

836. In the plasticity theory used for steel, which of the following assumptions are not applicable

(a) steel is ductile and can undergo plastic deformation without rupturing
(b) Elastic deforming is taken into account
(c) All connections provide satisfactory continuity so as to transmit the plastic moment
(d) Steel is assumed to be an ideal elastic - plastic material
(e) Plane sections before bending remain plane after bending

CGPSC AE 2014 Shift–I

Ans. (b) : Elastic deformation is not considered in steel structure in plastic theory.

837. The section modulus and the plastic modulus of a section are Z and P respectively. Then its shape factor is given by :

(a) Z/P (b) P/Z
(c) (P–Z)/P (d) (P–Z)/Z


TNPSC AE 2015

Ans. (b) Shape factor is ratio of plastic moment of resistance to the yield moment of resistance

Shape factor $= \frac{Mp}{My} = \frac{\sigma_y \times p}{\sigma_y \times z}$

p= plastic modulus
z = section modulus
shape factor = p/z

838. A propped cantilever of span L and having constant plastic moment capacity M_p is subjected to a point load at mid - span, then the load at collapse will.




(a) $8\ M_p/L$ (b) $6\ M_p/L$
(c) $11.7\ M_p/L$ (d) $2\ M_p/L$

DSSSB AE 2019
LMRC AM 2018
Haryana PSC AE 2017
TRB Poly. Lect. Tech. 2017
APTRANSCO 2017
AP TRANSCO AEE 2017
UPPCL AE 2014
TRB Poly. Tech. Lect. 2012
ESE 1999, 2001, 2005, 2010, 2011

Search on Telegram @apna_pdf

Ans. (b)



$r = 3 - 2 = 1$

Number of plastic hinge $= (n) = r + 1 = 2$

$$y = \frac{l}{2}\theta$$

External work = internal work

$w_e = w_i$

$w \times y = M_p\theta + M_p\theta + M_p\theta$

$$w.\frac{l}{2}\theta = 3Mp\theta$$

$$\boxed{w = \frac{6M_p}{l}}$$

839. In the plastic analysis, the ratio of plastic moment M_p to the yield moment M_y is called

(a) Plastic hinge (b) Shape factor
(c) Load factor (d) Plastic strain

ISRO Scientist/Engineer 2019
GPSC AE January 2018
UJVNL AE 2016

Ans : (b) :

- In plastic analysis the shape factor may be defined as the ratio of the plastic moment and the yield moment of the section.

$$\left[\text{Shape factor} = \frac{\text{Plastic moment } M_p}{\text{Yield moment } M_y}\right]$$

$$\left[S = \frac{f_y Z_p}{f_y Z_e} = \frac{Z_p}{Z_e}\right] \begin{matrix} Z_p \rightarrow \text{Plastic section modulus} \\ Z_e \rightarrow \text{Elastic section modulus} \end{matrix}$$

- Shape factor implies that the section gives larger warning before collapse or we can also say that shape factor gives an indication of reserve capacity of a section from on set of yielding at extreme fiber to full plasticization.

840. The type of roof suitable for plains where rainfall is less and temperature is high, is:

(a) Pitched and sloping (b) Flat roof
(c) Shell roof (d) None of the above

WBPSC Poly Lect. 2019

Ans. (b) : The type of roof suitable for plains where rainfall is less and temperature is high, is flat roof.

841. The following theorem is used in plastic analysis to compute the collapse load :

(a) Upper bound theorem
(b) Castigliano's theorem
(c) Maxwell-Betti's theorem
(d) Clapeyron's theorem

APTRANSCO AE 2017

Ans : (a) Upper bound theorem is used in plastic analysis.

842. The shape factor is maximum for the following cross-section :

(a) Rectangular section
(b) Circular section
(c) I section
(d) Triangular section

APTRANSCO AE 2017

Ans : (d) The shape factor is maximum for the following cross-section triangular section.

843. At the location of a plastic hinge.

(a) Radius of curvature is infinite
(b) Curvature is infinite
(c) Moment is infinite
(d) Flexural stress is infinite

AP TRANSCO AEE 2017
APTRANSCO 2017
UJVNL AE 2016
ESE 1995, ESE 2003, ESE 2010

Ans : (b) At the location of a plastic hinge curvature is infinite.

844. Match the information given in Group-I with those in Group-II :

Group-I	Group-II
P. Factor to decrease ultimate strength to design strength	1. Upper bound on ultimate load
Q. Factor to increase working load to ultimate load for design	2. Lower bound on ultimate load
R. Statical method of ultimate load analysis	3. Material partial safety factor
S. Kinematical mechanism method of ultimate load analysis	4. Load factor

(a) P-1, Q-2, R-3, S-4 (b) P-2, Q-1, R-4, S-3
(c) P-3, Q-4, R-2, S-1 (d) P-4, Q-3, R-2, S-1

APTRANSCO 2017

Ans : (c) :

845. Find out the wrong statement from the followings :

(a) The elastic section modulus of a section does not affect Shape Factor.
(b) The Shape Factor is a function of the cross-sectional shape.
(c) The Shape Factor represents the increase of strength due to plasticization.
(d) The Shape Factor of a section is a measure of reserve strength available in the section after initial yielding.

OPSC AEE 2019 Paper–I

Search on Telegram @apna_pdf

Ans. (a) : It is a function of the cross-section form or shape and is represented by S.

$$S = \frac{M_P}{M_Y} = \frac{Z_P}{Z}$$

M_P = Plastic moment
M_Y = Yield moment
Z_P = Plastic modulus
Z = Elastic modulus

It is a geometrical property of a section. It depends wholly on the shape of cross-section.

846. Find the correct statement with regards to Plastic Hinge :

(a) Plastic Hinges are reached first at sections subjected to least curvature.
(b) The plastic hinge will not form at the point of zero shear in a span under distributed load.
(c) Where three structural members meets, plastic hinge will form in all members irrespective of their capacities of taking the moment.
(d) A plastic hinge is a zone of yielding due to shear in a structural member.

OPSC AEE 2019 Paper–I

Ans. (c)


⇒ The plastic hinges are formed first at the sections subjected to the greatest deformation (curvature).
⇒ The plastic hinge is defined as a yielded zone due to flexure in a structure.
⇒ The plastic hinge will form at point of zero shear in a span under distributed load.
⇒ When three or four members meet at a point, plastic hinges are formed in all the members irrespective of their plastic modulus.

847. A fixed beam of 8 meters length is subjected to a single central concentrated load. If the plastic moment value is M_P, the ultimate load by mechanism method is :

(a) M_P (b) $2M_P$
(c) $1.5\ M_P$ (d) $4\ M_P$

OPSC AEE 2019 Paper–I

Ans. (a)



External work = Internal work done
$w \times 4\theta = M_p\theta + M_p.2\theta + M_p\theta$
$4w\theta = 4\ M_p\theta$
$\Rightarrow w = M_p$

848. Choose the correct statement :

(a) Through equilibrium condition will always be satisfied, a solution arrived at on the basis of an assumed mechanism will give a loading that is either correct or too high.
(b) The load obtained using the assumed moment diagram that does not violate the plastic moment condition will be either correct or too high.
(c) The strain at the onset of strain hardening is about 30 to 40 times the elastic strain in structural steel.
(d) The load factor of a rectangular steel section is 3.75, if the Factor of safety is 1.65.

OPSC AEE 2019 Paper–I

Ans. (a) :

⇒ A solution arrived at on the basis of assumed mechanism will yield a load carrying capacity that is either correct or too high.
⇒ A solution arrived at on the basis of a statical moment condition, will either be correct or too low.
⇒ The equilibrium condition however has to be satisfied in both the cases.

Load factor = FOS × shape factor
= 1.65 × 1.5
= 2.475

For ordinary steel the elastic strain is about $\frac{1}{12}$ to $\frac{1}{15}$ of strain at the beginning of the strain hardening.

849. The condition which are satisfied both in elastic and plastic analysis are :

(a) equilibrium condition
(b) yielding condition
(c) both 'a' and 'b'
(d) none of the above

PSPCL AE 2012
ESE 2011

Ans. (a) In both the elastic & plastic analysis the equilibrium conditions must be satisfied i.e. resultant of all force on the structure member should be equal to zero and resultant moment should be also equal to zero i.e, the bending moment shall be consistent with the load applied accordingly

$\sum F_x$ & $\sum F_y = 0$
$\sum M_2 = 0$ {equilibrium condition}

850. Poisson's ratio of structural steel in plastic range is

(a) 0.25 (b) 0.3
(c) 0.4 (d) 0.5

GPSC AE March 2018

Ans. (d) :

$$\text{Poisson's ratio } (\mu) = \frac{\text{Lateral strain}}{\text{Longitudinal strain}}$$

μ = range 0 to 0.5
μ = structural steel in plastic range is 0.5.


851. The collapse load for a propped cantilever of span I subjected to uniformly distributed load is

(a) $0.414\ M_p/I$ (b) $0.586\ M_p/I$
(c) $7.67\ M_p/I$ (d) $11.656\ M_p/I$

GPSC AE March 2018

Search on Telegram @apna_pdf

Ans. (d)



Plastic hinge will from at 0.414 from hinged end.

$$\left(\frac{wl}{2}-\frac{wl}{2}\right)(0.414l)-\frac{w(0.414\ell)^2}{2}=Mp$$

$$w=\frac{11.65\,M_P}{l^2}$$

w = collapse load

852. The moment capacity of a section at plastic hinge is

(a) zero
(b) yield moment
(c) twice of yield moment
(d) fully plastic moment

TRB Poly. Tech. Lect. 2012

Ans. (d) The moment capacity of a section at plastic hinge is fully plastic moment.
When the section is completely yielded the section is fully plastic.

853. A simply supported beam of rectangular section and span L is subjected to a uniformly distributed load at the center. The length of elastoplastic zone of the plastic hinge will be

(a) $\frac{L}{3}$ (b) $\frac{L}{\sqrt{3}}$
(c) $\frac{L}{2}$ (d) $\frac{L}{8}$

TSGENCO-2015

Ans. (b) : $L_P=L\sqrt{1-\frac{1}{\alpha}}$

where,
L = length of span
α = Shape factor
L_p = Plastic hinge length
For rectangular, α = 3/2

$$L_P=L\sqrt{1-\frac{2}{3}}$$


$$L_P=\frac{L}{\sqrt{3}}$$

854. For a fixed beam with length L, having plastic moment capacity of M_p, the ultimate central concentrated will be.

(a) $\frac{4M_p}{L}$ (b) $\frac{6M_p}{L}$
(c) $\frac{M_p}{8L}$ (d) $\frac{8M_p}{L}$

UJVNL AE 2016

Ans. (d) :



$D_s = \gamma_e - E$
$= 4–2$
$= 2$
$\eta = D_s + 1$
$= 2+1 = 3$

As per principle of virtual workdone

$w_e = w_i$

$$w_u \times \delta = \underset{\text{at A}}{M_p\theta} + \underset{\text{at C}}{M_p(\theta+\theta)} + \underset{\text{at B}}{M_p\theta}$$

$$w_u \times \frac{l}{2}\times\theta = 4M_p\theta$$


$$w_u=\frac{8M_p}{l}$$

855. A steel beam of rectangular cross – section is clamped at both ends. Plastic deformation is just observed when the udl on the beam is 10 kN/m. At the instant of collapse, the load on the beam will be

(a) 10 kN/m (b) 15 kN/m
(c) 20 kN/m (d) 30 kN/m

APPSC AEE 2012
ESE 1998

Ans. (c) :



When the load is such that maximum moment is equal to yield moment (M_y), the beam start deforming. The load for M is given as

W_1 = 10 kN/m

Now, hinges at clamps will be formed at a load equal to

w_2 = shape factor × w_1
= 15 × 10 = 15 kN/m


Since beam is clamped at both the end, so it can be treated as fixed beam.

Load required to collapse the beam, after becoming two hinges at the fixed end is,

Collapse load, $w_u = \frac{4}{3}\times 15 = 20\ \text{kN/m}$

Search on Telegram @apna_pdf


856. In propped cantilever loaded as shown in figure, the plastic hinge will form at



(a) 0.414 L from B (b) 0.414 L from A
(c) L/2 from B (d) L/2 from A

APPSC AEE 2012

Ans. (a) :



Whenever, a beam is supported as fixed from one end and rolled at other end, the plastic hinge will always be formed at 0.414 times span of beam from roller support i.e. from (B)

857. The value of the collapse load for a simply supported beam subjected to concentrated load at the centre is


(a) $\frac{5M_P}{L}$ (b) $\frac{4M_P}{3L}$

(c) $\frac{3M_P}{L}$ (d) $\frac{4M_P}{L}$

where M_P is the plastic moment and L is span.


BPSC Poly. Tech. Lect. 2016

Ans. (d) :




$$2\,M_p\theta = \frac{wl}{2}\theta$$

$$w = \frac{4M_p}{l}$$



858. A uniform beam shown in figure has the plastic moment Mp for span AB and 0.9 Mp for span BC. The correct virtual work equation is



(a) $M_P.\theta + M_P\left(\theta + \frac{2\theta}{3}\right) = W.2\theta$


(b) $M_P\theta + M_P\theta + 0.9M_P\frac{2\theta}{3} = W.2\theta$

(c) $M_P.\theta + 0.9M_P\left(\theta + \frac{2\theta}{3}\right) = W.2\theta$

(d) $M_P\theta + 0.9M_P\left(\theta + \frac{2\theta}{3} + \frac{2\theta}{3}\right) = W.2\theta$

APPSC AEE 2012

Ans. (c) : $\theta_2 = \frac{2}{3}\theta_1$



$W_e = W_1^0$

$M_P\theta_1 + 0.9M_p(\theta_1 + \theta_2) = W \cdot 2\theta_1$

$$M_p\theta + 0.9M_p\left(\theta + \frac{2}{3}\theta\right) = W.2\theta$$

859. The shape factor for a solid circular section of diameter D is equal to :

(a) $\frac{16}{3\pi}$ (b) $\frac{\pi D}{8}$

(c) $\frac{D}{2\pi}$ (d) $\frac{15}{2\pi}$

UPPCL AE 2015
ESE 2002

Ans. (a) :

$$\text{Shape factor} = \frac{z_p}{z_e}$$

$$z_e = \frac{I}{y} = \frac{\pi d^3}{32}$$

$$z_p = \frac{A}{Z}(y_1 + y_2)$$

$$z_p = \frac{\pi d^2}{8}\left(\frac{2d}{3\pi} + \frac{2d}{3\pi}\right)$$

$$z_p = \frac{d^3}{6}$$

$$SF = \frac{d^3}{6}\frac{32}{\pi d^3}$$

$$SF = \frac{16}{3\pi}$$

860. In plastic analysis of structures, the segment between any two successive plastic hinges is assumed to deform as .....

(a) A plastic material
(b) A rigid material
(c) An elastic material
(d) An inelastic material

GPSC AE January 2018
ESE 2005

Search on Telegram @apna_pdf

Ans. (b) : The initial slope and deflection of the beam don't affect the virtual work equation.
Thus, the displacement diagram can be simplified to consist of straight and un-deflected lines i.e., rigid deformation.

861. For a beam the shape factor is 1.12. The factor of safety in bending is 1.5. If the allowable stress is increased by 20% for wind and earthquake loads, then the load factor is

(a) 1.10 (b) 1.25
(c) 1.35 (d) 1.40

UPRVUNL AE 2015
ESE 1995

Ans. (d) : Given that : Beam shape factor = 1.12
The factor of safety in bending is = 1.5
Allowable stress increased by = 20%
load factor = ?
Sol : The factor of safety is given as

$$F_1 = \frac{\text{Yield stress}}{\text{Allowable stress}} = 1.5 \quad \text{———(1)}$$

Note : When the allowable stress is increased by 20%, then factor of safety will be.

$$F_2 = \frac{\text{Yield stress}}{1.2 \times \text{Allowable stress}} \leftarrow \text{Put the value of equation – (1)}$$

$$F_2 = \frac{1}{1.2} \times F_1 = \frac{1}{1.2} \times 1.5 = 1.25$$

Load factor = Shape factor × Factor of safety
= 1.12 × 1.25
Load factor = 1.4


862. As per IS 800 : 2007, the cross-sections which can develop plastic moment of resistance, but have inadequate plastic hinge rotation capacity for formation of plastic mechanism, due to local buckling is :

(a) compact section (b) semi-compact section
(c) plastic section (d) slender section

BHEL ET 2019
CGPSC AE 2017

Ans. (a) : As per 800 : 2007 the cross section which can develop plastic moment of resistance, but have inadequate plastic hinge rotation capacity for the formation of plastic mechanisms due to total buckling is compact section.

863. The minimum numbers of plastic hinges necessary for the complete collapse of the following structures are _____.



(a) 1 for beam and 1 for frame
(b) 3 for beam, and 3 for frame
(c) 4 for beam, and 5 for frame
(d) 2 for beam, and 2 for frame

UPPCL AE 2018


Ans. (b) : Minimum number of plastic hinge for beam is 3 and for frame shown in figure is 3.

864. For a steel beam of rectangular cross-section, with 20 mm width and 60 mm depth, what are the yield and plastic moments, if f_y = 25 N/mm^2?

(a) Yield moment = 3 kN-m, Plastic moment = 4.5 kN-m
(b) Yield moment = 3 kN-m, Plastic moment = 2 kN-m
(c) Yield moment = 4.5 kN-m, Plastic moment = 3 kN-m
(d) Yield moment = 3 kN-m, Plastic moment = 6 kN-m

UPPCL AE 2018

Ans. (a) : Yield moment of the steel section.




$$M_y = C \times \frac{2}{3}d = f_y \times \frac{b \times d}{4} \times \frac{2}{3}d = f_y \times \frac{bd^2}{6}$$

$$= 250 \times \frac{20 \times 60}{6}$$

= 3 kN-m

Plastic moment of the steel beam



$$M_p = f_y \times \frac{bd}{2} \times \frac{d}{2}$$

$$M_p = f_y \frac{bd^2}{4}$$

$$M_p = 250 \times 20 \times \frac{60^2}{4} = 4.5 \text{ kN-m}$$

865. Consider the following two statements:
Statement I : A semi-compact section cannot reach yield stress.
Statement II: A semi-compact section cannot develop plastic moment of resistance.
Which of the following is CORRECT?

(a) Statement I is true, but Statement II is false
(b) Both Statement I and Statement II are false
(c) Both Statement I and Statement II is true
(d) Statement I is false, but Statement II is true

UPPCL AE 2018

Ans. (d) : Semi-compact section cannot develop plastic moment of resistance so it cannot reach yield stress.

Search on Telegram @apna_pdf

866. In plastic bending of beams, the shape factor of a section is the ratio of _____:

(a) yield rotation to ultimate rotation
(b) yield moment to plastic moment
(c) elastic modulus to plastic modulus
(d) plastic moment to yield moment

UPPCL AE 2018

Ans. (d) :
In plastic bending of beams shape factor

$$= \frac{\text{plastic moment}}{\text{yield moment}} = \frac{M_p}{M_y}$$

867. The shape factor for a rectangular section is :



(a) 1.50 (b) 2.0
(c) 2.34 (d) 1.22
(e) 1.8

CGPSC AE 2017
TNPSC AE 2019
Nagaland PSC CTSE 2017 Paper–I
UPRVUNL AE 2015
ISRO Scientist/Engineer 2014
CGPSC AE 2014 Shift–I
UJVNL AE 2012

Ans. (a)
The shape factor for a rectangular section is 1.5

$$\text{Shape factor} = \frac{\text{Plastic moment capacity}\left(m_p\right)}{\text{Elastic moment capacity}\left(m_y\right)}$$

$$= \frac{\text{Plastic section modulus}\left(z_p\right)}{\text{Elastic section modulus}\left(z_e\right)}$$

	Shape	Shape factor
1.	Rectangular 	1.5
2.	Circular 	1.7
3.	Rhombus 	2
4.	Triangular 	2.343
5.	I-section 	1.1 – 1.2

868. The shape factor of standard rolled beam section varies from:

(a) 1.1 to 1.2 (b) 1.2 to 1.3
(c) 1.3 to 1.4 (d) 1.4 to 1.5
(e) 1.5 to 1.6

Haryana PSC AE 2018 Paper–I

Ans. (a) : The shape factor of standard rolled beam section varies from 1.1 to 1.2

869. If the shape factor of a section is 1.5 and the factor of safety to be adopted is 2, then the load factor will be:

(a) 3 (b) 4
(c) 1.5 (d) 2

Haryana PSC AE 2017

Ans. (a) : Load factor = (factor of safety) × shape factor = 2 × 1.5 = 3

870. Which one of the following is valid statement in the case of Plastic Analysis?

(a) Shape factor is the ratio of plastic section modulus to the elastic section modulus
(b) Shape factor is the ratio of elastic section modulus to the plastic section modulus
(c) Shape factor is the ratio of plastic section modulus to the elastic section modulus and its value is always less than 1.0
(d) Shape factor is the ratio of plastic section modulus to the elastic section modulus and its value is always greater than 1.0

HPPSC Poly. Lect. 2016

Ans : (d) In Plastic analysis, shape factor is defined as it is the ratio of plastic section modulus to elastic section modulus and its values always greater than one.

$$\boxed{\text{S.F} = \frac{Z_p}{Z_e} > 1}$$

871. Which of the following conditions to be satisfied both in elastic and plastic analysis?

(a) Equilibrium condition
(b) Yield condition
(c) Plastic moment condition
(d) Mechanism condition

WBPSC AE 2012

Ans. (a) : Equilibrium condition satisfied both in elastic and plastic analysis.

872. In plastic analysis, the shape factor for rectangular section is

(a) 1.4 (b) 1.5
(c) 1.6 (d) 1.7

WBPSC AE 2003

Search on Telegram @apna_pdf

Ans. (b) : Shape factor = $\frac{Mp}{My} = \frac{fy.Zp}{fy.Z} = \frac{Zp}{Z}$

The shape factor for rectangular section is 1.5.

873. A simply supported uniform beam ABC overhangs beyonds B to C, such that AB = L and BC = L/3. If it is to carry factored vertical loads of 2W at mid-span of AB and W at the free and C, what is the value of M_p that should be provided?

(a) $\frac{3}{15}WL$ (b) $\frac{6}{15}WL$

(c) $\frac{WL}{3}$ (d) $\frac{2}{9}WL$

WBPSC AE (PHE) 1998

Ans. (c) :

874. At a plastic hinge

(a) The maximum fiber stress reaches yield point

(b) The maximum tensile stress is equal to ultimate stress

(c) There is free rotation with aero B.M.

(d) The B.M. is equal to the fully plastic moment of the section

WBPSC AE (PHE) 1998

Ans. (d) : At a plastic hinge the B.M. is equal to the fully plastic moment of the section.

875. A fixed beam of span L carries a UDL of intensity w/unit run. If the plastic moment of the beam section is M_P, collapse occur when _____ number of plastic hinges are formed and wL = _____.

(a) 2 and 8 M_P/L (b) 3 and 8M_P/L

(c) 3 and 16 M_P/L (d) 2 and 16 M_P/L

TSPSC Deputy Engineer 2015

Ans. (c) :

876. A cantilever beam of span L carries a point load W at its free end. Plastic moment of the section from support to middle of span is 1.5 M_P and from there to free end is M_P. Collapse occurs when W = _____.

(a) 1.5 M_P/L (b) M_P/L

(c) 2M_P/L (d) 0.75 M_P/L

TSPSC Deputy Engineer 2015

Ans. (a) :

877. The structural steel cross-section which can develop plastic moment of resistance but have inadequate plastic hinge rotation capacity is classified as

(a) Plastic (b) Compact

(c) Semi-compact (d) Slender

TSPSC AEE 2017

Ans. (b) : The structural steel cross-section which can develop plastic moment of resistance but have inadequate plastic hinge rotation capacity is classified as compact.

878. Which of the below is an incorrect assumption among the following with regard to the distribution of stress in a curved flexural member?

(a) The material of the beam obeys Hook's law

(b) The material of the beam is perfectly homogenous

(c) The Young's modulus is not the same both in tension and compression

(d) The cross-section has an axis of symmetry in a plane along the length of the beam

DMRC AM 2020

Ans. (c) The young's modulus is same in both tension and compression.

879. The plastic section modulus for a rectangular section of width b and depth d is :

(a) $\frac{bd^3}{3}$ (b) $\frac{bd^2}{3}$

(c) $\frac{bd^2}{4}$ (d) $\frac{bd^2}{6}$

Nagaland PSC CTSE 2017 Paper–I

Ans. (c) : We know, shape factor for rectangular section $= \frac{Z_p}{Z_y} = 1.5$

$$= \frac{Z_p}{\frac{bd^2}{6}} = 1.5$$

$$= Z_p = \frac{3}{2} \times \frac{bd^2}{6}$$

$Z_P \rightarrow$ Plastic section modulus for rectangular section

$$\Rightarrow \boxed{Z_p = \frac{bd^2}{4}}$$

Search on Telegram @apna_pdf

08.

Building Construction and Maintenance Engineering

1. Masonary and Plaster Work

1. The portion of a brick cut across the width, is called
(a) closer (b) half brick
(c) bed (d) bat

TNPSC AE 2012

Ans. (d) The portion of a brick cut across the width, is called bat. If the bat is equal to half of the brick, it is known as half bat. It is called three quarter but if its length is equal to $3/4^{th}$ of the brick.

2. An external corner in brick masonry is called
(a) Quoin (b) Jamb
(c) Squint (d) Closer

WBPSC AE 2012

Ans. (a) : The external corner or angle of a wall surface is called quion.

3. A bull nose brick is not used for
(a) Rounding off sharp corners
(b) Pillars
(c) Decoration purpose
(d) Arches

RPSC AE 2018
UJVNL AE 2016

Ans. (d) : Bull nose brick is a style of brick that has one, some or all of its corners rounded off. These bricks can be used to craft soft and attractive curve edge to steps, still, pillars etc.

4. Surkhi is used as building material for the following:
(a) Floor covering (b) Pointing old works
(c) Brick masonry (d) All of these

[UPPSC State Eng. A.E. 2007(I)]

Ans : (d) Surkhi is used as building material for the floor covering, pointing old work and Brick masonary.

5. Minimum thickness of wall where single flemish bond can be used is:
(a) Half brick thickness
(b) One brick thickness
(c) One and half brick thick
(d) Two bricks thick


WBPSC Poly Lect. 2019

Ans. (c) : Minimum thickness of wall where single flemish bond can be used is One and half brick thick.

6. A stretcher bond is usually used for
(a) Half brick wall
(b) One brick wall
(c) One and half brick wall
(d) Two brick wall

RPSC POLY. TECH. LECT. 2011

Ans : (a) In Stretcher bond all the bricks are laid as stretchers on the face of walls. It is suitable for half brick walls only.



Stretcher bond

7. Minimum thickness of wall where-single Flemish bond can be used is
(a) Half brick thick
(b) One brick thick
(c) One and half brick thick
(d) Two brick thick

RPSC VPITI 2012
GPSC AE (CLASS 1 & 2) 2019

Ans : (c) Single flemish bond is a combination of both English and flemish bond. Facing of the wall consists of flemish bond and the backing is done in english bond. The minimum thickness of wall can be used is one and half brick thick.

8. For walls having thickness of wall more than one and a half brick, the following bond is more compact and stronger
(a) Double Flemish bond (b) English Bond
(c) Garden wall bond (d) Dutch bond

RPSC A. En. 2013

Ans : (b) English bond is most commonly used bond for all wall thickness. This bond is considered to be the strongest bond.
Note : (1) the flemish bond gives more pleasing appearance then the English bond.
(ii) The English bond is stronger than flemish bond for wall thicker than $1\frac{1}{2}$ brick.

9. As per IS, for a load bearing brick masonry wall built in cement mortar, the maximum permissible slenderness ratio is :
(a) 17 (b) 27
(c) 38 (d) 20

BHEL ET 2019

Ans. (b) : According IS 1905 : 1987, Table No. 7
Maximum slenderness ratio for a load bearing wall depends upon number of storey.

Search on Telegram @apna_pdf

No. of storey	Maximum slenderness ratio	
	Using portland cement or portland Pozzolana cement in mortar	Using lime mortar
Not Exceeding 2	27	20
Exceeding 2	27	13

10. The measurement for all types of grouting shall be made on the basis of the X of cement in the grout actually forced into the holes, where X is?

(a) Volume (b) Length
(c) Setting time (d) Weight

NPCC AE 2017

Ans. (d) : Grouting is the phenomenon of finishing or smoothening the sanitary ducts and holes by applying a cement paste based on it's (cement) weight for better work.

11. In which type of bond cavity existing?

(a) Flemish bond (b) English bond
(c) Segregation System
(d) Natural Ventilation System

Maharashtra PSC (Mains) 2017 Paper–I


Ans. (c) In segregation system of bond cavity exist.

12. A type of bond in the brick masonry in which each course consists of alternate headers and stretchers is–

(a) English bond (b) Ranking bond
(c) Dutch bond (d) Flemish bond

KPSC AE 2020
BPSC AE Pre 2018
Karnataka PSC AE 2017 Paper - II
ISRO Scientist/Engineer 2015
UK Combined AE Paper II 2012

Ans. (d) Flemish Bond - Flemish bond in brick laying is an arrangement of bricks such that each course consists of alternate bricks having their short sides (headers) and long sides (stretchers) facing outwards, with alternate courses being offset.



English Bond - English bond in bricklaying, an arrangement of bricks such that one course has the short sides of the bricks (headers) facing outwards, and the next course has the long sides of the bricks (stretchers) facing outwards.

Rankine Bond - In this bond the bricks are laid at some inclination to the face of the wall.


Dutch Bond - A brickwork bond in which the vertical joints of the stretchers in any course are in line with the centres of the first stretchers above and below.

13. A queen closer is

(a) Full brick (b) Longitudinally $\frac{1}{2}$ brick
(c) $\frac{3}{4}$ brick (d) $\frac{1}{2}$ brick

APPSC AE 2016 (Mains)

Ans. (b) : Queen closer : a brick of full length and thickness but half width that is the used at the end of a course next to quoin header.



14. The brick laid with its breadth parallel to the face of a wall is known as :

(a) Header (b) Stretcher
(c) Closer (d) Queen Closer

GPSC AE Class (1&2) Paper - 2 2017

Ans. (a) : The brick laid with breadth parallel to the face of wall is header.

15. When a brick is cut into two halves longitudinally, one part is called

(a) king closer (b) queen closer
(c) half bat (d) bevelled bat

GPSC AE March 2018

Ans. (b) : When a brick is cut along its length, making two equal halves then it is called queen closer and also known as Queen closer half.

16. Type of joint preferred in a single brick wall to save facing bricks is

(a) English bond (b) Flemish bond
(c) Garden-wall bond (d) Stretcher bond

UPSC JWM 2017

Ans. (c) : Garnden-wall bonds are spectacular to reduce no. of through heads to minimize the labour in selecting brick rough in both side in single brick wall.

17. Wetting of bricks for sufficient time before actually using in construction does not help in which of the following?

(a) help adhesion with mortar
(b) removal of dust, sand and dirt
(c) prevents suction of water from mortar
(d) reduces mortar thickness

UPPCL AE 2015

Ans. (d) : Mortar thickness used for building brick structure does not depend upon quality and condition of bricks.

18. The brick laid with its length parallel to the face of the wall is called a

(a) header (b) closer
(c) course (d) stretcher

GWSSB AAE 2015

Ans. (d) : Course of brick laid in a wall so that the lengths parallel the face of the wall are called stretchers. The brick whose length runs at right angle to the face of the wall are called headers. In soldier courses the brick stand on the end and in rowlock courses the lie on edge.


19. King closers are related to

(a) brick masonry (b) doors and windows
(c) king post truss (d) queen post truss

WBPSC Poly Lect. 2019
GWSSB AAE 2015
RRB SSE (Bilaspur) Yellow Paper : 21.12.2014
UPPSC State Eng. A.E. 2008


Search on Telegram @apna_pdf

Ans. (a) :



king closer

King closer is obtained by cutting a triangular portion of the bricks such that half of header and hall a stretcher are obtained on the adjoining cut face. A king closer is used near door and window opening to get a satisfactory arrangement of the mortar joints.



20. Single flemish bond consists of

(a) flemish bond facing and english bond backing in each course
(b) stretcher bond facing and double flemish bond backing in each course
(c) double flemish bond facing and header bond backing in each course
(d) english bond facing and double flemish bond backing in each course

Rajasthan Nagar Nigam AE Shift-2, 2016

Ans. (a) : Single flemish bond, each courses consist of alternate headers and strechers. The alternate headers of each course are centered over the strechers in the course.

21. ..... is considered as the strongest bond in brick work.

(a) English bond (b) Raking bond
(c) Garden-wall bond (d) Dutch bond
(e) None of the above options

Haryana PSC AE 2018 Paper–I

Ans. (a) : English bond:-In this alternate (Courses consist of headers and stretchers. This is considered to be the strongest bond.
Flemish bond:-In this type of bond each courses comprises of alternate header and stretcher. Alternate courses start with stretcher and header.

22. English Bond, Flemish Bond, Dutch Bond pertain to

(a) Masonry work
(b) Cement bonding
(c) Bonding between beams
(c) Bonding in foundation

RRB SSE Secunderabad : 21-12-2014

Ans : (a) English Bond, Flemish Bond, Dutch Bond are related to masonry work.

23. A king closer is a :

(a) Full brick
(b) Three fourth brick
(c) Crosswise half brick
(d) Longitudinally half brick

JPSC AE (Pre) 2019

Ans. (c) : The part of the brick obtained by cutting the triangular corner portion from the middle points of width and length of brick is called king closer.

24. For constructing 100 mm thick partition wall, it is preferable to use

(a) stretcher bond (b) header bond
(c) flemish bond (d) garden bond

[UPPSC State Eng. A.E. 2004 (II)]
[UPPSC State Eng. A.E. 2008]

Ans : (a) For constructing 100 mm thick partition wall, it is preferable to use stretcher bond.
Stretcher bond : To develop stretcher bond, bricks are placed horizontally like stretchers on the faces of walls. The length of the bricks remains along the horizontal direction of the wall.
Header bond : When all the bricks are arranged as headers on the faces of walls, the bond that is developed is described as "Header Bond".
Flemish bond : An arrangement of bricks such that each course consist of alternate bricks having their short sides (headers) and long sides (stretchers) facing outwards, with alternate courses being offset.

25. The type of bond in a brick masonry containing alternate course of stretcher and headers is called:

(a) Flemish bond (b) English bond
(c) Stretcher bond (d) Header bond

ISRO Scientist/Engineer 2020
GPSC AE (CLASS 1 & 2) 2019
OPSC AEE 2015 PAPER–I / GWSSB AAE 2015
TNPSC AE 2012
UPPSC State Eng. A.E. 2007(I)

Ans. (b)




Fig. English bond masonry

English bond – In this type of bond alternate layers of header & stretcher respectively which means that one layer will be header and other will be stretcher.
Flemish bond - In this type of bond each course consists of header and stretcher alternately arranged.
Header bond - Header bond is also known as heading bond. In header bonds all bricks in each course are placed as headers on the face of the wall.
Stretcher bond - All the bricks in this type of bond are laid as strecher on the face of wall.

26. In stone masonry, the stones are placed in such a way that their natural bedding plane is–

(a) parallel to the direction of pressure they carry
(b) normal to the direction of pressure they carry
(c) at 45° to the direction of pressure they carry
(d) at 60° to the direction of pressure they carry

Gujarat PSC AE (N.W.R.) 2020
GPSC AE Dec 2018

Ans. (b) In stone masonry, the stones are placed in such a way that their natural bedding plane is normal to the direction of pressure they carry load.


Search on Telegram @apna_pdf

27. The portion of a brick cut across its mid width and having its length equal to that of a full brick, is known as


(a) King closer (b) Cornice brick
(c) Queen closer (d) Voussoir

[Uttarakhand Combined State AE Paper II 2007]

Ans : (c) Queen closer is the portion of a brick obtained by cutting a brick length wise in to two portions.



King closer is the portion of a brick which is so cut that the width of its one end is half that of a full brick, while the width of the other end is equal to the full width.



28. In brick masonry-

(a) Mortar strength should match brick strength
(b) Mortar strength should exceed brick strength
(c) Brick strength should exceed mortar strength
(d) The strengths of masonry and brick are independent

(UPRVUNL AE 2015)


Ans : (a) In brick masonry mortar strength should be match brick strength. The arrangement of laying bricks and bonding them with mortar properly to form a unified mass which can transmit the super-imposed load safely to the foundation.

29. If after every three or four stretchers, one header is used in all course as a brick masonry wall, then the bond so formed will be called as

(a) English garden wall bond
(b) Flemish garden wall bond
(c) Stretcher bond
(d) Herring Bond

RPSC POLY. TECH. LECT. 2011

Ans : (b) Flemish garden wall bond is suitably adopted for one brick thick wall which may act as a garden wall or a boundary wall. In this type of bond, after every three or four stretchers, one header is used in all course as a brick masonry wall.



Flemish Garden wall

30. Brick masonry not to be raised, in one day, more than

(a) 1.5 m (b) 2.5 m
(c) 3.5 m (d) 0.5 m

[UPPSC State Eng. A.E. 2007(II)]

Ans : (a) A maximum of 1.5 m high wall can be raised in brick masonry in a day. By this, the strength of the wall is unaffected. By making a high wall, the lower wall cannot bear the weight of the top wall and it can bend laterally.

31. Dutch bond is a modification of.....

(a) Single Flemish bond (b) Header bond
(c) English bond (d) Stretcher bond

SJVNL ET 2019


Ans. (c) : Dutch bond is a modification of English bond.

32. Herring-bone is commonly used for:

(a) thick walls
(b) partition walls
(c) footings in foundations
(d) brick paving

[UPPSC State Eng. A.E. 2007(I)]

Ans : (d)



Herring – bone is commonly used for brick paving.

33. The purpose of constructing a brick wall using a proper bond is to-

(a) improve the appearance of a wall
(b) distribute the load on a large area of the foundation
(c) prevent unequal settlement of the foundation
(d) improve the appearance of wall, to distribute the load on a large area of foundation and to prevent unequal settlement of foundation

[UPPSC State Eng. A.E. 2004 (II)]

Ans : (d) The purpose of constructing a brick wall using the proper bond is :
(a) to improve the appearance of wall.
(b) to distribute the load on large area of foundation.
(c) to prevent unequal settlement of foundation.

34. The bond produced in brick masonry by laying alternate headers and stretchers in each course is called-

(a) Single Flemish Bond (b) English Bond
(c) Double Flemish Bond (d) None of these

[UPPSC State Eng. A.E. 2004 (II)]

Ans : (c) Flemish bond : This bond of bricks consists of alternate headers and stretchers in each course, features of this bond are follows :

1. Every course consists of headers and stretchers placed alternately.
2. For breaking vertical joints in successive course queen closers are inserted in alternate courses next to the quoin header.

Search on Telegram @apna_pdf

3. Every header is centrally supported over a stretcher below it.
4. It gives better appearance than the English bond.
5. In wall having their thickness equal to odd number of half bricks, bats are necessary to be used.

Double flemish bond : Double flemish bond consists of an alternative header, stretcher in each course.

Single flemish bond : This bond is a combination of English bond and flemish bond. In this work the facing of the wall consists of flemish bond and the backing consists of English bond in each course.

English Bond : It is the arrangement of bonding which consist of alternate courses of stretchers and headers. "In order to break the alignment of vertical joints to fall in same straight line queen closer half bricks is provided next to quoin header.


Flemish bond is further divided into two different types viz. single Flemish bond and Double flemish bond.

35. A queen closer is a

(a) brick laid with its length parallel to the face or direction of wall
(b) brick laid with its breadth parallel to the face or direction of wall
(c) Brick having the same length and depth as the other bricks but half the breadth
(d) brick with half the width at one end and full width at the other

OPSC AEE 2019 Paper–I
RPSC AE 2018
[UPPSC State Eng. A.E. 2003]

Ans : (c) When a brick is cut along its length, making it two equal halves then it is called queen closer. Thus a queen closer is a broken brick portion where width is half as wide as the original brick. This is also called as queen closer half.



Queen-Closer (Half)

36. Quoins in brick masonry are-

(a) bricks cut at corners in a triangular fashion
(b) half-brick with length same but width halved
(c) squint junction of walls
(d) corner junction of wall

BPSC AE Pre 2018

Ans. (d) Quoins - Quoins are large rectangular blocks of masonry or brick that are built onto the corners of a wall. They can be used as a load-bearing feature to provide strength and weather protection and also for aesthetic purposes to add detail and accentuate the outside corners of a building.

37. The stone masonry adopted in construction of architectural importance which gives smooth appearance is :

(a) Ashlar masonry
(b) Coursed rubble masonry
(c) Uncoursed rubble masonry
(d) Random rubble masonry

Karnataka PSC AE 2015 Paper - II

Ans. (a) : Ashlar's masonry is a type of stone masonry which is formed using finely dressed stones of same size, shape and texture laid together in cement or lime mortar of equal size joints at right angles to each other.

38. Which of the following features regarding Double-Flemish bond is not true?

(a) Every course consists of headers and stretchers placed alternately
(b) The facing and backing of the wall, in each course, have the same appearance
(c) Quoin closers are not required
(d) Headers of any course are supported centrally by the stretchers of their underlying course

GPSC AE (CLASS 1 & 2) 2019

Ans : (c) : In Flemish bond each course has alternate header & stretcher

- In starting Quoin header next is always quoin closer to break the alignment.
- Header in Central Sandwiched and stretched by both Horizontally & Vertically
- Aesthetic appearance is good but its strength is not as good as English bond & skilled labour is required for making Flemish bond
- In double Flemish bond the face & back both are the same.

39. The ornamental moulded course placed on the top of a wall is called

(a) cornice (b) Frieze
(c) Coping (d) Lintel

ISRO Scientist/Engineer 2019

Ans : (a) :

- **Cornice -** It is projected ornamental course near the top of a wall or at the junction of the wall and ceiling. It penetrates the full width of wall. It is weathered and throated to dispose of rain water. In order to prevent cornice, extra weight in the form of parapet wall should be provided.
- **Coping -** It is a covering of stone, conerete, brick of terracotta, placed on the exposed top of wall to prevent seepage of water.
- **Frieze -** It is course of stone placed immediately below the cornice, along the external face of the wall.

40. In Brick - nogged type of partition walls, the frame work consists of vertical posts are called .....

(a) noggings (b) studs
(c) sills (d) templates

GPSC R&B AE 2016

Ans. (b) : Studs are placed at a distance of 3 to 4 times of brick length. The nogging pieces are placed at a vertical distance of about 600 mm – 900 mm. The crossed braces are provided at intersection.

41. The type of masonry in which the stones of irregular size and shapes are used and there is no regular course, is known as

(a) uncoursed rubble masonry
(b) coursed rubble masonry
(c) uniform rubble masonry
(d) dry rubble masonry

Rajasthan Nagar Nigam AE Shift-2, 2016

Search on Telegram @apna_pdf

Ans. (a) : Rubber masonry uses stones of irregular size.
In this stones of same height are used and courses are of the same height.

42. The permissible diagonal tensile stress in the reinforced brick work is
(a) zero
(b) about 0.1 N/mm^2
(c) 0.3 N/mm^2 to 0.7 N/mm^2
(d) None of the above

APPSC AEE 2012

Ans. (d) : As per Indian standards tensile strength of brick is 5 to 6% of compressive strength of brick.

43. Which of the following bond for brickwork is used in half-brick thick leaves of
(a) English bond (b) Garden wall bond
(c) American bond (d) Stretcher bond

GPSC AE June 2019

Ans. (d) :
- Half brick leaves of cavity walls or partition walls have strecher band for brick work.
- American bond is provided for designing purpose and in this milly white paste (viscous) for joining brick work.
- Garden wall bond has one headers and four stretcher bond.
- In English bond headers are laid centered on the stretcher in course below and each alternate row is vertically aligned.

44. ..... are provided as a protective coatings to wall at its top to prevent seepage of water.
(a) Corbels (b) Cornica
(c) Copings (d) Floating

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (c) : Copings are provided as a protective coatings to walls at its top to prevent seepage of water.

45. A mortar joint in masonry which is normal to the face of wall is known as:
(a) Wall joint (b) Cross joint
(c) Bed joint (d) Bonded joint
(e) All of the above options

Haryana PSC AE 2018 Paper–I

Ans. (b) : Bed joint:-Bed joint can be defined as the horizontal mortar joint upon which masonary units are laid. Thus the pressure always acts normal to the bed joint.
Cross joints or simple joints:-The joints (other than bed joint) which are perpendicular to face of wall are termed as cross-joints or simple joints.
Wall joints:- Joints which are parallel to the face of wall are termed as wall joint.

46. Which of the following may b e a prime cost item?
(a) Brick (b) Steel
(c) Water (d) Water Cooler

GPHC AE 2018


Ans : (d) Prime cost Item – the cost item which is used as secondarily or for comfort is termed as prime cost item, Ex - Water Cooler.

47. Which is the conventional brick size used for construction presently for wall thickness of 35 cm and 46 cm etc.?
(a) 230 × 115 × 75 mm. (b) 190 × 90 × 90 mm.
(c) 225 × 90 × 75 mm. (d) 225 × 90 × 75 mm.

GPHC AE 2018

Ans : (a) The commonly adopted nominal size of traditional bricks is 23 cm × 11.4 cm × 7.6 cm


48. The Brick Bond shown in figure is :



(a) English Bond (b) Flemish Bond
(c) Garden wall bond (d) Stretcher Bond

GPHC AE 2018

Ans : (b Flemish Bond → In this type of joint each course is made up of alternate header and stretcher.



49. The operation of raking out of masonry joints for about 13 mm depth and then filling them up with rich cement sand mortar (1 : 3), is known as
(a) dressing (b) pointing
(c) hipping (d) surfacing

[Uttarakhand Combined State AE Paper II 2007]

Ans : (b) Pointing is the finishing of mortar joints in brick or stone masonry construction. All joints in masonry are raked down to a depth of 10 mm to 20 mm and filling it with better quality mortar in desired shape.
Mortar for pointing work–
(1) Lime mortar of 1 : 2 {1 fat lime : 2 sand or surkhi}
(2) Cement mortar of 1 : 3 { 1 cement : 3 sand}

50. Which one of the following is not true about English bond ?
(a) Bricks in one layer are laid on header bond and courses above and below are stretcher bond
(b) Bricks in one layer are laid on stretcher bond and courses above and below are header bond
(c) Every layer of bricks is laid on header and stretcher bond
(d) Bricks layer aligned such that vertical joint is continuous

Rajasthan JEN (Degree) Shift - II 2016

Ans. (d) : The vertical joints are not continuous in English bond.

51. While designing reinforced cement concrete wall carrying in plane loads, what is the permissible ratio of effective height to thickness?
(a) 30 (b) 35
(c) 20 (d) 25

CIL MT 2017

Ans. (a) : While designing reinforced cement concrete wall carrying in plane loads, permissible ratio of effective height to thickness is 30.

Search on Telegram @apna_pdf

52. Complete dislocation of plastered surface, resulting in formation of a patch is known as:-

(a) Peeling (b) Cracking
(c) Popping (d) Crazing

[UKPSC A E Paper II 2013]

Ans : (a) Peeling is the complete dislocation of some portion of plastered surface, resulting in the formation of a patch.

53. Consider the following statements:
Bricks are soaked in water before use in masonry work

A. to remove dust
B. to remove air voids
C. so that they do not absorb water from cement mortar

Which of these statements are correct?

(a) All three (b) Only A
(c) B and C (d) Only C

(UPRVUNL AE 2015)

Ans : (d) When brick is soaked in water, the brick absorb water and release air so that when it is used in masonry and placed over the wet mortor, it will no more absorb any water from the wet mortor. Thus, it will fail to make a strong bond between bricks and mortor.

54. The following defects may arise in plaster work:

(a) Cracking (b) Efflorescence
(c) Peeling (d) All the above

[U.K. Combined A E Paper II 2012]

Ans : (d) Different types of defects occurs in plastering work such as blistering, cracks, efflorescence, flaking, peeling, popping, softness and uneven surfaces. These defects in plastering need to be repaired as soon as they are observed.

55. For plastering the exposed brick walls, the cement sand mortar ratio should be :

(a) 1 : 2 (b) 1 : 3
(c) 1 : 4 (d) 1 : 6

(Uttarakhand Combined State AE Paper II 2007)

Ans : (c) For plastering the exposed brick walls, the cement sand mortar ratio should be 1 : 4,

[Cement mortar for different work]	**[Proportion of cement : sand in mortor]**
Brick masonry	1 : 6
Plastering works	1 : 4
Grouting the covernous rock	1 : 1.5
Guniting	1 : 3

56. For pointing the masonry is raked out to a depth of about:-

(a) 15 to 20 mm (b) 3 to 5 mm
(c) 5 to 10 mm (d) 20 to 40 mm

[UPPSC State Eng. A.E. 2007(II)]
[UKPSC A E Paper II 2013]

Ans : (a) Pointing is the implementing of joints to a depth of 10 mm to 15 mm and filling it with better quality mortar in desired shape. Pointing used to denote finishing of mortar joints of either stone masonry or brick masonry.

57. In building construction, gauging is the:

(a) process of mixing various constituents of plaster
(b) process of roughing the group to provide suitable bond for plastering
(c) process of scaling away patches of plaster or previous coats
(d) reflection on the surface of plaster

[UPPSC State Eng. A.E. 2007(I)]

Ans : (a) Gauging is the process of mixing various constituents of plaster i.e cement, lime and sand.

58. In stucco plastering, for finish coat the mortar is made of:

(a) 1 : 4 cement and sand
(b) 1 : 3 cement and sand
(c) 1 : 2 cement and sand
(d) 1 : 1 cement and sand

[UPPSC State Eng. A.E. 2007(I)]

Ans : (b) In stucco plastering the ratio of mix made for supply or finish coat should be in the ratio of 1:3 and in brick plowing 1:6 (cement : sand) is taken and $1:1\frac{1}{2}$ for grouting.

59. Expansion joint in masonry walls are provided in wall lengths greater than-

(a) 10m (b) 20m
(c) 30m (d) 40m

OPSC AEE 2015 PAPER–I
[UPPSC State Eng. A.E. 2003]

Ans : (c) According to IS-3414-1968 (R-2005), clause 6.3.1:-In brick or stone masonry expension joints normally need not be necessary expect in the case of long walls exceeding 30m in lenght. In such long walls the expension joints shall not be less than 15 mm wide and shall be spaced not more than 30 m apart.

60. Which of the following specifications are not correct with reference to a brickwork?

(i) Brickwork shall be done in such a way that all joints are full of mortar
(ii) For all exposed brickworks, double scaffolding having two sets of vertical supports shall be provided.
(iii) Bricks required for brick masonry with mud mortar need not be soaked.

(a) (i) and (ii) only (b) (i) and (iii) only
(c) (ii) and (iii) only (d) None of the above

MPSC (Mains) 2017 Paper–II

Ans. (d) : All the given statements are correct.

61. Preventive maintenance for a building work means-

(a) Taking action before break-down
(b) Breakdown maintenance
(c) Taking action after break-down
(d) None of these

OPSC AEE 2015 PAPER–I

Ans. (a) : Preventive maintenance is maintenance that is regularly performed to decrease the likelihood of failing. It is performed so that the building does not break down unexpectedly.

62. In ordinary residential buildings, D.P.C. may be provided-

(a) At ground level
(b) Between ground level and water table level
(c) At water table level

Search on Telegram @apna_pdf

(d) At plinth level

OPSC AEE 2015 PAPER–I

Ans. (d) : D.P.C. is short form of Damp Proof Course. It is always provided at plinth level.

63. The slenderness ratio for masonry walls should not be more than-

(a) 10 (b) 20
(c) 30 (d) 40

Haryana PSC AE 2017
OPSC AEE 2015 PAPER–I
Punjab MCP SDO 2015

Ans. (b) : According IS 1905 : 1987,
Maximum slenderness ratio for a load bearing wall depends upon number of storey.

No. of storey	Maximum slenderness ratio	
	Using portland cement or portland Pozzolana cement in mortar	Using lime mortar
Not Exceeding 2	27	20
Exceeding 2	27	13

64. Maximum slenderness ratio allowed as per Indian standard for an unreinforced load bearing wall (using Portland Cement or Portland Pozzolana Cement in mortar) is

(a) 13 (b) 20
(c) 27 (d) 35

GPSC AE (CLASS 1 & 2) 2019
APPSC AE 2016 (Mains)

Ans. (c) : According to IS 1905 : 1987, Table No. 7
Maximum slenderness ratio for a load bearing wall depends upon number of storey.

No. of storey	Maximum slenderness ratio	
	Using portland cement or portland Pozzolana cement in mortar	**Using lime mortar**
Not Exceeding 2	27	20
Exceeding 2	27	13

65. The test conducted for the calculation of basic compressive strength of masonry is :

(a) Vibration test (b) Prism test
(c) CBR test (d) Slump cone test

APPSC AE 2016 (Mains)

Ans. (b) : Prism test is a laboratory test to calculate the compressive strength of a masonry. A masonry Prism is an assembly of masonry unit and mortar that is constructed to serve as a test specimen for determining compressive strength.

66. In some brick masonry walls, patches of whitish crystals were found on the exposed surfaces, also chipping and spalling of bricks took place from the same walls. Which among the following are the causes of these defects?

1. Settlement of foundation
2. Over-loading of the walls
3. Sulphate attack
4. Efflorescence

Codes:

(a) 1 and 2 (b) 2 and 4
(c) 2 and 3 (d) 3 and 4

[HPPSC AE 2016]

Ans. (d) : White patches on brick are due to presence of alkali salts. This is known as efflorescence.
Sulphate attack causes spalling and chipping.

67. The process of finishing the joints with mortar of rich mix in brick and stone masonry is called:

(a) facing (b) pointing
(c) plastering (d) guniting

Karnataka PSC AE 2015 Paper - II


Ans. (b) : Pointing in masonry construction is the finishing of mortar joints in brick or stone masonry. Pointing is the implementing of joint to a depth of 10 to 20 mm and filling it with better quality mortar in desired shape.

68. The type of bond provided in brick masonry for carrying heavy load is

(a) English bond
(b) Single Flemish bond
(c) Double Flemish bond
(d) Zigzag bond


OPSC AEE 2019 Paper–I

Ans. (a) : English bond is the strongest bond. Hence it is generally used for load bearing constructions.
English bond consists of alternate courses of headers and stretchers



English Bond

⇒ Single Flemish Bond is a combination of English Bond and Flemish bond in this type of construction, the front exposed surface of wall consists of Flemish bond and the back surface of the wall consists of English bond in each course minimum thickness required for single Flemish bond is one and a half brick thickness.



⇒ Double Flemish bond :
Every course consist of headers and stretcher placed alternatively, the facing and backing of the wall in each course have the same appearance.

⇒ Zigzag Bond : This Bond is similar to herring-bone bond, except that the bricks are laid in zigzag fashion. This Bond is commonly used for making ornamental panels in the brick flooring.

69. A free standing brick wall 20 cm thick is subjected to a wind pressure of 75 kg/m^2.

(a) 0.64 m (b) 0.96 m
(c) 1.28 m (d) 1.50 m

Punjab MCP SDO 2015

Search on Telegram @apna_pdf

Ans. (a) : For stability, resisting moment = 1.5 × overturning moment

$$\therefore \quad WHt \times \frac{t}{2} = 1.5P\frac{H^2}{2}$$

$$H = \frac{Wt^2}{1.5P}$$

Assuming unit weight of brickwork equal to 2000 Kg/m^3

$$H = \frac{2000 \times 0.19^2}{1.5 \times 75} = 0.64\,\text{m}$$

70. Direct load carrying capacity of a brick masonry wall standing freely as against when it supports RC slab will be :
(a) more
(b) less
(c) the same in both the cases
(d) 100%

Punjab MCP SDO 2015
ESE 1995

Ans. (b) : Direct load carrying capacity of a brick masonry wall standing freely as against when it supports RC slab will be less.

71. As per NBC 2005, institutional buildings comes under :
(a) Group-A (b) Group-B
(c) Group-C (d) Group-D

TNPSC AE 2015

Ans. (c) : As per NBC 2005, buildings are classified in 9 groups–

A. Residential	B. Educational	C. Institutional
D. Assembly	E. Business	F. Mercantile
G. Industrial	H. Storage	I. Hazardous

72. In struck pointing, the face of the pointing is
(a) flat
(b) sloping outwards
(c) vertical but pressed inside
(d) grooved

Kerala PSC AE 2015

Ans. (b) : Cut or weatherd or struck pointing :-In this type of pointing, after the mortar is pressed into the racked joints is carefully pressed back by 3-6 mm at the top of horizontal joint with the help of pointing tool. Hence, this joint is finished. Sloping from top of the joint to its bottom.




Fig. Weathered or struck pointing

73. The quantities and unit rate of certain items of work of building are :
(i) brick work of 20m^3 and ₹ 2520/-per m^3
(ii) Plastering of 150 m^2 and ₹ 1250/-per m^2
Calculate the total cost of the items given :
(a) ₹ 50, 400 = 00 (b) ₹ 1,87,500 = 00
(c) ₹ 1,37,100 = 00 (d) ₹ 2,37,900= 00

TNPSC AE 2015

Ans. (d) : Total cost of brick work = 20 m^3 × 2520
= ₹ 50400
Total cost of plastering = 150 × 1250
= ₹ 187500
Net total cost = 50400 + 187500
= ₹ 2,37,900

74. Thickness of plastering is usually:
(a) 6 mm (b) 12 mm
(c) 25 mm (d) 40 mm

UJVNL AE 2012

Ans. (b) : Thickness of plastering is usually 12 mm

75. Dampness in a building is caused by:
(a) Rain water
(b) Ground moisture
(c) Defective construction
(d) Any of the above

UJVNL AE 2012

Ans. (d) : Dampness in a building is caused by:
Rain water
Ground moisture
Defective construction

76. Natural rupture along with the opposite walls have moved with respect to each other is called.....
(a) Fault (b) Conglomerate
(c) Cleavage (d) Joint

SJVNL ET 2019

Ans. (a) : Natural rupture along with the opposite walls have moved with respect to each other is called fault.

77. What is the operation of finishing the joints as the masonry work proceeds called?
(a) Chamfering (b) Bedding
(c) Profiling (d) Jointing

UPPCL AE 2015

Ans. (d) : The operation of finishing the joints as masonry work proceeds is called jointing.

78. What is the characteristic compressive strength of masonry mortar of grade MM 2?
(a) 2 – 2.5 (b) 2 – 3
(c) 1.5 – 2 (d) 2.5 – 3

UPPCL AE 2015

Ans. (b) : Masonry mortar (MM2) defined as minimum compressive strength in 28 days
MM 2 → 2 – 3 N/mm^2
MM 3 → 3 – 5 N/mm^2

79. The mode of failure of a very short masonry member having height/thickness ratio of less than 4 is by
(a) shear
(b) vertical tensile splitting
(c) buckling
(d) any of the above

GPSC AE June 2019

Ans. (a) : The mode of failure of a very short masonry member having height/thickness ratio of less than 4 is by shear.

Search on Telegram @apna_pdf

80. Consider the following statements:

(I) Stones should be placed in such a manner that its natural bed is at right angles to the expected pressure

(II) In doing so the stones offer maximum resistance to crushing & also maximum resistance to disintegration by rain water.

Out of above statements

(a) Both (I) and (II) are true
(b) (I) is true but (II) is false
(c) (I) is false but (II) is true
(d) Both (I) and (II) are false

PTCUL AE 2016

Ans. (b) : In stone masonry, natural bed of stones are placed right angled to the direction of the plane of pressure to prevent from crushing but not for disintegration of rain water.

81. For filling cracks in masonry structures, the type of bitumen used, is

(a) Cut-back bitumen (b) Bitumen-emulsion
(c) Blown bitumen (d) Plastic bitumen

UJVNL AE 2016

Ans. (d) : The plastic waste coated aggregate is mixed with hot bitumen and the resulting mix is used for road construction. The road laying temperature is between 110^0C to 120^0C.
It is also used filling cracks in masonary structure.

82. The basic stress in masonry unit having height to width ratio of 1.5 may be increased by a factor of:

(a) 1.2 (b) 1.4
(c) 1.6 (d) 2.0

Haryana PSC AE 2017
ESE 1998

Ans. (a):

Height to width ratio of units	**Shape modification factor**
Upto 0.75	1.0
1.0	1.1
1.5	1.2
2.0 to 4.0	1.3

83. Integrity and stability of a random-rubble masonry wall is ensured by :

(a) Providing parallel bedding layers
(b) Providing through stones
(c) Reducing the thickness at mortar joints
(d) Introducing vertical steel reinforcement

HPPSC Poly. Lect. 2016

Ans : (b) Integrity and stability of random-rubble masonry wall is ensured by providing through stones.

84. For earthquake resistant masonry buildings, the vertical distance between opening one above the other in a load bearing wall shall not be less than

(a) 50 cm (b) 60 cm
(c) 75 cm (d) 100 cm

WBPSC AE 2016


Ans. (b) : For earthquake resistant masonry buildings, the vertical distance between opening one above the other in a load bearing wall shall not be less than 60 cm.

85. The type of pointing in which V-sharped projection outside the wall surface is provided, is called:-


(a) Recessed pointing (b) Weather pointing
(c) V-pointing (d) Tuck pointing

[UKPSC A E Paper II 2013]

Ans : (b) Weather pointing is done by slopping the mortar outward from the upper edge of the lower brick, so that it sheds rainwater easily as can be seen from the image below.



V Point-



86. The fluid generally used for grouting is

(a) cement and water mix
(b) clay suspension
(c) sodium silicate
(d) all of the above

WBPSC AE 2014

Ans. (d) : • Sodiums silicate grouts are the most commonly used chemical grouts due to their safety and environmental compatibility.
• Suspension grouts basically consist of cement slurry with a cement/water ratio of approximately 0.1-0.4 and optional clay component.


87. The development of one or more local swelling on the finished plastered surface is called

(a) Foaming (b) Swelling
(c) Boiling (d) Blistering

WBPSC AE 2012

Ans. (d) : Blistering-Small patchees well out beyond the plastered surface. This is due to intense local relative expansion of the finishing coat. It is avoided by using proper slaked line.

88. The figure shows the plan view of a single-storey masonry shear wall building with rigid roof diaphragm. The traces of locations of the centre of mass (CM) and the centre of stiffness (CS) are as shown. Neglecting accidental eccentricity, the direction of the twisting moment on the diaphragm, for the lateral force direction shown, is



(a) Clockwise
(b) Anticlockwise
(c) Opposite to the direction of lateral force
(d) None of the above


ESE 2017

Search on Telegram @apna_pdf

Ans. (a)

- Centre of stiffness–centre through which the restoring force of a system acts.
- The shear wall rotates about centre of stiffness (CS), due to lateral loads.

So,



So, there will be clockwise rotation.

2. Partition and Cavity Walls

89. According IS 2212, the recommended type of brick wall for severe exposure condition is

(a) Unrendered 1/2 brick thick wall
(b) Unrendered 1-brick thick wall
(c) Unrendered 1.5-brick thick wall
(d) Rendered solid wall
(e) Cavity wall or rendered one-brick thick solid wall

CGPSC AE 2014 Shift–I

Ans. (e) : IS - 2212, Table- 3
Suitability of walls for various exposures
R = Recommended N = Not recommended

S. No.	Type of Brick wall	Exposure		
		Sheltered	Moderate	Severe
1.	Unrendred 1/2 brick thick wall	N	N	N
2.	Unrendred 1 brick thick wall	R	N	N
3.	Unrendred $1\frac{1}{2}$ brick thick solid wall	R	R	N
4.	Rendered solid wall	R	R	N
5.	Cavity wall or rendered one brick thick solid wall	R	R	R

90. Cavity walls

(a) prevent dampness from entering the building
(b) have lesser dead load for given wall thickness
(c) are better insulator against heat and sound
(d) all of these

TNPSC AE 2012

Ans. (d) Cavity walls prevent dampness, have lesser dead load due to cavity in them and provide better insulation against heat and sound.

91. Cavity wall is provided for

(a) heat insulation
(b) sound insulation
(c) prevention of dampness
(d) all of the above

GPSC AE (CLASS 1 & 2) 2019
[Uttarakhand Combined State AE Paper II 2007]

Ans : (d) The cavity wall construction is an effective method of damp prevention, in which the main wall of a building is shielded by an outer skin wall, leaving a cavity between the two. The cavity wall are often constructed for giving better insulation to the building. It also prevents the dampness to enter and acts as sound insulation.

92. In order to check dampness, a narrow hollow space constructed parallel to the external walls, is known as:-

(a) Cavity wall (b) Parapet wall
(c) Air drain (d) Water drain

[UKPSC A E Paper II 2013]

Ans : (c) In order to check dampness, a narrow hollow space constructed parallel to the external walls are known as Air drains.

93. Parapet wall is protected from rain water by:

(a) brick coping (b) brick sills
(c) brick corbels (d) brick lintel

[UPPSC State Eng. A.E. 2007(I)]

Ans : (a) Parapet wall is protected from rain water by brick coping.

94. Cavity or hollow space in a wall is provided for-

1. Prevention of dampness
2. Heat insulation
3. Sound insulation
4. Efflorescence

(a) 1 and 2 (b) 1 and 3
(c) 1, 2 and 4 (d) 1, 2, 3 and 4

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (d) : Cavity or hollow space in a wall serves various purposes such as sound and heat insulation. It is because air between the wall is a bad conductor of heat.
It can also help in prevention of dampness and efflorescence by preventing the movement of water inside.

95. Flying shores are used to strengthen-

(a) single wall (b) two adjacent walls
(c) tall walls (d) Any of the above

BPSC AE Pre 2018

Ans. (b) : The term shoring is applied to construction of the temporary structure required to support an unsafe structure. Flying shores are used to support two parallel walls which are in dange due to the removal of an intermediate building.
Flying shores is a system of providing temporary supports to the party walls of the two buildings where the intermediate building is to be pulled down and rebuild.

96. When large openings are to be made in existing wall, the type of temporary work used is-

(a) Raking shore (b) Flying shore
(c) Dead shore (d) Underpinning

BPSC AE Pre 2018

Search on Telegram @apna_pdf

Ans. (c) : Dead shores – Dead shore is the system of shoring which is used to render vertical support to walls and roofs, floors, etc. when the lower part of a wall has been removed for the purpose of providing an opening in the wall or to rebuild a defective load bearing wall in a structure

Raking shore – In this shoring, inclined members known as rakers are used to give lateral supports to walls

Flying Shore – Flying shores is a system of providing temporary supports to the party walls of the two buildings where the intermediate building is to be pulled down and rebuilt.

Underpinning – In construction or renovation, underpinning is the process of strengthening the foundation of an existing building or other structure

97. A temporary structure that is built to support and unsafe structure is called

(a) scaffolding (b) jacking
(c) shoring (d) underpinning

GPSC AE (CLASS 1 & 2) 2019

Ans : (c) : Shoring is :

- A temporary structure to support unsafe structure during repairs
- **Scaffolding –** A temporary structure used to support a work ; crew and material to aid in the construction, maintenance and repairs of building, bridges and all other non-made structure.
- **Underpinning →** A process of strengthening of foundation of newly structure or existing structure.

98. The projection of ornamental course at the junction of a wall and ceiling:

(a) Coping (b) Corbel
(c) Cornice (d) Parapet

Kerala PSC AE 2015

Ans. (c) : Cornice- It is any horizontal decorative molding which is provided at the junction of wall and ceiling or any two horizontal structure.

Coping- It is a covering of stone, concrete, brick or terracotta placed on the expose top of wall to prevent seepage of water.

Parapet- It is barrier which is an extension of the wall at edge of roof terrace, balcony walkway or other structure.

99. A covering of concrete placed on the exposed top of an external wall is known as

(a) Coping (b) Cornice
(c) Frieze (d) Lintel

ISRO Scientist/Engineer 2018

Ans : (a) :

- Coping is a covering of stone, concrete, brick of terracotta, placed on the exposed top of a wall to prevent seepage of water in compound wall. A coping is suitably weathered and throated.
- Cornice is projecting ornamental course near the top of wall or at the junction of the wall and ceiling.
- Frieze is a course of stone placed immediately below the cornice, along the external face of the wall.
- Lintel is a horizontal member of stone, brick wood, steel or reinforced concrete, used to support the masonry and the superimposed load above or opening.

100. When two walls separated by a small gap, are connected together by metal pins, it is called

(a) cavity wall (b) normal wall
(c) partition wall (d) double wall

GWSSB AAE 2015

Ans. (a) : Cavity wall is a double wall consisting of two separate wall called 'skins' so 'leaves of masonry separated by an air space and joined together by metal pins at suitable intervals.

The cavity should neighbour be less than 40 mm nor more than 100 mm in width.

101. A temporary lateral support to an unsafe wall is known as

(a) Raking shore (b) Vertical shore
(c) Dead shore (d) Flying shore

Rajasthan AE Nagar Nigam Shift-3, 2016

Ans. (a) : A temporary lateral support to an unsafe wall is known as raking shore.

102. The wall that are supported and restrained against lateral deflection along one to four sides is called.....

(a) Stocky wall (b) Un-braced wall
(c) Slender wall (d) Braced wall

SJVNL ET 2019

Ans. (d) : The wall that are supported and restrained against lateral deflection along one to four sides is called Braced wall.

103. The minimum eccentricity (mm) for vertical loading that should be considered while designing a 500 mm reinforced cement concrete wall would be

(a) 5 (b) 10
(c) 20 (d) 25

UPRVUNL AE 2016

Ans.: (d) The minimum eccentricity (mm) for vertical loading that should be considered while designing a 500 mm reinforced cement concrete wall would be 25mm.

104. What is the effective length of the wall when the wall is supported by a buttress of cross-wall?

(a) 1.0 L (b) 0.5 L
(c) 2.0 L (d) 2.5 L
(e) 5.0 L

CGPSC AE 2017
ESE 2015

Ans. (a) 1.0 L is the effective length of the wall when the wall is supported by a buttress of cross-wall.

105. In cinema theatre, to avoid reverberation, the longitudinal walls should be

(a) Perfectly parallel
(b) Converging towards screen
(c) Converging towards rear
(d) Should be curvilinear

Haryana PSC AE 2010

Ans. (b) : In cinema theatre, to avoid reverberation, the longitudinal walls should be converging towards screen. The front wall and ceiling can be reflective, enabling sound to reach everyone.

Search on Telegram @apna_pdf

106. Generally the unit of measurements for partition wall is

(a) volume (b) area
(c) length (d) number

WBPSC AE 2007

Ans. (b) : Generally the unit measurement of partition wall is in square meter (area).

3. Foundation

107. The foundations are placed below ground level, to increase

(a) strength (b) workability
(c) stability of structure (d) all of these

TNPSC AE 2012

Ans. (c) Foundation are placed below ground level to increase stability of structure because below ground level foundation is not free to move laterally and distribute the total load coming on the structure on large area.

108. Which of the following types of footing will be used to transmit heavy loads through steel columns?

(a) Raft foundation (b) Grillage foundation
(c) Well foundation (d) Isolated footing

KARNATAKA GESCOM AE 2011
OPSC AEE 2019 Paper–I

Ans : (b) Grillage foundation-This type of fooling is used to transmit heavy loads from steel columns to foundation soils having low bearing power. This type of foundation avoids deep excavation and provides necessary area at the base to reduce the intensity of pressure of the foundation soil is not stiff and there is a plenty of water with spring, the sides are protected by sharing.

109. The minimum depth of foundation below ground level for a residential building according to IS:1904 should be:

(a) 100cm (b) 80cm
(c) 60cm (d) 50cm

[UPPSC Civil Eng. A.E. 2013(II)]
[UPPSC State Eng. A.E. 2008]
[UPPSC State Eng. A.E. 2004(II)]

Ans : (d) As per IS 1904 : All foundation shall extend to a depth of at least 50 cm below natural ground level. Generally for two storey building minimum foundation depth is taken as 60 cm. below ground level.

110. The minimum height of plinth of a building with respect to the level of the centre of the road passing at its front or back should be:

(a) 10cm (b) 45cm
(c) 30cm (d) 60cm

UPPSC Civil Eng. A.E. 2013(II), 2004(II)
UPPSC State Eng. A.E. 2008, 2003

Ans : (b) The plinth or any part of a building or outhouse shall be so located with respect to average read level from site so that adequate drainage of the site is assured but at a height not less than 45 cm.
These shall be raised at least 15 cm. above the surrounding ground level and shall satisfactorily drained.

111. A ground in filling having low bearing capacity with heavy concentrated loads are generally supported by providing

(a) Combined footing (b) Strap footing
(c) Raft footing (d) Any of the above

[UPPSC State Eng. A.E. 2011]

Ans : (c) Raft foundation is actually a thick concrete slab resting on a large area of soil, reinforced with steel, supporting column or walls and transfer load from structure to soil. It is generally provided for soil having low bearing capacity and it has to carry heavy concentrated load.

112. For a two storey residential building on waterlogged and filled up soil, the type of foundation should be-

(a) pile type (b) spread footing type
(c) pier type (d) inverted arch type

[UPPSC State Eng. A.E. 2007(I)]
[UPPSC State Eng. A.E. 2007(II)]

Ans : (d) For a two floor residential building on a waterlogged and filler soil, reverse type of foundation is made and it prevents the water percolation in the structure.

113. The minimum depth of foundation in clayey soils is-

(a) 50cm (b) 70cm
(c) 90cm (d) 120cm

[UPPSC State Eng. A.E. 2003]

Ans : (c) The minimum depth of building foundations on:
(i) sandy soils is 80 cm to 100 cm
(ii) clay soils is 90 cm to 160 cm
(iii) rocky soils is 5 cm to 50 cm.

114. Match the following-

A. Electro-osmosis
B. Under reamed pile
C. Cellular cofferdam
D. Raft foundation
I. Provided water free area for work
II. Eliminate differential settlement
III. Dewatering of fine grained soil
IV. Foundation for expansive soil

	A	B	C	D
(a)	III	II	IV	I
(b)	III	IV	I	II
(c)	IV	III	I	II
(d)	I	IV	III	II

MPSC (Mains) 2017 Paper–II

Ans. (b) :
Electro-osmosis – Dewatering of line grained soil.
Under reamed pile – Foundation for expansive soil
Cellular cofferdam – Provided water free area for work
Raft foundation – Eliminate differential settlement

115. What is known as a watertight enclosure made up of sheet pile walls, usually temporary, built around a working areas for the purpose of excluding water during construction?

(a) cofferdam (b) bulkhead
(c) penstock (d) box caisson

Kerala PSC AE 2015

Search on Telegram @apna_pdf

Ans. (a) : Cofferdam: It is a structure that retains water and soil that allows the enclosed area to be pumped out and excavated dry. Coffer dams are commonly used for construction of bridge piers and other support structures built within water.

116. The allowable maximum settlement for commercial building is:

(a) 100 mm (b) 25 mm
(c) 75 mm (d) 50 mm

DSSSB AE 2019

Ans. (b) The allowable maximum settlement for commercial building is 25 mm.


117. The foundation in which a cantilever beam is provided to join two footings is called

(a) Raft footing (b) Strap footing
(c) Combined footing (d) Strip footing

ISRO Scientist/Engineer 2018

Ans : (b) :

- The strap footing is independent footings of two columns which are connected by a cantilever beam. A strap footing the columns is so great that a combined trapezoidal footing becomes quit narrow with high bending moments.



118. In case of foundation on black cotton soils, the most suitable method to increase the bearing capacity of the soil is :

(a) Increase the depth of foundation
(b) Drain the soil
(c) Compact the soil
(d) Replace the poor soil

OPSC AEE 2019 Paper–I

Ans. (d) : Generally, before the construction of foundation on black cotton soil sand bed is laid to act as a drainage layer. Drainage of water decreases the swelling nature of black cotton soil.

119. The lowest part of a structure which transmits the load to the soil is known as

(a) foundation (b) basement
(c) super-structure (d) plinth

GWSSB AAE 2015

Ans. (a) : The lowest part of a structure which transmits all loads and is direct contact with ground is called a foundation.

120. The portion of the building which is above ground level is termed as,

(a) sub-soil (b) foundation
(c) sub-structure (d) super-structure

GWSSB AAE 2015

Ans. (d) Superstructure is that structure which is above ground level and which reverse the purpose of its intended use. A part of the superstructure located between the ground and the floor level is known as plinth.

121. The arrangement of supports provided underneath the existing structure without disturbing its stability, is known as

(a) scaffolding (b) jacking
(c) shoring (d) underpinning

Rajasthan AE Nagar Nigam Shift-3, 2016
OPSC AEE 2015 PAPER–I

Ans. (d) : Underpinning is the process of strengthening of the foundation of existing building.

122. Trapezoidal combined footing is specifically adopted when :

(a) two column loads are close
(b) the interior column carries more load
(c) columns are close to property line
(d) the exterior column carries more load than the interior column

TRB Poly. Lect. Tech. 2017

Ans. (d) : Trapezoidal combined footing is specially adopted when the exterior column carriers more load than the interior column.

123. Floating foundation is a type of

(a) well foundation (b) raft foundation
(c) pile foundation (d) stepped foundation

BPSC AE Aug. 2019 Paper-V

Ans. (b) : A floating foundation is also known as balancing Raft it is a type of foundation where the weight of building plus weight of foundation is approximately equal to fill-weight of soil and water removed from the site of the building prior to construction.

124. The structures subjected to uplift due to hydrostatic pressure are anchored down by

(a) batter piles (b) tension piles
(c) anchor piles (d) compaction piles

BPSC AE Aug. 2019 Paper-V

Ans. (b) : Tension or uplift piles anchor down the structure subjected to uplift due to hydrostatic pressure or due to overturning moment.

125. Inverted arch footing is more suitable for

(a) residential buildings
(b) bridges
(c) single-storey building
(d) light warehouse

BPSC AE Aug. 2019 Paper-V

Ans. (b) : Inverted arch foundation is a type of bridge foundation is suitable when the depth of excavation for foundation is less. It is best suited where bearing capacity of soil is less.

126. The type of foundation suitable for under-water structures is

(a) cast-in-situ concrete piles
(b) continuous footing
(c) pier foundation
(d) stepped foundation

BPSC AE Aug. 2019 Paper-V

Ans. (c) : Caisson foundation is often used in the construction of bridge piers, hence it is also called as pier foundation. Caisson can be floated to the site and sunk to the required position. It is used in underwater also.

Search on Telegram @apna_pdf

127. A well cassion is a foundation facilating structure sunk in the ground or water; which is:
(a) Open at top as well as bottom
(b) Open at top and closed at bottom
(c) Open at bottom and closed at top
(d) Closed at top as well as at bottom

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (a) : A well caisson is a foundation facilating structure sunk in the ground or water; which is open at tap as well as at bottom.

128. What is the common between Rockwell, Brinell and shore? They pertain to–
(a) Surface finish (b) Heat treatment
(c) Metal turning (d) Hardness

RRB SSE Secunderabad : 21-12-2014

Ans : (d) Hardness is ability of a material to resist indentation and scratching.
Indentation hardness tests most often involved one of the three methods : Brinell, Rockwell or vickers. The shores scleroscope hardness testing is sometime employed as wall.

129. When column of framed structure building is situated near the edge of the property line and it is not possible to extend footing on one side of the column, then the foundation is generally designed for
(a) Strap footing (b) Strip footing
(c) Combined footing (d) any of the above

WBPSC AE (MCD) 1998

Ans. (c) : Hardness is ability of a material to resist indentation and scratching.
Indentation hardness tests most after involve one of the three methods : Brinell, Rockwall or Vickers. The shores scleroscope hardness testing is sometimes employed as well.

4. Doors, Windows & Ventilators

130. The window provided on the sloping roof of a building is called -
(a) Dormer window (b) Bay window
(c) Sky light window (d) Glazed window

OPSC AEE 2019 Paper–I
RPSC AE 2018
GPHC AE 2018

Ans. (a) Dormer window-Vertical window provides on sloping roof such window provides ventilation lighting to the enclosed space, below the roof and at the same time improve the appearance of the building.

131. A window that projects outside the external walls of a room is:
(a) Gable window (b) Sash window
(c) Dormer window (d) Bay window


Kerala PSC AE 2015
Karnataka PSC AE 2015 Paper - II

Ans. (d) : A bay window is a window space projecting outward from the main walls of a building and forming a bay in a room.
Due to space projecting outward from the main wall it has more area for ventilation for any room.

132. The horizontal member of the frame which divides the window horizontally is
(a) rail (b) transit
(c) transome (d) divider

TNPSC AE 2012

Ans. (c)



133. According to their movements, doors are classified as
(a) folding (b) swinging
(c) glazed (d) both (a) and (b)

TNPSC AE 2012

Ans. (d) Operational classification of door-
- Swinging door are shutters are hung to door frame on hinges fixed to one side of shutter, so the swing on vertical axis.
- Folding or Accordian door are used singly or as folding. Partitions so that two room may be used together as a single room or separately at top guide at bottom.

Glaze is a type of panel which can be used in any type of door.

134. The width of rebate provided in a door frame is equal to the width of the shutter whereas depth of the rebate provided should be
(a) 50 mm (b) 20 mm
(c) 12 mm or 13 mm (d) 5 mm to 8 mm.


TNPSC AE 2012

Ans. (c) Minimum depth of rebate provided is 12 mm to 13 mm.

135. Which of the following doors provides entrance to one and exit to another simultaneously, and closes automatically when not is use ?
(a) Sliding door (b) Collapsible door
(c) Revolving door (d) Flush door

Rajasthan AE (Nagar Nigam) 2016

Ans. (c) : Revolving door provides entrance to one and exit to another simultaneously and also used in air-conditioned buildings, a door has to serve both purposes of opening and closing.



Revolving position


• They are also used in hill stations to avoid strong wind blowing in.

136. In a wooden door, "stile" is the
(a) Outside vertical member of the shutter
(b) Top most horizontal member of the shutter
(c) Middle horizontal member of the shutter
(d) Horizontal projection of head

RPSC A. En. 2013

Search on Telegram @apna_pdf

Ans : (a)



137. From practical considerations and effective working of the ventilation system, the desired value of rate of air changes per hour is

(a) One (b) Five
(c) Twenty (d) Thirty

RPSC A. En. 2013

Ans : (b) Purposes of building ventilation are provide a continuous supply of fresh outside air. Maintain temperature and humidity at comfortable levels.
For the effective working of the ventilation system, the desired value of rate of air changes 5 m^3/hour.

138. Which of the following type of door can allow air circulation and privacy, even when it is closed?

(a) Wire gauge (b) Louvered
(c) Part paneled, part glazed (d) Flush door

[UPPSC Civil Eng. A.E. 2013(II)]

Ans : (b) Louvered door is recommended when privacy combined with natural ventilation and quietness for rest is desired, because they allow free passage of air even when closed. They are used for latrines, bathrooms of public building.

139. Glazed doors are more suited for

(a) Box room (b) Toilet
(c) Dressing room (d) Hospital

[UPPSC State Eng. A.E. 2007(II)]

Ans : (d) Glazed doors are used in public buildings as well as residential building such as hospitals, colleges, offices, libraries, showrooms, banks, shopping center etc.

140. For the orientation of residential building in North India, it is considered to be the best when it is facing-

(a) Towards East (b) Towards West
(c) Towards North (d) Towards South

[UPPSC State Eng. A.E. 2004 (II)]

Ans : (c) If it has been considered for building configuration, it would be best when its face is towards north direction, when it is facing north, sunlight does not come in the house much in the afternoon and it is still light during sunset.

141. What is a Mullion in a window shutter?

(a) Vertical member running through shutter of window
(b) Horizontal member of shutter
(c) Inclined battening
(d) None of the above

Maharashtra PSC (Mains) 2015 Paper–I


Ans. (a) : A mullion is a vertical element that forms a division between units of a window or screen or is used decoratively and its runs through the shutter or opening vertically.

142. Increased height of building or room give better ventilation due to

(a) Cross ventilation (b) Wind effect
(c) Stack effect (d) Combined effect

TNPSC AE 2018

Ans. (c) : Stack effect causes better ventilation in tall buildings.



143. A vertical window provided on the sloping roof is known as :

(a) Gable window (b) Dormer window
(c) Sky light (d) Lantern window

Karnataka PSC AE 2015 Paper - II

Ans. (b) : Dormer window:–

⇒ A dormer window is a form of roof window. A dormer is roofed structure, often containing a window, that projects vertically beyond the plane of a pitched roof.

⇒ Dormers are commonly used to increase the usable space in a lift and to create window opening in a roof plane.

144. In air-conditioned buildings, a door has to serve both purposes of opening and closing. The most suitable type of door is:-

[UKPSC A E Paper II 2013]

OR

The most suitable door for an entrance to an air-conditioned room is :

(a) Revolving door (b) Collapsible door
(c) Louvered door (d) Sliding door

Karnataka PSC AE 2015 Paper - II

Ans. (a) :

(i) A revolving door typically consists of 3 or 4 doors that hang on a central shaft and rotate around a vertical axis within a cylindrical enclosure.

(ii) Revolving doors are energy efficient as they prevent drafts (acting as an air lock). Thus decreasing the loss of heating or cooling for the building.

Search on Telegram @apna_pdf

145. The multiplying factor for measurement of painting on collapsible door is :

(a) 1.2 (Each side) (b) 0.8 (All over)
(c) 1.5 (All over) (d) 1 (Each side)

Karnataka PSC AE 2017 Paper - II

Ans. (c) :


Irregular Shapes	Multiplying Factor
• Collapsible/Folding doors	1.50 (over all)
• Corrugated metal doors	1.25 (For each side)
• Flush joinery/doors	1.20 (for each side)
• Partly paneled/glazed doors	0.80 (for each side)
• Open pale fencing and gates, brace and rails	1 (over all)

146. The vertical member used in door frame is called -

(a) Post (b) Hanging style
(c) Sill (d) Rail

RPSC AE 2018

Ans. (a) : The vertical member used in door frame is called post.



Door Step

147. The vertical sides of a door and window openings provided in a wall are known as

(a) Verticals (b) Reveals
(c) Jambs (d) Rebate

ISRO Scientist/Engineer 2018
[Uttarakhand Combined State AE Paper II 2007]

Ans : (c)

- The Jambs is the vertical wall face of a door opening which supports the door frame. It is the vertical portion of the door frame onto which a door is secured.
- Rebate is a depression or recess made all around the door frame, on one side of which the door shutter is fixed by the means of lingers.

148. What should be the aspect for a bedroom?

(a) West (b) North-West
(c) South-West (d) All of the above

Maharashtra PSC Mains 2018 Paper-1

Ans. (c) : Ideally, the bedroom at south-west brings good health and prosperity for the home owner and enhances longevity.

149. A horizontal member of stone, concrete or wood provided to give support for the vertical members of a wooden window, is called

(a) sill (b) quoin
(c) jamb (d) reveal

GWSSB AAE 2015

Ans. (a) : The bottom surface of a door or a window opening is known as a sill. Sill is the horizontal members of brick, stone, concrete or wood provided to give support for the vertical members of the opening and also to shed off rain water from the face of the wall immediately below the opening.

150. Sash doors are most suited for

(a) hospitals (b) toilets
(c) box rooms (d) dressing rooms

UKPSC(Urban engineering)-2011

Ans. (a) : Sash doors a door having panes of glass. Sash doors are most suited for hospitals.

151. In a residential building the width of a door should not be less than:

(a) 1.2m (b) 0.9m
(c) 0.6m (d) 0.75m

UJVNL AE 2012

Ans. (d) : In a residential building the width of a door should not be less than 0.75m.

152. Importance factor (I) for residential or commercial buildings with occupancy more than 200 persons as per IS:1893 (2016) is

(a) 1.5 (b) 1
(c) 1.2 (d) 2.0

GPSC AE January 2018

Ans. (c) : Importance factor depends upon the functional use of the structure characterized by hazardous consequences of its failure.
For residential or commercial building occupancy < 200 persons.

153. '10 DT 24' represents

(a) Frame of double shutter window with a width of 24 modules and height of 10 modulus
(b) Frame of double shutter window with a width of 10 modules and height of 24 modulus
(c) Frame of double shutter door with a width of 24 modules and height of 10 modules
(d) Frame of double shutter door with a width of 10 modulus and height of 24 modules

GPSC AE June 2019

Ans. (d) : As per IS 4021:1995
10 DT 24 represents
D - door opening
S - single shutter
T - double leaf shutter
10 and 24 - indication size of door

154. The minimum number of holdfasts recommended on each side of a door frame and a window frame respectively are

(a) 2 and 1 (b) 3 and 2
(c) 2 and 2 (d) 2 and 3

GPSC AE Dec 2018

Ans. (b) : Minimum number of holdfasts for door = 3
Minimum number of holdfasts for window = 2.

155. Dormer window is defined as -

(a) Windows provided in dormitories
(b) Vertical window built in sloping side of a pitched roof
(c) Window provided in the gable end of a pitched roof

Search on Telegram @apna_pdf

(d) Sloping window provided along the slope of a pitched roof

Rajasthan VP ITI 2018

Ans. (b) Dormer window-Vertical window provides on sloping roof such window provides ventilation lighting to the enclosed space, below the roof and at the same time improve the appearance of the building.

156. Match list I with list II and select the correct answer using code given below the two list in each question.

List I	List II
A. Revolving door	1. For air conditioned building
B. Sliding door	2. For Garrage and workshop
C. Swinging door	3. For residential building
D. Folding door	4. For covering large opening

Code:

	A	B	C	D
(a)	4	3	2	1
(b)	1	3	2	4
(c)	1	2	3	4
(d)	2	1	3	4

PTCUL AE 2016

Ans. (c) : Types of door and their uses
(i) Revolving door – for air conditioned building
(ii) Sliding door – for garrage and workshop
(iii) Swinging door – for residential building
(iv) Folding door – for covering large opening

157. Which kind of hinge is provided to open the door away from the wall at 180 degree?
(a) Butt hinge (b) Parliament hinge
(c) T hinge (d) Cut hinge

GPHC AE 2018

Ans : (b) Parliament hinge is provided for opening door away from the wall at 180 degree.
Butt hinge is used for 90º degree opening.

158. For the purpose of air circulation which door is provided?
(a) Battened and ledged door
(b) Louvered door
(c) Flush door
(d) Air vent door

GPHC AE 2018

Ans : (b) For air circulation and air ventilation louvered door is used.

159. Which of the following space needs maximum number of air changes per hour?
(a) Assembly hall (b) Classrooms
(c) Bedrooms (d) Restaurants

WBPSC AE (MCD) 1998

Ans. (b) : Air changes per hour is a measure of the air volume added to or removed from a space divided by the volume of the space. Classrooms needs maximum number of air changes per hour.

5. Arches and Lintels

160. The vertical distance between the springing line and highest point of the inner curve of an arch is known as:
(a) intrados (b) rise
(c) spandril (d) extrados


WBPSC Poly Lect. 2019

Ans. (b) : The vertical distance between the springing line and highest point of the inner curve of an arch is known as rise.

161. The highest point on the extrados of the arch is known as
(a) summit (b) ridge
(c) crown (d) peak

TNPSC AE 2012
UJVNL AE 2012

Ans. (c) The highest point on the extrados of the arch is known as crown.



162. Soffit is
(a) The under surface of an arch
(b) The top surface of an arch
(c) The curvature of an arch
(d) None of the above

KARNATAKA GESCOM AE 2011

Ans : (a) The under surface of an arch is called as soffit.

163. Lintels are associated with
(a) Doors and windows
(b) Ceilings
(c) Both (a) and (b)
(d) neither (a) nor (b)

KARNATAKA GESCOM AE 2011

Ans : (a) Lintel is a structural support used to span an opening in a wall or between two vertical supports. Most common material for lintel are timber, steel and concrete.

164. When the rise of an arch is more than the span, then the arch is called as
(a) Lancet arch (b) Venetian arch
(c) Drop arch (d) Ogee arch

RPSC POLY. TECH. LECT. 2011

Ans : (b) When the rise of an arch is more than the span, then the arch is called as venetian arch.

165. The economical construction on top of a three metre wide window will be that of
(a) a Lintel (b) I-Girder
(c) angle iron frame (d) an arch

[UPPSC State Eng. A.E. 2008]

Ans : (a) The economical construction on top of a three meter wide window will be that of a lintel.

Search on Telegram @apna_pdf

166. Which one of the following statements are incorrect when lintels are compared with arches:

(a) Lintels are simpler in construction
(b) Arches does not require strong abutments (walls) to withstand the arch thrust
(c) Arches require more head room to span the openings
(d) Lintels transfer the loads vertically to the walls

RPSC VIPITI 2012


Ans : (b) An arch is a curved structure that spans a space. A lintel is a structural horizontal block that spans the space. Arches require strong abutment (walls) to withstand the arch thrust.

167. The vertical distance between the springing line and the highest point on the intrados is called _____ of the arch.

(a) haunch (b) depth
(c) extrados (d) rise

ISRO Scientist/Engineer 2019, 2017
RPSC A En. 2013 / RPSC VPITI 2012

Ans : (d) Rise of an Arch - The clear vertical distance between the highest point on the intrados and the springing line is called as rise.



- The imaginary line joining the springing points of either ends is called as springing line.
- The lower half of the arch between the crown and skewback is called haunch.

168. The under surface of an arch is called

(a) Soffit (b) Haunch
(c) Springer (d) Lancet

ISRO Scientist/Engineer 2018

Ans : (a) :

- The under surface of an arch is called. Soffit or intrados; the outer curve is the extrados.
- The lower half of the arch between the crown and skewback is called haunch.
- The first voussoir at springing level which is immediately adjacent to the skewback is called springer.

169. The depth of an arch is the distance between


(a) Ground level and springing line
(b) Crown and springing line
(c) Crown and ground level
(d) Intrados and extrados

ISRO Scientist/Engineer 2015

Ans : (d) :

- The perpendicular distance between the intrados of arch to the extrados of arch is called depth of an arch or height of an arch.

→ Intrados - Inner curve of an arch
→ Extrados - Outer curve of an arch



170. The arrangement of supporting an existing structure by providing supports underneath, is known as

(a) Shoring (b) Underpinning
(c) Jacking (d) Piling

ISRO Scientist/Engineer 2015

Ans : (b) :

- Underpinning is the process of strengthening and stabilizing the foundation of an existing building or other structure. Underpinning is accomplished by extending the foundation in depth or in breadth so it either rests on a stronger soil stratum or distributes its load across a greater area. Use of micro piles and jet grouting are common methods of under pinning.
- Shoring is the means of providing support to get stability of a structure temporarily under certain circumstances during construction, repair or alteration.

171. The lintels are preferred to arches because :

(a) Arches require more head-room to span the opening like doors and windows.
(b) Arches require strong abutments to withstand arch thrust.
(c) Arches are difficult to construct.
(d) All of these.

OPSC AEE 2019 Paper–I

Ans. (d) : The lintels are preferred to arches because arches require more headroom to span the openings like doors, windows etc.

172. ..... is the triangular walling enclosed by the extrados of the arch, a horizontal line from the crown of the arch and a perpendicular line from the springing of the outer curves.

(a) Haunch (b) Spandril
(c) Key stone (d) Voussoirs

GPSC R&B AE 2016

Ans. (b) : A spandril is a triangular space, usually found in pairs between the top of an arch on a rectangular frame; between the tops of two adjacent arches or one of the four spaces between a circle within a square. They are frequently filled with decorative elements.

173. The most economical central angle of the arch rings in an arch dam, is

(a) 123° 44' (b) 133° 34'
(c) 143°34' (d) 153° 44'

Rajasthan Nagar Nigam AE Shift-2, 2016

Ans. (b) : The most economical central angle of arch ring in arch dam is 133°34' because in U shaped valley, central angle of about 133° can be adopted but a V shaped valley gives very low angle at bottom.

174. If T is the thickness of lintel and S is the clear span of opening, then length of lintel (L) is given by

(a) L = S + T (b) L = S + 2T
(c) L = S + 3T (d) L = S + 4T

GPSC AE June 2019

Ans. (b) : If T is the thickness of lintel and S is the clear span of opening then the length of lintel (L):
As per IS 9893 (1981)-

$$L = S + 2T$$

Search on Telegram @apna_pdf

175. The effect of arching a beam is

(a) to increase bending moment throughout
(b) to increase shear force
(c) to reduce bending moment throughout
(d) to decrease shear force

GPSC Assistant Prof. 2016

Ans. (c) : The effect of arching a beam is to reduce bending moment throughout.

6. Stairs

176. The recommended imposed load on staircase in residential buildings as per IS 875 is

(a) 5.0 kN/m^2 (b) 3.0 kN/m^2
(c) 1.5 kN/m^2 (d) 1.3 kN/step

ESE 2019

Ans. (b)

- Residential Buildings include any building in which sleeping accommodation is provided for normal residential purposes with or without cooking or dining or both facilities. It include one or multifamily dwellings, apartment houses, lodging or rooming houses etc.
- As per IS : 875 Part-2; the recommended imposed load on staircase–

→ Residential Building – 3kN/m^2
→ Educational Building – 4kN/m^2
→ Mercantile Building – 5kN/m^2
→ Industrial Building – 5 kN/m^2

177. Sum of tread and rise must lie between :

(a) 300 mm to 350 mm
(b) 400 mm to 450 mm
(c) 500 mm to 550 mm
(d) 600 mm to 650 mm

OPSC AEE 2019 Paper–I


Ans. (b) : Sum of tread and rise must lie between 400 mm to 450 mm.
• Sum of the tread and twice the riser must lie between 60 and 64 cm.
• Product of riser and tread must be 400 and 410.

178. Nosing is the outer projection of:

(a) Riser (b) Tread
(c) Baluster (d) Landing

WBPSC Poly Lect. 2019

Ans. (b) : The projecting part of the tread beyond the face of the riser is known as nosing.




Stair and Its different part

179. The vertical posts placed at the top and bottom ends of a flight supporting the hand rails, are known as:

(a) Baluster (b) Newel post
(c) Balustrade (d) Railing

WBPSC Poly Lect. 2019

Ans. (b) The vertical posts placed at the top and bottom ends of a flight supporting the hand rails, are known as newel post.



180. The vertical members fixed between steps and handrail in a staircase is known as

(a) Balusters (b) Strings
(c) Newel posts (d) Soffits

ISRO Scientist/Engineer 2018

Ans : (a) :

- Balusters is the vertical members fixed between steps and handrail in a staircase. Treads often require two balusters. The second baluster is closer too the riser and is taller than the first.
- Newel post used to anchor the handrail. A half newel post may be used where a railing ends in the wall.
- Soffit is the under side of a structural component, such as beam, arch, staircase or cornice.

181. Steps which are normally triangular in shape are called -

(a) Angular steps (b) Radial steps
(c) Winders (d) Spiral steps

RPSC AE 2018

Ans. (c) When we change the direction of flight without providing landing, then the steps used is called winder. They are triangular in shape and step approximately triangular in shape is spandril.

182. Minimum width of landing should be :

(a) Equal to width of stairs
(b) Half the width of stairs
(c) Twice the width of stairs
(d) One-fourth the width of stairs

OPSC AEE 2019 Paper–I

Ans. (a) : The minimum width of landing should be equal to the width of the stairs

183. The unit of measurement of Railing (Height and type specified) is

(a) Meter (b) Sqm
(c) cum (d) Kg

GUJRAT PSC AE - II 2017

Ans : (a) The unit of measurement of Railing (Height and type specified) is meter.

Search on Telegram @apna_pdf

184. For the design of a staircase, if R is the riser, T is the tread and D is the thickness of waist slab, then the load of waist slab per m width of stair in plan will be

(a) $25D\times\left(\frac{T}{\sqrt{T^2+R^2}}\right)$ (b) $25D\times\left(\frac{\sqrt{T^2+R^2}}{T}\right)$

(c) $25D\times\left(\frac{R}{\sqrt{T^2+R^2}}\right)$ (d) $25D\times\left(\frac{\sqrt{T^2+R^2}}{R}\right)$

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (b) For the design of a staircase, if R is the riser, T is the tread and D is the thickness of waist slab, then the load of waist slab per m width of stair in plan will be $25D\times\left(\frac{\sqrt{T^2+R^2}}{T}\right)$

T = tread
R = rise
D = thickness of waist slab

185. The number of steps in a flight generally should not be less than–

(a) 2 (b) 3
(c) 5 (d) no limit

UPPSC State Eng. A.E. 2003
KARNATAKA GESCOM AE 2011

Ans : (b) Minimum number of steps in building = 3
Maximum number of steps in building = 12

186. The maximum number of steps in a flight of a staircase generally should be

(a) 10 (b) 12
(c) 15 (d) No limit

TNPSC AE 2012
UPPSC State Eng. A.E. 2011
UPPSC State Eng. A.E. 2004(II)

Ans : (b) Minimum number of steps in flight = 3
Maximum number of steps in flight = 12

187. A series of steps without any landing in their direction is called

(a) riser (b) tread
(c) nosing (d) flight


[U.K. Combined A E Paper II 2012]

Ans : (d)

→ An unbroken series of steps between two landing is called flight.

→ A vertical portion of a step providing a support to the tread, is called riser.

→ The horizontal upper part of a step on which foot is placed in ascending or descending a stairway is called tread.



188. Outer projection of a 'Tread' is called

(a) nosing (b) tread
(c) step (d) going

[U.K. Combined A E Paper II 2012]

Ans : (a) The projecting part of the tread beyond the face of riser is called nosing.

189. The size of a step commonly adopted for staircase in a residential building is:

(a) 20 cm × 15 cm (b) 25 cm × 16 cm
(c) 27 cm × 15 cm (d) 30 cm × 13 cm

[UPPSC State Eng. A.E. 2007(II)]

Ans : (b) (i) For residential building : The size of step widely adopted 25 × 16 cm.
(ii) for public building : Generally length of steps are increased and width reduced slightly common step size for public building are
27 cm × 15 cm or 30 cm × 13 cm.

190. Which material is recommended for a staircase in an industrial workshop?

(a) timber (b) steel
(c) aluminium (d) RCC

[UPPSC State Eng. A.E. 2007(I)]

Ans : (b) Steel material is recommended for a staircase in an industrial workshop. Because it can be made in less space and also has more strength.

191. According to IS : 1256, the maximum distance between the farthest corner of a public building and the stair case should be:

(a) 18m (b) 25m
(c) 30m (d) 35m

[UPPSC State Eng. A.E. 2004 (II)]


Ans : (c) According to IS : 1256, the maximum distance between the farthest corner of a public building and the stair case should not be more than 30 m.

192. The under surface of stair is called as

(a) Soffit (b) Cornice
(c) Wall plate (d) Scotia

RPSC POLY. TECH. LECT. 2011

Ans : (a) The under surface of a stair, is called soffit. It is the inner surface of an arch. sometimes intrados and soffit are used simultaneously.



Stair and Its different part

193. Maximum pitch in any staircase is

(a) 25^0 (b) 35^0
(c) 40^0 (d) 45^0

Rajasthan Nagar Nigam AE Shift-2, 2016
RPSC ACF 2011

Ans : (c) Minimum pitch or slope in staircase = 25^0
Maximum pitch or slope in staircase = 40^0
Maximum pitch or slope in staircase for public building = 33^0

Search on Telegram @apna_pdf

194. The imposed floor load acting on staircase for residential and educational building is to be considered as-

(a) 2.0 kN/m^2 and 3.0 kN/m^2
(b) 3.0 kN/m^2 and 2.0 kN/m^2
(c) 4.0 kN/m^2 and 3.0 kN/m^2
(d) 3.0 kN/m^2 and 4.0 kN/m^2

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (d) : According to IS 875 : 1987 Part II, a UDL of 5 kN/m^2 is provided in general. But if the chances of overcrowding are negligible such as in residential educational buildings it is taken as 3 kN/m^2.

195. The height between two floors is 3.00 m and risers are of 150 mm. Assuming two flights between the floors, the number of treads will be-

(a) 18 (b) 19
(c) 20 (d) 21

OPSC AEE 2015 PAPER–I

Ans. (b) : Given that,
Height between two floor is 3 m = 3000 mm
Risers = 150 mm

$$\text{No. of treads} = \frac{\text{Height}}{\text{Risers}} - (2-1)$$

$$\text{No. of treads} = \frac{3000}{150} - (2-1) = 19$$


$$\text{No. of risers} = \frac{3000}{150} = 20$$

196. If *r* is rise and *g* is going of stairs, the empirical formula used to fix rise and going is 2*r* + *g* and it should be between-

(a) 500 mm-600 mm (b) 550 mm-650 mm
(c) 600 mm-650 mm (d) 650 mm-700 mm

BPSC AE Pre 2018

Ans. (b)




The normal relationship between the dimensions of rise and going is twice the rise plus the going (2r+g) equals between 550 mm to 700 mm.

197. The tapering steps which are provided to change the direction of a stair is :

(a) Landing (b) Spiral steps
(c) Winders (d) Going

GPSC R&B AE 2016
Karnataka PSC AE 2015 Paper - II

Ans. (c) : Winders are steps that are narrower on one side than the other. They are used to change the direction of the stairs without landing. A series of winders form a circular or spiral stairway. When 3 steps are used to turn 90^0 corner the middle step is called a bite winder as a bite shaped quadrilateral.




198. The lean-to-roof is suitable for a maximum span of :

(a) 3 m (b) 2.5 m
(c) 3.5 m (d) 4 m

Karnataka PSC AE 2015 Paper - II

Ans. (b) : The lean to roof is defined as single slope roof with its upper edge adjoining a wall or a building. Lean to roof is simplest type of pitched roof. The pitched roof is also known as a sloping roof. It is the most common roof and is generally regarded as the cheapest alternative for covering structure.



199. In any good staircase, the maximum and minimum pitch respectively should be :

(a) 90° and 0° (b) 75° and 5°
(c) 60° and 10° (d) 40° and 25°

GPSC AE Class (1&2) Paper - 2 2017
GPSC AE (CLASS 1 & 2) 2019

Ans. (d) : Maximum pitch & minimum pitch of staircase is to be 40^0 to 25^0 so that slow & fast can climb the staircase comfortably.


200. Which of the following is/are incorrect about a staircase?


(i) String is the part of tread which is projecting beyond the face of the riser
(ii) Soffit is a short of additional moulding provided under the nosing or treat beautify the step in elevation
(iii) Baluster is a member supporting the hand rail
(iv) Newel post is a vertical member at the ends of flights

(a) Only (i) (b) (i) and (ii)
(c) (i) and (iii) (d) (ii) and (iv)

GPSC AE (CLASS 1 & 2) 2019

Ans : (d) :





201. Doglegged stairs are

(a) Half turn stairs
(b) Quarter turn stairs
(c) Straight stairs
(d) Three quarter turn stairs

GPSC AE (CLASS 1 & 2) 2019
OPSC AEE 2019 Paper–I

Ans : (a) : Dog legged stairs are also known as 180º stairs or half turn stairs. It is commonly used in residential buildings.


Search on Telegram @apna_pdf

202. A ladder of weight W is resting against a smooth vertical wall and a smooth floor. The minimum force to be applied at the floor end to keep it in equilibrium at angle θ with floor is:

(a) $W \tan\theta$ (b) $0.5\ W \tan\theta$
(c) $W \cot\theta$ (d) $0.5\ W \cot\theta$

Kerala PSC AE 2015

Ans. (d) :



Since the floor is smooth, there will be no frictional force acting anywhere.

For equilibrium,

$$\sum M_B = 0$$

$$F \times l \sin\theta + W \times \frac{l}{2}\cos\theta = 0$$

$$F = -\frac{W\cos\theta}{2\sin\theta}$$

$$F = -\frac{W\cot\theta}{2}$$

(–ve) denotes force acts in left direction.

203. Which among the following is a step used for changing the direction of a stair?

(a) Flight (b) Nosing
(c) Landing (d) Winder

Kerala PSC AE 2015


Ans. (d) :

Flight – An unbroken series of steps between two landing.

Landing– A horizontal platform at the top or bottom of a flight between the floor.

Nosing– The projecting part of tread beyond the face of riser.

Winder– Winder are steps that are narrow on one side than other. They are used to change the direction of stair without landing.



Layout for stair winders

204. If height of the first storey of a building is 3.25m and riser is 13cm, the number of treads required is

(a) 12 (b) 18
(c) 24 (d) 25

ISRO Scientist/Engineer 2015

Ans : (c) : Height of building = 3.25m or 325 cm
Riser = 13 cm


Number of Riser required (R) = $\frac{325}{13}$

[R = 25]

Number of treads required (T) = R - 1

i.e. T = 25 - 1

T = 24



205. The projecting part of the tread beyond the face of riser is called

(a) baluster (b) stringer
(c) pitch (d) nosing

GWSSB AAE 2015

Ans. (d) : Nosing – It is the projecting part of tread beyond the face of rises it is usually rounded to give pleasing effect to tread and make start case convenient and easy to use.

206. Beams supporting steps of a stair are generally known as

(a) Spandrel beam (b) Winder beam
(c) Step beam (d) Stringer beam

Sikkim PSC AE 2017

Ans. (d) : Beams supporting steps of a stair are generally known as Stringer beam.

207. A multi storey building has floor to floor height is 3300 mm. If the riser is 150 mm then the number of treads required for each storey is

(a) 21 (b) 22
(c) 23 (d) 24

Sikkim PSC AE 2017

Ans. (b) : Floor height = 3300 mm
riser height = 150 mm

$$\therefore \quad \text{No. of riser} = \frac{3300}{150} = 22$$

Generally riser and treads are equal.

208. The term 'string' is used for

(a) the under side of a stair
(b) outer projecting edge of a tread
(c) a sloping member which supports the steps in a stair
(d) a vertical member between two treads

UKPSC(Urban engineering)-2011

Ans. (c) : The term 'string' is used for a sloping member which supports the steps in a stair.

209. In public building the maximum riser is limited to:

(a) 10 cm (b) 12 cm
(c) 15 cm (d) 18 cm

UJVNL AE 2012

Ans. (c) : In public building the maximum riser is limited to 15 cm

Search on Telegram @apna_pdf

210. A stair should NOT have a pitch more than.....

(a) 35^0 (b) 45^0
(c) 40^0 (d) 30^0

SJVNL ET 2019

Ans. (c) : A stair should NOT have a pitch more than 40^0.

211. The vertical distance between two consecutive treads in a staircase is called as :

(a) Riser (b) Waist
(c) Nosing (d) Soffit

SJVNL ET 2019

Ans. (a) : Riser is the vertical distance between two consecutive treads in a staircase –

- **Waist** is slab for a staircase is probably more used as a slang.
- **Nosing**– It is the front edge of the tread which project beyond the riser.
- **Soffit**– Soffit means something fixed underneath.

212. What is the effective span of staircase, supported at each end by landing spanning parallel with the risers, if the width of landing is 2.5 m, width of starting passage is 1.5 m and going of the stair is 2.2 m?

(a) 6.2 m (b) 4.2 m
(c) 3.95 m (d) 4.5 m

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (c) : x, y $\not> 1$

$x = \frac{1.5}{2} = 0.75$

$y = \frac{2.5}{2} = 1.25 > 1$

So, y = 1

effective span = x + y + 2.2 = 0.75 +1 + 2.2 = 3.95 m

213. For the design of staircase, self weight of waist slab is calculated as ..... Where, T = tred, R = riser and D = depth of waist slab, γ_c = density of R.C.C.

(a) $\gamma_c D$ (b) $\gamma_c D\left(\frac{T}{\sqrt{R^2+T^2}}\right)$

(c) $\gamma_c \frac{\sqrt{T^2+R^2}}{T}$ (d) $\gamma_c D\frac{\sqrt{T^2+R^2}}{T}$

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (d) : Self weight of waist slab=

$\gamma_c D\sqrt{\frac{T^2+R^2}{T}}$

T = Tread
R = Riser
D = depth of waist slab
γ_C = density of RCC


214. In residential buildings, the rise may vary between

(a) 150 to 180 mm (b) 200 to 250 mm
(c) 50 to 75 mm (d) 100 to 120 mm
(e) 275 to 300 mm

CGPSC AE 2017

Ans. (a) In residential buildings, the rise may vary between 150 to 180 mm.

215. What is the effective span of staircase supported at each end by edge of the landing slab, which spans parallel, with the risers, if width of both landings is 2.5 m and going of stair is 2.2 m (see figure):



(a) 7.2 m (b) 4.7 m
(c) 4.2 m (d) 2.2 m

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (c) : Both x any y are greater than 1.
So, effective span = G + 1 + 1
= 2.2 + 1 + 1 = 4.2 cm

216. How many treads would be there in a straight stair connection between two floors with height different of 3.6 m? The rise is 15 cm.

(a) 23 (b) 24
(c) 22 (d) 26

Haryana PSC AE 2010

Ans. (a) : Height of building = 3.6 m = 360 cm
Riser = 15 cm

Number of riser $= \frac{360}{15} = 24$

Number of treads = R – 1 = 24 – 1 = 23.

217. Half turn stairs are the stairs which change their direction through :

(a) 90º (b) 180º
(c) 270º (d) 45º

HPPSC Poly. Lect. 2016

Ans : (b) Half turn stairs are the stairs which change their direction through 180º.
Half turn stair can be either dog-legged or open newel type stair.

7. Floors and Floorings

218. The best and the common material to be used as damp-proofing material is

(a) cement concrete (b) bitumen
(c) paraffin wax (d) cement solution

Rajasthan AE Nagar Nigam Shift-3, 2016
TNPSC AE 2012

Ans. (b) The best and the common material to be used as damp-proofing material is bitumen because it is economical and easy to use.

219. In ordinary residential and public buildings, the D.P.C. is generally provided at:-

(a) Plinth level
(b) Ground level
(c) Water table level

Search on Telegram @apna_pdf

(d) Midway between ground level and water table level

[UKPSC A E Paper II 2013]

Ans : (a) In ordinary residential and public buildings, the D.P.C. is generally provided at plinth level to reduce seepage of water from soil. To prevent the entry of damp or moisture in the building, the damp-proof courses (D.P.C.) are provided at various levels of entry of damp into a building.

220. Damp-proof course should be

(a) impervious (b) horizontal (or) vertical
(c) continuous (d) all of these

TNPSC AE 2012

Ans. (d) DPC should be continuous and impervious. It can be in any direction. It consist of 40 mm thick cement concrete of 1:2:4.

221. Dampness causes

(a) growth of termites
(b) strengthening of concrete
(c) strengthening of plaster
(d) adhesion of paint to surface

TNPSC AE 2012

Ans. (a) Dampness increases moisture content which provides favorable condition for termites growth.

222. Percentage of imposed load to be considered ..... in seismic weight consideration for Imposed uniformly distributed floor load above 3 kN/m^2

(a) 25 (b) 30
(c) 50 (d) 75

Gujarat PSC AE 2017

Ans : (c) Table- 8, IS-1893 (part I) : 2002
Percentage of imposed load to be considered in seismic weight calculation–

Impose UDL (kN/m^2)	% of Imposed load
upto and including 3	25
above 3	50

223. As per IS 1893 : 2002, dynamic analysis shall be performed for regular buildings of height greater than ..... m in zones IV

(a) 50 (b) 40
(c) 45 (d) 60

Gujarat PSC AE 2017

Ans : (b) Dynamic analysis shall be performed to obtain the design seismic force for, those greater than 40 m in height for regular building zone IV and V and for those greater than 90 m in height in zone II and III.

224. In building, the fans are usually fitted at what height above the floor level?

(a) 7 feet (b) 8 feet
(c) 9 feet (d) 10 feet

Gujarat PSC AE (N.W.R.) 2020

Ans. (c) : In building, the fans are usually fitted at 9 feet of height above the floor level.

225. Which type of flooring would ensure a near noiseless floor?

(a) Cork flooring (b) Glass flooring
(c) Linoleum flooring (d) Wooden flooring

KARNATAKA GESCOM AE 2011

Ans : (a) Cork flooring ensure a near noiseless floor. Use in theaters and libraries.

226. What is trowelling?

(a) The final operation in finishing a floor
(b) The initial operation in finishing a floor
(c) An intermediate operation in the finishing of a floor
(d) Has nothing to do with floors

KARNATAKA GESCOM AE 2011

Ans : (a) Trowelling is the final operation in floor finishing which leaves a smooth and dense surface.

227. Decoupling of the superstructure from substructure resting on a shaking ground is called :

(a) Base isolation (b) Damping
(c) Shock absorption (d) Retrofitting

KPSC AE 2020

Ans. (a) : Decoupling of the superstructure from substructure resting on a shaking ground is called base isolation.

228. A floor using 3-6 mm marble chips is known as

(a) Marble floor (b) Chip floor
(c) Mosaic (d) Terrazzo floor

[Uttarakhand Combined State AE Paper II 2007]

Ans : (d) A floor using 3-6 mm marble chips is known as Terrazzo floor. In marble flooring we use 20-25 mm thick marble slab.

229. In concrete flooring, the sand cushion on earthen surface should be provided in thickness of about:

(a) 10 cm (b) 15 cm
(c) 20 cm (d) 25 cm

[UPPSC State Eng. A.E. 2007(II)]
[UPPSC State Eng. A.E. 2007(I)]
Mizoram PSC 2016 Paper- I

Ans : (a) In concrete flooring, the sand cushion on earthen surface should be provided in thickness of about 10 cm.

230. Marble chips in coloured cement forming the floor covering material is called:

(a) Terrazzo (b) Mosaic
(c) Linoleum (d) Magnesite

[UPPSC State Eng. A.E. 2007(I)]

Ans : (a) Terrazzo flooring consist of marble chip, quartz, granite, glass or other suitable chips poured with a binder like lime or cement. Terrazzo is cured and then polished to a smooth surface.

231. A type of flooring made with special aggregate of marble chips mixed with white and coloured cement, is called :

(a) Granolithic flooring (b) Terrazzo flooring
(c) Mosaic flooring (d) Asphalt flooring

RPSC POLY. TECH. LECT. 2011

Ans : (b) Terrazzo flooring consist of–
(i) Concrete bed
(ii) Mortar bed, 1 cm of cement mortar (cement sand mixture 1 : 3)
(iii) Metal strips
(iv) Marble chips 3 to 6 mm.

Search on Telegram @apna_pdf

232. As per building bye-laws, for fixing up the height of a building, which rule is generally used?

(a) $63\frac{1}{2}^{\circ}$Rule (b) $37\frac{2}{3}^{\circ}$Rule

(c) $65\frac{1}{2}^{\circ}$Rule (d) 45° Rule

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (a) : As per building bye law, no part of the tall building should cut the plane drawn from one edge of the road on the other side or the backspace border (minimum 3m) at the angle of 45^0 and 63.5^0 with the horizontal.

233. The type of flooring suitable for the use in theatres and public libraries and other places where noiseless floor covering is desire-

(a) Wooden flooring (b) Linoleum flooring

(c) Cork flooring (d) None of these

OPSC AEE 2015 PAPER–I

Haryana PSC AE 2010

Ans. (c) : Cork flooring will be suitable for theatres and public libraries since it will damp the noise level.

234. Sulphate attack over a building material is caused by salts of :

(a) Calcium (b) Magnesium

(c) Sodium (d) Potassium

GPSC AE Class (1&2) Paper - 2 2017

Ans. (b) : Sulphate attack in concrete result by magnesium which get degrade in the presence of lime.

$$MgSO_4 + Ca(OH)_2 + 2H_2O \rightarrow CaSO_4 + Mg(OH)_2 \downarrow$$

In precipitate form.

235. What is floor area ratio?

(a) ratio of total floor area of all floors to plinth area

(b) ratio of plinth area to plot area

(c) ratio of ground floor area to plot area

(d) ratio of total floor area of all floors to plot area

Kerala PSC AE 2015

Ans. (d) : Floor area ratio is the ratio of building & total floor area to the size of piece of land upon which it is built. It is often use as one of the regulation in city planning along the building to land ratio.

236. Vertical sides of concrete columns shuttering may be stripped after

(a) 1 to 2 days (b) 7 days

(c) 14 days (d) 21 days

ISRO Scientist/Engineer 2017

Ans : (a) Vertical sides of concrete columns shuttering may be stripped after 24 to 48 hours or 1 to 2 days.

237. In a residential building, the ideal shape of any room is preferably good when its

(a) Length = 2 x Breadth

(b) Length = 1.2 to 1.5 x Breadth

(c) Length = 5 x Breadth

(d) Length= Breadth

Rajasthan Nagar Nigam AE Shift-2, 2016

Ans. (b) : A residential building has basically
- A living room
- A sleeping room
- Conveniences
- Cooking room

it should be in length 1.2 to 1.5 of breadth.

238. The thickness of the damp proof course applied at the plinth level for a fourth class building will be :

(a) 3.5 cm (b) 1.2 cm

(c) 2.5 cm (d) 4.0 cm

(e) 0.5 cm

CGPSC AE 2017

Ans. (c) The thickness of the damp proof course applied at the plinth level for a fourth class building will be 2.5 cm.

239. An artificial stone made from pieces of marble and cement and used for floors, facing of walls etc. is known as

(a) Mosaic (b) Terrazo

(c) Marble (d) Teracotta

WBPSC AE 2012

Ans. (b) :

240. Epoxy injection technique is used for

(a) repairing the water retaining structures

(b) Sealing of large cracks

(c) Sealing of narrow cracks

(d) all of the above

Chandigarh SDE 2017

Ans. (c) : The epoxy injection method is an easy way to repair cracks in a structure and it work great for horizontal, vertical and overhead applies.

8. Roofs and Roof Covering

241. Queen post truss is suitable for spans up to :

(a) 5 to 8 m (b) 12 m

(c) 16 m (d) 24 m

TNPSC AE 2015

Ans. (b) :

Type of truss	Span
Queen post	8 to 12 m
King post	5 to 8 m
Howe truss	6 to 30 m
Pratt truss	6 to 10 m
Fan truss	10 to 15 m
North light roof truss	20 to 30 m

242. The function of king post in a king post roof truss is

(a) To support the framework of the roof

(b) To receive the ends of principal rafter

(c) To prevent the walls from spreading outward

(d) To prevent the tie beam from sagging at its centre

OPSC AEE 2019 Paper–I

Ans. (d) : A king post (or king-post) is a central vertical post used in architectural or bridge designs, taking tension to support a beam below from a truss apex above. In king post truss, the bottom chord of the truss acts as tie beam and this tie beam receives the ends of the principal rafters and prevents the wall from spreading out due to thrust. The vertical king post is used to prevent the sagging of tie beam at the center of a span.


Search on Telegram @apna_pdf

243. Name the short sections of wood or steel, which are fixed on principal rafter of trusses to support purlins:

(a) ridge plate (b) wall plate
(c) eaves board (d) cleat

Kerala PSC AE 2015

Ans. (d) : Cleats– They are small section of steel or timber fixed to the rafter of truss to support purlin from slip.



244. The type of roof suitable in plains where rainfall is meagre and temperature is high:-

(a) Pitched and sloping roof
(b) Flat roof
(c) Shell roof
(d) None of the above

[UKPSC A E Paper II 2013]

Ans : (b) A roof laid at an angle of less than 10º to the horizontal is known as flate roof. It may be RCC, reinforced brick work or precast concrete. Flat roofs are useful at places where rain fall is moderate. For less rain fall.

245. The type of truss suitable for a span of about 3 meter is

(a) Fink truss (b) King post truss
(c) Howe truss (d) None of the above

ISRO Scientist/Engineer 2019

Ans : (b) • King post truss - The spacing of the king post truss is limited to 3m centre to centre. The truss is suitable for spans varying from 5 to 8 meters.

- **Queen post truss -** This truss differs from a king post truss having two vertical posts, known as queen posts. This truss is suitable for spans varying from 8 to 12 meters.
- **Howe Truss -** This type of truss is a combination of steel and wood, which makes it elegant, while also offering a very appealing design. It has a very wide span, as it can cover anything from 6-30m.
- **Fink Truss -** It is used for longer span having high pitch roofs up to 10m the web members in such truss are Sub-divided to obtain shorter members.

246. The function of cleats in a roof truss is:

(i) To support purlins
(ii) To support common rafter
(iii) To prevent the purlins from tilting

The correct answer is,

(a) Only (i) (b) Only (iii)
(c) both (ii) and (iii) (d) None of the above

[UPPSC State Eng. A.E. 2004 (II)]
[UPPSC Civil Eng. A.E. 2013(II)]

Ans : (b) Cleat angles are used to prevent the tilting of purlins. The function of cleats in a roof truss to support the purlins.

247. The pitched roof which slopes in all the four directions is named as:

(a) Shed roof (b) Bable roof
(c) Hip roof (d) Mansard roof

RPSC POLY. TECH. LECT. 2011

Ans : (c) The pitched roof which slopes in all the four directions is named as hip roof. It is the ridge formed by the intersection of two sloped surfaces having an exterior angle greater than 180°.

248. Specification for corrugated galvanized iron roofing specifies that the roof slope shall not be laid flatter than ..... if not otherwise specially mentioned.

(a) 1 in 1 (b) 1 in 2
(c) 1 in 3 (d) 1 in 4

Karnataka PSC AE 2017 Paper - II

Ans. (d) : Corrugated galvanized iron roofing specifies that the roof slope shall not be laid flatter than 1 in 4 if not otherwise specially mentioned.

249. The pitched and sloping roofs are suitable for :

(a) Coastal regions
(b) Pain regions
(c) Covering large areas
(d) All of these

OPSC AEE 2019 Paper–I

Ans. (a) : Pitched Roofs are those which have the decks or surfaces with the considerable slope for covering the building structure. These roofs are generally lighter than a flat roof. Sloping roof is constructed by wood or steel. Sloping roof is most suitable for the area with the heavy rainfall and snowfall.
The pitched and sloping roofs are suitable for coastal regions.

250. Structural members of the truss which are supported on the principal rafter and which run transverse to the truss are called

(a) struts (b) purlins
(c) sagtie (d) rafters

GPSC Poly. Tech. Lect. 2016

Ans. (b) : Purlins–A structural member of the truss are supported on the principle rafter and run over transverse to the truss member.

251. The Queen Post Roof truss is suitable for

(a) 9 to 14 M (b) 5 to 9 M
(c) 14 to 18 M (d) None of the above

GPSC Poly. Tech. Lect. 2016

Ans. (a) : In this roof, the queen posts are the tension members which are used to prevent the sagging of tie beam. The upper ends of the queen-posts are kept in position by straining beam. Queen post-truss is suitable for 9 to 14 m.

Search on Telegram @apna_pdf

252. The pitch normally provided for corrugated galvanised iron (GI) sheets is :

(a) 1/24 to 1/12 (b) 1/48 to 1/12
(c) 1/3 to 1/6 (d) 1/10 to 1/15
(e) 1/12 to 1/16

CGPSC AE 2017

Ans. (c) The pitch normally provided for conjugated glvanished iron (GI) sheet is 1/3 to 1/6.

253. Which kind of roof truss is provided to have maximum day light?

(a) king post truss
(b) queen post truss
(c) north light truss
(d) fan truss

GPHC AE 2018

Ans : (c) North light truss have maximum day light.

9. Miscellaneous

254. The construction of a temporary structure required to support an unsafe structure is called

(a) shoring (b) jacking
(c) underpinning (d) scaffolding

GWSSB AAE 2015

Ans. (a) Shoring is the process of temporally supporting a building structure or trench with shores (prop) which is danger of collapse or during repairs or alternations. It comes from during repairs or alterations. It comes from shore a timber or metal prop. It may vertical angled or horizontal generally. It support wall laterally.

255. Working drawings include the following views.....

(a) section
(b) all of three mentioned here
(c) plan
(d) elevation

GWSSB AAE 2015

Ans. (b) Working drawings include the section, elevation and plant views.

256. For a rectangular room, better proportion is to adopt length as.....times of breadth.

(a) 1 to 1.2 (b) 1.2 to 1.7
(c) 1.2 to 1.5 (d) 1.5 to 1.7

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (c) For a rectangular room, better proportion is to adopt length as 1.2 to 1.5 times of breadth.

257. In residential building, kitchen should have ..... aspect.

(a) Eastern (b) Southern
(c) South-Eastern (d) Northern

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (a) In residential building, kitchen should have eastern aspect. For getting pure air from outside which can remove the fumes of cooking and the room remains cool in the day time.

258. Plinth area normally does not include area covered under

(a) lavatories (b) garage
(c) open courtyard (d) all of these

TNPSC AE 2012

Ans. (c) Plinth area is the covered built up area measured at floor level of basement or of any storey. It is also called as built up area. Plinth area is generally 10–20% more than carpet area. The following shall not be included in the plinth area:-
(i) Open platform, (ii) Terrace, (iii) Area of mumty, (iv) machine room, (v) courtyard.

259. The drawing issued to site for construction are called as :

(a) Tender stage drawings
(b) Contract drawings
(c) As-built drawings
(d) Good for construction drawings
(e) Engineering drawings

CGPSC AE 2014 Shift–I

Ans. (d) : The drawings issued to site for construction is good for construction drawings.

260. Select the number of type of construction according to fire resistance properties as per National building code of India

(a) 4 (b) 5
(c) 6 (d) 7

TNPSC AE 2018

Ans. (a) There are four types of construction according to fire resistance properties as follows:-
(a) Fire proof construction
(b) Non-combustible construction
(c) Exterior protected construction
(d) Wood construction

261. In measurement of plastering activity, No deduction is made for small opening up to .....and at the same time, no additions are made for jambs, soffits and of the sills of these opening.


(a) 0.0005 sqm. (b) 0.005 sqm
(c) 0.05 sqm (d) 0. 5 sqm

GUJRAT PSC AE - II 2017

Ans : (d) In measurement of plastering activity, No deduction is made for small opening upto 0.5 sqm.

Search on Telegram @apna_pdf

262. Calculate the quantity of internal plastering for a enclosure as shown below. The height is 3.0 m:



(a) $10m^2$ (b) $20\ m^2$
(c) $60\ m^3$ (d) $60\ m^2$

TNPSC AE 2015

Ans. (d)
Area of both internal long wall

$$= 2\times\left[\left(6.6-2\times0.3\right)\times3\right]=36m^2$$

Area of both internal short wall

$$=2\times\left[\left(4.6-2\times0.3\right)\times3\right]=24m^2$$

Total area = 36 + 24 = 60 m^2

263. In measurement of Masonry activity, No deduction is made for ends of beams, posts, rafters, purlins etc. upto ..... in section.

(a) 0.0005 sqm (b) 0.005 sqm
(c) 0.05 sqm. (d) 0.5 sqm

GUJRAT PSC AE - II 2017

Ans : (d) In measurement of Masonry activity, No deduction is made for ends of beams, posts, rafters, purlins etc. upto 0. 5 sqm in section.

264. For roominess, length to width ratio should be

(a) 1 : 1 to 1 : 5 (b) 1.2 : 1 to 1.5 : 1
(c) 1.5 : 1 to 2 : 1 (d) 1.5 : 1 to 1.75 : 1

Maharashtra PSC Mains 2018 Paper-1

Ans. (b) : For roominess and most economical usage, the aspect ratio used for rooms lie between 1.2 : 1 to 1.5 : 1.

265. For props to beam having span more than 6 m, minimum period before striking formwork is

(a) 7 days (b) 14 days
(c) 21 days (d) 28 days

GPSC Poly. Tech. Lect. 2016

Ans. (c) : Props left under beam can be removed after 7 days if spanning is less than 4.5 m and 14 day for spanning over 4.5 m.
Props left and beam/slab can be remove after 14 days if spanning is less than 6 m and 21 days for spanning over than 6 m.

266. The reflected sound concentrated at one point creates a spot which is known as

(a) Sound echo (b) Sound foci
(c) Dead spot (d) None of the above

GPSC Poly. Tech. Lect. 2016

Ans. (b) : Sound foci is observed where reflected sound wave meet and concentrated at one point create a sound of larger intensity. This defect can be eliminated by avoiding curvilinear interiors or by providing highly absorbent materials on the focusing areas.

267. ..... is a horizontal moulded projection provided near the top of a building or at a junction of a wall and ceiling:

(a) Cornice (b) Frieze
(c) Reveal (d) Jamb

GPSC R&B AE 2016

Ans. (a) : A projection ornamental course near the top of the wall or at the junction of the wall and ceiling, is known as cornice. It penetrates the full width of wall.

268. If there is unavailability of plain ground, the range of ground slope which is ideally suited for building construction is

(a) steeper than 30% (b) 3% to 10%
(c) 15% to 30% (d) 10% to 15%

Rajasthan AE Nagar Nigam Shift-3, 2016

Ans. (b) : 3% to 10% is suitable ground slope for building construction where plain ground is not available.

269. An undesirable site for the construction of a building is a/an

(a) Valley (b) Hill
(c) Undulating ground (d) Ridge

Rajasthan AE Nagar Nigam Shift-3, 2016

Ans. (a) : Building construction is unfavourable in valley due to earthquake and economic reason.

270. Cement pressure grouting is suitable for

(a) Very fine crack
(b) Weathered concrete
(c) Active crack where cause of crack is known and remedial action has been taken
(d) Crushed masonry

TANGEDCO AE 2018

Ans. (c) : Cement pressure gravity is suitable for active crack where cause of crack is known and remedial action has been taken.

271. Which of the following is not the characteristic of green building?

(a) Use of natural light and ventilation
(b) Solar PV Panels at roof
(c) Roof top rainwater harvesting
(d) Use of material with high thermal conductivity

GPSC AE January 2018

Search on Telegram @apna_pdf

Ans. (d) : In green building uses renewable energy such as solar energy.

• Use of natural light and ventilation

• Roof top rain water harvesting.

• Use of materials that are non-toxic, ethical and sustainable.

272. The process of generation and management of digital representations of physical and functional characteristics of building which can be extracted, exchanged or networked to support decision-making regarding a building is called

(a) FEM (b) GIS

(c) BIM (d) BOT

GPSC AE January 2018

Ans. (c) : Building information modeling (BIM) is a process supported by various tools technologies and contracts involving generation and management of digital representation of physical and functional characteristics of places.

273. Storey drift in any storey shall not exceed ..... times the storey height under the effect of design base shear applied as per IS 1893, 2016.

(a) 0.004 (b) 0.002

(c) 0.008 (d) 0.001

GPSC AE January 2018

Ans. (a) : Drift shall not exceed the 0.005 times the story height for structure having a fundamental period of less than 0.7 sec.

For fundamental period of 0.7 sec or greater storey drift shall not exceed 0.004 times storey height.

274. In Plastering, for opening more than 3 square meter deduction is made for

(a) Both faces of opening

(b) Both faces of opening plus jambs

(c) Both faces of opening plus soffit and sills

(d) Both faces of opening and jambs, soffits and sills.

GPSC AE June 2019

Ans. (d) : In plastering, for opening more than 3 square meter deduction is made for.

As per IS-1200, more than $3m^2$ each, deduction shall be made for openings on each face but jambs, soffits and sills shall be measured.

275. When was the National Safety Council set up in India?

(a) 1966 (b) 1867

(c) 1948 (d) 1962

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (a) : In 1966, the national safety council was setup in India.

276. Fire load, a fire risk criteria to classify occupancies, for a building having an area of 100 m^2 with combustible material of 1,000 kg having calorific value of 4,000 kcal/kg will be:

(a) 4,00,000 kcal/m^2 (b) 40,000 kcal/m^2

(c) 250 kcal/m^2 (d) 25 kcal/m^2

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (b)


277. From the top of a building 20 m high a ball is projected at 15 m/s at an angle 30^0 upwards to the horizontal, calculate the horizontal component of velocity of the ball just as it hits the ground.

(a) 12.99 m/sec (b) 21.18 m/sec

(c) 7.50 m/sec (d) 24.50 m/sec

UPPCL AE 2019

Ans. (a) :



parallel to the ball

$$\text{velocity} = 15\cos 30^0 = \frac{15\times\sqrt{3}}{2} = 7.5 \times \sqrt{3}$$

$\boxed{V_H = 12.99 \text{ m/sec}}$

$V_v = 15 \sin 30^0$

$\boxed{V_v = 7.5 \text{ m/sec}}$

277. The Number of cement bag required for 10 cu. m. of P.C.C. 1:2:4 is :

(a) 53 (b) 63

(c) 73 (d) 83

GPHC AE 2018

Ans : (b) Volume of dry cement for tm^3 = 1.52 m^3 proportion = 1:2:4.

$$\text{Total cement proportion} = \frac{1.52\times 1}{7} = 0.22 m^3$$

1 bag of cement volume = 0.035 m^3.

$$\text{No. of bag for 1 } m^3 \text{ concrete} = \frac{0.22}{0.35} \simeq 6.3$$

for 10 m^3 of concrete = 6.3 × 10 = 63

278. Live load as forces in dwelling home hospital bedrooms dormitories is :

(a) 2.0 KN/m^2 (b) 3.0 KN/m^2

(c) 4.0 KN/m^2 (d) 5.0 KN/m^2

GPHC AE 2018

Ans : (a)

Live load as forces in dwelling home hospital bedrooms dormitories is 2 KN/m^2.

Search on Telegram @apna_pdf

09.

Construction Management and Engineering Economics

1. Project Management & Network Theory

1. The difference between the total float and free float is known as

(a) Free float (b) Total float
(c) Independent float (d) Interfering float

APPSC AE 2016 (Mains)

Ans. (d)
Interfering float (F_{IT}) = Total float (F_T) – Free float (F_F)
Total float is the amount of time that an activity can be delayed from its early start time without delaying the project finish time.
Free float is the amount of time that an activity can be delayed without delaying the early start time of any successor activity.

2. The important events located on the activities in a bar chart are known as

(a) Key events (b) Key stones
(c) Milestones (d) Key points

APPSC AE 2016 (Mains)

Ans. (c) The important events located on the activities in a bar chart are known as milestones.

3. The difference between the latest allowable time and earliest expected time of an event is known as

(a) Float (b) Normal Deviate
(c) Free Float (d) Slack

APPSC AE 2016 (Mains)

Ans. (d) : Slack is the amount of time by which an activity can be delayed without affecting the total duration of the project.

$$\text{Slack (S)} = T_L - T_E$$

4. Earliest finish of an activity is always-

(a) Less than earliest event of the following node
(b) Greater than earliest event of the following node
(c) Less than or equal to earliest event of the following node
(d) Greater than or equal to earliest event of the following node

OPSC AEE 2015 PAPER–I

Ans. (c) : Earliest finish of an activity is always less than or equal to earliest event of the following node.

5. Which rule is used for numbering the events in a network, scientifically?

(a) Stevenson's rule (b) Jackson's rule
(c) Fulkerson's rule (d) Watson's rule

GPSC AE Dec 2018
Maharashtra PSC (Mains) 2017 Paper–I
APPSC AE 2016 (Mains)

Ans. (c) : Fulkerson's rule is used for numbering of network. Activities are generally identified by node number i.e. the number of events on either end of the activity arrow. To make sure that the numbering of events in the networks is in order and not in a random manner, we take the help of Fulkerson's rule.

6. Functional Organisation System of working was introduced by :

(a) F.W. Taylor (b) Henry Gantt
(c) M.R. Walker (d) J.E. Kelley

GPSC AE (CLASS 1 & 2) 2019
Karnataka PSC AE 2015 Paper - II
Maharashtra PSC AE (Mains) 2017, 2012 Paper–I
APPSC AEE 2012 / ESE 1995

Ans. (a) Functional Organization is suggested by F.W. Taylor. In functional organization different experts (specialists) guide the subordinates in organization. Workers or subordinates thus receive order from several specialists or officers and are responsible for their performance to different experts.

7. The event or events that immediately come before another event without any intervening events are called _____ events to that event-

(a) Successor (b) Dummy
(c) Predecessor (d) Slack

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (c) : The predecessor is the first task, it control the start or end date for all related successor tasks or end date is controlled by the predecessor. A dependency is the relationship between predecessor and successor tasks.
Event A comes before B and event C comes after B. Event A is predecessor to event B and event C is a successor to event B.

8. Which of the following best defines "Negative Slack"?

(a) Project ahead of schedule
(b) Project on schedule
(c) Project behind schedule
(d) None of the above

Maharashtra PSC (Mains) 2017 Paper–I

Search on Telegram @apna_pdf

Ans. (c) : A negative slack is obtained when T_L is less than T_E for an event.

$$S(-ve) = T_L - T_E$$

Negative slack indicates that–

(i) The event is behind the schedule by the time period equal to slack of that event any further delay in such events cause more delay in the project hence these events are called super critical event.


(ii) Resources deployed are not adequate enough.

9. Quality circles in the construction industry can have the following participants-

(a) Engineers and architects
(b) Contractors and raw material suppliers
(c) Clients and consultants
(d) All of the above

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (d) :



Quality circle is a technique to increase productivity and participate problem solving interaction among the various types of employees of an organisation.


10. Total float can be expressed as-

1. Latest start time – earliest start time
2. Latest finish time – earliest finish time

(a) Both 1 and 2 are false
(b) 1 is true but 2 is false
(c) Both 1 and 2 are true
(d) 1 is false but 2 is true

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (c) : Total float :



$\Rightarrow$ Float is difference between maximum time available and actual time required for the completion of the activity.

F_T = (Maximum available time) – (Actual time required)

$\Rightarrow$ Maximum available time we can get when activity starts at earliest start time and finish by latest finish time i.e.,

Maximum available time = LFT – EST

Actual time required for performing an activity is the estimated activity time t_{ij}

$$F_T = LFT - EST - T_{ij}$$

$$F_T = T_L^j - T_E^i - t_{ij}$$

$$F_T = \left(T_L^j - t_{ij}\right) - T_E^i$$

$$F_T = LST - EST$$

or

$$F_T = T_L^i - \left(T_E^i + t_{ij}\right)$$

$$F_T = LFT - EFT$$

11. Select the incorrect statement-

(a) Earliest start of an activity is the early event time of the node it leaves
(b) Latest finish of an activity is the late event time of the node it enters
(c) Latest start of an activity is its latest finish minus its duration
(d) Earliest finish of an activity is the late event time of the node it enters minus its duration

MPPSC AE 2017

Ans. (d) : Earliest Finish time (EFT)– It is the sum of the earliest start time (EST) and the estimated time to perform the concerning activity.

[EFT = EST + normal time for the activity]

- **Earliest Start time**– EST of any activity 'K' in a project equals the length of the longest path from start to node 'K' in the corresponding project network.
- **Latest Start time**– LST is the latest possible time that it can start without delaying the completion of the project.

[LST = EFT - Duration]

12. Which of the following activity is non-critical in the project given in the table below?

Activity	Predecessor	Duration	Cost slope	Workers / day
P	--	3	20	5
Q	--	4	30	4
R	P	4	25	4
S	P, Q	3	25	5
T	R	3	15	5
U	R, U	4	55	4

(a) P (b) R
(c) T (d) U

MPPSC AE 2017

Ans. (c) : Non critical activity is the one which has least cost slope, i.e, activity T.

13. Gantt charts indicate :

(a) Comparison of actual progress with the scheduled progress
(b) Balance of work to be done
(c) Progress cost of the project
(d) Inventory cost

JPSC AE (Pre) 2019
Haryana PSC AE 2017
Nagaland PSC CTSE 2017 Paper–I
ESE 1997

Ans. (a) : A Gantt chart is a horizontal bar chart that visually represents a project plan over time, it shows the status as well as who is responsible for each task in the project. Bar charts give idea about the physical progress of the project. i.e. comparison of actual progress with the scheduled progress. But the financial aspect involved is not known.

14. A serious limitation of interdependencies between various activities is generally observed in :

(a) Milestones chart (b) Bar charts
(c) Job layouts (d) Network analysis

JPSC AE (Pre) 2019
Haryana PSC AE 2017
ESE 2003

Search on Telegram @apna_pdf

Ans. (b) : A bar chart is a chart that presents categorical data with rectangular bars with heights or lengths proportional to the values that they represent. the bars can be plotted vertically or horizontally.


15. Consider following statements about need of construction project:

(a) Site clearance
(b) Erosion control
(c) Materials for structures
(d) Form work


Rajasthan JEN (Degree) Shift - II 2016


Ans. (c) : Materials for structure is the basic need for construction project.

16. If the activity A proceeds B, but succeeds C then network is

(a) 

(b) 

(c) 

(d) 

TNPSC AE 2018

Ans. (d) :



A proceeds B means A is after completion of B.


A succeeds C means after completion of A activity C starts.

17. Expected project duration generally follows :

(a) Normal distribution curve
(b) β- distribution curve
(c) Binominal distribution curve
(d) None of these

HPPSC 2016-II / UJVNL AE 2016
UPPSC State Eng. A.E. 2003, 2008

Ans. (a) : Expected project duration generally follows normal distribution curve. This curve is symmetrical about the mean $\bar{x}$ of the distribution.



Some observations made from curve are–

(a) Approximately 68% of all the values of the normal probability distribution curve lies with in the range $\pm\sigma$ from the average. It means that shaded area of the curve between $x = \bar{x} - \sigma$ to $x = \bar{x} + \sigma$ is 68% of total area.

(b) Similarly area between $x = \bar{x} - 2\sigma$ to $x = \bar{x} + 2\sigma$ is 95% of total area.

(c) And, area between $x = \bar{x} - 3\sigma$ to $x = \bar{x} + 3\sigma$ is 99.7% of total area.

18. Bar charts are suitable only for

(a) Minor projects (b) Medium projects
(c) Major projects (d) Huge projects

TNPSC AE 2018

Ans. (a) : Bar charts are suitable only for small size conventional projects, specially construction and manufacturing projects, in which time estimates can be made with fair degree of certainty therefore bar charts are suitable for minor projects only.

19. A Dummy activity

(a) has no bearing on the network and can appear anywhere
(b) has only head event but no tail event
(c) has tail event but no head event
(d) neither requires any time nor any resources

TNPSC AE 2018
CGPSC AE 2014 Shift–I
WBPSC AE 2007

Ans. (d) : A Dummy activity is a type of operation which neither requires time nor resources, but it denotes dependency among the activities. It is represented by dashed arrow.




Figure A dummy is shown.

20. Match List-I with List-II and select correct answer.

List-I	List-II
A. Activity	1. Resource less element
B. Event	2. Resource consuming element
C. Dummy	3. Spare time
D. Float	4. Instantaneous stage

	A	B	C	D
(a)	1	4	3	2
(b)	2	1	4	3
(c)	2	4	1	2
(d)	3	4	1	2

TNPSC AE 2018

Ans : (c) :

Activity – Resource consuming element
Event – Instantaneous stage
Dummy – Resource less element
Float – Spare time

21. Consider the following rules of network diagram and state which of them are correct:

(i) Network always have single initial final event.
(ii) An event can occur twice.
(iii) No activity can start until its tail end event has occurred.
(iv) It is usual practice to show time flow from right to left.

(a) (i), (ii) and (iii) (b) (i) and (iii)
(c) (i), (iii) and (iv) (d) (i), (ii), (iii) and (iv)

GPSC AE (CLASS 1 & 2) 2019


Search on Telegram @apna_pdf

Ans : (b) :
- An event can't occur twice.
- An activities arrow is from left to right.
- Network always have single initial final event
- No activity can start until its tail end event has occurred

22. The Time with which direct cost does not reduce with the increase in time is known as:
(a) crash time (b) normal time
(c) optimistic time (d) standard time

GPSC AE (CLASS 1 & 2) 2019
U.K. Combined A E Paper II 2012

Ans : (b) The time with which direct cost does not reduce with the increase in time is known as normal time.



It is the minimum time required to complete the project at the normal cost.

23. If there are n number of events in the networks diagram then number of dual role event will be
(a) n-1 (b) n+1
(c) n-2 (d) n+2

GPSC AE (CLASS 1 & 2) 2019

Ans : (c) : If there are n number of events in the network diagram then number of dual role event will be (n-2).

24. Consider following requirement of documents for agreement to be signed for a construction project :
(i) Letter of acceptance
(ii) General conditions of contract
(iii) Conditions of particular application
(iv) Technical specification
(v) Drawings
(vi) Priced bill of quantities
Which one of the following is correct answer ?
(a) (i), (ii), (iv) and (v) only
(b) (i), (iii), (iv) and (v) only
(c) (ii), (iii), (iv) and (v) only
(d) All

Rajasthan JEn (Degree) 2016

Ans. (d) Required documents for agreement to be signed for a construction project are-
(i) Letter of acceptance
(ii) General conditions of contract
(iii) Conditions of particular application
(iv) Technical specification
(v) Drawings
(vi) Priced bill of quantities

25. A dummy activity in a project network does not consume.
(a) Time (b) Material
(c) Money (d) All the above

Rajasthan JEn (Degree) 2016

Ans. (d) A dummy activity in a project neither consumes time nor any resource.

26. Critical Path is always :
(a) the longest path
(b) the shortest path
(c) the most profitable path
(d) the fastest path

GPSC AE Class (1&2) Paper - 2 2017
Gujarat PSC AE 2017
Nagaland PSC CTSE 2017 Paper–I
Punjab PSC Sub divisional Engineer 2014
APPSC AEE 2012

Ans. (a) Critical path is the longest path along which total floats are zero or minimum.

27. The area under β-distribution curve is divided into two equal parts by-
(a) Most likely time (b) Expected time
(c) Optimistic time (d) Pessimistic time

MPPSC AE 2017
GPSC AE Class (1&2) Paper - 2 2017

Ans. (b) : The expected time (t_E) for the completion of any activity is computed as–

$$\left[t_E = \frac{t_0 + 4t_m + t_p}{6} \right]$$

t_0 = Optimistic time,
t_m = Most likely time
t_p = Pessimistic time
The expected time (t_E) is such that there is fifty-fifty chance of completion of the activity in this time. If we draw a vertical line through t_E, the shaded area to its left is half of the total area. The expected time (t_E) divides the β distribution curve in two-halves.

28. The chart which gives an estimate about the amount of materials handling between various work stations is known as
(a) Flow chart (b) Process chart
(c) Travel chart (d) Operation chart

(UPRVUNL AE 2015)

Ans : (c) The chart which gives an estimate about the amount of materials handling between various work stations is known as travel chart.

29. In the critical path of construction planning, free float can be
(a) Greater than total float
(b) Equal to total float
(c) Greater than independent float
(d) Less than independent float

Karnataka PSC AE 2017 Paper - II
Punjab PSC SDE 2016
ESE 2016
UPRVUNL AE 2015

Ans : (c) In the critical path of construction planning free float can be greater than independent float. In free float preceding activity is not allowed to occur at its latest time and hence total float of preceding activity is affected. The float may be positive, negative or zero.

30. A term referring to the shortest possible time for which an activity can be schedule :
(a) Crash duration (b) Expansion
(c) Slack (d) Flexibility

(RRB SSE (shift-III), 02.09.2015)


Search on Telegram @apna_pdf

Ans : (a) It is the absolute minimum possible time associated with the crash cost. Crash time impose the condition that the duration cannot be further reduced even after expending the extra resources to any extent.
Hence, direct cost for expediting an activity per unit time i.e., cost slope of an activity.

31. Total float is the amount of time that a task in a project network can be delayed without causing a delay to the
(a) Subsequent tasks
(b) Milestone completion date
(c) Project completion date
(d) Subsequent project

RRB SSE (shift-II), 02.09.2015
CGPSC AE 2014 Shift–I

Ans : (c) The time span by which starting or finishing of an activity can be delayed without delaying the completion of the project.
It is maximum available time in excess to the activity completion time.



i = Tail event
j = Head event

$$F_T = \left(T_L^j - T_E^i\right) - t_{ij}$$

32. The technique for establishing and maintaining priorities among various jobs of a project is known as:-
(a) Event flow scheduling
(b) Critical flow scheduling
(c) Slotting technique for scheduling
(d) Short interval scheduling

[UKPSC A E Paper II 2013]


Ans : (b) The technique for establishing and maintaining priorities among various jobs of a project is known as critical flow scheduling.

33. For completion of a project, the critical path of a network represents
(a) minimum time (b) maximum time
(c) maximum cost (d) minimum cost

[Uttarakhand Combined State AE Paper II 2007]

Ans : (a) Critical path method are the project tasks that must start and finish on time to ensure that the project ends on schedule. These are the critical path of a network represents path with minimum time.

34. The given figures shows the arrow diagram for a particular project. The arrow A is known as



(a) Critical activity
(b) Logic arrow
(c) Dummy activity
(d) Sub-critical activity

(UPRVUNL AE 2015)

Ans : (d) The given figures shows the arrow diagram for a particular project. The arrow is joining sub-critical activities, for sub-critical activities total float is greater than zero.

$$F_T > 0$$

35. If the optimistic time, most likely time and pessimistic time for activity A are 7, 8 and 9 days respectively and for activity B are 6, 7.5 and 12 days respectively, then :
(a) Expected time of activity A is greater than the expected time of activity B
(b) Expected time of both the activities A and B will be same
(c) Expected time of activity B is greater than the expected time of activity A
(d) None of the above

OPSC AEE 2019 Paper–I
[UPPSC State Eng. A.E. 2007(I)]

Ans : (b) For activity A
$t_o = 7$ days
$t_m = 8$ days
$t_P = 9$ days

$$\text{Expected time} = \frac{t_0 + 4t_m + t_P}{6}$$
$$= \frac{7 + 4 \times 8 + 9}{6} = 8 \text{ day}$$

For activity B
$t_O = 6$ days
$t_m = 7.5$ days
$t_P = 12$ days

$$\text{Expected time} = \frac{6 + 4 \times 7.5 + 12}{6}$$
$$= 8 \text{ days}$$

Hence, expected time of both the activity A and B will be same.

36. The time by which a particular activity can be delayed without affecting the preceding and succeeding activity is known as :
(a) Total float (b) Free float
(c) Interfering float (d) Independent float

[UPPSC State Eng. A.E. 2003]

Ans : (d)
(i) Float : The term is associated with activity time. It denotes the range within which an activity start time (or) its finish time may fluctuate without affecting the completion time of the project.
(ii) Total Float (F_T) : It is the time span by which the starting (or finishing) of an activity can be delayed without delaying the completion time of the project. It is also equal to the time that is the excess of the maximum available time over the activity time.
∴ Total Float = (Maximum time available – time require to perform the activity)
i.e. F_T = (LST – EST)
= (LFT – EFT)

Search on Telegram @apna_pdf

(iii) Free Float : It is that portion of the positive total float that can be used by an activity without delaying any succeeding activity.

(iv) Independent Float : It is the excess of minimum available time over the required activity duration, it gives us an idea about the excess time that exists if the preceding activity ends as late as possible and the succeeding activity starts as early as possible.

(v) Interfering Float (F_{IT}) : It is equal to the difference between total float and the free float.

37. Given that
t = the duration of various jobs
t_m = mean time of different durations
n = number of observations
the standard deviation is given by ,

(a) $\frac{\sum t}{n}$ (b) $t - t_m$

(c) $\frac{\sum (t - t_m)^2}{n}$ (d) $\sqrt{\frac{\sum (t - t_m)^2}{n}}$

PTCUL AE 2016
[UPPSC State Eng. A.E. 2003]

Ans : (d) t = the duration of various job
t_m = mean time of different duration
n = number of observation


standard deviation $= \sqrt{\frac{\sum (t - t_m)^2}{n}}$

38. Latest start of an activity is always

(a) greater than or equal to latest event times of all the preceding nodes
(b) less than or equal to earliest event times of all the preceding nodes
(c) equal to the latest event times of all the preceding nodes
(d) equal to the earliest event time of all the preceding nodes

GPSC AE Dec 2018
MPPSC AE 2016
Punjab MCP SDO 2015

Ans : (a) The succeeding activity can only start when all of the preceding activities have finished. Hence the latest start time is always greater or equal to latest event time of preceding nodes.



39. For a given activity, the optimistic time, pessimistic time and the most probable estimates are 5, 17 and 8 days respectively. The expected time is :

(a) 8 days (b) 9 days
(c) 10 days (d) 15 days

[UPPSC State Eng. A.E. 2003]
ESE 1995

Ans : (b) $t_0 = 5$ days
$t_P = 17$ days
$t_m = 8$ days

Expected time, $(t_e) = \frac{t_0 + 4t_m + t_P}{6}$

$= \frac{5 + 4 \times 8 + 17}{6} = 9$ days

40. If "D" is the duration, 'ES' and 'EF' are the earliest start and finish times, 'LS' and 'LF' are latest start and latest finish times, the following relationship holds good.

(a) D = LF–EF (b) LS = LF+D
(c) LF = LS–ES (d) EF = ES+D

UPPSC Civil Eng. A.E. 2013(II)

Ans : (d)




EF = ES+D

41. If the Latest occurrence time for event J = T_L^j, the earliest occurrence time for event i = T_E^i and the duration of activity = t^{ij}, what is the total float for activity $\vec{F}_T^{ij}$?

(a) $T_E^i - T_L^i - t^{ij}$ (b) $T_L^j - T_E^i - t^{ij}$
(c) $t^{ij} - T_E^i - T_L^j$ (d) $t^{ij} - T_L^J + T_E^i$

TNPSC AE 2019

Ans. (b)



Total float = $T_L^j - T_E^i - t^{ij}$

Free float = $T_E^j - T_E^i - t^{ij}$

Independent float = $T_E^j - T_L^j - t^{ij}$

42. The standard deviation of the time of Completion of an activity is given by

(a) $\frac{t_p - t_o}{3}$ (b) $\frac{t_p - t_o}{4}$

(c) $\frac{t_p - t_o}{5}$ (d) $\frac{t_p - t_o}{6}$

TNPSC AE 2019

Ans. (d) Standard deviation $(\sigma) = \frac{T_p - T_o}{6}$

Where, T_P = Pessimistic time
T_0 = Optimistic time

And, Variance, $(\sigma^2) = \left(\frac{T_p - T_o}{6}\right)^2$

variance is measure of uncertainty, greater the variance greater will be uncertainty.

Search on Telegram @apna_pdf

43. Activities that can be performed simultaneously and independently to each other are known as

(a) Service activity (b) Parallel activity
(c) Successor activity (d) Predecessor activity

TNPSC AE 2019

Ans. (b) Activities that can perform simultaneously and independently to each other are known as parallel activity.

44. The earliest method used for planning of project was

(a) CPM (b) PERT
(c) Milestone chart (d) Bar chart

TNPSC AE 2019

Ans. (d) Earliest method was bar chart method, it's improvement is Milestone chart.

45. In a project, the major quality control methods are

(a) Testing and sampling
(b) Inspection and testing
(c) Inspection and sampling
(d) Inspection, testing and sampling

TNPSC AE 2019

Ans. (d) In a project, the major quality control methods are–
(1) Inspection
(2) Testing
(3) Sampling.

46. Match List I with List II and select correct answer.

	List-I		List-II
A	Optimal Cost	**1**	Activity Related
B	Overhead Cost	**2**	Developed by crashing process
C	Direct Cost	**3**	Project Related
D	Indirect Cost	**4**	Contained in or contributing exclusively to related product.

	A	**B**	**C**	**D**
(a)	4	3	2	1
(b)	2	1	4	3
(c)	4	1	2	3
(d)	2	3	4	1

TNPSC AE 2019
ESE 2004

Ans. (d) Fixed indirect cost is independent of the progress of project. It includes initial expenditure for purchase of equipment, installation and storage charge required for different activities.
Normal cost : It is the direct cost of an Activity associated with the normal time.

47. The most important two features of modern civilization are

(a) Infrastructure and population
(b) Urbanization and industrialization
(c) Population and construction
(d) Commercialization and globalization

TNPSC AE 2019

Ans. (b) The most important two features of modern civilization are Urbanization and industrialization which full fill our basic needs.

48. If the optimistic, most likely time and pessimistic time for an activity are 7, 8 and 10 respectively, the variance is

(a) 0.20 (b) 0.25
(c) 0.35 (d) 0.50

TNPSC AE 2019

Ans. (b) Variance

$$= \sigma^2 = \left(\frac{T_P - T_0}{6}\right)^2 = \left(\frac{10-7}{6}\right)^2 = \left(\frac{1}{2}\right)^2 = 0.25$$

49. A construction schedule indicates

(a) the rate of progress for each operation
(b) the actual progress of work
(c) both the actual progress and the rate of progress
(d) completion of the project

TNPSC AE 2012

Ans. (c) : A construction schedule indicates both the actual progress and the rate of progress.

50. Construction team means

(a) an engineer (b) an architect
(c) an owner (d) all of these

TNPSC AE 2012

Ans. (d) :

51. Which is a right sequencing of processes in overall management system?

(a) Conception, Time resource analysis, Feasibility study, Monitoring Updating and Scheduling
(b) Conception, Feasibility study, Scheduling, Time resource analysis, Monitoring and Updating
(c) Conception, Monitoring, updating, Feasibility stud, Time resource analysis and Scheduling
(d) Feasibility study, Conception, Scheduling, Time resource analysis, Monitoring and Updating

TNPSC AE 2012

Ans. (b) : The right sequencing of processes in overall management system is conception, feasibility study, scheduling, time resource analysis, monitoring and updating.

52. A project is

(a) A large dam constructed across a river for a single or multipurpose
(b) any job involving many people and large money
(c) a work of major importance involving huge men and material
(d) an organized team work to achieve a set task within the time limit

TNPSC AE 2012

Ans. (d) : A project is something which can be done by an organized team work to achieve a set task within the time limit.

Search on Telegram @apna_pdf

53. Which of the following is the main contribution of scientific management?

(a) A rational approach to solve organisation problem
(b) Development of principles of management
(c) Correlation between improved working conditions and high production
(d) All of the above

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (d) The main contribution of scientific management are–
(1) A rational approach to solve organisation problem
(2) Development of principles of management
(3) Correlation between improved working conditions and high production

54. When time to completion of a project is reduced, it usually results in :

(a) a decrease in indirect cost
(b) an increase in indirect cost
(c) a decrease in taxes
(d) a decrease in resource deployment

CIL MT 2017

Ans. (a) : When time to completion of a project is reduced, it usually results in a decrease in indirect cost.

55. Slack time refers to-

(a) an activity (b) an event
(c) both event and activity (d) none of the above.

Gujarat PSC AE (N.W.R.) 2020
OPSC AEE 2019 Paper–I
APPSC AEE 2012
(ESE 2011)

Ans. (b) : Slack time refers to an event.

56. Site order book is used for–

(a) recording the instructions of the executive engineer
(b) recording the constructions measurements
(c) issuing the requisition requests for materials
(d) maintaining the record of the ordered instruments and materials.

Gujarat PSC AE (N.W.R.) 2020
APPSC AEE 2012

Ans. (a) Site order book is used for recording the instructions of the executive engineer.

57. Which of the following statement(s) is/are incorrect?

(i) Earliest start of an activity is the early event time of the node it leaves.
(ii) Latest finish of an activity is the late event time of the node it enters.
(iii) Latest start of an activity is its latest finish minus its duration.

(a) Only (i) (b) (i) and (ii)
(c) (ii) and (iii) (d) None

Gujarat PSC AE (N.W.R.) 2020

Ans. (d) : The given all statement are true :
(i) Earliest start of an activity is the early event time of the node it leaves.
(ii) Latest finish of an activity is the late event time of the node it enters.
(iii) Latest start of an activity is its latest finish minus its duration.


58. If an activity has its optimistic, most likely and pessimistic times as 2, 4 and 9 respectively, then its expected time and variance are ____ and _____ respectively.

(a) 4.5 and 7/6 (b) 7 and 49/36
(c) 4.5 and 49/36 (d) 7 and 7/6

Gujarat PSC AE (N.W.R.) 2020

Ans. (c) :
Expected time is given by
$t_e = (t_0 + 4t_m + t_p)/ 6$
So $t_e = [2+ (4\times4) + 9]/6 = 4.5$
Now standard deviation is given by
$S = (t_p-t_o)/6 = 7/6$
As variance is square of standard deviation so variance = 49/36.

59. Figure below shows the network for a particular project which consists of four activities.



Normal time and crash time for each activity are given below:

Activity	Normal time (days)	Crash time (days)
1-2	3	2
2-3	4	2
2-4	5	4
3-4	7	5

The minimum time required for the completion of project is _____

(a) 9 days (b) 13 days
(c) 14 days (d) 19 days

Gujarat PSC AE (N.W.R.) 2020

Ans. (a) :
Critical activity→ 1–2–3–4
(1) Crash activity (3–4) by 2 days.
(2) Now, crash activity (2–3) by 2 days.
critical activity is still 1–2–3–4
(3) Crash 1 day of activity 1–2
Hence max 9 days after crashing.

60. If an activity lies on the critical path, its total float will be

(a) Positive
(b) Negative
(c) Zero
(d) Cannot be determined

GESCOM (Karnataka) AE 2011
ESE 2011

Ans : (c) Float is the amount of time by which an activity can be delayed without affecting the total duration of the project.

$$\text{Float (F)} = T_L - T_E$$

For critical activity total float will be zero.

Search on Telegram @apna_pdf

61. The planned or systematic actions necessary to provide enough confidence that a product or service will satisfy the given requirements is called:

(a) Quality control
(b) Quality improvement
(c) Quality Assurance
(d) Quality Audit

KPSC AE 2020

Ans. (c) : The planned or systematic actions necessary to provide enough confidence that a product or service will satisfy the given requirement is called quality assurance.

62. The direct cost of a project with respect to normal time is :

(a) Minimum (b) Maximum
(c) Zero (d) Infinite

OPSC AEE 2019 Paper–I
Nagaland PSC CTSE 2017 Paper–I

Ans. (a) : Normal cost : It is the direct cost of an Activity associated with the normal time. Minimum cost is calculated using normal time.

63. Latest finish time in CPM technique is indicated by a :

(a) Rectangle (b) Circle
(c) Triangle (d) Line

Nagaland PSC CTSE 2017 Paper–I


Ans. (c) : Latest finish time in CPM technique is indicated by a Triangle (Δ)

64. Slack is :

(a) Difference of latest allowable time and earliest expected time
(b) Least allowable time-earliest expected time
(c) Earliest expected time-least least allowable time
(d) Time gained by an activity

Nagaland PSC CTSE 2017 Paper–I

Ans. (b) : Slack (S) : This is the time by which an event may be delayed without affecting the completion time of the project.



65. Negative float can occur when it is :

(a) Sub-critical activity
(b) Critical activity
(c) Super critical activity
(d) Normal activity

Nagaland PSC CTSE 2017 Paper–I
Punjab PSC SDE 2016

Ans. (c) : When slack of an activity is negative – It represent that a program falls behind schedule and additional resources are required to complete the project in time. When slack of an activity is zero - the activity is critical & delay in its preference will delay the completion of whole project.

66. Crashing is :

(a) Reduction in duration
(b) Reduction in resources
(c) Reduction in cost
(d) Reduction in project size

Nagaland PSC CTSE 2017 Paper–I
ESE 2011

Ans. (c) : The main objective of crashing is to reduce total project cost and to obtain optimum project duration corresponding to the minimum total project cost.

67. On a bar chart the various activities of a project are shown by :

Nagaland PSC CTSE 2017 Paper–I

Or

How do you represent the various activities of a project on bar chart?

OPSC Civil Service Pre-2011

(a) Shaded area (b) Horizontal lines
(c) Vertical lines (d) Dot marks

Ans. (b) : Various activities of a project are shown on bar charts by Horizontal lines.

68. Gantt chart is drawn for

(a) Time versus activity
(b) Activity versus activity
(c) Resources versus progress
(d) Progress versus time

Nagaland PSC CTSE 2017 Paper–I
WBPSC AE 2007

Ans. (a) : Gantt chart is drawn for time versus activity where time is represented on horizontal axis.

69. The annual financial statements of the receipt and expenditure is known as :

(a) Account statement (b) Financial statement
(c) Budget (d) Balance sheet

DMRC AM 2017

Ans. (d) : The annual financial statements of the receipt and expenditure is known as balance sheet.

70. A systematic measurement and evaluation of the way in which an organization manages its health and safety programme against a series of specific and attainable standards is called

(a) Safety inspection (b) Safety audit
(c) Safety plan (d) Safety committee

ESE 2019

Ans. (c)

- **Safety and Health Audit**–Refers to a regular and critical examination of project sites, safety programs, records and management performance on program standard on safety and health.
- **Safety Committee**–It means a group is tasked with the authority to monitor; inspect and investigate all aspects of the construction project pertaining to health and safety of construction workers.
- **Safety Inspection**–In this inspection the work environment, including the location and operation of machinery other than those covered by technical safety inspections, protection facilities and other safety and health hazards in the workplace.
- **Safety plan**–A formal procedure to be followed to ensure safety of workers at a work place. It generally contains rules and regulations to be followed and the site plan map.

Search on Telegram @apna_pdf

71. The three phases involved in the management of large projects are

(a) scheduling, designing, operating
(b) scheduling, operating, evaluating
(c) planning, scheduling, evaluating
(d) planning, scheduling, controlling

AP (VSS-1) PART - A 2017

Ans : (d) The three phase involved in the management of large projects are :

(i) Planning : Planning means defining the objectives of the project and to identify the different task materials equipment etc. That are required for completing the project.

(ii) Scheduling : Scheduling is deciding the order of all the activities and allocation of resources (like time, space, equipment, material and manpower) to the activities.

(iii) Controlling : The process of controlling involve comparing the progress of work with the scheduled one at regular intervals and the taking corrective measure to get the desire result, if it is running behind the schedule.

Note : Planning and scheduling are done before the start of a project where as controlling is performed after the start of project.

72. Which of the following is a weakness of bar chart?

(a) Interdependencies of activities
(b) Project progress
(c) Uncertainties
(d) All of these

OPSC AEE 2019 Paper–I

Ans. (d) : Short comings of bar chart is–
1. Lack of inter-dependencies of activities.
2. Critical path cannot be found.
3. project progress cannot be monitored.
4. Uncertainties in activity time cannot be Analyzed by bar chart.

73. Free float is mainly used to :

(a) Identify the activities which can be delayed without affecting the total float of preceding activity.
(b) Identify the activities which can be delayed without affecting the total float of succeeding activity.
(c) Establish priorities.
(d) Identify the activities which can be delayed without affecting the total float of either of preceding or succeeding activities.

GUJARAT AE (CLASS 1 & 2) 2017, 2019
OPSC AEE 2019 Paper–I
GPSC AE Class (1&2) Paper-2 2017

Ans. (b) : Free float is time with which activity can be delayed without affecting completion time of succeeding activities.

74. The process in which differences between the plan and actual performance are reviewed after the project has started is known as

(a) scheduling (b) controlling
(c) levelling (d) smoothing

AP (VSS-1) PART - A 2017

Ans : (b) Controlling : The process of controlling involve comparing the progress of work with the scheduled one at regular intervals and the taking corrective measure to get the desire result, if it is running behind the schedule.

75. Resource smoothing is :

(a) An optimization and economical utilization of resources
(b) An adjustment of resources with-out affecting project duration
(c) A gradual increase in resources
(d) A gradual decrease in resources

ESE 2020

Ans. (b) : **Resource Smoothing–** It is defined as a technique that adjusts the activities in a schedule model so that all requirements for the resources do not go beyond the resources limits (which is already pre-defined during the planning) without affecting the project duration.

Following are some characteristics of resource smoothing :

- It is used when the time constraints takes important priority in project planning.
- It removes as much resource conflicts as possible.
- The project duration remains the same.
- No change occurs in critical path.

76. Which of the following relations are correct for determining different components of a bid price ?

1. Bid price = Direct cost + Indirect cost + Mark up amount
2. Direct cost = Project overheads + Common plant and equipment cost + Common work men cost
3. Mark up amount = Profit + Contingency + Allowances for risks + General overheads

(a) 1, 2 and 3 (b) 1 and 2 only
(c) 1 and 3 only (d) 2 and 3 only

ESE 2020

Ans. (c) : Any construction project consists of direct and indirect costs which forms the total costs and expenses resulting from the use of principal components for implementing construction projects.

- Bid price = Base cost + Mark up amount
  = (Direct cost + Indirect cost) + Mark up amount
- Direct cost = Labour cost + Plant and Equipment cost + Material cost + sub contractor cost
- Mark up amount = Profit + Contingency + General overheads + Allowance for risks.

Note – Project overhead is indirect cost.

77. The project plan for construction :

1. Clearly defines project's scope of work. It breaks down project objectives into clear, identifiable, attainable and verifiable goals.
2. Identifies critical activities, thus enabling management of projects by exceptions.

Search on Telegram @apna_pdf

3. **Provides the basis for coordinating the efforts of clients, consultants, architects, designers, quality surveyors, specialists, supplies, contractors and project staff.**

(a) 1 and 2 only (b) 1, 2 and 3
(c) 1 and 3 only (d) 2 and 3 only

ESE 2020

Ans. (b) : The project plan is a formal, approved document used to manage project execution.
The project plan includes–
(i) Project charges.
(ii) Project management approach/strategy.
(iii) Scope statement.
(iv) WBS (Work Breakdown Structure).
(v) Cost estimates.
(vi) Performance measurement baseline for technical scope and schedule and cost base line.
(vii) Major milestones and target-dates.
(viii) Risk management plan.
The primary use of the project plan are to document planning assumptions and decisions, facilitate communication among stakeholders.

78. Which of the following is a dummy activity?

(a) Awaiting the arrival of concrete material
(b) Excavation of foundations
(c) Laying the foundation concrete
(d) Curing the foundation concrete

Punjab PSC SDE 2016

Ans. (a) : Dummy activity in the network is the activity which neither consumes any time nor resources.

79. What is the purpose of job layout?

(a) To provide more economical methods of working
(b) Shorter leads of materials
(c) Reduction in completion
(d) All of the above

Maharashtra PSC Mains 2018 Paper-1

Ans. (d) : The purpose of job layout:
(1) To provide more economical methods of working.
(2) Shorter leads of materials
(3) Reduction in completion time

80. Which of the following are the significant achievements of Taylor towards scientific management approach?

(a) Work study
(b) Incentive scheme
(c) Standardization of tools and equipment or workman and working conditions
(d) All of the above

Maharashtra PSC Mains 2018 Paper-1

Ans. (c) : Standardization of tools and equipment or workman and working conditions are the significant achievements of Taylor towards scientific management approach.

81. Which of the following are the methods of scheduling?

(a) Bar charts or Gantt charts
(b) Milestone charts
(c) Network analysis
(d) All of the above

Maharashtra PSC Mains 2018 Paper-1


Ans. (d) : The methods of scheduling are :
(a) Bar charts or Gantt charts
(b) Milestone charts
(c) Network analysis

82. The time by which the completion of an activity can be delayed without affecting the start of succeeding activities is called

(a) total float (b) interfering float
(c) independent float (d) free float

ISRO Scientist/Engineer 2020
GPSC AE March 2018
Haryana PSE AE Paper-2 2018
APPSC AEE 2012
ESE 2007

Ans. (d) : Free float:-The time by which the completion of an activity can be delayed without affecting the start of succeeding activities.



$$F_F = T_E^j - T_E^i - t_{ij}$$


or $$F_F = F_T - S_i$$

83. If the probability factor is zero, the chances of completing the project in scheduled time are

(a) 0% (b) 50%
(c) 75% (d) 100%

GPSC AE March 2018

Ans. (b) : If probability factor is zero i.e. the chances of completing the project in scheduled time are 50%.



84. Float may be defined as the difference between

(a) latest start time and the earliest start time
(b) latest finish time and the earliest finish time
(c) time available and the time required to completed the activity
(d) all of the above

GPSC AE March 2018

Ans. (d) : Float indicates the time by which starting or finishing of an activity can be delayed without affecting the project management. Float are of four types-
1. Total float, 2. Free float, 3. Independent float, 4. Interfering float.
Float may be defined as difference between
(i) latest start time and earliest start time.
(ii) latest finish time and earliest finish time.
(iii) time available and time required to completed the activity.

Search on Telegram @apna_pdf

85. Interfering float is the difference between

(a) total float and independent float
(b) total float and free float
(c) free float and independent float
(d) independent float and free float

GPSC AE March 2018
GPSC AE Class (1&2) Paper-2 2017

Ans. (b) : Interfering float is the difference between total float and free float.
It is also equal to slack of head event of head activity.
$F_{IT} = F_T - F_F = S_j$

86. The purpose of dummy activity is

(a) to provide logical link to maintain the correct relationship of activities
(b) To show the correct critical path of network
(c) To maintain the sequence of network
(d) To calculate exact duration of project

GPSC Poly. Tech. Lect. 2016

Ans. (a) : Dummy activity often have a zero completion time and are used to provide logical link to maintain the correct relationship of actual activities involved in the project. By convention dummies are always shown as dotted arrow in network diagrams.

87. Study of project duration probabilities may become 'pointless' in situations where :

1. **There exist several components of WBS**
2. **There exists cross inputs from one WBS to another as regards milestone events**
3. **Inputs from other infrastructure projects are essential for the progress of the project under consideration**
4. **Regarding project inventory, situations may prevail where both supply and demand of input materials are deterministic.**

The severity of these causes to contribute to the 'pointlessness' mentioned above is gradable (most severe to least severe) in most cases as:

(a) 3, 2, 1 and 4 (b) 4, 3, 2 and 1
(c) 3, 1, 2 and 4 (d) 4, 2, 3 and 1

UPSC JWM 2017


Ans. (a) :

88. Which of the following does not represent an activity?

(a) site located
(b) foundation is being dug
(c) the office area is being cleaned
(d) the invitations are being sent

WBPSC Poly Lect. 2019
OPSC AEE 2015 PAPER–I
Punjab PSC Sub divisional Engineer 2014

Ans. (a) : Activity-Any task or work which consumes resources and time.
Event-The movement at which any activity starts or finish.



89. Total float for any activity is defined as the difference between

(a) its latest finish time and earliest start time for its successor activity
(b) its latest start time and earliest start time
(c) its latest start time and earliest finish time
(d) its earliest start time and earliest start time for its successor activity

Punjab PSC Sub divisional Engineer 2014

Ans. (b) : Total float = Latest start time – earliest start time.

90. A critical activity has:

GPSC R&B AE 2016
ISRO Scientist/Engineer 2015
TNPSC AE 2012

OR


A critical activity in a project management network has

(a) zero float (b) average float
(c) minimum float (d) maximum float

ISRO Scientist/Engineer 2017

Ans. (a) : A critical activity cannot be delayed. Delay in critical activity will increase in the project completion time, therefore critical activity or critical path have zero float.


91. In the network shown in figure, the earliest start time of activity 6 – 7 is



(a) 6 (b) 10
(c) 11 (d) 12

UKPSC(Urban engineering)-2011

Ans. (d) : EST of activity 6-7 is 12



Path → 1–3–4–5–6–7.


92. Which of the following is an activity?

(a) Construction of foundation
(b) Construction of roof
(c) Construction of superstructure
(d) All of these

Punjab PSC SDE 2016

Ans. (d) : A project has various jobs in forms of operations and processes necessary for its completion. Each of these operation or processes consuming time or resource is called as an activity.

93. The flow net of the activities of a project are shown in the network given in figure indicating the duration of the activities along their arrows. The critical path of the activities is along




Search on Telegram @apna_pdf

(a) $1 \to 2 \to 4 \to 5 \to 7 \to 8$
(b) $1 \to 2 \to 3 \to 6 \to 7 \to 8$
(c) $1 \to 2 \to 3 \to 5 \to 7 \to 8$
(d) $1 \to 2 \to 4 \to 5 \to 3 \to 6 \to 7 \to 8$

APPSC AEE 2012
ESE 2010

Ans. (c) : EST = 15 EST = 18



EST = 10 EST = 14

Critical path = longest path of Network
= 1 – 2 – 3 – 5 – 7 – 8

94. Which of the following is commonly used software for non-linear analysis of structures?
(a) STAAD Pro (b) STRAP
(c) CADS (d) SAP 2000

GPSC AE June 2019

Ans. (d) : SAP 2000 Software commonly used for non-linear analysis of structures.

95. In time-cost optimization of project, crashing is done
(a) on all the activities
(b) on original critical activities and those that become critical at any stage of crashing in order of ascending cost slope
(c) On all activities lying on original critical path and having flatter cost slopes
(d) only on activates lying on original critical path and having flatter cost slopes

GPSC AE June 2019

Ans. (b) : Crashing in project management aims to shorten the duration of the entire project by reducing one or more activities during the life cycle. It is done on original critical activities and those that become critical at any stage of crashing in order of ascending cost slope.

96. Items of 'C' type are identified for a project using ABC analysis. Which of the following statements are true for them?
1. Even rough quantity estimate is sufficient
2. Bulk ordering is preferred
3. Ordering on EOQ basis is preferred
4. Even junior level staff is authorized to order
Answer options:
(a) All of the above (b) 1, 2 and 4
(c) Only 3 (d) None of the above

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (b) : True statements are :
(1) Even rough quantity estimate is sufficient
(2) Bulk ordering is preferred
(3) Even junior level staff is authorized to order

97. Independent float of an activity (i, j) is denoted by 1F(i, j). The earliest occurrence times of i and j are denoted by E_i and E_j respectively. The latest occurrence times of i and j are denoted by L_i and L_j respectively. D(i, j) indicates the duration of the activity. Select correct option giving IF (i, j):
(a) $E_i - L_j - D(i, j)$ (b) $L_j - E_i - D(i, j)$
(c) $L_i - E_j - D(i, j)$ (d) $E_j - E_i$

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (a) : Independent float – It doesn't effect previous or succeeding activity $E_i - L_j - D(i, j)$

98. A part of quality management system, that indicates the degree to which design quality is achieved in the actual construction work is called:
(a) Quality Assurance
(b) Quality of design
(c) Quality conformance
(d) Quality performance

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (a) : A part of quality management system, that indicates the degree to which design quality is achieved in the actual construction work is called quality assurance.

99. Economic saving of time results by crashing
(a) cheapest critical activity
(b) cheapest non-critical activity
(c) costliest critical activity
(d) costliest non-critical activity

GPSC AE Dec 2018
GPSC AE Class (1&2) Paper - 2 2017
APPSC AEE 2012

Ans. (a) : Economic saving of time results by crashing the cheapest critical activity means whose cost-slope is minimum.

100. To prepare the master plan for a city, the following basic studies have to be undertaken. Choose the answer using codes.
C1 : Delineation of planning area
C2 : Historical evolution
C3 : Geographical, climatology and related aspects
C4 : Religion, Caste and gender data
(a) C2, C3 and C4 (b) C1, C3 and C4
(c) C1, C2 and C3 (d) C1, C2, C3 and C4

BHEL ET 2019

Ans. (c) : To prepare the master plane for a city. The basic studies are :
(1) Delineation of planning area
(2) Historical evolution
(3) Geographical, climatology and related aspects
We don't need caste, religion and gender data for master plan of a city.

101. The duration of any activity in PERT is given by t, where t_0 = optimistic time; t_P = pessimistic time, t_m = most probable time
(a) $t = \frac{t_0 + t_m + 4t_P}{6}$ (b) $t = \frac{t_0 + 4t_m + t_P}{6}$

Search on Telegram @apna_pdf

(c) $t = \frac{4t_0 + t_m + t_p}{6}$ (d) $t = \frac{4t_0 + t_m + 4t_p}{6}$

KPSC AE 2020
Maharashtra PSC (Mains) 2019 Paper–I
PTCUL AE 2016
CGPSC AE 2014 Shift–I
RRB SSE Bilaspur : 21.12.2014

Ans. (b) In PERT analysis the estimation of time estimate is done by probabilistic approach & expected time is calculated by weighted avg. method :

$$t_e = \frac{t_o + 4_{tm} + t_p}{6}$$

$t_o \rightarrow$ optimistic time
$t_p \rightarrow$ pessimistic time
$t_m \rightarrow$ most likely time

102. The technique for establishing and maintaining priorities among various jobs of a project, is known
(a) Event flow scheduling technique
(b) short interval scheduling
(c) Critical ratio scheduling
(d) Slotting technique for scheduling

GOA PSC Assistant Prof. 2020
APPSC AEE 2016

Ans. (c) : Critical ratio is calculated by dividing the time remaining until a job's due date by the total time remaining for the job, which is defined as the setup, processing move and expected waiting times of all remaining operations, including the operation being scheduled.

103. The performance of a specific task in CPM, is known
(a) Dummy (b) Event
(c) Contract (d) Activity

APPSC AEE 2016

Ans. (d) : Critical path activities are the project tasks that must start and finish on time to ensure that the project ends on schedule.

104. In construction project management, Sensitivity Analysis is a modeling technique used
(a) to identify sensitive components of the project
(b) to determine impact of uncertainties having significant impact on project
(c) to determine important activities of a project
(d) to determine accuracy of budget estimation

GPSC AE January 2018

Ans. (b) : In construction project management, sensitivity analysis is used to assess how robust the results are to uncertain decisions or assumptions in the model.

105. A typical sequence of following development phases in a construction project is
(P) Plan development,
(Q) Commissioning
(R) Concept analysis
(S) Execution
(a) P-Q-R-S (b) P-R-S-Q
(c) P-S-R-Q (d) R-P-S-Q

GPSC AE January 2018

Ans. (d) : There are 5 operations in project completion-

Concept analysis
↓
Design testing
↓
Planning operation
↓
Execution
↓
Commissioning

106. If the optimistic time, most likely time and pessimistic time of activity A are 4, 6 and 8 weeks. Respectively and for activity B are 5, 5.5 and 9 weeks respectively, then
(a) Expected time of activity A is greater than the expected time of activity B
(b) Expected time of activity B is greater than the expected time of activity A
(c) Expected time of both activities A and B are same
(d) Data too inadequate to compute expected times of activities

MPPSC AE 2014

Ans. (c)
(1) Activity A,

$$\left.\begin{aligned} t_o &= 4 \\ t_m &= 6 \\ t_p &= 8 \end{aligned}\right\} \text{weeks}$$

$$t_{e_A} = \frac{t_o + 4t_m + t_p}{6} = \frac{4 + 4(6) + 8}{6} = 6$$

(2) Activity B,

$$\left.\begin{aligned} t_o &= 5 \\ t_m &= 5.5 \\ t_p &= 9 \end{aligned}\right\} \text{weeks}$$

$$t_{e_B} = \frac{t_o + 4t_m + t_p}{6}$$

$$= \frac{5 + 4(5.5) + 9}{6} = 6$$

$t_{e_B} = 6$

$\therefore \boxed{t_{e_A} = t_{e_B} = 6}$

107. Mobilization advance up to certain percentage of cost of work is given to a contractor
(a) On commencement of work at site for payment of loan taken by him
(b) For the purchase of construction materials
(c) For the payment of advances to labour and other staff
(d) For all activities required to start the work at site on finalization of the contract documents

MPPSC AE 2014

Ans. (d) : In mobilization advance up to certain percentage of cost of work is given to a contractor for all activities required to start the work at site on finalization of the contract document.

Search on Telegram @apna_pdf

108. In the context of planning and scheduling of activities in project management, consider the following statements:
Statement–1: In the PERT formulation, the completion time of activities is assumed to follow a Gamma distribution
Statement -2 : The forward pass gives an estimate of the earliest time when an activity can be started.
Which of the following is CORRECT?
(a) Statement–1 is TRUE and Statement–2 is FALSE
(b) Both statements are FALSE
(c) Both statements are TRUE
(d) Statement–1 is False and Statement–2 is TRUE

UPPCL AE 2018

Ans. (d) Statement I : In the PERT formation, the completion time of activities is assumed to follow Beta distribution.
Statement II : The forward pass gives an estimate of the earliest time when an activity can be started.

109. The following table gives the data on four activities A, B, C, D, E of a project.

Activity	(Stat-End) week number	Resource needed/week
A	4-7	4
B	6-13	7
C	8-17	5
D	12-19	4
E	10-21	8

Find the maximum total resources load in any week, and the corresponding week :
(a) 24 ; (12-13) week (b) 24 ; (14-15) week
(c) 20 ; (12-13) week (d) 28 ; (11-12) week

CIL MT 2020
BHEL ET 2019

Ans. (a) :

110. Which of the following is the limitation (shortcoming) in the critical chain project management?
(a) Investment and work-in-progress are minimized.
(b) Promoters of CPM maintain that application of CPM has resulted in early completion of some projects.
(c) Executive have an effective tool in the form of a buffer for making decision.
(d) The basic assumption that all resources shall be in position for starting for an activity and there will be no other bottleneck.

DMRC AM 2020

Ans. (d) : All the resources shall not be in position for starting of an activity and there will be no other bottleneck. This statement is wrong.

111. Select the correct statement from the following:
(a) The duration between the earliest start time of the preceding event and latest finish time of the succeeding activity is called 'free float'
(b) The duration of time by which an activity can be delayed without affecting the succeeding activity is called 'free float'
(c) The float which affects neither the processor nor the successor activities is called 'independent float'
(d) The difference between total float and free float is called 'interfering float'
(e) All of the above options

Haryana PSE AE Paper-2 2018

Ans. (e) : All the above statement is the basic definition of float and it's different types.

112. If t is the duration of an activity, t_1 is the latest finish possible moment of its preceding activity and t_2 is the earliest start possible moment, the independent float of the activity is:
(a) $(t_1 - t_2) - t$ (b) $t - (t_1 - t_2)$
(c) $(t_1 - t_2) + t$ (d) $(t_1 + t_2) - t$
(e) $t + (t_1 - t_2)$

Haryana PSE AE Paper-2 2018

Ans. (a) : Total float $(F_T) = T_L^i - T_E^i - t_{ij}$
Effect both Predecessor and Successor Activity
→ Free float $(F_T) = T_E^i - T_E^i - t_{ij}$
• Effect any Processor activity
→ Independent float $(F_{ID}) = T_E^i - T_L^i - t_{ij}$
→ Interfering float
$(F_{IN}) = T_L^j - T_E^i$ → [Total float – Free float]

113. In critical path network, which of the following are involved?
1. A series of interconnected activities
2. Considerations for uncertainties in time estimate
3. A logical sequence of activities is provided
4. The node number at the arrow head is numerically smaller than that at tail end
(a) 1 and 2 (b) 2 and 3
(c) 3 and 4 (d) 1 and 3

Haryana PSC AE 2017

Ans. (d) : Uncertainties is not considered in time estimate.
The node number at arrow head is numerically greater than that at tail end because the time in chart move from left to right.

114. Consider the following statements pertaining to CPM network analysis:
1. It is event - oriented method
2. It is activity oriented method
3. Time and cost are controlling factors
4. Time alone is controlling factor
Which of these statements are correct?
(a) 1 and 2 (b) 2 and 3
(c) 3 and 4 (d) 1 and 4

Haryana PSC AE 2017

Ans. (b) : CPM is activity oriented and PERT is event oriented.

Search on Telegram @apna_pdf

115. The profits and associated probability of making the profits are given below in respect of four projects:

Project	Profit	Probability of making the profit
1	15%	0.5
2	10%	0.8
3	12%	0.7
4	11%	0.6

When the motive is maximum of expected profit, the correct order of preference of these projects would be:

(a) 1, 3, 4, 2 (b) 2, 3, 4, 1
(c) 3, 2, 1, 4 (d) 3, 4, 2, 1

Haryana PSC AE 2017

Ans. (c) :

116. Casual Labour Roll (CLR) is used for

(a) emergency work (b) regular work
(c) both (a) & (b) (d) none of these

TNPSC AE 2012

Ans. (a) :

117. The contractor's ledger is maintained in the

(a) section office (b) Division office
(c) Sub-division (d) Circle office

TNPSC AE 2012

Ans. (b)

118. Optimum duration of project corresponds to which of the following?

(a) Direct project cost
(b) Indirect project cost
(c) Crash project cost
(d) Total project cost

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (d) Total Project cost means the expected aggregate project costs, including for the avoidance of double cost incurred for operation and maintenance expenses and mobilization costs during the construction period.

119. As per Indian arbitration act 1996 the number of arbitrators should be appointed for arbitration is:

(a) 3 (b) 2
(c) 5 (d) 4

IRCON AE 2017

Ans. (a) : Arbitration is the reference of dispute between not less than two parties, determination, after hearing both sides in a judicial manner, by a person or persons other than a court of competent jurisdiction. As per Indian Arbitration, no. of arbitration is 60.

120. Latest start of a activity is always

(a) greater than or equal to latest event time of preceding node
(b) less than or equal to latest event time of preceding node
(c) equal to latest event time of preceding node
(d) less than latest event time of preceding node

WBPSC AE 2016

Ans. (a) :

121. One of the main disadvantages of the bar chart for construction management is-

(a) The time schedule is not shown properly
(b) Progress of the work cannot be monitored
(c) The financial aspect is not shown
(d) Does not show the interdependencies of the activity

OPSC AEE 2015 PAPER–I

Ans. (d) : A bar chart shows progress of activities with time but fails to depict interdependencies between various activities.

2. PERT & CPM

122. Independent float is an amount of time by which the start of an activity may be delayed without affecting.

1. the preceding of the following activity
2. the start of a following activity
3. the completion of the project

(a) 1 only (b) 2 only
(c) 3 only (d) 1, 2 and 3

ESE 2020

Ans. (d) : **Independent Float–** The maximum amount of time an activity can be delayed without delaying the early start of the succeeding activities and without being affected by the allowable delay of the preceding activities.

Thus, independent float can be calculated as–

Independent float = Total float – Tail event slack

In case negative value is obtained, it is taken as zero.

123. The PERT calculations yield a project length of 50 weeks, with a variance of 9. Within how many weeks would you expect the project to be completed with probability of 95%, take probability factor Z equal to 0.65 for 95% probability :

(a) 54.95 (b) 56.6
(c) 60 (d) 70

OPSC AEE 2019 Paper–I

Ans. (a) Given $\sigma^2 = 9$, so $\sigma = 3$

$$\frac{T_1 - T_s}{\sigma} = z, \quad \frac{T - 50}{3} = 1.65$$


$T_{95\%} = 54.95$ weeks.

124. The duration of an activity *i – j* is 8. The (EPO)*j* is 18. The EST is 5. What is the Free float of *i -j*

(a) 5 (b) 13
(c) 10 (d) 8

APPSC AE 2016 (Mains)

Ans. (a) :



$F_F = T_{EJ} - T_{Ei} - T_{ij}$
$= 18 - 5 - 8 = 5$ days

125. If the values of t_o, t_p of an activity are 4 and 15, what is the variance of the activity?

(a) 3.22 (b) 3.36
(c) 3.87 (d) 3.92

APPSC AE 2016 (Mains)

Search on Telegram @apna_pdf

Ans. (b) : Given as,

$$\sigma^2 = \left(\frac{t_p - t_o}{6}\right) = \left(\frac{15-4}{6}\right)^2 = 3.36$$

126. In time estimates PERT follows

(a) Probabilistic approach
(b) Deterministic approach
(c) Possibility approach
(d) Non-Probabilistic approach

APPSC AE 2016 (Mains)

Ans. (a) : In PERT projects have no previous record of times estimate and hence these are non-deterministic in nature. Hence PERT follow probabilistic approach.

127. In the context of construction management, PERT stands for :

DMRC AM 2020

OR

The full form of PERT method of project network analysis is:

GPSC AE January 2018

OR

PERT stands for

(a) Programme evaluation and research technique
(b) Programme examination and review technique
(c) Programme examination and research technique
(d) Programme evaluation and review technique

DMRC AM 2020
WBPSC Poly Lect. 2019
ISRO Scientist/Engineer 2019
Maharashtra PSC Mains 2018 Paper-1
APPSC AE 2016 (Mains)
TNPSC AE 2012

Ans. (d) : PERT – Programme Evaluation and Review Technique.

128. Critical Path Method (CPM) network is-

(a) Activity oriented
(b) Event oriented
(c) Both activity as well as event oriented
(d) None of these

OPSC AEE 2015 PAPER–I
GPSC R&B AE 2016
Maharashtra PSC AE (Mains) 2012 Paper–I

Ans. (a) : CPM networks is activity oriented whereas PERT network is event oriented.

129. In a CPM network latest finish time for an event I is 8 weeks. Activity I-J takes 4 weeks for completion. Even J starts after 12 weeks. Float for activity I-J is :

(a) 4 weeks (b) 8 weeks
(c) 12 weeks (d) 0 weeks

Rajasthan JEN (Degree) Shift - II 2016


Ans. (d) : Float for activity I-J is
= 12 – (8+4)
= 0 weeks

130. There are three parallel paths in a part of a network between a bursting node and the next merging node with only one activity in each path. The minimum number of dummy arrows needed will be-

(a) Zero (b) 1
(c) 2 (d) 3

OPSC AEE 2019 Paper–I
MPPSC AE 2017

Ans. (c) : Certain activities that neither consume time nor resources, but are used simply to represent a connection or a link between events are known as dummies.



2 dummy arrows to correctly represent the networks

131. Slack in a PERT network refers to :

(a) Activity (b) Event
(c) Dummy Activity (d) None of the above

Rajasthan JEN (Degree) Shift - II 2016

Ans. (a) Slack in a PERT network refers to Activity.

132. Which one of the following is a point in time when certain conditions have been fulfilled, such as the start or completion of one or more activities ?

(a) Activity (b) Network
(c) Event (d) Node

Karnataka PSC AE 2017 Paper - II

Ans. (c) : An event occurs at a point in time (it has no duration), something starts, finishes or occur.
An activity takes time and consumes resources (e.g. time, material etc.)

133. Which one of the following does have some limitations when applied to detailed engineering design work during early stages of a project ?

(a) CPM (b) PERT
(c) Dummy activity (d) Estimate

Karnataka PSC AE 2017 Paper - II

Ans. (a) Critical path method (CPM) have some limitations when applied to detailed engineering design work during early stages of project.

134. The optimistic, most likely and pessimistic estimates for an activity are 4 days, 11 days and 12 days respectively. The expected completion time of this activity is :

(a) 9 days (b) 10 days
(c) 11 days (d) 12 days

JPSC AE (Pre) 2019
Karnataka PSC AE 2017 Paper - II
ESE 1997

Ans. (b) : $t_e = \frac{t_o + 4t_m + t_p}{6}$

$= \frac{4 + 4\times 11 + 12}{6} = 10\text{days}$


135. In PERT analysis, the time estimates of activities and probability of their occurrence follow :

Search on Telegram @apna_pdf

(a) Normal distribution curve
(b) Poisson's distribution curve
(c) Beta distribution curve
(d) None of the above

JPSC AE (Pre) 2019
Nagaland PSC CTSE 2017 Paper–I
Karnataka PSC AE 2017 Paper - II
WBPSC AE 2016 / MPPSC AE 2014
APPSC AEE 2012 / U.K. Combined A.E. Paper II 2012
UPPSC State Eng. A.E. 2011 / JPSC AE 2009
UPPSC State Eng. A.E. 2007(II)
ESE 2020, 2001, 2010, 2011, 2012, 2014

Ans. (c)



Frequency distribution curve

In PERT analysis, the time estimates of activities and probability of their occurrence follow beta distribution curve but the project as a whole follows normal distribution curve since all the activities combined together cancel out the skewedness.

136. In PERT analysis, event means :
(a) start or finish of a task
(b) time taken for a task
(c) end of an activity
(d) work involved in the project

Karnataka PSC AE 2015 Paper - II

Ans. (a) : In PERT analysis–
- An event is either the start or completion of an activity.
- An event represents a note worthy, significant and recognizable point in the project.
- Event acts as control points in a project.
- An event is an accomplishment occurring at an instantaneous point in time, but requiring no time or resources itself.

137. Duration along the critical path defines which of the following ?
A. Shortest duration needed
B. Shortest duration permissible
C. Longest duration needed
D. Longest duration permissible
Select the code for the correct answer from the options given below :
(a) A and B only (b) A and D only
(c) B and C only (d) C and D only

Karnataka PSC AE 2017 Paper - II
ESE 2007

Ans. (b) : Critical path is shortest duration needed and longest duration permissible. Critical path method does not take resources limitations into account.

138. Match List-I with List-II and select correct answer:

List-I	List-II
A. Earliest start time of successor activity minus earliest duration of activity	1. Total float
B. Time available for an activity performance minus duration of the activity	2. Free float
C. Excess of minimum available time over the required activity duration.	3. Interfering float
D. Difference between total and free float of activity	4. Independent float

	A	B	C	D
(a)	1	2	3	4
(b)	1	2	4	3
(c)	2	1	3	4
(d)	2	1	4	3

TNPSC AE 2018

Ans. (d) : Total float:- It is time in excess of maximum available time over the activity time.
Free float:- It is the excess of available time over the activity time when all job start as early as possible.
Independent float:- Independent float of an activity is the excess of minimum available time over activity time.
Interfering float:- It is difference between total float and free float.

139. Slack time in PERT analysis
(a) can never be greater than zero
(b) is always zero for critical activities
(c) can never be less than zero
(d) is minimum for critical events

GPSC AE (CLASS 1 & 2) 2019
***ESE 2016 /* TSGENCO_2015**
Punjab PSC Sub divisional Engineer 2014

Ans. (d) : Slack can be positive, zero or negative, depend upon the relation b/w latest event time (T_L) and earliest event time (T_E)
1. Positive slack ($T_L > T_E$)-It is indication of an ahead of schedule condition (excess resources).
2. Zero slack ($T_L = T_E$)-It is an indication of a schedule condition (adequate resources).
3. Negative slack ($T_L < T_E$)-When the scheduled time of completion, T_s (and here (T_L)) is less than T_E. It is an indication of a behind of schedule condition (lack of resources).
• A critical path is one which connects the events having zero or minimum slack time.

140. Consider the following statements of network
1. Only one time estimate is required for each activity.
2. Three time estimator for each activity.
3. Time and cost are both controlling factors.
4. It is built-up event oriented diagram.

Search on Telegram @apna_pdf

Which of the above statements are correctly applicable to CPM network?

(a) 1 and 3 (b) 1 and 2
(c) 2 and 4 (d) 3 and 4

TNPSC AE 2018

Ans. (a) :
- CPM is an activity oriented diagram where PERT is event oriented diagram.
- One time estimate is required in CPM. Three time estimate are required in PERT network.

141. Which of the following data(s) is/are required for updating of plan at intermediate stage of execution of project?

(i) Original network with calculation chart
(ii) Point of data for updating
(iii) New information and knowledge which will affect the duration time of the activities to be performed.

(a) (i) and (ii) (b) (i) and (iii)
(c) Only (iii) (d) (i), (ii) and (iii)

GPSC AE (CLASS 1 & 2) 2019

Ans : (d) : For updating-
(i) Original network with network chart
(ii) New information & knowledge which will affects new activities
(iii) Point of data for updating

142. In a CPM network latest finish time for an event I is 10 weeks. Activity i-j takes 4 weeks for completion. Event J starts after 16 weeks. Float for activity i-j is :

(a) 6 weeks (b) 10 weeks
(c) 12 weeks (d) 2 weeks

Rajasthan JEn (Degree) 2016


Ans. (d) : Float for activity I-J is = 16– (10+4)
= 2 Weeks

143. A critical path has:

(a) Zero slack (b) Minimum slack
(c) Maximum slack (d) Infinite slack

(UKPSC AE paper II 2016, 2013)
(U.K. Combined A E Paper II 2012/

Ans : (a) Critical path sequence of activities which decide the total project duration. It is formed by critical activities. A critical path consumes maximum resources. It is the longest path and consumes maximum time. A critical path has zero float or slack.



1-2-4-5 is the critical path.

144. The following is not a PERT event :

(a) Site investigation started
(b) Sessional work completed
(c) Bus started from Lucknow
(d) The class is being attended

[UPPSC State Eng. A.E. 2003]

Ans : (d) Attending class is a repetitive type of work hence it would be CPM activity.

145. The completion of an activity in PERT techniques is called :

(a) Head activity (b) Head event
(c) Dual role event (d) Tail event

OPSC Civil Services Pre 2011
UPPSC State Eng. A.E. 2007(I)

Ans. (b) Head event – Head event slack of an activity in a network is the slack at the head (or terminal point) of an activity.

146. Which of the following networks is activity oriented?

Maharashtra PSC Mains 2018 Paper-1

OR

The technique which is activity oriented is :

(a) PERT
(b) CPM
(c) CPM and PERT both
(d) Neither CPM nor PERT

UPPSC State Eng. A.E. 2003, 2008

Ans : (b) Critical path method (CPM) is activity oriented whereas PERT is event oriented.

PERT	CPM
1. It is basically analytic in concept and deals with probabilistic network.	It is basically synthesizing in concept and deals with deterministic network.
2. Three time estimates for activities linking two events.	Only one time estimate for activities.
3. It is an event oriented diagram.	It is an activity oriented diagram.
4. Times are not related to cost.	Times are related to cost.

147. In PERT analysis, the probability of completion of any activity within its expected time is :

(a) 50% (b) 100%
(c) 75% (d) 99.9%

OPSC AEE 2019 Paper–I
UPPSC State Eng. A.E. 2003

Ans : (a) In PERT analysis the probability of completion of any activity within its expected time is 50% whereas in CPM it is 100%

148. In PERT analysis of a project having large number of activities in its critical path, which of the following assumption is correct?

(a) Both activity durations and project completion time follow β– distribution/
(b) Both activity durations and project completion time follow normal distribution
(c) Activity duration follow Normal–distribution, but project completion time follow β–distribution
(d) Activity duration follow β–distribution, but project completion time follows normal distribution

[MPPSC AE 2016]

Search on Telegram @apna_pdf

Ans : (d) PERT analysis is based on probabilistic approach, hence it can skew to left or right making the activities follow β-distribution but if the activities are combined, then the whole project follows normal distribution.

149. Which of the following is true for Project evaluation and review technique (PERT)?

(a) It is event oriented and is a tool for planning
(b) It is activity oriented and extensively used in construction
(c) It uses cost as a critical input factor
(d) It minimizes the importance of events
(e) The events in such a network do not fall in logical sequence

CGPSC AE 2014 Shift–I

Ans. (a) : PERT stands for programme evaluation and review technique.

- It is event oriented
- It is a tool for planning.
- There time estimates are made.
- Based on probabilistic approach.
- Cost is directly proportional time hence minimum cost will be achieved C/S to minimum completion time.
- Suitable for new type of project. (which not happened earlier)

150. The management techniques that are more suitable for application in a construction project are

(a) PERT (b) CPM
(c) both PERT and CPM (d) none of these

TNPSC AE 2012

Ans. (b) : The management techniques that are more suitable for application in a construction project is CPM because CPM is used in projects which happened earlier.

151. Dummy activity means

(a) neither requires any time nor any resources
(b) a connecting link for control purposes
(c) for maintaining uniqueness of activity
(d) all the these

TNPSC AE 2012

Ans. (d) Dummy activity :

- It is a type of activity in the network which neither consumes any time nor recourse.
- It is an artificial activity.
- It is represented by dashed arrow and identified by the terminal node or event which it connects.
- It maintains logic of network diagram.
- It maintains uniqueness of activity.
- It act as a connecting link for control purpose.

152. The optimistic time, pessimistic time and most likely time required for completion of an activity is 4, 8 and 6 days respectively. The variance of time estimate is

(a) 0.4356 (b) 0.450
(c) 0.400 (d) 0.500

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (a) Standard deviation

$$\sigma = \left(\frac{t_p - t_0}{\sigma}\right)$$

Given,
$t_p = 8$ days
$t_0 = 4$ days
$t_m = 6$ days

$$\sigma\left(\frac{8-4}{6}\right) = 0.66$$

Variance is the square of standard deviation
So variance $= (0.66)^2 = 0.44$
Most suitable option is (a).

153. The optimistic time, pessimistic time and most likely time required for completion of activity is 4, 11 and 6 days respectively. The expected time is

(a) 5 days (b) 6 days
(c) 5.5 days (d) 6.5 days

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (d) Given,
$t_p = 11$ days
$t_0 = 4$ days
$t_m = 6$ days

$$\text{Expected time } (t_E) = \frac{t_0 + 4t_m + t_p}{6}$$

$$t_E = \frac{4 + 4\times 6 + 11}{6} = 6.6 \text{ days}$$

154. For which of the following purposes can be Geographic Information System not be used?

(a) Development of public infrastructure facilities
(b) Deforestation
(c) Disaster and business continuity planning
(d) Studying the relative motion of planets

CIL MT 2017

Ans. (d) : Application of GIS:

- Management of resources
- Investigations of the earth's surface that is scientific in nature.
- Archeological uses.
- Planning of locations and management of assets
- Urban and regional planning
- Criminology matters
- Development of public infrastructure facilities
- Study of deforestation
- Disaster and business continuity planning

155. The path along the activities having total float zero is known as _____.

(a) Special path (b) Balanced path
(c) Direct path (d) Critical path

LMRC AM 2019

Ans. (d) Critical path is the path along the activities having total float zero.

156. Which one of the following is associated with a critical activity in a A-O-A network ?

(a) Maximum float (b) Minimum float
(c) Zero float (d) Free float

Nagaland PSC CTSE 2017 Paper–I

Search on Telegram @apna_pdf

Ans. (c) : Zero float is a condition where there is no excess time between Activities. An Activity with Zero Float is considered a critical Activity.

157. Select the incorrect statement

(a) A critical path always beings at the very first event
(b) A critical path always terminates at the last event
(c) Critical activities control the project duration
(d) Critical activity is the one for which free float is zero

Nagaland PSC CTSE 2017 Paper–I

Ans. (d) : In CPM analysis critical path is determined with the help of float approach critical path is the path along which total float of the Activities is zero.

158. Number of pre-operation associated with an operation may be :

(a) Only one (b) two only
(c) More than one (d) Three only

Nagaland PSC CTSE 2017 Paper–I

Ans. (c) : Number of Pre-operation associated with an operation may be more than one.

159. The post-operation in CPM are marked

(a) Right to an operation (b) At the end
(c) Left to an operation (d) In the middle

Nagaland PSC CTSE 2017 Paper–I

Ans. (a) : The Post-operation in CPM are marked Right to an operation.

160. 'Wait' in PERT, belong to the category of :

(a) Activity (b) Node
(c) Event (d) Motion

Nagaland PSC CTSE 2017 Paper–I

Ans. (a) Activity– It is a Resource consuming element of a project.

161. Which of the following is a PERT event ?

(a) Transport of sand
(b) Transport of cement
(c) Concreting of roof completed
(d) Making of form work continues

`Nagaland PSC CTSE 2017 Paper–I

Ans. (c) Event – It is a instant of time or state at which some specified milestone is Achieved in the project i.e. concreting of Roof completed. (As PERT is event oriented)

162. Critical path

(a) Is the shortest path
(b) Had 'null' slack
(c) Had the maximum slack
(d) Had the minimum slack

Nagaland PSC CTSE 2017 Paper–I

Ans. (d) : Critical path : The time wise longest path is called critical path, in this path any type of delay in any event will cause delay to the project. These are shown by double line or dark line in a network.
→ An event is critical if its slack is zero.

163. Work study comprises

(a) Motion study
(b) Work measurement
(c) Probabilistic analysis
(d) Method study and work measurement

Nagaland PSC CTSE 2017 Paper–I

Ans. (d) Work study comprises main technique of method study and work measurement.

164. The amount of time by which the start of the activity may be delayed without interfering with the start of any succeeding activity is called

(a) Activity float (b) Free float
(c) Total float (d) Interfering float

ESE 2017, 2019

Ans. (b)

- Free float is the amount of time an activity can be delayed without delaying the early start of its successor activity.
  It is the spare time allowable for an activity so that the start time of succeeding activities are not affected.
  It is based on the possibility that all events occur at their earliest time.
- Total float it is the total free time for an activity i.e. maximum time by which completion of an activity can be delayed without affecting project completion time.

165. Consider the following statement associated with critical path:

1. Critical path is the most important sequence of activities which has no float and which determine the project completion period
2. Critical path is the largest path with shortest duration which the project can be completed
3. The difference between early time and late finish time must be equal to the activity duration
4. Cannot pass through dummy activity

Which is among the above are correct statements?

(a) 1, 2 and 4 (b) 1, 2 and 3
(c) 1, 3 and 4 (d) 1, 2, 3 and 4

ISRO Scientist/Engineer 2020

Ans. (b) :
1. Critical path is the most important sequence of activities which has no float and which determine the project completion period
2. Critical path is the largest path with shortest duration which the project can be completed
3. The difference between early time and late finish time must be equal to the activity duration
4. Cannot pass through dummy activity
5. Critical path can pass through dummy activity.

166. An activity in a project management network is

(a) The beginning or end of a specified job
(b) An element of work entailed in the project
(c) Represented by a circle in a network with a number in it
(d) The progress of work up to a certain limit

ISRO Scientist/Engineer 2017

Ans : (b) An activity in a project management network is an element of work entailed in the project.

Search on Telegram @apna_pdf

167. Which of the following techniques belong to 'Project Time Plan'?

1. Critical path method
2. Precedence network analysis
3. Line of balance technique
4. Linear programme chart

(a) 1, 2 and 3 only (b) 1, 2 and 4 only
(c) 3 and 4 only (d) 1, 2, 3 and 4

ESE 2019

Ans. (a)Techniques for project time plan are–

- Critical path method is used for preparing maintenance shutdown and schedule.
- The longest path in CPM network is called critical path.
- Line of Balance scheduling technique it is a planning technique for repetitive work. It is very powerful and easy to use process when the conditions are ideal for this type of work.
- Precedence network analysis but Linear programme chart is used for profit maximization; cost minimization and resources allocation.

168. The PERT is.....approach.

(a) deterministic
(b) optimistic
(c) probabilistic
(d) pessimistic

AP (VSS-1) PART - A 2017

Ans : (c) The PERT is probabilistic approach.

169. A dummy activity is required when

(a) two or more activities having different ending events
(b) two or more activities having the same starting events
(c) the network contains two or more activities that have identical starting and ending events
(d) two or more activities having the same ending events

AP (VSS-1) PART - A 2017

Ans : (c) Dummy activity :

- It is a type of activity in the network which neither consumes any time nor recourse.
- It is an artificial activity.
- It is represented by dashed arrow and identified by the terminal node or event which it connects.
- It maintains logic of network diagram.
- It maintains uniqueness of activity.
- It act as a connecting link for control purpose.
- The network contains two or more activities that have identical starting and ending events.

170. Which one of the following is not valid for CPM?

(a) Activities are represented by arrows.
(b) Emphasis is given to activities.
(c) The beginning and end of an activity is denoted by nodes.
(d) Uncertainties are allowed to exist.

AP (VSS-1) PART - A 2017

Ans : (d) Uncertainties are not allowed to exist in CPM.

171. Consider the following activity for the total project :


Activity	Immediate Predecessors	Duration (Days)
A	–	10
B	–	9
C	A	9
D	A	8
E	B	7
F	B	11
G	D, E	5

The total project duration for the critical path will be :

(a) 25 days (b) 23 days
(c) 21 days (d) 19 days

ESE 2020

Ans. (b)



Path	Duration
A – C	19 hours
A – D – G	23 hours
B – E – G	21 hours
B – F	20 hours

Hence, critical path is A – D – G and project duration is 23 hours.

172. Which of the following statements are correct for Network Critical Path ?

1. **The path of critical activities, which links the start and end events is critical path.**
2. **It is the path of activities having zero float.**
3. **It is the path of events having zero slack**
4. **The sum of the duration of the critical activities along a critical path gives the duration of the project**

(a) 1, 2, 3 and 4 (b) 1, 2 and 3 only
(c) 1 and 4 only (d) 2, 3 and 4 only

ESE 2020

Ans. (a) : Following are some properties of Network Critical Path–

(i) The path of critical activities, which links the start and end events is critical path.
(ii) It is the path of activity having zero float.
(iii) It is the path of event having zero slack.
(iv) The sum of the duration of the critical activities along a critical path gives the duration of the project.

173. Which of the following sentences is correct?

(a) Except initial and end events, all events in the network are dual role events.
(b) All events in the network are dual role events.
(c) There is only one dual role event in the network.
(d) None of the above

Maharashtra PSC Mains 2018 Paper-1

Search on Telegram @apna_pdf

Ans. (a) : Events with dual function i.e. as head event to some activity and as tail events to some activities are known as dual role events. All events except initial and final events are dual roll events.

174. What is dummy activity?

(a) Activity having zero duration
(b) Activity shown by dotted line
(c) Activity which shows dependency
(d) All of the above

Maharashtra PSC Mains 2018 Paper-1

Ans. (d) : Dummy activity:
- The activity which neither uses any resources nor any time for its completion.
- It is represented by dotted arrow or line.
- It is use to identify a dependency among operations.

175. The time required to complete an activity under abnormal or extremely adverse conditions in which everything goes wrong is called

(a) optimistic time (b) most likely time
(c) pessimistic time (d) None of the above

Maharashtra PSC Mains 2018 Paper-1

Ans. (c) To take uncertainties into account, PERT network uses three types of time estimates.
(1) **Optimistic time (t_o) :** Shortest time for an activity, if everything goes well.
(2) **Pessimistic time (t_P) :** Longest time, if everything goes wrong. (Doesn't include catastrophic effect like earth quake, floods, labour strike, fire etc.
(3) **Most likely time (t_l) :** Normal time, if normal conditions prevail.

176. The excess of minimum available time over activity duration is called

(a) total float (b) free float
(c) independent float (d) None of the above

Maharashtra PSC Mains 2018 Paper-1


Ans. (c) : The independent float time of an activity is the amount of float time which can be used without affecting either the head or the tail events. It represents the amount of float time available for an activity when its preceeding activities are completed at their latest and its succeeding activities being at their earliest time - leaving the minimum time available for its performance.

177. The difference between EST of succeeding activity and EFT of the activity under consideration is called

(a) Total float (b) Independent float
(c) Interfering float (d) Free float

Maharashtra PSC Mains 2018 Paper-1

Ans. (d) :



Free float = $E_j - E_i - t_{ij}$

178. In PERT, the critical path represents the

(a) shortest path for the earliest completion of project
(b) the longest path of the network from the initial to the final event
(c) the ideal path by proceeding along which the project can be completed as per schedule
(d) the path which takes into account the completion of the parallel activities

GPSC AE March 2018

Ans. (b) : Critical path-Critical path represents the longest path of the network from the initial event to the final event.
Critical path consist of only critical activities.

179. The probability distribution taken to represent the completion time in PERT analysis is

(a) gamma distribution
(b) normal distribution
(c) beta distribution
(d) log-normal distribution

GPSC AE March 2018

Ans. (c) : PERT analysis usually follow β-distribution curve.




Figure : Left skew β-distribution curve.

t_e = expected time or completion time

$$t_e = \frac{t_o + 4t_m + t_p}{6}$$

180. Program evaluation and review technique is used when

(a) Repetitive type of work exists
(b) Time estimation is uncertain
(c) Cost optimization is of prime importance
(d) Time estimation is very easy

GPSC Poly. Tech. Lect. 2016
Maharashtra PSC AE (Mains) 2012 Paper–I

Ans. (b) : PERT is a visual tool used in project planning. It is used when technique time estimate is uncertain time period. Using the technique helps project planners identify start and end dates, as well as interim required tasks and time lines.
PERT is used when time estimation is uncertain. ex.: Research and development programmes.

181. P.E.R.T. is an …… technique

(a) Activity oriented
(b) Event oriented
(c) Both A and B
(d) None of the above

GPSC Poly. Tech. Lect. 2016

Search on Telegram @apna_pdf

Ans. (b) : PERT or programme evaluation and review technique is an event oriented method of network planning. In it, the emphasis is focused on start and completion of events rather than on activities. In PERT network, the event fall in logical sequence.

182. Cost slope of the direct cost curve is given by

GPSC AE March 2018

OR

A critical path method (CPM), cost slope is determined by:

(a) $\frac{(\text{Crash cost} - \text{Normal cost})}{\text{Crash time}}$


(b) $\frac{(\text{Crash cost})}{(\text{Normal time} - \text{Crash time})}$

(c) $\frac{(\text{Crash cost} - \text{Normal cost})}{\text{Normal time}}$

(d) $\frac{(\text{Crash cost} - \text{Normal cost})}{(\text{Normal time} - \text{Crash time})}$

OPSC AEE 2019 Paper–I
GPSC R&B AE 2016
ESE 2001

Ans. (d) : The term cost slope in CPM is defined as 'the increase in cost of the activity per unit decrease in time.'



$$Slope = \tan\theta = \frac{AB}{AC}$$

$$\text{Cost slope} = \frac{\text{Crash cost} - \text{Normal cost}}{\text{Normal time} - \text{Crash time}}$$

$$m_C = \frac{C_C - N_C}{T_N - T_C}$$

183. Pick up the correct statement from the following:

(a) CPM analysis is activity oriented
(b) PERT analysis is event oriented
(c) CPM does not make any allowance for the uncertainties in the duration of time
(d) All the above

GOA PSC Assistant Prof. 2020

Ans. (a) : (1) CPM analysis is activity oriented.
(2) PERT analysis is event oriented.
(3) CPM does not make any allowance for the uncertainties in the duration of time.

184. Critical path connects the events that have :

(a) Negative slack (b) Positive slack
(c) Zero slack (d) High slack

OPSC Civil Services Pre 2011

Ans. (c) : Critical path connects the events which has zero slack or zero float.

185. An activity that shows dependency consumes no time or resources is called?

(a) Critical (b) Dummy
(c) Event (d) Float

OPSC Civil Services Pre 2011

Ans. (b) : Dummy activity – A dummy activity is a simulated activity of sorts, one that is of a zero duration and consumes no resources called dummy activity.

186. The waiting time required between activities is known as :

(a) Slack (b) Float
(c) Lag (d) Free float

OPSC Civil Services Pre 2011

Ans. (c) : Lag is the delay of a successor activity and represents time that must pass before the second activity can begin. There are no resources associated with a lag.

187. An activity is

(a) The movement of heavy vehicles from one place to another
(b) An element of work entailed in the project
(c) The beginning or the end of a specified job
(d) The progress of work up to a certain limit

Punjab PSC SDE 2016

Ans. (b) : The processes in a project consuming time or resource is called as activity.

188. PERT technique of network analysis in mainly useful for:

(a) Small projects
(b) Large and complex projects
(c) Research and development project
(d) Deterministic activities

APPSC AEE 2012
UJVNL AE 2012

Ans. (c) : PERT technique of network analysis is mainly useful for research and development projects. It is based on probabilistic approach.

189. Consider the following pairs :

i. Difference between total float and free float = interfering float
ii. Sum of independent float and tail slack = Free float
iii. Sum of independent float, tail slack and interfering float = Total float

Which of the following pairs are correctly matched?

(a) i, ii and iii (b) i and ii
(c) i and iii (d) ii and iii

GPSC AE June 2019

Ans. (a) : Total float – free float = Interfering float
Independent float + tail slack = Free float
Independent float + tail slack + interfering float = total float

190. Read the following statements carefully

(i) PERT network is event oriented and CPM network is activity oriented
(ii) In CPM times are related to costs

(a) Both (i) and (ii) are correct

Search on Telegram @apna_pdf

(b) Both (i) and (ii) are wrong
(c) Only (i) is correct
(d) Only (ii) is correct

GPSC Assistant Prof. 2016

Ans. (a) •PERT network is even oriented and CPM network is activity oriented.
•In CPM times are related of cost.

191. The time estimates obtained from four contractors, A, B, C and D for excavating same size of pit are a under :

Contractor	Optimistic Time (t_0)	Most Likely Time (t_L)	Pessimistic Time (t_p)
A	5	10	13
B	6	10	12
C	5	10	14
D	4	10	13

Which one of the contractors is more certain about completing job in time?
(a) A (b) B
(c) C (d) D

GPSC AE June 2019

Ans. (b) : For more certain about completing job in time the contractor must have lowest variance.
Variance is given as the square of standard deviation(σ) and:

$$\sigma = \frac{T_P - T_0}{6}$$

for contractor A,

$$\sigma = \frac{13-5}{6} = 1.33$$

Variance = 1.77
for contractor B,

$$\sigma = \frac{12-6}{6} = 1$$

Variance = 1
for contractor C,

$$\sigma = \frac{14-5}{6} = 1.5$$

Variance = 2.25
for contractor D,

$$\sigma = \frac{13-4}{6} = 1.5$$

Variance = 2.25
so, contractor B is more certain about completing job on time.

192. Slack time is PERT analysis:
(a) Can never be greater than zero
(b) Is always zero for critical activity
(c) Can never be less than zero
(d) Is minimum for critical event

PTCUL AE 2016

Ans. (d) : For critical event slack will be minimum or zero.

193. The PERT network analysis is a ..... based method
(a) activity, research and development projects
(b) event, construction projects
(c) event, research and development projects
(d) activity, construction projects


GPSC AE January 2018

Ans. (c) : PERT is an event oriented technique used for research and development project. It is a probabilistic model.

194. In CPM and PERT methods activities are connected with each other in.....
(a) finish-to-start manner
(b) overlapping manner
(c) partially finish-to-start and partially overlapping manner
(d) random manner

GPSC AE January 2018

Ans. (a) :



A PERT and CPM project are clearly identified activities whose accomplishment results in project completion. Once started activities continues without means they may be started, stopped and performed independently in a prescribed manner.

195. Precedence Network Analysis (PNA) method of network analysis better addresses the real life situation in a construction project than CPM because
(a) it is very precise
(b) it is independence of activities
(c) it does not allow overlapping of activities
(d) it allows overlapping of activities

GPSC AE January 2018

Ans. (d) : The precedence network analysis (PNA) presents a better appearance than CPM.
In PNA activities are generally arranged in rows. CPM contains arrow and dummy arrows. Overlapping of activities is allowed in PNA, not in CPM.

196. The full form of acronym CPM is:
(a) Construction Project Method
(b) Critical Project Method
(c) Critical Path Method
(d) Critical Program Method

GPSC AE January 2018

Ans. (c) : Critical Path Method (CPM) is an algorithm for scheduling a set of project activities. It is commonly used in conjunction with PERT.

197. The CPM network analysis is a ..... base method useful for .....
(a) activity, research and development projects
(b) event, construction projects
(c) event, research and development projects
(d) activity, construction projects

GPSC AE January 2018

Ans. (d) : The CPM network analysis is a activity based method.
This method is useful for construction projects.


198. Positive float for any activity means that the activity is
(a) Supercritical (b) Sub critical
(c) Critical (d) None of these

Punjab PSC SDE 2016

Search on Telegram @apna_pdf

Ans. (b) :
- Activity for which total float is positive is known as sub-critical activity.
- Activity for which total float is zero is known as critical activity.
- Activity for which total float is negative is known as super critical activity.

199. The given figures shows the arrow diagram for a particular project. The arrow A is known as





(a) Critical activity (b) Logic arrow
(c) Dummy activity (d) Sub critical activity


UPRVUNL AE 2015


Ans. (d) : Sub critical activity the second longest path in the network.
- It is shorter than the critical path all activity on sub critical path are not critical.
- Some of the activity may be critical.

200. A burst event is represented by

(a)



(b)


(c)


(d)


MPPSC AE 2014

Ans. (b) Burst Event- when more than one activity leaves an event then such an event is known as burst event.



201. In a PERT formulation, the Optimistic, Most likely and the Pessimistic times for the completion of an activity in a project are known to be 6, 12 and 24 weeks.
Which of the following statements is TRUE?

(a) The Expected time (in weeks) of completion of the activity, and the standard deviation (in weeks) 12 and 3, respectively.
(b) The Expected time (in weeks) of completion of the activity, and the standard deviation (in weeks) 13 and 4, respectively.
(c) The Expected time (in weeks) of completion of the activity, and the standard deviation (in weeks) 12 and 4, respectively
(d) The Expected time (in weeks) of completion of the activity, and the standard deviation (in weeks) 13 and 3, respectively.

UPPCL AE 2018

Ans. (d) : Given,
optimistic time = 6 weeks
most likely time = 12 weeks
pessimistic time = 24 weeks

$$\text{Expected time} = \frac{6+4\times12+24}{6}$$

$$= \frac{78}{6} = 13 \text{ week}$$

$$\text{Standard deviation} = = \frac{24-6}{6} = 3 \text{ weeks}$$

202. It is noted that casting a 'column starter' takes not less than 6 minutes and takes sometimes as long as 45 minutes. But 15 minutes is more frequent. If casting period is considered an activity in a PERT network, what will be the expected time.

(a) 15 minutes (b) 11.0 minutes
(c) 30.25 minutes (d) 18.5 minutes

UPPCL AE 2019

Ans. (d)
Optimistic time = t_0 = 6 minutes
Most likely time = t_m =15 minutes
Pessimistic time = t_p = 45 minutes

$$t_e = \frac{t_o + 4t_m + t_p}{6}$$

$$= \frac{6+4\times15+45}{6} = \frac{111}{6}$$

$$\boxed{t_e = 18.5 \text{ minutes}}$$

203. In network techniques of construction management, optimistic time, pessimistic time and most likely time are the types of time estimates under which of the following?

(a) CPM (b) Activity
(c) PERT (d) Event

LMRC AM 2018

Ans. (c) : PERT (programme Evaluation and Review Technique) technique is used for scheduling and controlling. The projects whose activity posses considerable degree of uncertainty in their performance time. It has following three time estimates for each activity of the network –
(i) Optimistic time estimate (t_0)
(ii) Pessimistic time estimate (t_p)
(iii) Most likely time estimate (t_m)

Search on Telegram @apna_pdf

204. Calculate the expected time for the given activity, where t_0 = 22 days, t_m = 30 days, t_p = 50 days.

(a) 32 days (b) 34 days
(c) 36 days (d) 12 days

LMRC AM 2018

Ans. (a) : expected time $T = \frac{(t_o + t_p + 4t_m)}{6}$

$= \frac{(22 + 50 + 4 \times 30)}{6} = \frac{192}{6} = 32$ day

205. While doing the project planning of a Construction project, using PERT, it is intended to identify the variance of the project. This can be done by:

(a) Sum of variance of the activities along critical path of the project
(b) Sum of squares of the total floats of all activities in the project
(c) Sum of variance of all activities of the project
(d) Sum of squares of free floats of all activities along the critical path of the in the

CIL MT 2020

Ans. (a) : During the project planning of a Construction project, using PERT, it is intended to identify the variance of the project. This can be done by the sum of squares of the total floats of all activities in the project

206. The optimistic time, the most likely time and the pessimistic time estimates in a network are 4, 6 and 14 months. The expected time is -

(a) 7 months (b) 8 months
(c) 9 months (d) 10 months

Rajasthan VP ITI 2018

Ans. (a) : Given that,
t_0 = 4 months
t_p = 14 months
t_m = 6 months

$t_E = \frac{t_0 + 4t_m + t_p}{6} = \frac{4 + 4 \times 6 + 14}{6} = 7$ months

207. Critical Path Method (CPM):

(a) Is an improvement upon bar chart method
(b) Provides a realistic approach to daily problems
(c) Avoids delays which are very common in bar charts
(d) Was invented by Morgan R. Walker of DuPont and James E. Kelley Jr. of Remington Rand in the USA in 1957
(e) All of the above options

Haryana PSE AE Paper-2 2018

Ans. (e) : Critical Path Method –
- Method developed in 1950s to control large defence and technology projects.
- It is a method to control costs and time for a construction project.
- It helps in easy scheduling, planning, organizing and controlling various repetitive type of works.

208. Choose the statement which is correct:

(a) PERT is event oriented
(b) PERT is not event oriented
(c) CPM is event oriented
(d) CPM is not event oriented

RRB SSE Bilaspur : 21.12.2014

Ans : (a) PERT is event oriented while CPM is activity oriented.

209. In PERT technique, the critical path has slack equal to

(a) Always zero (b) Positive value
(c) Negative value (d) Zero or negative value

WBPSC AE 2012, 2007

Ans. (a) :

210. Which of the following statements is/are correct for a non-critical activity?

1. It demands very special attention and action.
2. One can do with normal attention to this activity with some leeway for action.

Select the *correct* answer using the codes given below:

(a) 1 only (b) 2 only
(c) Both 1 and 2 (d) Neither 1 nor 2

ESE 2017

Ans. (b)
- Non-critical activities or work items that have positive float. (i.e. within defined limits, can take longer to complete than is planned without affecting the total project duration.)
- Non-critical activity can be carried out with normal attention. Whereas critical activity must be carried out with special attention.

3. Crashing of Network, Resource Allocation & CPM Updating

211. Updating may result:

(a) change of critical path.
(b) decrease in project completion time.
(c) increase in project completion time.
(d) All of the above

WBPSC Poly Lect. 2019

Ans. (d) : →Updating is done whenever there is a major change in the duration of any of the activity.
→ Critical path may change during updating which may result in increase or decrease in project completion time.

212. A project with the production cost of ₹ 100 crore, has 20,000 man-months as direct labour, of which 60% is non-productive time. The labour cost as estimated while tendering is 20% of project cost. If 15% of the wastage resulting from non-productive time is eliminated by using improved methods, the resulting saving in labour cost will be

(a) 14.5% (b) 18.5%
(c) 22.5% (d) 26.5%

ESE 2019

Search on Telegram @apna_pdf

Ans. (c) : Production Cost = Rs. 100 crores
Labour cost = 20% of project cost.
Labour cost = 0.2 × 100
Labour cost = 20 crores
Non-productive labour time at 60% of labour cost = 0.6 × 20 = 12 crores.
Productive time cost = 0.4 × 20 = 8 crores.
Non-productive time = 0.15×12 = 1.8 crores.
Saving as per percentage of productive work value

$$= \frac{\text{Nonproductive time cost}}{\text{Prdocutive time cost}} \times 100$$


$$= \frac{1.8}{8} \times 100 = 22.5$$

% of savings = 22.5%

213. Consider the following data:
Work is carried out by a contractor employing labour with 25% overtime per day
Working for 5 days a week
Contractor peak manpower is 40 per day
Build-up period is 20%
Rundown period is 10%
Total effort in standard man days is 1200
The duration of work by Trapezoidal manpower distribution pattern will be
(a) 5.5 weeks (b) 6.5 weeks
(c) 7.5 weeks (d) 8.5 weeks

ESE 2019

Ans. (a) : By Trapezoidal Manpower Distribution Pattern–



Average number of worker/day = $A_1+A_2+A_3$

$$= \frac{1}{2} \times 0.2 \times 40 + \frac{5}{7} \times 40 + \frac{1}{2} \times 0.1 \times 40$$

= 4 + 28 + 2
[No. of workers = 34]
working time/week = overtime × Number of working days. = 1.25 × 5 = 6.25
[Working time = 6.25 day]
Number of man days available = 6.25 × 34 = 212.5
Number of man days required = 1200
Number of weeks required = $\frac{1200}{212.5} = 5.64$
[Duration or number of week required ≅ 5.5 weeks]

214. A crew consisting of two carpenters and one helper can fix 10 m^2 of a slab form work in 8 hours and the hourly labour rate of a carpenter is ₹ 85 and for a helper is ₹ 69.50. An average hourly rate per worker of the crew will be nearly
(a) ₹ 90 (b) ₹ 80
(c) ₹ 70 (d) ₹ 60

ESE 2019

Ans. (b)
Crew : – 2 Carpenters
1 Helper
Hourly labour rate of carpenter = Rs. 85
and for Helper = Rs. 69.50
So, Hourly rate of crew = (2×85+69.5) = Rs. 239.5
Average hourly rate per worker = $\frac{239.5}{3}$ = Rs. 79.83
[Average hourly rate per worker ≅ Rs. 80]

215. Resource smoothing will be adopted when
(a) resources are unlimited
(b) resources are limited
(c) resources are constant
(d) in all the cases

APPSC AE 2016 (Mains)

Ans. (a) : Resource smoothing is used when the time constraint takes priority. The objective is to complete the work by the required time through the resources demand. In resource smoothing project duration does not change and the critical path remains unchanged.

216. Injury frequency rate per lakh of man-hours worked is calculated as-
(a) $\frac{\text{No. of days lost} \times 1,00,000}{\text{No. of man - hours worked}}$
(b) $\frac{\text{No. of disabling injuries} \times 1,00,000}{\text{Total No. of man - hours worked}}$
(c) $\frac{\text{Injury frequency rate} \times \text{Injury service rate}}{1000}$
(d) $\frac{\text{No. of disabling injuries}}{\text{Total No. of man - hours worked}} \times 100$

Maharashtra PSC (Mains) 2015 Paper–I
APPSC AE 2016 (Mains)

Ans. (b) : Injury frequency rate per lakh of man hours worked.

$$= \left(\frac{\text{No. of disabling injuries}}{\text{Total no. of man hour's worked}} \right) \times 100000$$

217. The process of incorporating changes and rescheduling or re-planning is called:
(a) resource levelling
(b) resource smoothing
(c) updating
(d) critical path scheduling

Gujarat PSC AE 2017
U.K. Combined A E Paper II 2012
ESE 2006

Ans : (c) The process of incorporating changes and rescheduling or re-planning is called updating.

218. In resource levelling :
(a) total duration of project in reduced
(b) total duration of project is increased
(c) uniform demand of resources is achieved
(d) cost of project is controlled

UPPSC State Eng. A.E. 2003
Punjab PSC Sub divisional Engineer 2014
ESE 1995

Search on Telegram @apna_pdf

Ans : (b) In the resource levelling process activities are rescheduled such that maximum demand of resources requirement does not exceed the limit of availability of resources.
During this process at first re-arrangement of activities having floats is done. Even if by doing so, resource requirement is more than availability of resources, then duration of some activities is increased such that resource requirement of these activities is reduced. Hence project duration might get increased during the process of resource levelling.

219. The type of float which give an idea about the excess time that exists if the preceding activity ends as late as possible and the succeeding activity starts as early as possible.
(a) Total float (b) Free float
(c) Independent float (d) Slack

GUJRAT PSC AE - II 2017

Ans : (b) Free float is defined as the amount of time by which on activity can be delayed without affecting the early start time of succeeding activity. In other words it is that portion of total float that can be used by an activity without delaying any succeeding activity.

220. The difference between the time available to do a job and the time required to do the job, is known as -
(a) Event (b) Float
(c) Duration (d) Constraint

Rajasthan VP ITI 2018
TNPSC AE 2012

Ans. (b) : Float indicates the time by which starting or finishing of an activity can be delayed without affecting the project completion time. Float is associated with an activity and is analogous to the term slack (in PERT).
Float is of four type –
(i) Total float (ii) Free float (iii) Independent float (iv) interfering float.
The difference between the time available to do a job and the time required to do the job, is known as total float.

221. The sequence to be followed while developing the network diagram is
A. defining objectives
B. sequencing the activities
C. breaking down the structure
D. developing the relation between events
(a) A, C, B, D (b) A, B, C, D
(c) A, D, C, B (d) C, A, B, D

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (a) The sequence which should be followed while developing the network diagram is as follows –
i) Define the objective
ii) Break down the structure of activities
iii) Put activities in proper sequence
iv) Develop the relation between activities.
So, the correct answer is (a).

222. The short coming of bar chart is
(a) lack of degree of details
(b) activity inter-relationship
(c) does not show progress of work
(d) All the above

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (d) The short coming or limitation of bar chart is as follows –
i) Lack of degree of detail
ii) It does not show project progress
iii) Activity inter-relationship
iv) Time uncertainties
v) Does not indicate critical activities of project
vi) No cost optimization

223. In construction project planning, free float can effect which of the following?
(a) Only that particular activity
(b) Succeeding activity
(c) Preceding activity
(d) Overall completion

CIL MT 2017

Ans. (a) Free float is defined as the amount of time by which on activity can be delayed without affecting the early start time of succeeding activity. In other words it is that portion of total float that can be used by an activity without delaying any succeeding activity. So, as per definition, the free float can effect only that particular activity.

224. 'Float' which does not interfere with the start of the subsequent activity in a project is :
(a) Total float (b) Independent float
(c) Free float (d) Interfering float

KPSC AE 2020

Ans. (c) : Free float does not interfere with the start of the subsequent activity in a project.
*** Total float (F_T) :** The time span by which starting or finishing of an activity can be delayed without delaying the completion of the project.

$$F_T = LST - EST$$

LST = latest start time
EST = earliest start time
*** Free float :** The delay which can be made without delaying succeeding activities it affects preceding activities.

$$F_F = F_T - S_J$$

F_T = Total float
S_J = head event slack

225. The time corresponding to minimum total project cost is :
(a) Crash time
(b) Normal time
(c) Optimistic time
(d) B/w normal time and crash time

Nagaland PSC CTSE 2017 Paper–I

Ans. (d) : The time corresponding to minimum total project cost is between normal time and crash time.

226. Time estimated time required to complete an activity is termed as :
(a) Event (b) Duration
(c) Active time (d) Float

Nagaland PSC CTSE 2017 Paper–I

Ans. (b) Duration – Time estimated time required to complete an activity is known as duration.

Search on Telegram @apna_pdf

227. An event is :

(a) A definite job
(b) A definite time interval
(c) The terminals of an activity
(d) A definite position of an activity

Nagaland PSC CTSE 2017 Paper–I

Ans. (b) Event– It is a instant of time or state at which some specified mile stone is achieved in the project. Ex- Completion of preceding activity (activities) or start of succeeding activity (activities).

228. The graphical representations wherein long duration jobs are broken down to key segmental elements, wherein events are shown in chronological order without attention to logical sequencing, and wherein interdependencies between the events is not highlighted, is referred to as

(a) CPM (b) Milestone chart
(c) GANTT chart (d) PERT

ESE 2019

Ans. (b) : Milestone chart is a graphical representation of a project in which the project activities are identified by horizontal bars. The long duration activity that can be divided into key segmental element. Events are known as milestones which show the occurrence as well as completion of a particular segment. Milestones are generally used to indicate important dates on the project plan, often key events or goals.

229. On a construction project, the contractor, on an average, employed 100 workers with 50 hours working per week. The project lasted for 35 weeks and, during this period, 14 disabling injuries occurred. The injury-frequency rate will be (based on one lakh of man hours worked)

(a) 5 (b) 6
(c) 7 (d) 8

ESE 2019, 2010

Ans. (d)

Number of workers/week = 100
Working hours/week = 50
Project Duration = 35 weeks
Number of Injuries = 14

So, Total Working Hours = $35 \times 50 \times 100$


Total Working Hours = 175000 hours

$$\text{Injury frequency rate (lakhs)} = \frac{\text{Number of Injuries}}{\text{Man hours in lakh}}$$

$$= \frac{14}{\frac{175000}{100000}} \text{ lakhs}$$

Injury Frequency rate=8

230. Consider the following assembly with different operations:




Operation	Standard time minutes
A	60
B	65
C	29
D	37
E	28
F	63
G	36
H	126
K	64

There are 250 working days in a year to produce 4000 units in a year. The minimum number of work stations required will be

(a) 13 (b) 12
(c) 11 (d) 10

ESE 2019

Ans. (a)



Path	Duration
■ A–B–D–G–H–K	60+65+37+36+126+64 = 388
■ A–C–F–H–K	60+29+63+126+64 = 343
■ A–C–E–G–H–K	60+29+28+36+126+64 = 342

So, the maximum duration or time required to complete one product = 388 min.

Total time required to produce 4000 units = 4000 × 388 = 15,52,000 min.

Available time = 250×8×60

= 12,0000 min. (Assuming 8 hrs work/day)

$$\text{Minimum number of work station} = \frac{\text{Total time required}}{\text{Available time}}$$

Number of working station required to manufacture 4000 units in a year will be

$$= \frac{15,52000}{120,000} = 12.93$$

Minimum work stations = 13

231. Statement (I): A Dummy is an activity in the network.
Statement (II): A Dummy is a representation in the network requiring neither time nor resources.

(a) Both Statements-I and Statement-II are individually true and Statement-II is the correct explanation of Statement-I.
(b) Both Statements-I and Statement-II are individually true but Statement-II is NOT the correct explanation of Statement-I
(c) Statement-I is true but Statement-II is false.
(d) Statement-I is false but Statement-II is true.

ESE 2018

Ans. (d) A Dummy is not an activity, it is just a representation in the network requires neither time nor resources. It is just use to complete the network.
Hence, Statement–I is wrong and Statement-II is correct.

Search on Telegram @apna_pdf

232. Consider the following statements regarding quality control:

1. It refers to absolute conformity to specifications
2. It may not vouch against overspending.
3. It may unknowingly resort to overdesign in the hope of risk minimization.
4. It is intended to reduce maintenance costs.

Which of the above statements are *correct*?

(a) 1 and 3 only (b) 2 and 3 only
(c) 2 and 4 only (d) 1 and 4 only

ESE 2017

Ans. (d)

- Quality control is meant for conforming the design specifications and reducing maintenance costs.
- Increase in sales of the product is the main objectives of quality control system.
- Quality control is an important technique in the hands of management to maintain the quality of the product.

233. Statement (I): Hiring and firing is a poor substitute for proper selection and proper training of labourers.
Statement (II): Bad training facilities for new employees cause them to be discharged during or at the end of the probationary period.

(a) Both Statements-I and Statement-II are individually true and Statement-II is the correct explanation of Statement-I.
(b) Both Statements-I and Statement-II are individually true but Statement-II is NOT the correct explanation of Statement-I
(c) Statement-I is true but Statement-II is false.
(d) Statement-I is false but Statement-II is true.

ESE 2017

Ans. (b)

- The primary rationale for instituting a probationary period is to have the ability to fire the employee for any or for no reason. Once the probationary period has ended, an employee can only be fired for cause.
- Hiring is defined as the addition of workers to provide services for a company while firing is defined as the reduction of workers that have not properly provided services for a company.

234. For an activity normal and crash durations are 4 and 2 weeks respectively. The normal and crash costs are Rs. 4000 and Rs. 12000 respectively. The cost slope will be:

(a) Rs. 2000 per week (b) Rs. 4000 per week
(c) Rs. 6000 per week (d) Rs. 8000 per week

WBPSC Poly Lect. 2019

Ans. (b) :

$$\text{Cost slope} = \frac{C_c - C_t}{N_t - N_c}$$

$N_t = 4$
$N_c = 2$
$C_c = 12000$
$C_t = 4000$

N_t = Normal time
N_c = Crashing time
C_t = cost of activity in N_t
C_c = Cost of activity in N_c

$$\text{Cost slope} = \frac{12000 - 4000}{4 - 2} = \frac{8000}{2} = 4000$$

Cost slope = 4000 per week.

235. By performing which of the following functions the construction manager can achieve the project goals ?

1. **Envisioning the task ahead**
2. **Setting targets and monitoring performance**
3. **Motivating the work force**
4. **Building the line supervisors team**

(a) 1, 2 and 4 only (b) 1, 2 and 3 only
(c) 1, 3 and 4 only (d) 1, 2 , 3 and 4

ESE 2020

Ans. (d) : The construction manager can play the most vital lead role in achieving the project goals by performing the following functions effectively and efficiently, these functions are –


- Envisioning the task ahead.
- Enabling the individuals to perform the task systematically and efficiently.
- Setting targets and monitoring performance.
- Providing resources support.
- Implementing a sound incentive scheme.
- Communicating feed back.
- Motivating the work force.
- Building the line supervisors team.
- Creating safe working environments.
- Abiding by professional ethics.
- Leadership makes all the difference.

236. Which one of the following techniques is not covered in Project Network Analysis ?

(a) Critical Path Method
(b) Program Evaluation and Review Techniques
(c) Procedure Network Analysis
(d) Measurement Book

ESE 2020

Ans. (d)



- Measurement of all works and supplies are recorded in a special type of note book called Measurement Book (M.B.).

237. In the time-cost optimization using CPM, the crashing of the activities along the critical path is done starting with the activity having

Search on Telegram @apna_pdf

(a) least cost slope (b) highest cost slope
(c) least time slope (d) highest time slope

OPSC AEE 2019 Paper–I
TNPSC AE 2018
GPSC AE March 2018
ESE 1998

Ans. (a) : In time cost optimisation using CPM, the crashing of the activities along the critical path is done starting with activity having least cost slope.

$$\text{Cost slope} = \frac{C_c - C_N}{T_N - T_c}$$

238. The optimistic, most likely and pessimistic time estimates of an activity are 5, 10, 21 days. What is the expected time and standard deviation

(a) 12, 3 (b) 11, 4
(c) 11, 2.67 (d) 10, 16

GPSC AE March 2018

Ans. (c) : $t_o = 5$ days, $t_m = 10$ days, $t_p = 21$ days

(1) Expected time $(t_e) = \frac{t_o + 4t_m + t_p}{6}$

$$= \frac{5 + 4 \times 10 + 21}{6} = 11 \text{ days}$$

(2) Standard deviation $(\sigma) = \frac{t_p - t_o}{6}$

$$= \frac{21 - 5}{6} = 2.67 \text{ days}$$

239. Slack is given as the difference between

(a) latest allowable time and earliest expected time
(b) latest allowable time and pessimistic time estimate
(c) earliest expected time and latest allowable time
(d) final event time and initial event time

GPSC AE March 2018

Ans. (a) : Slack– Slack of any event is defined as the difference between the latest allowable occurrence time and earliest expected occurrence time of an event.

$$\boxed{S = T_L - T_E}$$

(i) S > 0 → Positive slack → condition of excess resources deployed.
(ii) S = 0 → Resources deployed are adequate or just enough.
(iii) S < 0 → Negative slack → Resources deployed are not adequate enough.

240. In project management, an important principle in drawing a network is

(a) no activity can start until all the previous activities in the same chain are completed
(b) parallel activities should begin and end at the same time
(c) between two events there should not be more than two activities
(d) the number of dummy activities in a network should not exceed four

GPSC AE March 2018

Ans. (a) : Principle of drawing a network-
(1) A network will have only one initial node.
(2) A network will have only one final node.
(3) No activity can start until all previous activities in same chain are completed.
(4) No event can occur twice.
(5) Arrows should be straight line, curved arrows should be avoided.

241. The constraints in case of resource smoothing operation would be :

(a) resources
(b) project duration time
(c) both resources and project duration time
(d) none of the above

Punjab MCP SDO 2015

Ans. (b) : The constraints in case of resource smoothing operation would be project duration time.

242. The time of completion of an activity which can not be reduced further irrespective of cost considerations is :

(a) Crash time (b) Normal time
(c) Slack time (d) Float time

OPSC Civil Services Pre 2011

Ans. (a) : The time of completion of an activity which can not be reduced further irrespective of cost considerations is crash time.

243. The cost of labour in a construction activity is :

(a) Fixed cost (b) Marginal cost
(c) Variable cost (d) Sunk cost

OPSC Civil Services Pre 2011

Ans. (c) Fixed cost – Insurance, rent, CEO salary, materials etc.
Variable costs – Construction labour, fuel cost, supplies etc.

244. The flow of time in a network is generally

(a) From right to left (b) From left to right
(c) Both ways (d) Not important

Punjab PSC SDE 2016

Ans. (b) : Flow of time in a network is from left to right because it add ups the time duration of all previous activity in sequential manner.

245. PERT analysis is based on:

(a) Optimistic time (b) Pessimistic time
(c) Most likely time (d) All of the above

UJVNL AE 2012

Ans. (d) : Part analysis is based on optimistic time, pessimistic time and most likely time.

246. Which one of the following statements is correct for every activity in a network?

(a) Interference float can never be negative
(b) Interference float can exceed free float
(c) Total float can exceed free float
(d) Interference float and independent float may be equal to each other in magnitude

GPSC AE Dec 2018

Search on Telegram @apna_pdf

Ans. (a & c) : Free float (F_F) is the portion of total float (F_T) that can be used by an activity without delaying any succeeding activity.

So, $\boxed{F_F > F_T}$

Interfering float is defined as difference of total float & free float of an activity. As total float can not exceed free float, so interfering float can never be -ve.

Option (a) & (c) both are correct.

247. Mile stone chart is an improvement over

(a) Bar chart (b) CPM scheduling
(c) PERT scheduling (d) OPST scheduling

GPSC AE Dec 2018

Ans. (a) : Mile stone chart is an improvement over bar chart.

In milestone chart, we can represent the milestone by symbol so that it can be understood that some milestone is achieved.

248. Match the Items in List 1 (description of planning) with those in List 2 (Type of development) and choose the best answer using the codes.

List 1	List 2
A. Development occurring in vacant or underused lots in otherwise built up areas.	1. Planned unit development
B. Developing a large area as single entity merging zoning and subdivision control.	2. Infill development
C. Development with compatible land uses integrating varied activities at different times of the day	3. Transit oriented development
D. Development located within walking distance from mass transit stations along the corridor	4. Mixed use development

(a) A-4, B–1, C–2, D–3
(b) A–2, B–1, C–4, D–3
(c) A–2, B–4, C–1, D–3
(d) A–3, B–2, C–1, D–4

BHEL ET 2019

Ans. (b) : A–2, B–1, C–4, D–3

249. If a is the optimistic time, b is the pessimistic time and m is most likely time of an activity, the expected time of the activity, is

(a) (a+m+b)/6 (b) (a+2m+b)/6
(c) (a+4m+b)/6 (d) (a+5m+b)/6

APPSC AEE 2016
ESE 2006

Ans. (c) We know,

$$\text{Expected time } (t_e) = \frac{t_o + 4t_m + t_p}{6}$$

t_o = optimistic time (i.e, a)
t_m = most likely time (i.e, m)
t_p = pessimistic time (i.e, b)

So correct answer is $= \frac{a + 4m + b}{6}$

250. Milestones in a bridge construction project are: (i) compaction; (ii) concreting; (iii) leveling.

(a) (i) and (ii) (b) (ii) and (iii)
(c) (i), (ii) and (iii) (d) (i) and (iii)
(e) None of the above options

Haryana PSE AE Paper-2 2018

Ans. (e) • Milestone are tools used in project management to mark specific points.
• These points indicate start and end date of specific works
• Milestones are task with zero duration.

251. For a distribution which is symmetrical about mean the skewness coefficient is

(a) Positive (b) Negative
(c) Zero
(d) Sometimes positive and sometimes negative

WBPSC AE 2012

Ans. (c) :

252. Negative slack occurs

(a) When latest allowable time is greater than earliest expected time
(b) When events stick to their schedule
(c) When deficiency of resource exist
(d) None of the above

WBPSC AE 2012

Ans. (c) :

253. The balance sheet is -

(a) a summary of what company owns and what the company owes
(b) the evaluations of effective cash flow characteristics of a project
(c) the cost for mobilization and demobilization of personnel, equipment, temporary facilities & other facilities
(d) performing cost optimization

Rajasthan VP ITI 2018

Ans. (a) A balance sheet is financial statement that reports a company's assets, liabilities and shareholder's equity at a specific point in time. It shows, what company owns and what company owes.

254. If an activity has its optimistic, most likely and pessimistic times us 2, 3 and 7 respectively, the expected time and variance are

(a) 3.5 and $\frac{5}{6}$ (b) 5 and $\frac{25}{36}$
(c) 5 and $\frac{5}{6}$ (d) 3.5 and $\frac{25}{36}$

WBPSC AE 2012

Ans. (d) :

Search on Telegram @apna_pdf

255. Critical path is PERT network is the one for which

(a) Most likely time estimate of the activities is the largest
(b) Optimistic time estimate of the activities is the largest
(c) Expected time estimate of the activities is the largest
(d) Pessimistic time estimate of the activities is the largest

WBPSC AE 2001

Ans. (c) :

256. Select the correct statement

(a) Activity arrows in a CPM network are drawn to scale
(b) The trail of an arrow represents the finish of an activity
(c) Arrow head represents the start of an activity
(d) none of the above

Chandigarh SDE 2017

Ans. (d) :

257. A bar chart is drawn for

(a) time versus activity
(b) activity versus resources
(c) resources versus progress
(d) progress versus time

Chandigarh SDE 2017

Ans. (a) :

4. Engineering Economy

258. With the usual notations, capital recovery factor is given by

(a) $\left(\frac{i(1+i)^n}{(1+i)^n-1}\right)$ (b) $\left(\frac{i}{(1+i)^n-1}\right)$

(c) $\frac{i}{(1+i)^n}$ (d) $(1+i)^n$

MPPSC AE 2014

Ans. (a)

$$\text{Capital recovery factor} = \frac{i(1+i)^n}{(1+i)^n-1}$$

Where,
i = Annual interest rate
n = number of annual return period

259. A structural steel building under construction is hit by a truck, the action that will be caused can be called as

(a) Permanent action (b) Variable action
(c) Accidental action (d) No action

UPRVUNL AE 2016

Ans.: (c) A structural steel building under construction is hit by a truck, the action that will be caused can be called as accidental action.

260. Indirect cost due to accidents includes :

(a) Legal charges
(b) Medical expenses for the injured
(c) Compensation amount to the injured
(d) Over time payment to make up the loss of time

ESE 2020

Ans. (d) : Cost of an accident includes direct cost and indirect cost.
Direct cost includes worker's compensation payment, medical expenses and legal services.
Indirect cost includes–

- Training and replacement of employees.
- Accident investigations.
- Implementation of corrective measure.
- Lost productivity.
- Repairs of damaged equipment and property.
- Cost of absenteeism.

261. A contract is an agreement between-

(a) Two parties valid in law
(b) Several agencies
(c) Three agencies
(d) Two parties without legal binding

OPSC AEE 2015 PAPER–I


Ans. (a) : A contract is an agreement between two parties enforced by law. It has some terms and conditions.

262. ABC analysis is referred to as-

(a) Always Better Control analysis
(b) Alphabetical Backup Control analysis
(c) Analytical Boost Crane analysis
(d) None of the above

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (a) For selective inventory control three classes of materials have been found to be convenient. This is known in general as the ABC classification. The alphabets A, B & C stands for the three different classes and it is popularly known as Always Better Control.



263. The security deposit deducted from contractor's bill is-

(a) Refunded as soon as the construction is over
(b) Not refunded
(c) Refunded in the middle of the contract
(d) Refunded after maintenance period

OPSC AEE 2015 PAPER–I

Ans. (d) The security deposit shall be collected by deduction from each running bill of the contractor it is 5% of the Gross amount of the Bill.

264. The reduction in project time normally results in-


(a) Increasing the direct cost and decreasing the indirect cost
(b) Decreasing the direct cost and increasing the indirect cost

Search on Telegram @apna_pdf

(c) Increasing the direct cost and the indirect cost both
(d) Decreasing the direct cost and the indirect cost both

GUJRAT PSC AE - II 2017
OPSC AEE 2015 PAPER–I
MPPSC AE 2014

Ans. (a) The reduction in project time normally results in increasing the direct cost and decreasing the indirect cost.



265. Which of the following is a "Class-A" item in ABC analysis?
(a) items with low cost but large in number
(b) items with average cost but moderate in number
(c) Items with high cost but few in number
(d) Items with high cost but large in number

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (c) Item A : In ABC of inventory control, items categorized under A are goods that register the highest value in terms of annual consumption. It is interesting to note that the top 70-80% of the yearly consumption value comes from about 10-20% of total inventory.

266. The application of human biological science along with engineering sciences for achieving the optimum level of adjustment between man and his work is known as _____.
(a) Ergonomics
(b) Economics
(c) Ecology
(d) Engineering Science and Economics

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (a) : Ergonomics is the study of person's efficiency in their working environment.

267. What are the advantages of a good site layout or job layout?
(a) Smooth and economical working of project
(b) It reduces the completion time of project
(c) Provides more safety on site
(d) All the above

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (d) : A good site layout :
1. Reduces labour cost
2. Helps in production control
3. Improves supervision
4. Reduces other manufacturing cost
5. Is beneficial for the workers as it improves safety.

268. Sensitivity analysis is study of-
(a) Comparison of profit and loss
(b) Comparison of assets and liabilities
(c) Change in output due to change in input
(d) Economics of cost and benefits of the project

GPSC AE (CLASS 1 & 2) 2019
MPPSC AE 2017
ESE 1998

Ans. (c) Sensitivity measures how independent variables value will impact a particular dependent value under a given set of assumptions. It basically correlates output change w.r.t. input change.
Sensitivity analysis is a very powerful tool for interacting with simple or complex models.

269. If cost control is neglected in construction management it will resulted in
(a) profit to the owner of the project
(b) increase in the profit margins to the contractor
(c) reduced profit margins to the contractor
(d) no change in profit

TNPSC AE 2018

Ans. (c) When costs control is neglected in construction management it will result in reduced profit margins to the contractor. They are responsible for ensuring that a project remains within budget while meeting its scope, quality and performance requirement.

270. Productivity performance variance is equal to
(a) $\frac{\text{Actual Productivity}}{\text{Planned Productivity}}$
(b) $\frac{\text{Planned Productivity}}{\text{Actual Productivity}}$
(c) Planned productivity minus actual productivity
(d) Actual productivity minus planned productivity

GPSC AE (CLASS 1 & 2) 2019

Ans : (c) :

271. Which of the following is the formula for Economic Order Quantity if M is annual demand, C_o is ordering cost, C_c is inventory carrying cost and S is unit price of an item?
(a) $EOQ = \sqrt{\frac{2MC_o}{SC_c}}$ (b) $EOQ = \sqrt{\frac{MC_oC_c}{2S}}$
(c) $EOQ = \sqrt{\frac{MC_c}{SC_o}}$ (d) $EOQ = \sqrt{\frac{2MS}{C_oC_c}}$

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (a) Economic Order Quantity (EOQ) is the ideal order quantity a company should purchase to minimize inventory costs such as, holding cost shortage cost & order cost. It is given as –

$$EOQ = \sqrt{\frac{2MC_0}{S.C_C}}$$


The EOQ formula is best applied in situation where demand, ordering and holding costs remain constant over time.

272. A delay in completion time of project will increase :
(a) indirect cost (b) direct cost
(c) labour cost (d) fixed cost


UPPSC State Eng. A.E. 2008, 11

Search on Telegram @apna_pdf


Ans : (a)



Indirect Cost : It includes overhead, revenue loss, outage loss, penalty, rent etc. It increase with time.



Direct cost : It include, labour cost, material cost, equipment cost etc. It decrease with increase in time.



A delay in completion time of project will increase indirect cost. Whereas direct cost and labour cost decreases with delay in project completion.


273. In what way does ABC analysis help the manager?

(a) To purchase material at low price
(b) To exercise selection control
(c) To purchase material very fast
(d) To select good quality material

Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (b) For selective inventory control three classes of materials have been found to be convenient. This is known in general as the ABC classification. The alphabets A, B & C stands for the three different classes and it is popularly known as Always Better Control.

It helps to exercise selection control.



274. Which of the statements given below is not correct :

When there is a dispute in a construction site,

(a) The dispute must be submitted initially to the site Engineer for decision, before referring to arbitration
(b) The contractor has to stop the work till the settlement of dispute
(c) All actions related to there should be recorded and referred for future negotiations and agreements
(d) A meeting must be held between the superintendent and union leader

KPSC AE 2020

Ans. (b) When there is a dispute in a construction site.
- The dispute must be submitted initially to the site engineer for decision, before referring to arbitration.
- All actions related to there should be recorded and referred for future negotiation and agreements.
- A meeting must be held between the superintendent and union leader.

275. Which value of asset will fetch more money from market?

(a) Monopoly value (b) Sentimental value
(c) Potential value (d) Distress value

GPSC Poly. Tech. Lect. 2016
Maharashtra PSC Mains 2012 Paper -2

Ans. (b) Sentimental value– It is the value of an object that is derived from personal or emotional association rather than its material worth. It is the inflated opinion value based on what the sellers want. Usually the assets associated with sentiments of buyer fetch more money than usual.

276. Annual income from a property is ₹ 25,000. The capitalized value of this property for a prevailing rate of 12.5% interest is

(a) ₹ 5,00,000 (b) ₹ 2,00,000
(c) ₹ 2,50,000 (d) ₹ 3,12,000

Maharashtra PSC Mains 2012 Paper -2

Ans. (b) : Capitalized value $= \dfrac{\text{Annual Income}}{\text{Rate}}$

$$\text{Capitalized value} = \frac{25000}{\frac{12.5}{100}} = 200000$$

277. The amount of examination of the difference between mutually exclusive alternatives is known as :

(a) Life cycle analysis
(b) Benefit cost analysis
(c) Incremental analysis
(d) Present worth analysis

OPSC Civil Services Pre 2011

Ans. (c) Incremental Analysis – It is a decision making technique used in business to determine the trace cost difference between alternatives also called the relevant cost approach, marginal analysis or differential analysis. Incremental analysis disregards any sunk cost or past cost.

278. Total project cost


(a) Initially reduces and then increases with the increase in time

Search on Telegram @apna_pdf

(b) Increases with the increase in time
(c) Reduces with the increase in time
(d) Initially increases and then reduces with the increase in time

Punjab PSC SDE 2016

Ans. (a) :



Upto certain duration, the cost reduces, then it increases abruptly.

279. A machine costs Rs. 16,000 by constant rate of declining balance method of depreciation, its salvage value after an expected life of 3 years is Rs. 2,000. The rate of depreciation is

(a) 0.25 (b) 0.30
(c) 0.40 (d) 0.50

APPSC AEE 2012
ESE 1999

Ans. (d) : Machine cost = ₹ 16,000
Salvage value = ₹ 2000
time = 3 year

$$\text{Rate of depreciation} = 1 - \sqrt[t]{\frac{\text{salvage value}}{\text{cost}}}$$

$$= 1 - \sqrt[3]{\frac{2000}{16000}}$$

$$= 1 - 0.5$$

Rate of depreciation = 0.5

280. Capital recovery factor at 15% p.a. discrete compounding for 4 years is 0.35. Rs. 10,000 deposited now at 15% p.a. discrete compounding will yield an amount 'X' at the end of each 4 – year – period in perpetuity. The value of 'X' is

(a) Rs. 7,500 (b) Rs. 6,666
(c) Rs. 6,000 (d) Rs. 9,000

APPSC AEE 2012

Ans. (a) : Given,
C.R.F. = 0.35, P = 10,000, i = 0.15
A = 10000 × 0.35 = 3500 Rs.
now,

$$X = A \times (CAF) - P \qquad \text{Given CAF} = \frac{(1+i)^4 - 1}{i}$$

$$= 3500 \times \left[\frac{(1+0.15)^4 - 1}{0.15}\right] - 10000$$

$$= 3500 \times 5 - 10000$$

$$\boxed{X = 7500 \text{ Rs.}}$$

281. The original cost of an equipment is Rs. 10,000. Its salvage value at the end of its total useful life of live years is Rs. 1,000. Its book value at the end of two years of its useful life (as per straight line method of evaluation of depreciation) will be

(a) Rs. 8,800 (b) Rs. 7,600
(c) Rs. 6,400 (d) Rs. 5,000

APPSC AEE 2012
ESE 1995

Ans. (c) : Annual depreciation $= \frac{P - C_s}{n}$

$$= \frac{10000 - 1000}{5} = 1800$$

∴ Book value at the end of two years
$= 10000 - 2 \times 1800 = 6400$

282. A tractor has purchase price of Rs. 4.7 lakhs and could save the organization an amount of Rupees one lakh per year on operating costs. The salvage value after the amortization period is 10% of the purchased price. The capital recovery period will be

(a) 3.7 years (b) 4.2 years
(c) 5 years (d) 7.8 years

APPSC AEE 2012

Ans. (b) : Given:
Purchase price = Rs. 4.7 Lakhs
Save amount = ₹ 1 Lakhs/year on operating cost
Salvage value = 10% purchase price

$$\text{Salvage value} = \frac{10}{100} \times 4.7 \text{ Lakhs}$$

= ₹ 0.47 Lakhs

S = P – (I × T)
47000 = 470000 – (100000×T)
T = 4.23 year

283. Which of the following is not related with the International Federation of Consulting Engineers (FIDIC) form of contract

(a) 1987 Red Book
(b) 1987 Yellow Book
(c) 1990 Blue Book
(d) 2007 Gold Book

GPSC AE June 2019

Ans. (c) International Federation of Consulting Engineers (FIDIC)
1987 Red book - General conditions with forms of tender and agreement.
1987 Yellow book - Conditions of contract for electrical and mechanical works.
2007 Gold book - Bureau of land management
1990 Blue book - It is not related to (FIDIC). It is a used for car prices.

284. If a worker dies while working on a site, under which one of the following laws the compensation is payable?

(a) Factories Act
(b) Provident Fund Act
(c) Workmen's compensation Act

Search on Telegram @apna_pdf

(d) Employees State Insurance Act

GPSC AE January 2018

Ans. (c) Workmen's Compensation Act (1923, Amended 1984) – This act provides social security to the workers. Compensation is to be paid to the workers in case of accidents sustained during the course of employment and the amount is decided upon its seriousness. The dependents are eligible to receive the compensation under this act financial relief is given in the following cases–
i) In case of death.
ii) On account of occupational diseases.

285. Cost–benefit studies are essential to

(a) Assess the total cost of the work
(b) Ascertain the relevant escalation in price
(c) Monitor the expenditure
(d) Evaluate the viability and worthwhileness of taking up the project

MPPSC AE 2014
ESE 1996

Ans. (d) Cost-benefit studies are essentials to evaluate the viability and worthwhileness of taking up to the project.

286. If the expected time for completion of a project is 10 days with a standard deviation of 2 days, the anticipated time of completion of the project with 99.9% probability is

(a) 16 days (b) 12 days
(c) 10 days (d) 6 days

MPPSC AE 2014

Ans. (a)

$$Z = \frac{Ts - 10}{2}$$

For 99.9% probability, probability factor 2 & 3

$$\therefore 3 = \frac{Ts - 10}{2}$$

$$\Rightarrow Ts = 10 + 6$$

$$\boxed{Ts = 16\,days}$$

287. Indirect cost of project is-

(a) project overheads + labour cost + equipment cost
(b) labour cost + sub contractors cost
(c) common workmen cost + contingency
(d) project overheads + common workmen cost

Rajasthan VP ITI 2018

Ans. (d) Indirect Cost (IDC) – These costs are not directly accountable to a cost object. It may be either fixed or variable. It includes administration, personnel and securing costs.
Project overhead and common workman cost comes under Indirect cost.

288. The net installment of periodical payment for repayment of the capital amount invested in a property for a specified period is called as ____.

(a) Amortization (b) Annuity
(c) Mortgage (d) Appreciation

NPCC AE 2017

Ans. (b) : Annuity is a series of payments made at equal intervals.
Annuity can be classified by frequency of payment dates.

289. The Years purchase is :

(a) One divided by interest rate
(b) Multiplied to net rent to get capitalized value
(c) The amount whose annual interest is equal to rupee one
(d) All the above

GPHC AE 2018

Ans : (d) The year purchase is the amount or Sum multiplied to net rent and the amount whose annual budget Interest is equal to one rupee.

5. Engineering Equipments

290. A front-end loader on a given job moves a load of 1.5 m^3 of loose soil in one cycle consisting of loading-lifting-travelling-unloading-return rip-and-ready for next loading. If each cycle time is 1.2 minutes, the actual output will be

(a) 75 m^3/hour (b) 70 m^3/hour
(c) 65 m^3/hour (d) 60 m^3 /hour

ESE 2019

Ans. (a) : Volume of front–end loader bucket capacity (v) = 1.5m^3/cycle.
Cycle time (CT) = 1.2 minutes.
[CT = 1.2 × 60 = 72 sec]

$$\text{Output capacity of loader} = \frac{\text{Volume of bucket} \times 3600}{\text{Cycle time}}$$

$$\text{Output capacity of loader} = \frac{1.5 \times 3600}{72}\ (1\times1)\ (\text{Factor})$$

$$\boxed{\text{Actual Output} = 75 m^3/\text{hour}}$$

291. For excavating utility trenches with precise control of depth, the excavation equipment used is

(a) Hoe (b) Shovel
(c) Dragline (d) Clamshell

GPSC AE June 2019
ESE 1997

Ans. (a) : Hoe is an excavating tool which consists a metal plate attached to a long handle with acute angle. So, hoe is used for excavating trenches with precise control of depth.

292. In an excavation of 3,000 cub.mtr of common earth for a canal project, 6 men can be effectively employed on the job. If an output of a man is taken as 100 cub.mtr per day, the duration of excavation activity will be :

(a) 5 days (b) 6 days
(c) 7 days (d) 8 days

ESE 2020

Ans. (a) : Given,
Output of man = 100 cubic mtr per day
No. of men employed = 6
Output per day = 6 × 100 = 600 cubic mtr per day
So,

$$\text{No. of days} = \frac{3000}{600} = 5\ \text{days}.$$

Search on Telegram @apna_pdf

293. If the failure rate of a machine has been established as 25 failures during every 1,000 hours of operation, the mean time before failure (MTBF) will be :
(a) 40 hours (b) 0.025 hours
(c) 2.5 hours (d) 4 hours
[UPPSC State Eng. A.E. 2007(I)]

Ans : (a) $\text{MTBF} = \frac{1000}{25} = 40 \text{ hr.}$

294. Outriggers are used for
(a) crawler mounted mobile cranes to enhance its stability
(b) wheel mounted mobile cranes to enhance its stability
(c) fixing the lattice boom in a crane
(d) fixing the telescopic boom in a crane
[MPPSC AE 2016]

Ans : (b) Outriggers may be referred to legs on a wheeled vehicle which are folded out when it needs stablization, for example on a crane that lifts heavy loads.

295. Which of the following excavator is most suitable for digging under water?
(a) Drag line (b) Hoe
(c) Calm shell (d) Dipper shovel
Gujarat PSC AE 2017

Ans : (a) By dragline it usually does not need to go into a pit or hole for excavating the earth. It may operate on natural firm ground therefore, It is more useful when the earth is removed from a ditch, canal or pit containing water.

296. The fire safety requirements of the building are designed as per
(a) IS 1645-1960 (b) IS 1256-1967
(c) IS 1647-1961 (d) IS 1646-1960
Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (a)
IS 1645-1960 : Code of practice for fire safety of building (general)
IS 1256-1967 : Code of practice for building byelaw.
IS 1647-1961 : Code of practice for fire safety of building (electrical installation)
IS 1646-1960 : Code of practice for fire safety of building (non-electrical equipment)

297. Which of the following Acts specially covers safety legislation of construction industry in India?
(a) Contract Labour Act
(b) Workmen's Compensation Act
(c) Inter State Migrant Workers Act
(d) There is no safety legislation oriented to construction industry
Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (d) There is no such act exist in Indian which specially covers safety legislation of construction industry.

298. Most of the accidents in construction industry happen due to
(a) lack of education and training
(b) negligence and ignorance
(c) Both (a) and (b)
(d) None of the above
Maharashtra PSC AE (Mains) 2012 Paper–I

Ans : (c) Most of the accidents in construction industry happen due to lack of education and training, negligence and ignorance.

299. A canal is trimmed on its side and bottom by :
(a) Dragline (b) Trimmer
(c) Trencher (d) Angle dozer
Nagaland PSC CTSE 2017 Paper–I

Ans. (b) Trimmer is used to trim a canal on its sides and bottom.

300. Grader is used mainly for
(a) Trimming and finishing
(b) Shaping and trimming
(c) Finishing and shaping
(d) Finishing, shaping and trimming
Nagaland PSC CTSE 2017 Paper–I
Gujarat PSC AE 2017
ESE 1997

Ans. (d) : Grader is a equipment used for :
(A) Levelling (B) shaping (C) finishing
(D) Mixing gravel (E) Flattening & smoothing
(F) Trimming slopes

301. Which one of the following is not an excavating and moving type of equipments ?
(a) Bulldozer (b) Clamshell
(c) Dump truck (d) Scraper
Nagaland PSC CTSE 2017 Paper–I
ESE 1997

Ans. (c) : Excavating and moving types of equipments are power shovel, Hoe Dragline, clam shell, bulldozer, scraper, trencher etc.
→ Dump trucks are used for the purpose of transporting or earth moving equipment.

302. For excavating solid rocks, the most suitable equipment is :
(a) Dragline (b) Power shovel
(c) Clamshell (d) Hoe
Nagaland PSC CTSE 2017 Paper–I
ESE 2012

Ans. (b) For excavating solid rocks, the most suitable equipment is power shovel.

303. The size of a power shovel is indicated by the size of
(a) Boom (b) Hoist live
(c) Dipper (d) Cab
Nagaland PSC CTSE 2017 Paper–I

Ans. (c) Size of power shovel is indicated by the size of dipper generally expressed in m^3. they are available in size $\frac{3}{8}, \frac{1}{2}, \frac{3}{4}, 1, 1\frac{1}{4}, 1\frac{1}{2}, 2, 2\frac{1}{2}$ m^3 which come under the category of standard power shovels.

304. Which one of the following does not form a part of Derrick crane?
(a) Mast (b) Boom
(c) Guys (d) Jack
Nagaland PSC CTSE 2017 Paper–I

Ans. (d) Boom, Mast, guys, Bull wheel are the some components of Derrick crane. But Jack is not a component of Derrick crane.

305. Which one of the following does not fall under the category hoisting equipment ?

Search on Telegram @apna_pdf

(a) Chain hoist (b) Draglines
(c) Jack (d) Hoist winch

Nagaland PSC CTSE 2017 Paper–I

Ans. (b) Hoisting is the operation of lifting the load. Hence, equipments used for hoisting is called hoisting equipment. Type of hoisting equipment are Pulley, Chain hoist, Jack, Winch, Cranes.
Dragline is mainly used for excavation and transportation of excavated material for short distance.

306. The construction equipment suitable for lifting and transportation is :
(a) Lift truck (b) Winch crab
(c) Spiral chute (d) Both (a) and (c)

Nagaland PSC CTSE 2017 Paper–I

Ans. (d) Lift truck and spiral chute are those construction equipment which is suitable for both lifting and transportation.

307. When it is necessary to brace the walls of trench to hold sheeting on trench walls, the best excavating instrument is :
(a) Hoe (b) Dragline
(c) Clamshell (d) Trenching equipment

Nagaland PSC CTSE 2017 Paper–I

Ans. (b) : Dragline is an excavating equipment is which bucket is dragged against the material to be excavated. It does not have to go into the pit to excavate hence. It may operate on natural firm and deposit excavated material on nearby banks.

308. Which of the following is not-another name of hoe ?
(a) Backhoe (b) Back-shovel
(c) Pull shovel (d) trenching machine

Nagaland PSC CTSE 2017 Paper–I

Ans. (d) : A trencher is a piece of construction equipment used to dig trenches especially for laying pipe.

309. For three dimensional movement of a weight one of the following in most suitable ?
(a) Crane hoist (b) Winch
(c) Crane (d) Jack

Nagaland PSC CTSE 2017 Paper–I
ESE 2007

Ans. (c) : Crane is the equipment used for 3–D movement of weight where as winch, Crane hoist and Jack are used for 1–D dimensional vertical movement.

310. A construction equipment has an initial cost of ₹ 2,00, 000 and salvage value of ₹ 50,000 at the end of an economic life of 5 years. The rate of straight-line depreciation and total depreciation will be
(a) 0.1 and ₹ 1,50,000 (b) 0.2 and ₹ 1,50,000
(c) 0.1 and ₹ 1,00,000 (d) 0.2 and ₹ 1,00, 000

ESE 2019

Ans. (b)
Initial cost 'P' = 2,00,000
Salvage value (SV) = 50,000
Economic life (n) = 5 years
Total depreciation = Initial Cost – Salvage value
Depreciation (D) = 200,000 – 50,000 = 150,000]

[Rate of depreciation = $\frac{1}{n} = \frac{1}{5} = 0.2$]

311. A machine cost Rs. 32,000. By constant rate of declining balance method of depreciation, its salvage value after an expected life of 3 years, is Rs. 4,000. The rate of depreciation:
(a) 0.25 (b) 0.30
(c) 0.40 (d) 0.50

WBPSC Poly Lect. 2019

Ans. (d) : $C_i = 32000$ $C_s = 4000$
expected life n = 3 year

$$D = 1 - \sqrt[n]{\frac{C_s}{C_i}}$$


$$= 1 - \sqrt[3]{\frac{4000}{32000}}$$

$$= 1 - \sqrt[3]{\frac{1}{8}} = 1 - \frac{1}{2} = \frac{1}{2} = 0.5$$

312. The cost of the machine is ₹ 20,00,000, and if it is purchased under installment basis; the company has to pay 25% of the cost at the time of purchase and the remaining amount in 10 annual equal installments of ₹ 2,50,000 each. If rate of interest is 18%, compounded annually the present worth of the machine will be :
(a) ₹17,01,000 (b) ₹16,22,500
(c) ₹15,43,000 (d) ₹14,64,500

ESE 2020

Ans. (b)



P = 0.25 × 20,00,000
= 5,00,000

Now,
Present worth of machine

$$= 5,00,000 + 2,50,000 \times \left[\frac{(1+0.18)^{10} - 1}{0.18\,(1.18)^{10}}\right]$$

= 5,00,000 + 11,23,521
= ₹ 1623521

313. For deep pits excavation which machine is most suitable
(a) Shovels (b) Clamshell
(c) Backhoes (d) Trenchers

GPSC Poly. Tech. Lect. 2016

Ans. (b) : In deep pits excavation the machine which is most suitable is clamshell.
The clamshell is widely used for re-handling of material and for working in limited space as in case of foundation trenches of pipe lines etc. It is also used for jobs that require fairly accurate dumping and disposal of material.

314. Cermets are
(a) metals for high temperature use with ceramic like properties
(b) ceramics with metallic strength and luster
(c) coated tool materials
(d) metal-ceramics composites

APPSC (PHE) AE Paper-2 2012

Search on Telegram @apna_pdf

Ans. (c) : Cermets are used instead of tungsten carbide in saws and other brazed tools due to their superior wear and corrosion properties. Cermets are coated tool materials.

315. One of the following is not a earth excavation and lifting equipment

(a) Power shovel (b) Backhoe
(c) Dragline (d) Bulldozer

GPSC AE January 2018

Ans. (d) : Bulldozer are called a Dozer, powerful machine for pushing earths or rock. It is not an excavating or lifting machine.

316. A machine costing Rs. 8,500 will have a scrap value of Rs 300. Machines of this class have a working hour average life of 25,000 hours. What will be the depreciation charge at the end of first year, if the machine is operated for a total of 1500 hours? Use straight line method of depreciation

(a) Rs 492 (b) Rs 542
(c) Rs 548 (d) Rs 692

UPRVUNL AE 2015

Ans. (a) : Given that :
Machine Cost : Rs. 8500/-
Scrape value : Rs 300/-
Working hour avg life : 25000 hour
Machine operated $\Rightarrow$ 1500 hour
Depreciation charge at the end of first year $\Rightarrow$?

$$\text{Depreciation} = \frac{\text{Cost} - \text{residual value}}{\text{useful life}} = \frac{C_i - C_s}{n}$$

$$n = \frac{25000}{1500} = 16.67$$

$$\text{Depreciation} = \frac{8500 - 300}{16.67} = 492 \text{ Rs.}$$

317. For which of the following materials, the output of power shovels for a fixed shovel size will be maximum

(a) Moist loam (b) Good common earth
(c) Well blasted rock (d) Wet sticky clay

UPRVUNL AE 2015

Ans. (a) : The moist loam and the common earth fall in the same category and have a factor ranging between 0.8 and 1.1.

318. Match List I (crane) with List II (Suitable for) and select the correct answer using the given lists.

List I		List II
A.	**Tower crane**	**a. Hydraulic structure**
B.	**Floating crane**	**b. High industrial plant**
C.	**Mobile crane**	**c. Longitudinal and lateral movement of load**
D.	**Gantry crane**	**d. Railway electrification**

(a) A-b, B-a, C-d, D-c (b) A-c, B-d, C-a, D-b
(c) A-b, B-d, C-a, D-c (d) A-c, B-a, C-d, D-b

UPRVUNL AE 2015
ESE 2007

Ans. (a) : Tower crane– High industrial plant
Floating crane – Hydraulic structure
Mobile crane – Railway electrification
Gantry crane– Longitudinal and lateral movement of load.

319. Which of the following are the advantages of crawler mounted bulldozer over wheel mounted bulldozers?
A. Higher travel speed
B. Able to travel over very soft soil
C. Able to travel over very rough surfaces having no haul roads
Which of these statements are correct?

(a) All three (b) Only A and B
(c) Only A and C (d) Only B and C

UPRVUNL AE 2015
ESE 2006

Ans. (d) : Crawler mounted bulldozer weight is less in comparison of wheel mounted bulldozer.
and It is efficient to drive on rough surface.

320. The nominal lead and lift allowed for earthwork in excavations of foundations are-

(a) 30 m and 1.5 m (b) 20 m and 2.0 m
(c) 15 m and 30 m (d) 10 m and 4.5 m

MPSC (Mains) 2017 Paper–II

Ans. (a) : The nominal lead and lift allowed for earthwork in excavations of foundation are 30 m and 1.5 m respectively.

321. In estimation of earthwork the measurements shall be taken separately for what lead and height?

(a) 30 m, 1.5 m (b) 25 m, 2.0 m
(c) 20 m, 1.0 m (d) 40 m, 3.0 m

OPSC AEE 2019 Paper–I

Ans. (a)
Lead $\rightarrow$ 30 m
Lift $\rightarrow$ 1.5 m

322. Which of the following is not an excavation equipment?

(a) Backhoes (b) Power shovels
(c) Drag line (d) Grader

HPPSC Poly. Lect. 2016

Ans : (d) Various types of Excavation equipment use on construction site–
1. Power shovels
2. Bull Dozers
3. Scrapers
4. Draglines
5. Clamshell
6. Backhoe

323. Which of the following equipments is used for sounding?

(a) Ceylonghat tracer (b) Lead line
(c) Line ranger (d) (a) and (b) above

GPHC AE 2018

Ans : (b) Measurement of depth below the water surface is called sounding.
Note : Lead lines, Sounding boat, Sounding Poles are use for sounding.

324. The most commonly used cranes in high rise construction sites where concentration of work is in a limited area of the site

(a) Tower cranes (b) Overhead cranes
(c) Crawler cranes (d) Goliath cranes

TSPSC AEE 2017

Ans. (a) :

Search on Telegram @apna_pdf

10.

Estimating, Costing and Valuation of Building & Civil Works

1. Building Valuation & Rent Fixation

1. The series of cells or dots or pixels to which value are assigned and that represent an image is known as

(a) Vector data (b) Raster data
(c) Random data (d) Object oriented data

LMRC AM 2019

Ans. (b) The series of cells or dots or pixels to which values are assigned and that represent an image is known as raster data.

2. Working out exact quantities of various items of work is known as :

(a) Quantity Surveying (b) Estimating
(c) Valuation (d) All of the above

[UPPSC State Eng. A.E. 2011]

Ans : (b) Estimating is a process in which exact quantities of various items of work are found out.

3. A contractor agreed to build 30 temporary sheds in 90 days at a price of Rs. 10000/unit. Twenty days later, the contractor has finished 8 sheds with an actual total cost of Rs. 85000. What is the status of the project?

(a) The project is on time and cost overrun
(b) The project time is overrun and cost under run
(c) The project time is under run and cost overrun
(d) The project is on time and cost under run

MPPSC AE 2016

Ans : (c) 30 sheds in 90 day @ Rs. 10000/unit.
Current situation 20 days – 8 sheds – Rs. 85000
for 8 sheds,

$$\text{critical time} = \frac{8}{30} \times 90 = 24 > 20 \text{ days}$$

critical money = 8 × 10000 = 80000 < 85000
Hence the project is time under run and cost over run.

4. The relationship between the capital recovery factor and sinking fund factor in a uniform series of payments is given by

(a) Capital recovery factor = Sinking fund factor – Interest rate
(b) Capital recovery factor = Sinking fund factor – (Interest rate)^2
(c) Capital recovery factor = Sinking fund factor + (Interest rate)^2
(d) Capital recovery factor = Sinking fund factor + Interest rate

MPPSC AE 2016

Ans : (d) CRF = equal payments equivalent to present

$$\text{payment} = \left[\frac{i(1+i)^n}{(1+i)^n - 1}\right]$$

$$\text{SFF} = \left[\frac{i}{(1+i)^n - 1}\right]$$

$$\text{SFF} + \text{i} = \frac{i}{(1+i)^n - 1} + \frac{i\left[(1+i)^n - 1\right]}{(1+i)^n - 1}$$

$$= \frac{i + i(1+i)^n - i}{(1+i)^n - 1} = \left[\frac{i(1+i)^n}{(1+i)^n - 1}\right]$$

= CRF

$\boxed{\text{CRF} = \text{SFF} + \text{i}}$

5. A recurring deposit of Rs. 5000 per month for 12 installments will grow to _____ at the end of 12 months for the given nominal interest rate of 12 percent, but compounded monthly (consider deposit being done on the last day of the month and also accrual of interest being calculated on the last day of the month).

(a) Rs. 60,000 (b) Rs. 62,834
(c) Rs. 63,413 (d) Rs. 64,047

MPPSC AE 2016

Ans : (c) Interest for 1 month = $\frac{12\%}{12} = 1\%$

P = 12 × 5000 = 60000

To, find f, $\frac{f}{A} = \frac{(1+i)^n - 1}{i}$

$$= \frac{(1+0.01)^{12} - 1}{0.01} = 12.6825$$

f = 12.6825 × 5000

$\boxed{\text{f} = 63413 \text{ Rs}}$

6. While comparing alternatives of different lives, most preferred method would be

(a) net present worth analysis
(b) net future worth analysis
(c) net annual worth analysis
(d) break even analysis

MPPSC AE 2016

Search on Telegram @apna_pdf

Ans : (c) For comparing alternatives of different lives, most preferred method would be net annual worth analysis. It will incorporate all the expenditure and profits for equal span of time i.e. 1 year.

7. While assessing rate of return on certain investments, the investor assumes certain interest rate and calculates his net present value of all his cash inflows and outflows. Which of following will be correct?

(a) If net present value is positive for the assumed value of interest rate, the actual rate of return will be higher than assumed interest rate

(b) If net present value is positive for the assumed value of interest rate, the actual rate of return will be lower than the assumed interest rate

(c) It cannot be assessed in the absence of cost of capital

(d) It cannot be assessed in the absence of actual loan period

MPPSC AE 2017

Ans. (a) : A rate of return (ROR) is the net gain or loss on investment over a specified time period, expressed as a percentage of the investment's initial cost.

$$\text{Rate of return} = \frac{\text{Current value - original value}}{\text{Original value}} \times 100$$

If net present value is (+Ve) for assumed value of interest rate, the actual rate of return will be higher.

8. The system of organization introduced by F.W. Taylor is known as-

(a) Effective organization

(b) Functional organization

(c) Line and staff organization

(d) Line organization

MPPSC AE 2017

Ans. (b) :

- Functional organization is suggested by F.W. Taylor. In functional organization different experts (specialist) guide the subordinates in organization. Worker or subordinates thus receive order from several specialists or officers and are responsible for their performance to different experts.
- Line organization is the traditional and simplest form of organization structure. Line organization is also called as military organization as it is adopted from military administration.

9. If the excavation of earth is done manually then it costs Rs. 100 per cum. A machine can excavate at a fixed cost of Rs. 40,000 plus a variable cost Rs. 20 per cum. The quantity of the earth for which the cost of excavation by machine will be equal to the cost by manuals excavation is-

(a) 500 cum (b) 1000 cum

(c) 1500 cum (d) 2000 cum

MPPSC AE 2017
GPSC AE (CLASS 1 & 2) 2019

Ans. (a) : Let the earth excavated by x cum

$100x = 40000 + 20x$

$80x = 40000$

$x = 500$ cum

10. At what change of price level is revised estimate prepared?

(a) 2.0% (b) 2.5%

(c) 4.0% (d) 5.0%

[MPSC 2015 Paper-II Mains]

Ans. (d) : Revised estimate is prepared

⇒ When original sanctioned estimate is likely to exceed by more than 5%.

⇒ When the expenditure on a work exceeds the amount of administrative sanctioned by more than 10%.

11. Salvage value is defined as-

(a) value of dismantled materials of a property at the end of its utility period

(b) estimated value of a built up property at the end of its useful life without being dismantled

(c) value of the property shown in the account book in that particular year

(d) present value of a property considering it to be replaced at the current market rates

[MPSC 2015 Paper-II Mains]

Ans. (b) : Scrap value - value of dismantle materials of properties at the end of its utility period.

Salvage value - Estimated value of property at the end of life without dismantled.

Book value - Value of the property shown in account book in that particular year.

Marked value - It is the price that an asset fetches from the market.

12. The rights and privileges which an owner of a property enjoys through or over the property of another is known as-

(a) Property right (b) Lease right

(c) Legal right (d) Easement

[MPSC 2015 Paper-II Mains]

Ans. (d) : There are two type of easements

1. Positive easements - It is an easement that permits the owner of dominant land to do some thing on servient land.

2. Negative easements - Easements that limit what the owner may do on the servient land.

Note :

⇒ Legal rights - Refers to rights according to law.

⇒ A lease is a contract outlining the term under which one party agree to rent property owned by another party.

13. Decrease or reduction in the value of an equipment or asset is called as-

(a) Saturation (b) Depreciation

(c) Negotiation (d) Valuation

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (b) :

⇒ Depreciation refers to decreases in value of assets. It is a method of reallocating the cost of a tangible asset over its useful life span of it being in motion.

14. The cost inflow a firm receives if a machine still has value at the time of its disposal is known as-

(a) Salvage value (b) Purchase expenses

(c) Operating cost (d) Ownership cost

Maharashtra PSC (Mains) 2017 Paper–I

Search on Telegram @apna_pdf

Ans. (a) : Salvage value is the value a material posses at the time of its disposal.
Operating cost : Operating cost are the expenses which are related to the operation of a business or to the operation of a device component, piece of equipment or facility. They are the cost of resources used by organization just to maintain its existence.
Ownership cost : The total cost of ownership (T_{CO}) include the purchase price of particular asset plus operating costs over the assets in lifespan. Looking of the total cost of ownership is a way of assessing the long term value of a purchase to a company or individual.

15. Measurement of 50 mm thick concrete flooring will be done in-
(a) Cubic m (b) % sq m
(c) Meter (d) Sq. m

OPSC AEE 2015 PAPER–I

Ans. (d) : Since the thickness has been fixed, we will measure in terms of area only.

16. Work Breakdown structure for a construction project will help in-
(a) Breaking the project into several elements
(b) Identifying the activities
(c) Identifying the functional elements of a project and their interrelationship
(d) None of these

OPSC AEE 2015 PAPER–I

Ans. (a) Work Breakdown structure for a construction project will help in breaking the project into several elements.
Work break down structure is a device that identifies the functional elements of a project and there inter-relationship. It is a process of breaking the project into easily identifiable system, there sub-system and discrete activities, is called the work break down structure. It follow up to down approach.

17. When a property is sold at a lower price than that of an open market rate is known as
(a) Assessed value (b) Replacement value
(c) Distress value (d) Book value

TNPSC AE 2018

Ans. (c) : Distress value : Distress value would be the value of those tangible assets when you have to sell them at a fire sale. Owner sells a commodity at low price to fulfill urgent need of money for various reasons.
Book value : The value of security or asset as entered in a firm books.
Assessed value : An assessed value is the dollar value assigned to a property to measure applicable taxes.

18. The value of the dismantle property at the end of useful life period is known as
(a) scrap value (b) salvation value
(c) junk value (d) consolidated value

TNPSC AE 2018

Ans. (a) Scrap value : It is the value of an dismantled asset after it has come to the end of its useful life.
Ex- Selling of vehicle after severe accident now vehicle can not be used as whole but some part can be used.

19. In long and short wall method of estimation, the length of long wall is the centre to centre distance between the walls and plus :
(a) Breadth of the wall
(b) Half breadth of wall on each side
(c) One fourth breadth of wall on each side
(d) None of these

Rajasthan JEn (Degree) 2016

Ans. (b) In long and short wall method of estimation, the length of long wall is the centre to centre distance between the walls and plus half of breadth of wall on each side.
Note :
(i) For finding out length of short wall or cross wall subtract from the centre length, so the one short wall (in-to-in) (instead of adding)
(ii) The length of the long wall usually decrease from earthwork to brickwork, and the length of short wall is increased.

20. Number of bricks required for 1 cubic meter of brick masonry is
(a) 400 (b) 450
(c) 500 (d) 550

GPSC AE (CLASS 1 & 2) 2019

Ans : (c) : $1m^3 \rightarrow 100 \times 100 \times 100\ cm^3$

$1\,\text{brick} - \begin{cases} \text{size } 19\times9\times9\,cm^3\,(\text{Standard brick size})\,(\text{without mortar}) \\ \text{size } 20\times10\times10\,cm^3\,(\text{With mortar}) \end{cases}$

$$\text{Number of brick with mortar required} = \frac{100\times100\times100}{20\times10\times10}$$
$$= 500 \text{ nos.}$$

21. Which of the following is considered as Outgoing in expenses?
(i) Repairs
(ii) Sinking fund
(iii) Loss of rent
(a) (i) and (ii) (b) (ii) and (iii)
(c) (i) and (iii) (d) (i), (ii) and (iii)

GPSC AE (CLASS 1 & 2) 2019

Ans : (d) : The various types of outgoing are as follows taxes, repair, management and collection changes, sinking fund, loss of rent, miscellaneous.

22. All the tenders received may be rejected if
(i) The lowest tender has quoted a figure, which is higher than the funds available for the execution of the work
(ii) Radical changes in design are found necessary during the interval preceding the opening of the tenders
(iii) The minimum number of tenders to assure adequate competition has not been received.
(iv) There exists a well-grounded suspicious collusion between tender or some other form of the fraud has been detected.

Which of the following statements are correct?
(a) (i) and (ii) (b) (iii) and (iv)
(c) (i), (ii) and (iii) (d) (i), (ii), (iii) and (iv)

GPSC AE (CLASS 1 & 2) 2019

Search on Telegram @apna_pdf

Ans : (d) : All tender will be rejected if –
(i) The lowest tender has quoted figure which more than quoted figure (fund) of the work execution.
(ii) Minimum number of tenders has not received.
(iii) When collision between tenders or any faced ditched.
(iv) Any necessary changes in design during preceding of project.

23. Cost slope is the ratio of
(a) increase in cost by increase in time
(b) decrease in cost by increase in time
(c) increase in cost by decrease in time
(d) decrease in cost by decrease in time

TNPSC AE 2018

Ans. (c) : Cost slope : The cost slope is the slope of the direct cost curve, approximated as straight line.

$$\text{Cost Slope} = \left(\frac{\text{Crash cost - Normal cost}}{\text{Normal time - Crash time}}\right)$$

$$\text{CS} = \frac{C_C - C_n}{t_n - t_c} = \frac{\triangle C}{\triangle t}$$

$$= \left(\frac{\text{Increase in cost}}{\text{Decrease in time}}\right)$$

24. The total cost of the project depends much on
(a) Area of the building
(b) Specification of material
(c) Specification of labour
(d) Specification of both material and labour

TNPSC AE 2018

Ans. (d) : The total cast of project depends much on both material and labour. The most common way to estimate cost is to make a list of items you need and add up their costs. It is applicable to cost, such as equipment and parts, materials, and supplies, labour, financing, fees on licensing, transportation and acquisition costs for land or facilities.

25. Which of the following method of valuation is most suitable for hotel and cinemas?
(a) Rental method
(b) Direct comparison
(c) Valuation based on profit
(d) Valuation based on cost

GPSC AE (CLASS 1 & 2) 2019

Ans : (c) Valuation of Hotel & Cinemas are based upon value based on profit accordingly.

26. Which of the following is not included in tender document?
(a) Declaration letter (b) Tender notice
(c) Bill of quantities (d) Invoice

UPPCL AE 2019

Ans. (d) Invoice is not include in tender document.

27. A detailed estimate, which is prepared to maintain the structure or work in proper order and safe condition, is called a/an :
(a) supplementary estimate
(b) annual repair estimate
(c) revised estimate
(d) detailed estimate
(e) item rate estimate

CGPSC AE 2017

Ans. (b) A detailed estimate, which is prepared to maintain the structure or work in proper order and safe condition, is called an annual repair estimate.
Detailed or item rate estimation : It is an accurate and reliable method and consists of work out the quantities of each item of works and working the cost.
Revised Estimate :
- It is prepared when original sanctioned estimate is likely to exceed by more than 5%.
- It is also prepared when there are material deviation from original proposal even through cost may be met from sanctioned cost.

Supplementary Estimate : Supplementary estimate is required due to some new works or due to change of design, so additions or revisions of drawing may be necessary.

28. Capitalized value of a property is given by
(a) Net annual rent × year's purchase
(b) Net annual rent × sinking fund
(c) Gross annual rent × year's purchase
(d) Gross annual rent × 2

TNPSC AE 2019

Ans. (a) Capitalized value of property = Net annual rent × year's purchase.

29. Which of following method of valuation will be adopted to value underdeveloped properties
(a) Depreciation method of valuation
(b) Valuation based on cost
(c) Rental method of valuation
(d) Development method of valuation

TNPSC AE 2019

Ans. (d) In development method of valuation the method of valuation is done for undevelopment properties eg : painted, renovation work etc.

30. Which of the following is not related to the cost slope:
(a) Crash Cost (b) Normal Cost
(c) Crash time (d) Slack

TNPSC AE 2019

Ans. (d) Cost slope : The cost slope is the slope of the direct cost curve, approximated as straight line.

$$\text{Cost Slope} = \left(\frac{\text{Crash cost - Normal cost}}{\text{Normal time - Crash time}}\right)$$

$$\text{Cost Slope} = \frac{C_c - C_n}{t_n - t_c} = \frac{\Delta c}{\Delta t}$$

31. Consider the following statements regarding the slope of Cost-time curve.
1. It is given by difference between normal cost and crash cost divided by crash time.
2. it is given by difference between crash cost and normal cost divided by difference between crash time and normal time.
3. It is given by difference of crash cost and normal cost divided by normal time.
4. It is given by crash cost divided by crash time.

Which of these statements are/is correct?
(a) 1 only (b) 2 only
(c) 2 and 3 (d) 3 and 4

TNPSC AE 2019
ESE 2010

Search on Telegram @apna_pdf

Ans. (b) Cost slope : The cost slope is the slope of the direct cost curve, approximated as straight line.

$$\text{Cost Slope} = \left(\frac{\text{Crash cost - Normal cost}}{\text{Normal time - Crash time}}\right)$$

$$\text{Cost Slope} = \frac{C_c - C_n}{t_n - t_c} = \frac{\Delta c}{\Delta t}$$

32. The unit of measurement in MKS for steel works using rolled steel joists

(a) Quintal (b) Kilogram
(c) Cu.m (d) Sq.m

TNPSC AE 2019

Ans. (a) MKS for rolled steel & roller steel → Quintal

33. Floor area ratio and plot coverage will helps to determine

(a) Actual cost of the Building
(b) Approximate cost of the Building
(c) Administrative approval cost
(d) Security deposit amount

TNPSC AE 2019

Ans. (b)

$$\text{Floor Area ratio} = \frac{\text{Area between wall of all Room}}{\text{Plot area}}$$

In floor area ratio Plinth area is excluded (By this we can find approximate rate of building)

34. In rate analysis, the unit of measurement of Indian W.C. size 580 mm size is

(a) Kg (b) Number
(c) Pair (d) Sq. meter

Gujarat PSC AE 2017

Ans : (b) Indian WC size are measured in number.

35. The check measurement certificate should be obtained

(a) in the site order book
(b) on a separate prescribed form
(c) in the measurement book itself
(d) in the indent form

TNPSC AE 2012

Ans. (c) The check measurement certificate should be obtained in the measurement book itself.

36. Which of the following is the most correct estimate?

(a) Plinth area estimate
(b) Cube rate estimate
(c) Analysis of rates
(d) Building cost index estimate

TNPSC AE 2012

Ans. (c) Analysis of rates - The process of determining the rates of an item is termed as analysis of rates or rate analysis.
The rate analysis is the method of deriving the rate per unit of a particular item of work, from the cast of material, labour, machineries and other miscellaneous expenses for its completion.
Plinth area means the covered built up area that is calculated at the floor level of any storey or at the floor level of the basement.
Cube rate estimate : The cost of structure is calculated approximately as the total cubical contents (volume of building) multiplied by local cubic rate. The volume of building is obtained by length × Breadth × depth or height.

37. Of the total estimated cost of a building, electrification usually accounts for

(a) 1% (b) 2%
(c) 8% (d) 15%

TNPSC AE 2012

Ans. (c) Work	**% of estimate**
Contract charge	10
Labour charge	25
Electrification	8
Sanitary & water supply charge	8
Contgencies charges	3-5
Work charge establishment	1.5-2
Tools and plants	1-1.5

38. The cost of a machine is Rs. 10,000 with a useful life of 10 years. Its depreciated cost, after 5 years, if the salvage value is Rs. 1,000 on straight line basis, will be

(a) Rs. 1,500 (b) Rs. 3,500
(c) Rs. 5,500 (d) Rs. 7,500

TNPSC AE 2012

Ans. (c) : We know that,

$$\text{Depreciation } (D) = \frac{C - V}{n}$$

Where D = Depreciation of machine
C = Cost of machine = Rs. 10000
V = Salvage value = Rs . 1000
n = number of useful year = 5 years

$$D = \frac{10000 - 1000}{10} = \frac{9000}{10} = 900$$

value after n_1 year = $C - (D \times n_1)$
$= 10000 - (900 \times 5)$
$= 5500$

39. Detailed specifications includes :

(a) Rates of various items of work
(b) Measurements taken after execution of work
(c) Quantities of items dumped at site
(d) Quantities and qualities of materials

TNPSC AE 2015

Ans. (d) Detailed specifications includes quantities and qualities of materials.

40. The covered area of a building measured at floor level is called :

(a) Floor area (b) Plinth area
(c) Carpet area (d) Circulation area

KPSC AE 2020

Ans. (b) : The covered area of a building measured at floor level is called plinth area.
Carpet area – Carpet area is the area that can be used to carpet inside the house it is the net usable area of the apartment it include thickness of the internal wall but excludes balcony and terrace.
Circulation area– The sum of all area on all floors of a building required for physical access to some subdivision of space, whether physically bounded by partition or not.

Search on Telegram @apna_pdf

41. A building costs Rs. 40000. Considering scrap value as 10% of the cost and life as 60 years, the depreciated value after 12 years is :

(a) 33800 (b) 34800
(c) 32800 (d) 31800

KPSC AE 2020

Ans. (c) : We know that formula

$$\text{Depreciation (D)} = \frac{C - S}{n}$$

C (cost of building) = Rs 40000
S (Scrap value) = Rs 10% of cost of building
n (no. of use full year) = 60 years

$$D = \frac{40000 - 4000}{60}$$

D = 600 per year
After 12 year depreciation value
= C – (D × n) = 40000– (600 × 12)
= 40000–7200 = 32800

42. Steel reinforcement bars in RCC is measured in :

(a) Quintals (b) Metre
(c) Number (d) Cum

KPSC AE 2020

Ans. (a) Steel reinforcement bars in RCC is measured in quintals.

43. The original cost of property minus the depreciation till the previous year is called :

(a) market value (b) sinking value
(c) book value (d) rentable value

DMRC AM 2017

Ans. (c) : The original cost of property minus the depreciation till the previous year is called book value.
Book Value : Purchase value (or initial cost)-Depreciation. This is the value recorded in the account books in a particular year.
Reliable value: it is the value described to the property based on its size, location and other factors to determine the rates payable by its owner.
Rentable value : Rentable value is the fair market value of property while rented out in a lease. It may be the consideration paid under the lease for the right to occupy or the royalties or return received by a landlord under a license to real property.

44. An item not included in the plinth area estimate is the:

(a) Verandah (b) Water closet
(c) Wall thickness (d) Court yard

DMRC AM 2017

Ans. (d) : Plinth area is covered built up area measured at the floor level of any storey or at the floor level of the basement. It is generally 10–20% more than carpet area. The following is not to be include in the calculation of plinth area–
(1) Cantilevered porch
(2) Balcony
(3) Court yard
(4) Area of loft
(5) Open platform
(6) Terrace at first floor
(7) Spiral staircase including landing

45. According to BIS method of measurement, the order of the sequence is

(a) Length, breadth, height
(b) Breadth, length, height
(c) Height, length, breadth
(d) Length, height, breadth

DMRC AM 2017
ISRO Scientist/Engineer 2015

Ans : (a) : The sequence of booking dimension is Length, Breadth, Height.

46. Revised estimate is a detailed estimate and is required to be prepared under the condition when :

(a) The original estimate exceeds or likely to exceed by more than specified in OPWD manual.
(b) The expenditure on a work exceeds or likely to exceed the amount of administrative sanction as specified in OPWD manual.
(c) There are material deviation from the original proposal even through the cost may be met from the sanctioned strength.
(d) Any or all such case prevails.

OPSC AEE 2019 Paper–I

Ans. (b) : Revised estimate is a detailed estimate and is required to be prepared under the condition when the expenditure on a work exceeds or likely to exceed the amount of administrative sanction as specified in OPWD manual. Revised estimate is prepared when original estimate is likely to exceed by more than 5%.

47. The Schedule of Rates is prepared based on :

(a) Analysis of rates
(b) Experience
(c) General abstract of cost
(d) Building cost index

OPSC AEE 2019 Paper–I

Ans. (a) : Analysis of rates is done to prepare schedule of rates.

48. In analysis of rates which is/are included from the following?

(a) Cost of quantities of materials.
(b) Cost of labour and other miscellaneous expenditures.
(c) Contractor's profit
(d) All of these

OPSC AEE 2019 Paper–I

Ans. (d) : Rate analysis include :
1. Cost of labour wages.
2. Cost of material.
3. Overhead charges.
4. Location of site.
5. Contractor profit.

49. In 1.0 cubic meter of 1:2:4 cement concrete, how many bags of cement (approximately) is required?

(a) 6.6 (b) 16.6
(c) 26.6 (d) 36.6

OPSC AEE 2019 Paper–I

Search on Telegram @apna_pdf

Ans. (a) : Given 1 : 2 : 4
The sum of ratio = 7
Volume of wet cement concrete = 1.54 m^3

1) In cum = $\frac{1.54 \times 1}{7} = 0.22\ M^3$

2) In kg = 0.22×1440 cum $\times \frac{kg}{cum} = 316.8$ kg

3) In bags = $\frac{316.8}{50} = 6.3$ bags ≈ 6.6 bags

50. The head of Public Works Department of any Indian state is:
(a) Transport Minister
(b) Chief Engineer
(c) Superintending Engineer
(d) Executive Engineer

OPSC AEE 2015 PAPER–I
UJVNL AE 2012

Ans : (b) Professional head of Public Works Department in a state is chief engineer.

51. Assertion (A) : Earnest money deposit is usually 1% to 2% of the total estimated cost of the work.
Reasoning (R) : Earnest money deposit prevents unnecessary and unhealthy competition.
(a) Both (A) and (R) are true
(b) Both (A) and (R) are false
(c) (A) is true and (R) is false
(d) (A) is false and (R) is true

Maharashtra PSC Mains 2018 Paper-2

Ans. (a) : Earnest money deposit (EMD) is must 1–2% of project cost and is need to be submitted along with tender document so that only worthy persons goes for tendering. EMD is refundable for those who do not get contract.

52. In order to compute the quantities of R.C.C. beams, lengths of beams are measured to the
(a) nearest millimeter
(b) nearest half centimeter
(c) nearest centimeter
(d) nearest inch

Maharashtra PSC Mains 2018 Paper-2

Ans. (a) : For accurate estimation, the length, breadth and height are measured to the nearest millimeter.

53. Following is not the method of apportionment of total cost of multipurpose reservoir:
(a) Remaining benefit method
(b) Use of facilities method
(c) Equal apportionment
(d) Direct method

Maharashtra PSC Mains 2018 Paper-2

Ans. (d) : The method of apportionment of total cost of multipurpose reservoir-
(1) Remaining benefit method
(2) Use of facilities method
(3) Equal apportionment
(4) Alternative justifiable expenditure method.

54. The value of property (without being dismantled) at the end of the useful life period is known as

GWSSB AAE 2015

OR

The value of a particular entity at the end of the utility period without dismantling is called as the
(a) scrap value (b) book value
(c) salvage value (d) sinking value

GPSC AE March 2018

Ans. (c) : Salvage value is the value of a particular entity at the end of utility period without dismantling.

$S = P - (I \times y)$

S = Salvage value
P = Original price
I = Depreciation
y = no. of years
Salvage value of property or an asset may be positive, zero or negative.

55. Original cost of property minus depreciation is
(a) Salvage value (b) Market value
(c) Book value (d) Obsolescence value

GPSC Poly. Tech. Lect. 2016
PTCUL AE 2016

Ans. (c) : Book value is the amount shown in the account book after allowing necessary depreciations. The book value of a property at a particular year is the original cost minus the amount of depreciation allowed per year and will be gradually reduced year to year and at the end of the utility period of the property, the book value will be only scrap value.

56. The technique of finding the fair price of an existing building or property is known as
(a) pricing (b) costing
(c) estimating (d) valuation

TNPSC AE 2019
GWSSB AAE 2015

Ans. (d) : Valuation is the technique of estimating or determining the fair price or value of property such as building, factory, other engineering structures of various types, land etc.
By valuation the present value of property is defined the present value of property may be decide its selling price or income or rent it may fetch.

57. The information which cannot be included in drawings is conveyed through
(a) progress chart
(b) none of three mentioned here
(c) always additive
(d) always subtractive

GWSSB AAE 2015

Ans. (c) : The information which cannot be included in drawings is conveyed through specifications. A good drawing may be defined as that contains all of the information required by the various design and manufacturing people who will use it in producing the subject part.

Search on Telegram @apna_pdf

58. **Assertion (A) : Rate analysis is carried out to work out the actual cost of the structure or building.**
Reason (R) : Rate analysis is carried out to revise the schedule of rates.
State whether
(a) Both A and R are true
(b) A is true and R is false
(c) A is false and R is true
(d) Both A and R are false

Maharashtra PSC Mains 2012 Paper -2

Ans. (c) : Purposes of Rate Analysis :
(i) To determine the current rate per unit of an item of work at the locality.
(ii) To examine the viability of rates quoted by contractors.
(iii) To ascertain the quantity of materials and labour strength required to complete the project.
(iv) To revise the schedule of rates due to increase in the cost of materials and labour or due to changed situation.

59. **A property whose owner is in the absolute possession of the property, and the owner can utilize the same in any manner he likes subject to the rules and regulations of Govt. and local authorities is known as**
(a) Leasehold property (b) Saleable property
(c) Freehold property (d) Absolute property

Maharashtra PSC Mains 2012 Paper -2

Ans. (c) : A freehold is the common ownership of real property, or land and are immovable structures attached to such land.

60. **The money that is already spent as a result of a past decision is called.**
(a) Sunk cost (b) Fixed cost
(c) Variable cost (d) Marginal cost

OPSC Civil Services Pre 2011

Ans. (a) Sunk cost : A sunk cost is a cost that has already been incurred and cannot be recovered. Sunk costs are contrasted with prospective costs, which are future costs that may be avoided if action is taken.

61. **An equipment is purchased for Rs. 40000 and is fully depreciated by straight line method over 8 years. Considering interest on average annual cost at 15% per annum, the charge on the Company due to use of this equipment, if made uniformly over the 8 years, is**
(a) Rs. 5750 (b) Rs. 8000
(c) Rs. 8375 (d) None of the above

UJVNL AE 2016

Ans. (c) :
Avg. annual value (P_{avg})

$$P_{avg} = \frac{P(n+1)}{2n}$$

Given, P = 40000, n = 8

$$P_{avg} = \frac{40000(8+1)}{16} = 22500 \text{ Rs.}$$

$$\text{Annual depreciation} = \frac{40000}{8} = 5000$$

Total cost = 5000 + 0.15 × 2250 = 8375 Rs.

62. **The valuation of a building depends upon:**
(a) Its structure and durability
(b) Size, shapes and types
(c) Quality of material used
(d) All the above

UJVNL AE 2012

Ans. (d) : The valuation of a building depends upon:
- Its, structure and durability
- Size, shapes and types
- Quality of material used

63. **Revised estimate is needed to be prepared when original estimate is exceeded or likely to exceed by more than**
(a) 5% (b) 10%
(c) 15% (d) 20%

GPSC AE June 2019

Ans. (b) : Revised estimate is prepared under any one of the following circumstances.
⇒ When the original sanctioned estimate is likely to exceed by more than 5%.
⇒ When the expenditure on a work exceeds the amount of administrative sanctioned by more than 10%, if there is change of rate or quantity of material.

Direction : Match list I with list II and select the correct answer using code given below the two list in each question.

64.

List I	List II
A. Valuation	1. Determining price of property
B. Mortgage	2. Charges levied on property
C. Taxation	3. Security taken for giving load
D. Specification	4. Mode of describing nature and class of work

Code:

	A	B	C	D
(a)	1	2	3	4
(b)	1	3	2	4
(c)	4	3	2	1
(d)	3	4	2	1

PTCUL AE 2016

Ans. (b) : (i) Valuation used for determining price of property.
(ii) Mortgage is a security taken for giving loan.
(iii) Taxation is charges levied on property.
(iv) Specification is a mode of describing nature and class of work.

65. **The depreciation charge for a machine are thirty paise per working hour. The machine has a scrap value of Rs 2000 and a working hour average life of 24000 hours. What is the purchase price of the machine?**
(a) Rs. 1800 (b) Rs. 7200
(c) Rs. 9200 (d) None of the above

UJVNL AE 2016
ESE 2007

Ans. (c) : Purchase price = scrap value + depreciation
= 2000 + 24000 × 0.3 = 9200

Search on Telegram @apna_pdf

66. The amount which is paid at the time of submitting a tender is known as:

(a) earnest money deposit
(b) security deposit
(c) license money deposit
(d) earnest and security money deposits

GPSC AE January 2018

Ans. (a) : Earnest money deposit is used in tender and bidding process and also used in real estate transactions. It is paid at the time of submitting a tender.

67. Once a tender is accepted, a deposit of about 5% of the total estimated cost of the work is called:

(a) earnest money deposit
(b) security deposit
(c) license money deposit
(d) earnest and security deposits

GPSC AE January 2018

Ans. (b) : The security deposit is the amount the contractor has to deposited with owner before awarding a work, after his tender is accepted, this amounts to generally 5% to 10% of estimated cost of the project and is inclusive of the EMD already deposited by the contractor along with the tender.

68. At the time of opening of the tenders invited for public works by a public body,

(a) the contractor is not allowed to remain present
(b) the contractor is invited to remain present
(c) the contractor may be or may not be invited
(d) the contractor do not like to remain present

GPSC AE January 2018

Ans. (b) : The contractor is invited to remain present at the time of opening of the tenders invited for public works by a public body.

69. In case of a unit-price contract, if a contractor quotes higher rates for some items and lower for the other items in the tender, then such a tender is known as:

(a) irregular tender (b) unbalanced tender
(c) balanced tender (d) regular tender

GPSC AE January 2018

Ans. (b) : Unbalanced tender is the tender in which a contractor quotes higher rates for some items and lower for other items.

70. In a civil engineering work contract, the purpose of appointing an arbitrator is to

(a) arbitrarily take measurement of works done
(b) avoid legal formalities, delays and expenses
(c) make the contract legal
(d) avoid arbitration and increase speed of work

GPSC AE January 2018

Ans. (b) : An arbitrator is appointed for avoiding legal formalities, delays and expanses in work contract.

71. The main purpose of framing the conditions of contract is

(a) to make the work stronger and long lasting
(b) to avoid the disputes between parties
(c) to make the contractor responsible for any problem
(d) to make the owner responsible for any problem

GPSC AE January 2018

Ans. (b) : The condition of contract is framed to avoid the dispute between parties.

72. Amount of annual installment of the sinking fund

(a) $I = \frac{Si}{(1+i)^{n-i}-1}$ (b) $I = \frac{Si}{1-(1+i)^{n}}$

(c) $I = \frac{1-(1+i)^{n}}{Si}$ (d) $I = \frac{1+(1+i)^{n}}{Si}$

UP Jal Nigam AE 2016

Ans. (*) :

Amount of annual Installment (I) $= \frac{Si}{(1+i)^{n}-1}$

S = sinking fund
n = year
i = rate of interest

73. Determine the approximate proportion of dry cement mortar required for brick work with bricks of nominal size 19 cm x 9 cm x 9 cm, with 18% extra for frog filling and wastage is : (assume 1 m^3 of wet mortar = 1.3 m^3 of dry mortar) :

(a) 32.5% (b) 26.7%
(c) 35.3% (d) 41%

CIL MT 2020

Ans. (c) : Mortar required for 1 m^3 masonry after taking nominal size brick = 0.2308 m^3.
Mortar for frog filling = 0.230 × 1.18 = 0.2724 m^3.
Given,
1 m^3 wet mortar = 1.3 m^3 dry mortar
Quantity of dry mortar = 0.272 × 1.3 × 100
= 35.4%

74. For 12 mm thick cement plastering 1 : 6 (cement : sand) on 100 sq.m. new brick work, the quantity of cement required is :

(a) 0.305 m^3 (b) 0.274 m^3
(c) 0.197 m^3 (d) 0.200 m^3

DMRC AM 2020

Ans. (b) : Quantity of cement (X) $= \frac{1.25x}{a+b}$
for 12 mm plastering we add 30% extra area
Area = 100 × 0.012 × 1.25 = 1.5
total area = 1.5 + (0.30 × 1.5) = 1.95
quantity of cement $= \frac{1.95}{7} = 0.278\ m^3$

75. If a contractor fails to complete the work, an agency is employed to execute a part of whole of the work at the cost of contractor. Such agency is known as:

(a) Substitute Agency (b) Debitable Agency
(c) Secondary Agency (d) Creditable Agency

JUVNL AE 2016

Search on Telegram @apna_pdf

Ans. (b) : If contractor fails to perform the work successfully or discontinues the work before completion of the period of agreement, the agency handles that work at same cost is known as debitable agency.

76. Which of the following is NOT one of the main purpose of estimating in a civil contract?
(a) To form a basis of arbitration and litigation
(b) To fix up completion period for a given volume of work
(c) To invite tenders and prepare bills for payments
(d) To justify investment based on cost to benefit ratio

NPCC AE 2017

Ans. (a) : In civil engineering, estimation is used to estimate completion period, tender, economy and not for any legal activities.

77. The estimated value of a built-up property at the end of its useful life without being dismantled is its:
(a) Market value (b) Salvage value
(c) Scrap value (d) Book value

NPCC AE 2017

Ans. (b) : Salvage value is the estimated book value of an asset after depreciation is complete.

78. Which of the following is NOT a method for estimating building works?
(a) Long and short wall method
(b) Crossing method
(c) Center line method
(d) Le Chatelier's method

NPCC AE 2017

Ans. (d) : Le-chatelier's method used to test soundness of cement, not for building estimation.

79. The unit weight of 20 mm dia reinforcement steel is :
(a) 1.58 kg/rmt (b) 0.59 kg/rmt
(c) 2.47 kg/rmt (d) 3.85 kg/rmt

GPHC AE 2018

Ans : (c) The unit weight of constructing steel is 8750 kg/m^3.

Unit weight of steel $= \frac{d^2}{162}$

Given, d = 20 mm

$= \frac{20 \times 20}{162} = 2.47 \text{ kg/rmt}$

80. Provision made in estimate for miscellaneous small expenditure which is not included in any item is known as :
(a) Sundries (b) Contingencies
(c) Provisional sum (d) Provisional item

GPHC AE 2018

Ans : (a) Sundries are the provision made in estimate for miscellaneous small expend it are which is not included in any Item.

81. The earnest money is kept equal to :
(a) 1.5% to 2% of tender cost.
(b) 3% to 5% of tender cost.
(c) 4% to 6% of tender cost.
(d) 8% to 10% of tender cost.

GPHC AE 2018

Ans : (a) The earnest money or security money is kept for security of tender and it is about 1.5 to 2% of tender cost.

82. In one cubic meter of cement concrete at 1 : 2 : 4 to be mixed by volume, the number of cement bags requires will be about
(a) 1 (b) 5
(c) 6 (d) 11

WBPSC AE 2012

Ans. (c) : Given 1 : 2 : 4
The sum of ratio = 7
Volume of wet cement concrete = 1.54 m^3

in cum $= \frac{1.54 \times 1}{7} = 0.22 \text{ m}^3$

in kg = 0.22 × 144D

$\text{cum} \times \frac{\text{kg}}{\text{cum}} = 316.8 \text{ kg}$

In bag $= \frac{316.8}{50} = 6.3 = 6 \text{ bags}$

83. Sinking fund is
(a) fund required for sinking of well
(b) fund required for maintenance work
(c) fund required to take c are depreciation of property
(d) fund set aside from income to built up the property at the end of its life

WBPSC AE 2007

Ans. (a) :

84. The Plinth area of building not includes
(a) area of a wall at the floor level
(b) internals shaft for sanitary installations upto 2 sqm in area
(c) lift and wall including landing
(d) area of the cantilevered porch

Chandigarh SDE 2017

Ans. (d) :

2. Basic Principal & Procedure of Estimating

85. The approximate proportion of dry cement mortar required for brick work is :
(a) 20% (b) 10%
(c) 15% (d) 30%

JPSC AE (Pre) 2019

Ans. (d) : Volume of wet cement mortar required for $1m^3$ of brick work is calculated as follows–
Number of brick in 1 m^3 of brick work

$= \frac{1}{0.200 \times 0.1 \times 0.1} = 500 \text{Numbers}$

Hence volume of mortar = 1–500×0.19×0.09×0.09= $0.2305m^3$
Adding additional 10% for wastage (wet mortar total = $0.25m^3$).
Now $1m^3$ of wet mortar = 1.25 mortar of dry mortar

Search on Telegram @apna_pdf

for $0.25m^3$ of wet mortar = $0.3125\ m^3$ of dry mortar
Approximate proportion Dry mortar

$$= \frac{0.3125}{1} \times 100 = 31.25\%$$

86. The cement to dry sand proportion recommended for plastering concrete surface is-

(a) 1 : 3 (b) 1 : 6
(c) 1 : 8 (d) 1 : 10

BPSC AE Pre 2018

Ans. (b) : Cement and sand in the ratio of 1:6 (1 cement : 6 sand) for inner plastering of bricks and for outer plastering mix it is in the ratio of 1:4. On a brick wall never do plastering of thickness more than 12 mm or 15 mm.

87. The method of measurement of concrete work specifies cubic content shall be worked out to the nearest.

(a) $0.1\ m^3$ (b) $0.01\ m^3$
(c) $0.001\ m^3$ (d) $1.0\ m^3$

Karnataka PSC AE 2017 Paper - II

Ans. (b) : Weight of 1 bag of cement = 50 kg and volume of 1 bag of cement = 35 lt, or $0.0345\ m^3$ Therefore cubic content of concrete shall be worked out to nearest $0.01\ m^3$ so that amount of cement used can be calculated correctly without much error.

88. What is the quantity of cement (in kg) and of dry sand (in cubic meter) respectively required for preparing one cubic meter of wet cement mortar of 1 : 5 proportion ?

(a) 310 and 1.05 (b) 290 and 1.05
(c) 280 and 1.00 (d) 280 and 2.00

JPSC AE (Pre) 2019

Ans. (*) : Since $1m^3$ wet cement mortar = $1.25m^3$ of dry mortar and sum of proportions = 1+5=6

So, quantity of cement required $= \frac{1 \times 1.25}{6} = 0.208m^3$

$$= 0.2083 \times \frac{50}{0.0347} = 300kg$$

And, sand $= \frac{5 \times 1.25}{6} = 1.042m^3$

89. The cement consumption per 100 sqm area for 12 mm thick plastering with cement mortar proportion of (1 : 4) is

(a) 18 bags (b) 15 bags
(c) 12 bags (d) 9 bags

GUJRAT PSC AE - II 2017

Ans : (d) Since $1m^3$ wet cement mortar = $1.25m^3$ of dry mortar and sum of proportions = 1+4=5

So, quantity of cement required $= \frac{1.25}{5} = 0.25m^3$

$$= 0.25 \times \left(\frac{50}{0.0347}\right) = 360.23kg$$

Number of cement bag required $\frac{360.23}{50} = 7.2$

Nearest answer is 9 bags.

90. Physical depreciation is due to ___.

(a) Inadequacy
(b) Suppression
(c) Obsolescence
(d) Wear and tear from operation

LMRC AM 2019

Ans. (d) Physical depreciation is due to wear and tear from operation.

91. For painting corrugated steel sheet, surfaces shall be measured flat and the area worked out shall be increased by-

(a) 10% (b) 12%
(c) 14% (d) 20%

MPSC (Mains) 2017 Paper–II

Ans. (c) For painting corrugated steel sheet, the surface area measured is increased by a factor of 14% to account for error and loss of paints.

92. The ability of a building material to withstand prolonged action of high temperature without melting or losing shape is :

(a) Thermal capacity (b) Refractoriness
(c) Specific Heat (d) Fire Resistance

GPSC AE Class (1&2) Paper-II-2017

Ans. (b) : The ability of Building material to withstand prolonged action of high temperature without melting or losing shape is called refractoriness.

93. Which of the following is NOT applicable in contracts as far as security deposit is concerned?

(a) Amount depends on tendered amount
(b) Refundable after maintenance period
(c) Amount can be withheld from any other contract with the same client
(d) Necessary before entering into a contract

CIL MT 2017

Ans. (c) : Amount can be withheld from any other contract with the same client is not applicable in contracts as for as securing deposit is concerned.

94. Earnest money is generally asked to be deposited

(a) at the time of purchase of tender document
(b) at the time of submission of bid
(c) by the successful bidder after he gets the letter of acceptance
(d) at the time of entering the agreement

MPPSC AE 2016

Ans : (b) Earnest money has to be deposited at the time of submission of bid whereas security deposit has to be made after awarding the tender.

95. Which committee recommended that an allowance of 10% of the prime cost as the contractor's profit would be reasonable?

(a) The Rates and Costs Committee, 1957
(b) MPWD Committee, 1940
(c) CPWD committee, 1950
(d) MPSC committee, 2010

[MPSC 2015 Paper-II Mains]

Ans. (a) : The rates and costs committee 1957 recommended that an allowance of 10% of the prime cost as the contractor's profit.

Search on Telegram @apna_pdf

96. For a contract to be valid-

1. Parties to the contract should be competent
2. Proper proposal and its acceptance
3. Free consent of parties involved in the agreement
4. Lawful consideration

(a) 1 and 3 (b) 3 only
(c) 1, 2 and 4 (d) All of the above

[MPSC 2015 Paper-II Mains]

Ans. (d) : A contract is legally binding agreement that recognizes and governs the rights and duties of the parties to the agreements.
For a valid contract –
(1) Parties to the contract should be competent.
(2) Proper proposal and its acceptance,
(3) Free consent of parties involved in the agreement,
(4) Lawful consideration.

97. Which of the following is not a principle of planning?

(a) Aspect (b) Floor Area Ratio
(c) Roominess (d) Prospect

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (b) : Floor area ratio (FAR) is the ratio of a building's total floor area (gross floor area) to the size of the piece of land upon which it is built. It is not a principle of planning and it is fixed by the municipal corporation of the area.

98. Which method of depreciation is suitable for finding depreciation of a building having a life of 100 years?

(a) Constant percentage method
(b) Straight-line method
(c) Sinking fund method
(d) Quantity survey method

MPSC (Mains) 2017 Paper–II

Ans. (b) : Straight line method is suitable for used in depreciation of a building with life of 100 years. Straight line basis is calculated by dividing the difference between an asset's cost and its expected salvage value by the number of years it is expected to be used.
Sinking fund method : It is a technique for depreciating an asset while generating enough money to replace it at the end of its useful life.

99. For 1 cum of cement concrete proportion with stone chips 1 : 2 : 4, the required number of cement bags is-

(a) 6.35 (b) 6.0
(c) 5.5 (d) 4.5

MPSC (Mains) 2017 Paper–II

Ans. (a) : No of cement bags

$$= \frac{\text{Volume of cement required (in } l)}{35l}$$

$$= \frac{1000l \times 1.5}{7 \times 35} = 6.12$$

No. of cement bags = $6.12 \approx 6.35$

100. Purposes of rate analysis are-

(i) To determine the current rate per unit of an item at the locality
(ii) To examine the viability of rates offered by contractors
(iii) To calculate the quantity of materials and labour strength required for project planning.
(iv) To fix labour contract rates

(a) (i), (ii) and (iv) (b) (ii), (iii) and (iv)
(c) (i), (ii) and (iii) (d) (i), (ii), (iii) and (iv)

MPSC (Mains) 2017 Paper–II

Ans. (d) : Purposes of Rate Analysis :
(i) To determine the current rate per unit of an item of work at the locality.
(ii) To examine the viability of rates quoted by contractors.
(iii) To ascertain the quantity of materials and labour strength required to complete the project.
(iv) To revise the schedule of rates due to increase in the cost of materials and labour or due to changed situation.

101. A document containing detailed description of all the items of work together with their current rates is called-

(a) Analysis of rates (b) Abstract of estimate
(c) Schedule of rates (d) None of these

OPSC AEE 2015 PAPER–I

Ans. (a) : A document containing detailed description of all the items of works together with their current rates is called Analysis of rates.

102. A tender is said to be informal-

A. When it is not submitted in the form sold by the department
B. When the tender is not properly filled in or signed by the contractor
C. When the tender is made conditional by way of adding indefinite and uncertain liabilities of usual character to it
D. When it is not supported by the requisite earnest money in the manner prescribed for the purpose in PWD form

(a) A, B and C (b) A, B, C, D
(c) A and D (d) D only

[MPSC 2015 Paper-II Mains]

Ans. (b) : It is a request for tenders to be a formal, structured invitation from supplier to submit a bid to supply products or service.
$\Rightarrow$ All given condition are being informal for a tender.

103. While submitting a tender, the contractor is required to deposit some amount with the department, as guarantee of the tender, known as-

(a) Bank Guarantee (b) EMD
(c) S.D. (d) F.D.

[MPSC 2015 Paper-II Mains]

Ans. (b) : Earnest Money Deposit : The seller takes this amount to check the earnestness of a bidders in case they are selected as winners. The EMD amount has to be paid around 2% of the tender value.
Bank Guarantee - It means a lending institution ensure that the liabilities of debtor will be met in other words, if debtor fails to settle a debt, the bank will cover it.

Search on Telegram @apna_pdf

104. The carpet area of a residential building may be ..... of plinth area.

(a) 15% to 30% (b) 30% to 40%
(c) 40% to 50% (d) 50% to 65%

TNPSC AE 2018

Ans. (d) : Carpet area is the covered area of the usable spaces of rooms at any floor. It is measured between walls to walls within the building and is the sum of the actual areas of the rooms where you can use carpet. For residential building it is generally around 50% to 65% of plinth area.

105. The out-turn (or) task for (per day, per person) brick work in cement mortar (or) lime mortar in arches

(a) 1.25 cu.m (b) 0.85 cu.m
(c) 0.55 cu.m (d) 0.35 cu.m

TNPSC AE 2018

Ans. (c) :

Particulars of items for brick work	Quantity per mason per day
1. In lime or cement mortar in foundation	1.25 cum
2. In lime or cement mortar in super structure	1 cum
3. In lime or cement mortar in arches	0.55 cum
4. Rubble stone masonry in lime or cement mortar.	1 cum

106. Which of the following is the most accurate estimate?

(a) Plinth area estimate
(b) Cube rate estimate
(c) Detailed estimate
(d) Building cost index estimate

TNPSC AE 2018

Ans. (c) : A detailed estimate is a cost of all the activities and materials that would be used in finishing the project. It differs from cost estimate by the meter depth of detailing. It is the most accurate estimate.

107. The following are the types of

(i) Plinth area method
(ii) Cubical content method
(iii) Cost Index method
(iv) Bay-method

(a) Bay-method
(b) Detailed estimate
(c) Approximate estimate
(d) Centre line estimate

TNPSC AE 2018

Ans. (b) : Different types of detailed estimates are as follows:-

(i) Preliminary estimate/rough cost estimate
(ii) Plinth area estimate
(iii) Cube rate or cubical content estimate
(iv) Cost index estimate
(v) Bay estimate method.

108. Floor Area Index (FAI) is

(a) $\frac{\text{Covered area of all floors}}{\text{Plot area}} \times 100$

(b) $\frac{\text{Covered area of ground floors}}{\text{Plot area}} \times 100$

(c) $\frac{\text{Plot area}}{\text{Covered area of ground floors}} \times 100$

(d) $\frac{\text{Plot area}}{\text{Covered area of all floors}} \times 100$

TNPSC AE 2018

Ans. (a) : Floor area index is ratio of covered area of all floor to the plot area.

$$\text{Floor Area Index} = \frac{\text{covered area of all floors}}{\text{Plot area}} \times 100$$

109. Sinking fund is :

(a) the fund for rebuilding a structure when its economic life is over.
(b) raised to meet maintenance costs
(c) the total sum to be paid to the municipal authorities by the tenants.
(d) a part of the money is kept in reserve for providing additional structures and structural modifications

Karnataka PSC AE 2015 Paper - II

Ans. (a) : A sinking fund is a fund established by an economic entity by setting aside revenue over a period of time to fund a future capital expense or repayment of a long term debt. It is a means of repaying funds borrowed through a bond issued. The funds are repaid through periodic payments to a trustee who returns part of the issue by purchasing the bonds in open market.

110. Municipal taxes are assessed on percentage of net income from property and it varies from :

(a) 2% to 5% (b) 6% to 9%
(c) 10% to 12% (d) 18% to 25%

Karnataka PSC AE 2017 Paper - II

Ans. (c) : Municipal taxes are assessed on percentage of net income from property and it varies from 10% to 12%.

111. A portion of an embankment having a uniform up-gradient 1 in 500 is circular with radius 1000 m of the centre line. It subtends 180^0 at the centre. If the height of the bank is 1 m at the lower end, and side slopes 2 :1, the earth work involved is ..... × 1000 m^3.

(a) 24.5 (b) 25.5
(c) 26.5 (d) 27.5

Karnataka PSC AE 2017 Paper - II

Ans. (d) :

112. For the task of estimating and costing, doors and windows are computed in

(a) Running meter (b) Square meter
(c) Cubic meter (d) Numbers

GPSC AE (CLASS 1 & 2) 2019

Search on Telegram @apna_pdf

Ans : (b)

- Stone/brick work, wood work/sunshade → m^3
- Shutter, panel, batten, door, window → m^2
- Windows and door fitting hinges bolts & handle = Number
- Earthwork → such as excavation, filling foundation and plinth → m^3
- Concrete work (all work) → in m^3 (except LC in roof tracing which is measure in m^2)
- Steel work → except iron grills measure in m^2 all other work measure in quintal such as (Iron sheet, steel reinforcement, Rivet) , bolts nut Iron Railing)
- Roofing → measured of centering & shuttering form AC sheet roofing, LC roof cover in m^2 except RCC & RBC slab → m^3
- Plastering, Point & finishing → Point, Pointing, DPC, white washing plastering measure in m^2
- Glass panel → measure in m^2
- Steel wooden truss → measure in m^2
- Pipe → measure in meter.

113. Working out the exact quantities of various items of works is known as

(a) estimating (b) mensuration
(c) valuation (d) quantity surveying

TNPSC AE 2018

Ans. (d) : Quantity surveying (QS) is a method to working out the exact quantities of various, items of works.


114. Sinking Fund Co-efficient (Y_c) is

(a) $Y_c = \frac{i}{(1+i)^n}$ (b) $Y_c = \frac{i}{(1+i)^n - 1}$

(c) $Y_c = \frac{(1+i)^{n-1}}{i}$ (d) $Y_c = (1+i)^{n-1}$

TNPSC AE 2018
ESE 1998

Ans. (b) : Sinking fund factor (SFF) -



$$F = P(1+i)^n$$

$$P = A\left[\frac{(1+i)^n - 1}{i(1+i)^n}\right]$$

$$A = F\left[\frac{i}{(1+i)^n - 1}\right]$$

$$\frac{A}{F} = \left[\frac{i}{(1+i)^n - 1}\right] = SFF$$

SFF = Sinking fund factor
i = Periodic interest rate
n = Number of periods.

115. For a project, it is estimated that the quantity of concrete to be poured, reinforcement work and shuttering work will be 500m^3, 5MT and 250 m^2, respectively. Further, it is estimated that the unit rates for these items will be INR 5000, INR 15000 and INR 4000, respectively, Now, it is proposed that the rates for reinforcement and shuttering work be included in the concrete rate itself. The composite unit rate for the concrete works should be taken as _____ per m^3.

(a) 7050 (b) 6050
(c) 7150 (d) 7250

UPPCL AE 2018

Ans. (c) : Given quantity of concrete poured = 500 m^3
Reinforcement work = 5 MT
shuttering work = 250 m^2
Rate for concrete = Rs. 5000
Rate for R/f work = Rs. 15000
Rate for shuttering work = Rs. 4000
Total cost = Rs. 3575000
compound unit rate of concrete work after R/f and shuttering work included is

$$= \frac{3575000}{500} = 7150/m^3$$

116. Unit of measurement of rock excavation is :

(a) m^3 (b) m^2
(c) cm (d) ft^2
(e) m

CGPSC AE 2017

Ans. (a) Unit of measurement of rock excavation is m^3.

S. No.	Particular of item	Unit of measurement
1.	Earth work in excavation filling	Cubic meter
2.	Concreting works in foundation lintels, slab, chhajja.	Cubic meter
3.	Damp proof coarse	Square meter
4.	Brick work in foundation, Plinth superstructures, walls, arches etc.	Cubic meter
5.	Shutters of doors and windows	Cubic meter
6.	Steel reinforcing bars in RCC and reinforced brick work	Kg/ Quintal
7.	Rivets, bolts, nuts etc	Quintal
8.	Iron grills	Quintal
9.	RCC and RB slab roof	Cubic meter
10.	Lean concrete roof	Square meter
11.	AC shut roofing	Square meter
12.	Plastering, painting, white washing, colour washing, distempering painting works etc.	Square meter
13.	Flooring works	Square meter
14.	Steel, wooden truss	Number
15.	Rain water pipe/ Plain pine	Running meter
16.	Cornice	Running meter

Search on Telegram @apna_pdf

117. For $10m^3$ of reinforced brick work, the number of bricks used will be

(a) 2000 (b) 3700
(c) 4200 (d) 5000

Haryana PSC AE 2010

Ans. (d) : We know that
For, 1 m^3 = 500 bricks
So for, 10 m^3 reinforcement bricks is
= 5000 bricks

118. What is the quantity of cement (in kg) and of dry sand (in cubic meter) respectively required for preparing 1 cubic meter of wet cement mortar of 1:5 proportion?

(a) 270 and 1.00 (b) 290 and 1.04
(c) 290 and 1.00 (d) 310 and 1.04

Haryana PSC AE 2017

Ans. (d) : We know that, the wet volume of cement mortar is = 1.54 m^3
Sum of ratio = 1+5 = 6
The quantity of cement

$$\text{in cum} = \frac{1.54}{6} \times 1 = 0.256 \text{ m}^3$$

in kg = 0.256 × 1440 = 368.64 kg

$$\text{in bag} = \frac{368.64}{50} = 7.3 \text{ bags}$$

and
sand = 7.3 × 1.226 × 5 = 45.19 CuFt
= 1.27 cum

119. The revised estimate will be prepared when the original estimate is likely to exceed more than

(a) 5% (b) 10%
(c) 10.5% (d) 11%

TNPSC AE 2019

Ans. (a) : Revised estimate is prepared
⇒ When original sanctioned estimate is likely to exceed by more than 5%.
⇒ When the expenditure on a work exceeds the amount of administrative sanctioned by more than 10%.

120. The following are known as

(i) Advancement in the planning ideas
(ii) Extra high ceiling
(iii) Structural change
(a) Obsolescence
(b) functional obsolescence
(c) Economic obsolescence
(d) junk value

TNPSC AE 2019

Ans. (b) Functional obsolescence- It occurs when the property loses value due to architectural changes, building style & contractor construction technology changes.

121. Name the type of contract when the contractor undertakes the specific work with all its contingencies for a fixed amount of money.

(a) Labour contract (b) Lump sum contract
(c) Item wise contract (d) Sub Contract

TNPSC AE 2019

Ans. (b) Lump sum contract – where the contractor is required to asked his lump-sum contract to undertake the work.
Item wise rate:- Where the contractor is required to asked rate against each item to take a work.
Lump-sum contract in construction is one of the construction contracts, which is sometimes referred to as stipulated sum of a single price is quoted for the entire project based on plans and specifications and cover the entire project and the owner knows exactly how much the work will cost in advance.

122. A type of estimate required if there is change amounting to more than 5% of the original value due to price hiking or change in specification, but does not include any major change in structural design is called

(a) Detailed estimate
(b) Revised estimate
(c) Supplementary estimate
(d) Rough cost estimate

GUJRAT PSC AE - II 2017

Ans : (b) A type of estimate required if there is change amounting to more than 5% of the original value due to price hiking or change in specification, but does not include any major change in structural design is called Revised estimate.

123. Certain amounts such as water supply fittings, sanitary fittings, door and window fittings, etc. are to be decided by the architect in consultation with his client at some future date. The details of such items are not worked out at the time of inviting tenders, but for execution of such items, a lump sum amount is put up in the bill of quantities. This amount is known as

(a) Prime cost (b) Provisional sum
(c) Spot amount (d) Deviated cost

Gujarat PSC AE 2017

Ans : (a) The term prime cost sum is an allowance for the supply of labour, plant and materials to be provided by a contractor or supplier that will be nominated by the client.

124. In case of big projects, a certain amount to the extent of about 1.5% to 2% the estimated cost is provided in the estimate as

(a) Work charged establishment
(b) Revised estimates
(c) Supplementary estimate
(d) Annual estimate

Gujarat PSC AE 2017

Ans : (a) In case of big projects, a certain amount to the extent of about 1.5% to 2% of the estimated cost is provided in the estimate as work charged establishment.

125. The bill to be used for making a single payment for a work is

(a) First and final bill
(b) Running account bill
(c) Lump-sum contract bill
(d) none of these

TNPSC AE 2012

Ans. (a) : The bill to be used for making a single payment for a work is first and final bill.

Search on Telegram @apna_pdf

126. The field of activities of an engineer includes
(a) estimation
(b) tendering
(c) approval of construction plans by the local authority
(d) all of these


TNPSC AE 2012

Ans. (d) The field of activities of an engineer includes-
- Estimation
- Tendering
- Approval of construction plans by the local authority

127. Quantity of earthwork in excavation for foundation of a room size 4.20m × 3.60m whose wall thickness is 30 cm, breadth of foundation 90 cm and depth of excavation 1 m, is
(a) 15.12 m^3 (b) 14.04 m^3
(c) 16. 20 m^3 (d) none of these

TNPSC AE 2012

Ans. (a) :



Total length of wall
$= 2 \times (4.2 + 0.30) + 2 \times (3.6 + 0.30)$
$= 2 \times 4.5 + 2 \times 3.90$
$= 9 + 7.80$
$= 16.80$ m
Width of foundation = 90 cm = 0.9 m
Quantity of earthwork in excavation for foundation
= 1 m
Total volume $= 16.8 \times 0.9 \times 1$
$= 15.12\ m^3$

128. Estimate
(a) the actual cost of construction of structure
(b) the probable cost arrived at before commencement of the structure
(c) a random guess of the cost of the structure
(d) none of these

TNPSC AE 2012

Ans. (b) Estimate is the probable cost arrived at before the commencement of the structure.

129. In detailed estimate the volumes are worked out to the nearest
(a) 0.001 m^3 (b) 0.005 m^3
(c) 0.01 m^3 (d) 0.05 m^3

TNPSC AE 2012, 2015

Ans. (c) In detailed estimate the volumes are worked out to the nearest 0.01 m^3. Area, worked out to the nearest of 0.01 m^2 and length worked out to the nearest of 0.01 m.

130. The approximate cost of the complete labour as a percentage of the total cost of the building is
(a) 10% (b) 25%
(c) 45% (d) 60%

TNPSC AE 2012

Ans. (b) The approximate cost of the complete labour as a percentage of the total cost of the building is 25%.

131. 'Lead and lift' is the term used in
(a) earthwork
(b) reappropriation of funds
(c) salvage value
(d) tender notification

TNPSC AE 2012

Ans. (a) Allowable in foundation work
Lead = 30 m, lift = 1.5 m

132. Abstract estimate is :
(a) Estimation of quantities of various items of work
(b) Estimation of unit rates of various items of work
(c) Estimation of cost of various items of work
(d) Estimation of leads of various items of work

TNPSC AE 2015

Ans. (c) Abstract Estimate : It is actually last thing or method to do in the completion of detailed estimate. All the rates as well as the quantities of every type of work item is made in the abstract form in this.

133. Estimate the rate of metal at site per Cu.m. whose rate at source is ₹800/Cu.m (including loading & unloading) and lead of 35 km @ a rate of ₹20/km :
(a) ₹ 800.00 (b) ₹ 700.00
(c) ₹ 1500.00 (d) ₹ 2000.00

TNPSC AE 2015

Ans. (c) Lead rate = 35 × 20 = 700
Total rate of metal = 700 + 800
= ₹ 1500.00

134. Estimate the cost of brick work for a wall of 4 m long, 3 m high and 30 cm thick . The rate of brick work is ₹1,500 per Cu.m.
(a) ₹5,40,000 (b) ₹54,000
(c) ₹18,000 (d) ₹5,400

TNPSC AE 2015

Ans. (d) Volume of brick work = $3 \times 4 \times 0.3 = 3.6\ m^3$
Cost of brick = 3.6 × 1500 = Rs. 5400

135. Calculate the quantity of earth work by mid-ordinate method, for 200 m length of a portion of road in an uniform ground. The heights of banks at the two ends being 1.00 m and 2.00 m. The formation width is 10 m and side slope 2:1
(a) 3800 Cu.m (b) 3900 Cu.m
(c) 3950 Cu.m (d) 400 Cu.m

TNPSC AE 2015

Ans. (b) $D_m = \frac{D_1 + D_2}{2} = \frac{1+2}{2} = 1.5\text{m}$

Quantity of earth work = $(B \times D_m + S \times D_m^2) \times L$
$= (10 \times 1.5 + 2 \times 1.5^2) \times 200$
= 3900 Cu.m

136. In building work, the cost for internal electrification, sanitary and water supply works is around.
(a) 10% of estimated cost of building.
(b) 15% of estimated cost of building.
(c) 20% of estimated cost of building.

Search on Telegram @apna_pdf

(d) 25% of estimated cost of building.

Gujarat PSC AE (N.W.R.) 2020

Ans. (c) In building work, the cost for internal electrification, sanitary and water supply works is around 20% of estimated cost of building.

137. In rate analysis, for 100 cubic meter mixed mortar the sum total volume of dry ingredient materials may be taken as–

(a) 115 cubic meter (b) 125 cubic meter
(c) 152 cubic meter (d) 160 cubic meter.

Gujarat PSC AE (N.W.R.) 2020

Ans. (b) : In rate analysis, for 100 cubic meter mixed mortar the sum total volume of dry ingredient materials may be taken as 125 cubic meter.

138. For mortgage purpose, the mortgage value of property is taken as–

(a) 1/2 to 2/3 of the valuation or capitalized value
(b) 2/5 to 2/3 of the valuation or capitalized value
(c) 1/3 to 2/3 of the valuation or capitalized value
(d) 1/4 to 3/4 of the valuation or capitalized value.

Gujarat PSC AE (N.W.R.) 2020

Ans. (a) : For mortgage purpose, the mortgage value of property is taken as 1/2 to 2/3 of the valuation or capitalized value.

139. The purchase price of a machine is Rs. 25,000. The machine has a working life of 35,000 hours and at the end of the working life, the machine can be sold for Rs. 7,500 as scrap. The depreciation charge on the machine is constant. How much will be the per hour depreciation charge on this machine?

(a) Rs. 0.21
(b) Rs. 0.50
(c) Rs. 0.72
(d) Cannot be determined based on the given data

GESCOM (KARNATAKA) AE 2011

Ans : (b) : Given,
Cost of machine (C) = Rs. 25000
Scrap value of machine (V) = Rs. 7500
Working hour of machine (n) = 35000 hrs
By wing formula for depreciation,

$$D = \frac{C - V}{n}$$

$$D = \frac{25000 - 7500}{35000} = 0.5$$

140. Which of the following is a construction estimate?

(a) Initial feasibility estimate
(b) Conceptual preliminary budget
(c) Definite estimate
(d) All of the above

GESCOM (KARNATAKA) AE 2011

Ans : (d) All the given estimates are used for construction estimation.

141. Which of the following items of work would necessarily be included in the estimation of plinth area?

(a) Wall thickness (b) Room area
(c) Verandah area (d) All of the above

GESCOM (KARNATAKA) AE 2011

Ans : (d) Following areas are included during measurement of plinth area:-
(i) Area of wall at floor level.
(ii) Vertical duct for AC and lift well including landing.
(iii) Staircase room or head room other than terrace level.
(iv) Open projection of verandah, Balconies, and parapets.
(v) Room Area.

142. While doing cost analysis, if the standard deviation is high, it would generally lead to

(a) Higher levels of uncertainty
(b) Lower levels of uncertainty
(c) Increased costs
(d) Reduced costs

GESCOM (KARNATAKA) AE 2011

Ans : (c) While doing cost analysis, if the standard deviation is high, it would generally lead to cost increment.

143. Estimate the quantities of plastering (two faces) that is 3 m long, 3 m high and 30 cm thick.

(a) 18 m^2 (b) 27 cum
(c) 18 cum (d) 27m^2

LMRC AM 2019

Ans. (a) Length = 3m
Height = 3m
we don't consider thickness for plastering
$3 \times 3 = 9m^2$ since for two faces = $9 \times 2 = 18m^2$

144. The years purchase for 6% interest is :

(a) 20 (b) 13.33
(c) 16.67 (d) 0.06

KPSC AE 2020

Ans. (c) : Year purchase $(y_p) = \frac{100}{i} = \frac{100}{6}$
$= 16.67$

145. For calculating floor area, area of balcony is considered up to :

(a) 75% (b) 50%
(c) 100% (d) 25%

DMRC AM 2017

Ans. (b) : For calculating floor area, area of balcony is considered up to 50%.

146. Unit of measurement of damp proof course (D.P.C.) is _____.

(a) sq. m. (b) cub. m.
(c) meters (d) cm

DMRC AM 2017

Ans. (a) : Unit of measurement of damp proof course (D.P.C.) is sq.m. DPC is provided at plinth level.

147. The measurement of brick work is not counted in cu.m if it is:

(a) Brick work in arches
(b) Reinforced brick work
(c) One or more than one brick wall
(d) Half brick wall

DMRC AM 2017

Ans. (d) : The measurement of brick is not counted in cu.m if it is half brick wall. All the given options are counted in m^3.

Search on Telegram @apna_pdf

148. No reduction is made in the estimation of masonry for openings of area smaller than:
(a) 1.5 m^2 (b) 1 m^2
(c) 0.5 m^2 (d) 0.1 m^2

DMRC AM 2017

Ans. (b) : No reduction is made in the estimation of masonry for opening of area smaller than 1 m^2.

149. Quintal is a unit of measurement for:
(a) Expanded metal wire netting
(b) Rolling shutters
(c) M.S. reinforcement of R.C.C. works
(d) Collapsible gates with rails

DMRC AM 2017

Ans. (c) : Quintal is a unit of measurement for mild steel (M.S) reinforcement of RCC works.

150. The area to be measured for painting distemper for an internal surface of a plastered 230mm thick brick wall having dimension of 3000mm length and 3200mm height and having a glazed louvered ventilator of size 600mm × 400mm in the wall is
(a) 9.60 sq.m (b) 9.36 sq.m
(c) 9.84 sq.m (d) 9.12 sq.m

ISRO Scientist/Engineer 2018

Ans : (b) Given, length = 3000 mm = 3m
height = 3200 mm = 3.2m
- The total surface area of wall,
  A_1 = Length x Height
  $A_1 = 3 \times 3.2 = 9.6\ m^2$.

Given size of ventilator = 0.6m × 0.4m
- Area of the ventilator,
  $A_2 = 0.6 \times 0.4 = 0.24m^2$

Hence area of wall which is to be painted distemper,
$A = A_1 - A_2$
$A = 9.6 - 0.24$
Area 'A' = $9.36m^2$
Hence, area of wall which is to be painted distemper will be 9.36 m^2.

151. In case of approximate estimation, which one is correct?
(a) It gives a rough idea of the probable expenditure for project financing.
(b) It is used for administrative approval for the project.
(c) It is used for valuation and rent fixation.
(d) All of these

OPSC AEE 2019 Paper–I

Ans. (d) : uses of approximate estimate
1. It gives rough idea of cost of project.
2. To get administrative approval.
3. To decide time for completing project.
4. For valuation and rent fixation.

152. The earthwork quantities are calculated :
(a) By mid-sectional method
(b) By mean-sectional method
(c) By Primordial method
(d) All of these

OPSC AEE 2019 Paper–I

Ans. (d) : The earthwork quantities can be calculated by:
1. Mid-section method.
2. Mean-sectional method.
3. Prismordial method.

153. The detailed estimated of the cost of the project is done by
(a) Unit-quantity method
(b) Total-quantity method
(c) BOQ method
(d) By first two methods

OPSC AEE 2019 Paper–I

Ans. (b) : Detailed estimate is done by total quantity method.

154. Approximate cost of building commonly estimated by
(a) Service unit method
(b) Comparison of costs at relative dates
(c) Rough grouped quantities or elemental bill method
(d) All of these methods

OPSC AEE 2019 Paper–I

Ans. (d) : Approximate method of estimation
(1) Service unit method.
(2) Plinth area method.
(3) Cubical rate method.
(4) Elemental bill method.
(5) Bay method.
(6) Cost comparison method.

155. In long wall and short wall method of estimation which one of the following is correct?
(a) Short wall length in-to-in = centre to centre length – one breadth
(b) Short wall length in-to-in = centre to centre length + one breadth
(c) Long wall length out-to-out = centre to centre length + one breadth
(d) Long wall length out-to-out = centre to centre length – two breadth

OPSC AEE 2019 Paper–I

Ans. (a & c) : Long wall – Short wall method–In this method, the wall along the length of room is considered to be long wall while the wall perpendicular to long wall is said to be short wall.
To get the length of long wall or short wall, calculate first the centre line lengths of individual walls.

156. The Petty Cash limit is not exceed to
(a) Rs. 10,000 (b) Rs. 40,000
(c) Rs. 1, 00,000 (d) Rs. 50,000

TNPSC AE 2018

Ans. (d) : The Petty Cash limit is not exceed to Rs. 50,000.

157. Which of the following measurement is not used in PWD?
(a) Ordinary Measurement Book
(b) Standard Measurement Book
(c) Check Measurement Book
(d) Running Measurement Book

PSPCL AE 2012

Ans. (a) : PWD consist of 3 measurement book mainly
1) Standard measurement book – It is permanent to nature. In this detailed measurement of building are correctly recorded for its completion and estimate for periodic repairs.

Search on Telegram @apna_pdf

2) Check measurement book– It is for exposing errors that afflicts over time and can work for as replicated
3) Ordinary measurement book.

158. Equation for cement requirement in tonners for four-storey R.C.C. framed building (super structure) recommended by C.B.R.I. is
(a) 0.153 A + 0.57 (b) 0.145 A + 0.54
(c) 0.182 A – 0.35 (d) 2.26 A + 66.8

Maharashtra PSC Mains 2018 Paper-2

Ans. (c) : Cement required in tonnes = 0.0204 A – 0.014
A = Plinth area
approximately answer is (c).

159. If the length of 16 mm diameter bar is 10 m, then its weight is
(a) 16.5 kg (b) 16.9 kg
(c) 15.8 kg (d) 16.2 kg

Maharashtra PSC Mains 2018 Paper-2

Ans. (c) : Length of bar l = 10 m
Diameter of bar d = 16 mm = 0.016 m
Density of steel = 7850 Kg/m^3
Total weight = volume × density

$$= \frac{\pi}{4} \times d^2 \times L \times \text{density}$$

$$= \frac{\pi}{4} \times (0.016)^2 \times 10 \times 7850$$

= 15. 78 Kg. ≈ 15.8 Kg.

160. Which of the following is the most correct estimate?
(a) detailed estimate
(b) building cost index estimate
(c) plinth area estimate
(d) cube rate estimate

GWSSB AAE 2015

Ans. (a) : Detailed estimates are prepared by carefully and separately calculating in detail the costs of various items of the work that constitute the project from the detailed working drawings after the design has been finalized. It is a most correct method.

161. The quantum of work of any item a skilled labour is supported to turnout in a day is known as
(a) target work (b) basic work
(c) unit work (d) task work

GWSSB AAE 2015

Ans. (d) : The capacity of doing work by skilled labour in the form of quantity per day is called task or construction activities. It has been listed below particular of item.

162. The most reliable estimate is
(a) Detailed estimate
(b) Preliminary estimate
(c) Plinth area estimate
(d) None of these

Maharashtra PSC Mains 2012 Paper -2

Ans. (a) : The most reliable estimate is detailed estimate as a cost of all the activities and materials that would be used in finishing the project is to be estimated.

163. The unit of measurement for concrete work in R.C.C. is:
(a) Sq.m (b) Cu.m
(c) 10 Sq.m (d) 10 Cu.m

UJVNL AE 2012

Ans. (b) : The unit of measurement for concrete work in R.C.C. is Cu.m.

164. In building estimate, cornice are measured in
(a) Number (nos.) (b) Running meter
(c) Square meter (d) Cubic meter

GPSC AE June 2019

Ans. (b) : • Work consists linear measurements involve length like cornice, fencing, hand soil, bands of specified width etc. are expressed in running meter, (RM).
• Works consists aerial surface like, white washing, plastering in square meter, like volume contents earth work, cement, concrete in cubic meters.
• Single unit works like doors window etc are expressed in numbers.

165. Read the following statements carefully
(i) Plinth area is calculated by taking the external dimensions of the building at the floor level excluding plinth offsets if any.
(ii) Balconies and cantilever projections are not included in the plinth area
(iii) Floor area is equal to plinth area minus area occupied by walls
Now, choose the correct answer from the following
(a) Only (i) and (ii) are correct
(b) Only (ii) and (iii) are correct
(c) Only (i) and (iii) are correct
(d) All (i), (ii), (iii) are correct

GPSC Assistant Prof. 2016

Ans. (d)
(i) Plinth area is calculated by taking the external dimensions of the building at the floor level, excluding plinth off set if any.
(ii) Balconies & cantilever projections are not included in plinth area.
(iii) Floor area is equal to plinth area minus area occupied by walls.

166. Quantity of cement required for 1 cubic meter of concrete of 1:2:4 mix will be
(a) 6.25 bags (b) 4.10 bags
(c) 5.50 bags (d) 6.50 bags

Sikkim PSC AE 2017

Ans. (a) : For cement concrete - Approximately 52% volume is increased for wastage, voids and shrinkage.
Given: 1 m3 → 1:2:4 → M-15
Add 52% final volume = 1.52 m^3
M15 → 1 : 2 : 4

$$\text{Quantity of cement} = \frac{1.52}{1+2+4} = 0.217 m^3$$

We know that,
volume of 1 bag of cement = 0.035 m^3

$$\therefore \quad \text{no. of bag} = \frac{0.2171}{0.035} m^3$$

= 6.20 (bag)

Search on Telegram @apna_pdf

167. The correct match of Column I (type of contract) with Column II (type of works where they can be used) is

Column I	Column II
P. Unit price contract	1. Limited work but exact quantities are known
Q. Lump-sum contract	2. Quality of each item of work is known but exact quantities are unknown
R. Percentage contract	3. Quality as well as quantity of each item of work are unknown

(a) P-1, Q-3, R-2 (b) P-3, Q-2, R-1
(c) P-2, Q-1, R-3 (d) P-3, Q-1, R-2

GPSC AE January 2018

Ans. (c) : Unit price contract - Quality of each item of work is known but exact quantities are unknown
Lump-sum contract- Limited work but exact quantities are known
Percentage contract- Quality as well as quantity of each item of work are unknown

168. The chart which gives an estimate about the amount of materials handing between various work station is known as

(a) Flow chart (b) Process chart
(c) Travel chart (d) Operation chart

UPRVUNL AE 2015

Ans. (c) : A travel chart is a simple table that is useful where there are multiple (and possible irregular) movement between places. It is variation on the check sheet indicating movement from and to any combination of a given set of location.

169. In PWD, a tender is called "for and on behalf of the"

(a) Chief Engineer
(b) Executive Engineer
(c) Governor of the State
(d) Government

TNPSC AE 2012

Ans. (c) : In PWD, a tender is called for and on behalf of the State Governor.

170. Measurement for different kind of work is defined and carried out as per which IS code?

(a) IS 456-1978 (b) IS 1200-1974
(c) IS 475 (d) IS 269-1976

GPHC AE 2018

Ans : (b)
IS : 456 – 1978 → For Plain & RCC Concern
IS : 875 → For earthquake design.
IS : 120 – 1974 → Measurement for civil work.
IS : 269-1976 → For ordinary port land cement.

171. Normal interval of lift in estimation and quantity survey of earthwork is :

(a) 1.0 m (b) 1.5 m
(c) 2.0 m (d) 3.0 m

GPHC AE 2018

Ans : (b) Normal Interval of lift in estimation and quantity survey of earth work is 1.5 m.

172. The cost slope is defined as

(a) $\frac{\text{crash cost - normal cost}}{\text{crash time}}$

(b) $\frac{\text{crash cost}}{\text{normal cost - crash time}}$

(c) $\frac{\text{crash cost - normal cost}}{\text{normal time}}$

(d) $\frac{\text{crash cost - normal cost}}{\text{normal time - crash time}}$

WBPSC AE 2016

Ans. (d) :

173. While submitting a tender the contractor is required to deposit some amount with the department, as guarantee of this tender known as

(a) Bank guarantee (b) Earnest money
(c) Security deposit (d) Caution money

WBPSC AE 2012

Ans. (b) :

174. During the construction period, price variation clause in contracts cater to

(a) variation in cost of materials and labour elements
(b) rate of inflation
(c) variation in total cost of the project on an ad hoc basis
(d) increase in rates of only important materials

WBPSC AE 2007

Ans. (a) :

175. Working out the exact quantities of various items of work is known as

(a) A Estimating (b) Mensuration
(c) Quantity surveying (d) Valuation

WBPSC AE 2003

Ans. (c) :

176. A rectangular box made with thin uniform plate measures 2000 mm × 1000 mm × 1000 mm. When the box is subjected to certain internal pressure, the dimensions in respective directions have changed by +2.0 mm, –1 mm and +1 mm. The change in the volume of the box is _____.

(a) 2.0×10^6 mm^3 (b) 1.0×10^5 mm^3
(c) 2.0×10^3 mm^3 (d) 2.0×10^5 mm^3

TSPSC Deputy Engineer 2015

Ans. (a) :

177. In earth work excavation, normally lead and lift is considered for preparation of road estimate

(a) 30 m and 1.5 m (b) 20 m and 1.5 m
(c) 20 m and 2.0 m (d) 30 m and 2.0 m

TSPSC Deputy Engineer 2015

Ans. (a) :

Search on Telegram @apna_pdf

178. When additional works were found necessary during construction, which were not contemplated at the beginning, the estimate prepared for such items is known as:
(a) Preliminary estimate
(b) Complementary estimate
(c) Supplementary estimate
(d) Revised estimate

TSPSC AEE 2017

Ans. (c) :

179. A ring type of foundation is constructed with internal and external diameters of 8 m and 12 m respectively. If thickness of the slab is 10 cm and cost of RCC per cubic meter is ` 1000, the cost of RCC used in the slab is
(a) ` 8628 (b) ` 6280
(c) ` 2680 (d) ` 1000

TSPSC AEE 2017

Ans. (b) :

180. A fund which is gradually accumulated and set aside to reconstruct the property after the expiry of its period of utility is known as
(a) Annuity (b) Dividend
(c) Mutual fund (d) Sinking fund

TSPSC AEE 2017

Ans. (d) :

181. The system in which the owner acquires land, prepare drawings & estimation and the contractor execute the work, operate and collect fee from the users till the full cost is realized, is known as:
(a) Rate Contract (b) BOT
(c) Lumpsum contract (d) Turnkey

TSPSC AEE 2017

Ans. (b) :

182. The excavation exceeding 1.5 m in width and 10 sq.m. in plan area with a dept not exceeding 30 cm, is termed as
(a) Excavation (b) Surface dressing
(c) Cutting (d) Surface excavation

Chandigarh AE 2017

Ans. (d) :

183. Pick up the incorrect statement from the following:
(a) No deduction is made for the volume occupied by reinforcement
(b) No deduction is made for the opening upto 0.1 sq.m.
(c) No deduction is made for volumes occupied by pipes, not exceeding 100 sq.cm in cross-section
(d) None of these

Chandigarh AE 2017

Ans. (d) :

184. The value of demolished material is known as
(a) scrap value (b) resultant value
(c) salvage value (d) scrap value

Chandigarh SDE 2017

Ans. (c) :

3. Building, Road & Canal

185. If the excavation of earth is done manually then it costs Rs. 80 per m^3 . A machine can excavate at a fixed cost of Rs. 60000 plus a variable cost of Rs. 20 per m^3 . The quantity of earth for which the cost of excavation by machine will be equal to the cost by manual excavation is
(a) 500 m^3 (b) 1000 m^3
(c) 1500 m^3 (d) 2000 m^3

MPPSC AE 2016

Ans : (b) Let amount of earth excavated for equal cost with machine excavation and manual excavation (x)

$80x = 60000 + 20x$

$x = 1000\ m^3$

186. Site order book is used for recording-
(a) Instructions of the executive engineer
(b) Construction measurements
(c) Requisition of plants and equipments
(d) Indents for materials to be ordered

MPPSC AE 2017

Ans. (a) : Site order book is used for recording instructions of the executive engineer and contains the following data :
1. Name of the work
2. Estimate cost
3. Name of the scheme
4. Administrative sanction detail
5. Name of contractor
6. Date of commencement
7. Technical sanction detail
8. Probable date of completion

187. The capitalized value of a property fetching a net annual rent of ₹ 1000 with highest rate of interest prevailing being 5%, would be-

[MPSC 2015 Paper-II Mains]

(a) ₹ 800 (b) ₹ 1000
(c) ₹ 10,000 (d) ₹ 20,000

Ans. (d) :

Capitalized value is given as $C = \frac{A}{r} = \frac{\text{Annual return}}{\text{rate of intrest}}$

$$C = \frac{1000}{0.05} = 20000$$

188. The unit of measurement for earthwork in surface excavation exceeding 1.5 m in width as well as 10 sqm on plan but not exceeding 30 cm in depth, is in-
(a) cu. m (b) sq. m
(c) 10 sq.m (d) R.mt

[MPSC 2015 Paper-II Mains]

Ans. (b) : If excavated depth is less than 30 cm then it is known as surface excavation and measured in square meter.
⇒ If excavated depth is more than 30 cm then it is known as a volumetric excavation and measured in cubic meter.

Search on Telegram @apna_pdf

189. Generally at what rate should slip form be lifted?

(a) 1 m per hour (b) 5 – 10 cm per hour
(c) 20 – 30 cm per hour (d) 50 – 60 cm per hour

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (c) :
⇒ Slip form construction or continuously formed construction, is a construction method in which concrete is poured into a continuously moving form.
⇒ Basically, this method involves the continuous placing of concrete in a shallow mould having the same plan as the building to be constructed. This rigid mould or "slip-form" forms the working deck which is jacked slowly upwards at a controlled rate (20-30 cm/hour) until the required elevation is reached.

190. Principles of planning for buildings include-

A. Aspect and Prospect
B. Roominess
C. Grouping
D. Flexibility and Privacy

(a) A and B only (b) B and D only
(c) A and C only (d) A, B, C and D

Maharashtra PSC (Mains) 2017 Paper–I

Ans. (d) Principles of planning for building include.
i) Aspect and prospect
ii) Roominess
iii) Grouping
iv) Flexibility and privacy

191. Match List-I with List-II and select correct answer:

List-I	List-II
A. Excavation and moving	1. Derrick
B. Pure excavation	2. Dump truck
C. Pure transportation	3. Power shovel
D. Pure hoisting	4. Scrapers

	A	B	C	D
(a)	1	2	3	4
(b)	3	4	2	1
(c)	4	3	2	1
(d)	4	3	1	2

TNPSC AE 2018


Ans. (c) : Equipments used for excavation are power shovel, drag line, hoes and clam shell.
Equipments of transportation are dump truck, belt conveyors, etc. hoisting equipments are pulley, chain hoists, jacks, winch, cranes etc.
Scrappers are used for both excavation and transportation.

192. Drag lines are used to excavate

(a) Hard earth below ground level
(b) Soft earth below ground level
(c) Hard earth above ground level
(d) Soft earth above ground level

TNPSC AE 2018

Ans. (b) : Drag lines are used to excavate soft earth below ground level.



193. The height of extra quantity of earth filled is known as

(a) settlement allowances
(b) additional settlement
(c) extra height allowances
(d) embankment allowances

TNPSC AE 2018

Ans. (a) : Settlement of soil banks is possible due to moisture content changes, increase in loading, etc. So an allowance of 5 to 7% is made along embankment to compensate the settlement of soil.

194. The capacity of a "28 S type" concrete mixer is 0.8 m^3. For mixing one cubic meter of concrete, the quantity of cement required is 5.5 bags. In order to avoid fractional usage of cement bags, the volume of concrete (m^3) to be mixed per batch will be :

(a) 0.78 (b) 0.49
(c) 0.73 (d) 0.44

Karnataka PSC AE 2017 Paper - II

Ans. (c) : For $1m^3 \rightarrow$ 5.5 bags of cement
For $0.8\ m^3 \rightarrow 0.8 \times 5.5 = 4.4$ bags of cement
Now, to avoid fractional usage of cement bags: assume that 4 bags of cement are used.

Quantity of concrete = $\frac{4}{4.4} \times 0.8m^3 = 0.73m^3$

195. The number of cement bags required in making plane cement concrete flooring in an area of size 3 m × 3 m and 100 mm thick using cement concrete of mix 1 : 3 : 6 is :

(a) 4 Bags (b) 44 Bags
(c) 2.6 Bags (d) 26 Bags

Karnataka PSC AE 2017 Paper - II

Ans. (a)
Volume of concrete work = 3 × 3 × 0.1 = 0.9 m^3
wet volume of cement = 1.54
The sum of ratio = 10
In this ratio 1 part of cement is used,

So, $= \frac{1.54 \times 1}{10} = 0.154 = 0.154 \times 1440 = 221.76$ Kg.

No. of bags cement = $\frac{221.76}{50} = 4.4$ bag.

So number of cement bags used in concrete work = volume of concrete work × No. of bags
= 0.9 × 4.4 = 3.96 bag ≈ 4 bag

Search on Telegram @apna_pdf

196. As per IS 1200, in the measurement of brickwork, no deductions shall be made for :

(a) Opening up to 0.1 sq. m in area
(b) Opening up to 0.01 sq. m in area
(c) Opening up to 0.001 sq. m in area
(d) Opening up to 1.0 sq. m in area

Karnataka PSC AE 2017 Paper - II

Ans. (a) : • No deduction is made for following.
• Opening each up to 1000 sq. cm (0.1 sq.meter)
• Ends of beams rafters etc up to 500 sq.cm or 0.05 sq.m in section.

197. Excavation exceeding 1.5 m in width as well as 10 m^2 on plan but not exceeding 30 cm in depth shall be described as :

(a) Surface excavation
(b) Surface dressing
(c) Excavation in trenches
(d) Cutting

Karnataka PSC AE 2017 Paper - II


Ans. (a) : For excavation not exceeding 30 cm in depth, it is described as surface excavation and if the surface excavation is more than 30 cm it will be described as excavation in trenches.

198. In Mass Haul diagram (Mass diagram), the term haul represents the :

(a) Sum of the product of each load by its distance
(b) Distance at any time from the working face of an excavation to the tip end of the embankment
(c) Distance from the centre of gravity of a cutting to that of tipped material
(d) Horizontal distance through which the load is shifted

Karnataka PSC AE 2017 Paper - II

Ans. (a) : Mass haul is defined as the volume of material multiplied by the distance it is moved during construction. A mass haul diagram consists of two objects: a mass-haul line and a mass haul view. The mass haul line represents the free haul and over haul volume in cut and fill conditions along an alignment. The mass haul view is the grid on which the mass haul line is drawn.



Mass haul diagrams are used to compare the economics of the various methods of earth works distribution on road or railway construction schemes.

199. In the method of measurement of earthwork in filling in foundation trench, the filling shall be measured and ..... of deduction will be made for settlement to arrive at the net quantities, in the case where quantity is measured in loose stacks or in carts or lorries. Fill in the blank choosing the correct answer from the options given below :

(a) 10% (b) 5%
(c) 25% (d) 45%

Karnataka PSC AE 2017 Paper - II

Ans. (c) : This deduction is made to compensate for the consolidation of the sand.

200. Group B buildings are:

(a) residential (b) institutional
(c) assembly (d) educational

Kerala PSC AE 2015

Ans. (d) : • **Residential building-** Which have more area than half of its floor area for dwelling purposes.
• **Non-Residential building-** Which building have less area than its floor area for dwelling purposes.
• **Classification of building based on occupancy-**

Group A – Residential
Group B – Educational
Group C – Institutional for care
Group D – Health care
Group E – Business
Group F – Mercantile
Group G – Industrial
Group H – Storage
Group I – Assembly
Group J – Hazardous
Group K – Garages
Group L – Utility
Group M – Miscellaneous

201. The notational colour for existing hazardous building in a site plan is:

(a) Black (b) Red
(c) Purple (d) Dark blue

Kerala PSC AE 2015

Ans. (a) : The existing hazardous building in a site plan are shown in black color.

202. What is the area of building, excluding the area occupied by walls?

(a) net area (b) plinth area
(c) carpet area (d) floor area

Kerala PSC AE 2015

Ans. (b) Net area- Net area is the area required for specific uses such as; classrooms, offices etc. It is measured to the interior face of enclosing wall.
Plinth area- Plinth area is the covered built-up area measured at the floor level of any story.
Carpet area- It is internal measure required to lay carpet which obviously does not include the thickness of wall.
Floor area- It is the area calculated by multiplying the outer to outer dimension of floor, not consider the boundary wall, but include the outer and inner wall of building.

Search on Telegram @apna_pdf

203. An equipment that has an initial value of INR 6.5 lakhs and a service life of 5 years. Taking the salvage value of the equipment to be INR 50,000, which of the following statements is TRUE?

(a) For the 2nd year, the depreciation using the linear method is INR 1.6 lakhs, and the depreciation using sum of years methods in INR 1.2 lakhs

(b) For the 2nd year, the depreciation using both the linear method and the sum of years methods is INR 1.2 lakhs

(c) For the 2nd year, the depreciation using both the linear method and the sum of years methods is INR 1.6 lakhs

(d) For the 2nd year, the depreciation using the linear method is INR 1.2 lakhs, and the depreciation using sum of years methods is INR 1.6 lakhs

UPPCL AE 2018

Ans. (d) : Initial value of equipment = INR 6.5 lakhs
service life = 5 years
salvage value = INR 50000
So, for the 2nd year, the depreciation using linear method is INR 1.2 lakhs, and the depreciation using sum of years, method is INR 1.6 lakhs.

204. Consider the below statements with respect to Large hauled container system :
A. Reduces Handling time.
B. Reduces Un slightly accumulations
Identify the correct statement.

(a) Both statements are false
(b) Both statements are true
(c) Statement A is true B is false
(d) Statement B is true A is false

UPPCL AE 2019

Ans. (b) Handling time is reduced by the use of large container method used for transportation; And the (smell) of the collecting material decreases.
Containers are used to transport large quantities of solid waste materials.

205. Given pc + uc = 0.4 h/trip and dbc = 6 min per trip. Determine the pickup time per trip (phcs), where :
pc = time required to pick up loaded container, h/trip
uc = time required to unload empty container, h/trip
dbc = time required to drive between container locations, h/trip.

(a) 4 h/trip (b) 0.5 h/trip
(c) 0.04 h/trip (d) 0.3 h/trip

UPPCL AE 2019

Ans. (b) For container method

$$\boxed{phcs = pc + uc + dbc}$$

Given,

$$pc + uc = 0.4h / trip$$

$$dbc = 6\,min/\,trip = 0.1h / trip$$

$$phcs = 0.4 + 0.1$$

$$\boxed{phcs = 0.5h / trip}$$

206. A concrete mix is designed as per IS 10262 : 2009. The maximum water content for 20mm aggregate for 50mm slump range is 186 litres. Estimated water content for concrete having 100 mm required slump is _____.

(a) 195.30 Litre (b) 197.00 Litre
(c) 193.44 Litre (d) 191.58 Litre

UPPCL AE 2019

Ans. (b) : As per IS 10262 : 2009, the amount of water should be increased by 3% per 25 mm of slump i.e. if the amount of water is 186 liter for 50 mm slump then the volume of water has to be increased by 6% for 100 mm slump.
Therefore, the amount of water
for 100 mm of slump = 186 × 1.06 = 197.16 liter

207. The minimum floor area of a living room is :

(a) 10 m^2 (b) 15 m^2
(c) 20 m^2 (d) 25 m^2
(e) 50 m^2

CGPSC AE 2017

Ans. (a) The minimum floor area of a living room is 10 m^2.

208. Type of crane used in a congested area is

(a) Gantry cranes (b) Tower crane
(c) Climbing crane (d) Mast crane

TNPSC AE 2019

Ans. (d) Gantry cranes or overhead cranes : These type of cranes due to its large service area freedom from floor obstructions and there way motion are mostly used in factories, steel plants, storage yards, power house, workshop etc.
Tower crane : These cranes are usually employed in erection of high industrial and residential buildings reaching upto several meters in height. It is usually used in assembling high industrial plants with elements of steel structure.
Climbing crane : Self constructing tower cranes are known as climbing crane. They grow in height by easy mechanism while working.
Mast crane : Mast crane is a compact design heavy lift crane having lifting capacity upto 8000 mt. This crane is generally used in congested area.

209. In the context of Town planning, the bye-law must be revised in every

(a) 5–10 years (b) 10–15 years
(c) 15–20 years (d) 20–15 years

TNPSC AE 2019

Ans. (b) In context of town planning, the bye law must be revised after every 10-15 years.

210. The conditions of contract include

(a) conditions relating to measurements and payments
(b) conditions relating to settlement of disputes
(c) conditions relating to labour
(d) all of these

TNPSC AE 2012

Search on Telegram @apna_pdf

Ans. (d) : The conditions of contract include–
(1) Conditions relating to measurements and payments
(2) Conditions relating to settlement of disputes
(3) Conditions relating to workman.

211. Pick up the incorrect statement from the following:
(a) The built-up covered area at the floor level of any storey of a building is called plinth area
(b) The usable covered area of the rooms of any storey of a building is called carpet area
(c) The carpet area of a building along unit area of its kitchen, pantry, store, lavatory, bathroom and glazed verandah is called floor area
(d) none of these

TNPSC AE 2012

Ans. (c)

212. Pick up the correct statement regarding the central line method of estimating a building:
(a) Product of the centre line of the walls and area of cross-section of any item, gives total quantity of the item.
(b) The centre line is worked out separation for different sections of walls of a building
(c) The centre line length is reduced by half the layer of main wall joining the partition wall
(d) All of these


TNPSC AE 2012

Ans. (d)
- Product of the centre line of the walls and area of cross-section of any item, gives total quantity of the item.
- The centre line is worked out separation for different sections of walls of a building.
- The centre line length is reduced by half the layer of main wall joining the partition wall.

213. While estimating for building, the length of long walls and short walls is to be found out at the centre lines of the walls called
(a) long wall short wall method
(b) crossing method
(c) centre line method
(d) whole to part

TNPSC AE 2012

Ans. (c)



Centre line method : In this method, calculate the total centre line length of walls in a building and multiply the same by the breadth and depth of the respective item to get the total quantity at the time.

214. The approximate cost of a building can be found out by
(a) service-unit method
(b) square-metre method
(c) cubic-metre method
(d) all of these


TNPSC AE 2012

Ans. (d) The approximate cost of a building can be found out by any of these.

215. Calculate the earthwork (cum) required to fill a trapezoidal cross-section that has breadth of formation as 20m, center height as 4 m and side slopes as 1 vertical to 2 horizontal. The length of this section is 2km:
(a) 168000 (b) 224000
(c) 246400 (d) 268800

APPSC Poly. Tech. Lect. 2020

Ans. (b) : Length of the trapezoidal c/s = 2 km
Breath of trapezoidal c/s = 20m
Height of trapezoidal c/s = 4m
Side slop = 1V : 2H



Area of Trapezoid

$$= \frac{1}{2}(36+20)\times 4 = 112\text{m}^2$$

Earth work to required to fill a trapezoidal cross section = 112×2000
= 224000m^3

216. You are required to plan the laying of a gully. Which of the following costs should you include?
(a) Setting and laying
(b) Bed concreting
(c) Connection to drains
(d) All of the above

GESCOM (KARNATAKA) AE 2011


Ans : (d) Cost which should be considered while laying a gully is–
(a) Setting and laying
(b) Bed concreting
(c) Connection to drains
(d) Connection of electricity.

217. The formation width of a highway with no transverse slope on an embankment is B. The height of the embankment is d and side slope of the embankment is S:1. The area of cross section of the embankment is
(a) B + d + Sd (b) B × d + Sd
(c) $B\times d+Sd^2$ (d) $\frac{1}{2}(B\times d+Sd^2)$

ISRO Scientist/Engineer 2019

Search on Telegram @apna_pdf

Ans : (c) :



For area of cross section of embankment -


- Area of mid section = Area of rectangular portion area of two triangle portion
- Area of mid section = $B \times d + 2\left(\frac{1}{2} \times Sd \times d\right)$
- Area of embankment = $Bd + Sd^2$

218. For an earthwork, if B is formation width, s is the side slope, L the length of the section and d be the height of the embankment, then quantity of earthwork can be given

(a) (Bd + sd) L (b) (B + s) dL
(c) (B + sd) dL (d) (B + sd^2) dL

GPSC AE March 2018

Ans. (c) :



L = length of section

Area of cross section $= \left[\frac{B + B + 2ds}{2}\right] \times d$

= (B + ds).d

Quantity of earth work = Area × length

= (B + ds) dL

219. In the trapezoidal formula, the line jointing to the top ordinates is assumed to be

(a) circular (b) parabolic
(c) curved (d) straight

GWSSB AAE 2015

Ans. (d) : In this method, boundaries between the ends of ordinates are assumed to be straight. Thus the area enclosed between these line and the irregular boundary lines are considered as trapezoids.

$A = \frac{d}{2}\left[O_1 + O_n + 2\left(O_2 + O_3 + ...O_{n-1}\right)\right]$

O_1 = first ordinate
O_n = Last ordinate
O_2, O_3 = other ordinate

220. In plaster works measurement deduction for opening less than ..... is not made as per mode of measurement.

(a) 1 sq. mt (b) 1.5 sq. mt
(c) 0.5 sq. mt (d) 2 sq. mt

GPHC AE 2018

Ans : (c) As per IS code, In plaster works measurement deduction for opening less than 0.5 m^2 is not mode for mode of measurement.

221. The minimum ratio of opening of door and windows to carpet area of room for ventilation shall be :

(a) 20% (b) 10%
(c) 25% (d) 30%

GPHC AE 2018

Ans : (b) The minimum ratio of opening of door and window to carpet area of room for ventilation shall be 10% and the minimum time for ventilation after unlocking the rooms be 10 minutes.

222. Formula to workout quantity of trapezoidal portion of footing is :

(a) $\frac{h}{3}(A1 + A2 + \sqrt{A1 \times A2})$

(b) $\frac{h}{3}(A1 + A2)$

(c) $\frac{h}{2}(A1 + A2)$

(d) $\frac{h}{2} \times \sqrt{A1 \times A2})$

GPHC AE 2018

Ans : (a) Workout quantity of trapezoidal Portion of footing is given by :

$= \frac{h}{3}(A_1 + A_2 + \sqrt{A_1 + A_2})$

h → height of footing

A_1, $_A2$ → are the parallel length.

223. If the cross sectional areas of an embankment at 30 m intervals are 20, 40, 60, 50 and 30 m^2 respectively, then the volume of the embankment on the basis of prisomoidal rule is

(a) 5300 m^3 (b) 8300 m^3
(c) 9300 m^3 (d) 9400 m^3

WBPSC AE 2016

Ans. (a) :

224. Clamshell is used for

(a) vertical excavation (b) rock drilling
(c) pressure grouting (d) trench construction

WBPSC AE 2007

Ans. (a) :

225. If the cross-sectional areas of an embankment at 30 m intervals are 20, 40, 60, 50 and 30 sq. m respectively, the volume of the embankment of the bass of prismoidal rule is

(a) 5300 m^3 (b) 8300 m^3
(c) 9300 m^3 (d) 10300 m^3

WBPSC AE 2007

Ans. (a) :

4. Miscellaneous

226. Match List I correctly with List II and select your answer using the codes given below:

List I	List II
A. Price work contract	1. Not practiced in government
B. Lump-sum contract	2. Payment made by detailed measurement of different items

Search on Telegram @apna_pdf

C. Item rate contract buildings
3. Adopted for roads, bridges and electrical works

D. Labour contract
4. Petty works and regular maintenance works

Codes

	A	B	C	D
(a)	1	2	3	4
(b)	2	3	4	1
(c)	1	4	3	2
(d)	4	3	2	1

TNPSC AE 2012

Ans. (d) :
Price work contract – Petty works and regular maintenance works
Lump-sum contract – Adopted for roads, bridges and electrical works
Item rate contract buildings – Payment made by detailed measurement of different items
Labour contract – Not practiced in government

227. In long and short wall method of estimation the length of long wall is the centre to centre distance between the wall and
(a) breadth of the wall
(b) half breadth of wall on each side
(c) one fourth breadth of wall on each side
(d) none of these

TNPSC AE 2012

Ans. (b) : In long and short wall method of estimation the length of long wall is the centre to centre distance between the wall and half breadth of wall on each side.

228. The centre **line method is specially adopted for estimating**
(a) circular buildings
(b) hexagonal buildings
(c) octagonal buildings
(d) all of these

TNPSC AE 2012

Ans. (d) : For any shape of building centerline method can be adopted for estimation.

229. Unit of measurements for R.C.C. sunshades (breadth and thickness specified) is
(a) running meter (b) square meter
(c) cubic meter (d) numbers

TNPSC AE 2012

Ans. (a) As breadth and thickness is specified so we measure only length which will be measured in running meter.

230. When the standard data are not available in the standard data book, the materials and labour requirements are actually observed during the execution called
(a) main data (b) sub-data
(c) observed data (d) detailed estimate

TNPSC AE 2012

Ans. (c) When the standard data are not available in the standard data book, the materials and labour requirements are actually observed during the execution called observed data.

231. The specifications define
(a) the quality of materials (b) workmanship
(c) both (a) and (b) (d) none of these

TNPSC AE 2012

Ans. (c) The specifications defined by the quality of material and workmanship.

232. Batching refers to :
(a) Controlling the total quantity at each batch
(b) Weighing accurately, the quantity of each material for a job before mixing
(c) Controlling the quantity of each material into each batch
(d) Adjusting the water to be added in each batch according to the moisture content of the materials being mixed in the batch

Nagaland PSC CTSE 2017 Paper–I

Ans. (c) : Batching refers to -
→ controlling the total quantity at each batch weighing accurately.
→ the quantity of each material for a Job before mixing.
→ Controlling the Quantity of each material into each batch.

233. Which of the following contracts is not type of cost plus contract?
(a) Cost plus percentage contract
(b) Cost plus lump sum contract
(c) Cost plus fixed fee contract
(d) Cost plus fluctuating fee contract

GPSC AE (CLASS 1 & 2) 2019

Ans : (b) : Cost-plus contract where a contractor is paid for all of its allowed expenses, plus additional payment to allow for a profit.
(i) Cost plus percentage contracts
(ii) Cost plus fixed fee contracts
(iii) Cost plus fluctuating fee contract.

234. The 'Force – Majeure' clause in a contract document generally refers to-
(a) Agitation and strikes only
(b) Epidemic of large proportion only
(c) (a) and (b) above
(d) None of the above

Maharashtra PSC (Mains) 2015 Paper–I

Ans. (c) : A "force-majeure" clause (french for superior force) is a contract provision that relieves the parties from performing their contractual obligations when certain circumstances beyond their control arise, making performance inadvisable, commercially impracticable, illegal or impossible.

235. While submitting tender by three envelope method, which envelope contains rates/ amount offered by the tenderer?
(a) Envelope : 3
(b) Envelope nos. : 1 and 2
(c) Envelope : 1
(d) None of the above

Maharashtra PSC Mains 2018 Paper-2

Ans. (a) : Envelope I - Document related to eligibility criteria
Envelope II - Technical bid
Envelope III - Financial bid


Search on Telegram @apna_pdf

236. The length of L-bend for steel to be provided at each end of the reinforcing bars is

(a) 12 times diameter (b) 6 times diameter
(c) 3 times diameter (d) 150 mm

Maharashtra PSC Mains 2018 Paper-2

Ans. (b) :



Total length = $l + 6\phi + 6\phi = l + 12\phi$

For one 'L' bend the length required is 6ϕ (ϕ-diameter).

237. In case of which type of contract, unbalanced tender is not possible?

(a) Open tender
(b) Item rate contract
(c) Percentage rate contract
(d) Unit price rate contract

Maharashtra PSC Mains 2018 Paper-2

Ans. (b and d) : In item rate contract rates are fixed for each item separately

- The amount to be received by the contractor depends on the work done.
- If any imbalances happens in the rates the contractor may stop the work so unbalanced tender is not possible.

238. Which of the following types of contract is used for execution of large works financed by public bodies or the government?

(a) Item rate contract
(b) Percentage rate contract
(c) Cost plus type contract
(d) Target contract

Maharashtra PSC Mains 2018 Paper-2

Ans. (b) : • In Government work profit percentage is given as profit to the contractor.
• Cost plus is not used in government works and item rate, target cannot be fixed for huge projects perfectly.

239. Security deposit is

(a) deposited at the time of filling tender
(b) deposited by the contractor whose tender is accepted
(c) deposited at the time of opening tenders
(d) deposited for fair competition

Maharashtra PSC Mains 2018 Paper-2

Ans. (b) : Security deposit is deposited by the contractor whose tender is accepted in order to do the work effectively and refunded after one monsoon season/6 months which ever is more time period.

240. What will be the mode of measurement for Damp Proof Coarse (D.P.C.)?

(a) Cubic meter (m^3) (b) Square meter (m^2)
(c) Running meter (Rmt) (d) None of above

GPSC Poly. Tech. Lect. 2016

Ans. (b) : A damp-proof course (D.P.C.) is a barrier through the structure designed to prevent moisture rising by capillary action such a phenomenon is known as rising damp. DPC measured in square meter (m^2).

241. Which of the following documents will not be required for drafting the tender notice?

(a) Nature of work and its location
(b) Estimated cost of the work
(c) Mode of submitting tender
(d) Schedule 'A' of the proposed work

Maharashtra PSC Mains 2012 Paper -2

Ans. (d) : Schedule 'A' of the proposed work will not be required for drafting the tender notice.

242. While computing masonry work, no deductions are generally made for

(a) opening each upto 0.10 sq.m
(b) ends of beam upto 0.05 sq.m
(c) bed planes and wall plates upto 10 cm
(d) All the above

Maharashtra PSC Mains 2012 Paper -2

Ans. (d) : While computing masonry work, no deductions are made for the following-

- opening each upto 0.10 sq.m
- ends of beam upto 0.05 sq.m
- bed planes and wall plates upto 10 cm.

243. The estimated quantity of cement required per m^3 in a compacted cement concrete of 1 : 2 : 4 nominal mix is

(a) 305 kg (b) 330 kg
(c) 285 kg (d) 255 kg

Maharashtra PSC Mains 2012 Paper -2

Ans. (a) : 1:2:4 for $1m^3$

Wet volume of cement $= \left(\frac{1}{7} \times 1\right) m^3 = 0.143 m^3$

Dry volume of cement $= \left(1.54 \times \frac{1}{7}\right) m^3 = 0.22 m^3$

Mass density of cement = 1440 kg/m^3

Mass of cement required = 0.22 × 1440
= 316.8 kg

244. Identity correct statements from the following:

1. **Centre line method is the most common method for calculating the quantities of walls.**
2. **Centre line method is suitable for determining quantities of walls which are curved in plan.**
3. **Out-to-out and in-to-in method is the most common method for calculating quantities of walls.**

(a) 1 and 2 (b) 1 and 3
(c) 1 only (d) 2 and 3

Maharashtra PSC Mains 2012 Paper -2

Ans. (d) :

- Center line method is suitable for determining quantities of walls which are curved in plan.
- Out to out and in-to-in method is the most common method for calculating quantities of walls.

Both the statements are correct.

245. The first year cost of maintenance of a building is Rs. 100 and it increases at a uniform rate of 10% per year. If the interest rate is 8%, what is the present worth of cost of the first 5 years of maintenance?

(a) 490.42 (b) 480.42
(c) 500.42 (d) 470.42

OPSC Civil Services Pre 2011

Ans. (b) :

Search on Telegram @apna_pdf

246. The soffit formwork to the beam should not be removed before D days, where D is :

(a) 7.0 (b) 14.0
(c) 1.0 (d) 3.0

UPPCL AE 2015

Ans. (a) : 7 days is a standard time for the setting and getting strength, so soffit framework should be removed before 7 days.

247. According to IS 1200, the formwork shall be measured in :

(a) tonne (b) sq m
(c) cum (d) linear m

UPPCL AE 2015

Ans. (b) : According to IS code 1200, meter square is the unit form for the measurement of fromwork.

248. Which are some of the factors to be considered while designing site layout?

1. Construction sequence
2. Quantity of materials to be stored
3. Parking of workers
4. Sanitary facilities
5. Soil conditions

Answer options:

(a) 1, 2, 3 and 4 (b) All of the above
(c) 1 and 2 (d) 1, 2 and 5

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (b) The factors to be considered while designing site leyout are :

- Construction sequence
- Quantity of materials to the stored
- Parking of workers
- Sanitary facilities
- Soil condition.

249. A construction company has annual demand of 200 M.T. of steel. The annual cost of carrying per M.T. of steel is Rs. 2,000 and the cost to place an order is Rs. 50,000. What is the economic order quantity?

(a) 50 M.T. (b) 70.7 M.T.
(c) 100 M.T. (d) 40 M.T.

Maharashtra PSC (Mains) 2019 Paper–I

Ans. (c) : $\frac{Q}{N} \times C_0 = \frac{1}{2} \times N \times C_n$

$N = \sqrt{\frac{2QC_0}{C_n}}$

$N = \sqrt{\frac{2 \times 2000 \times 50000}{2000}}$

$N = 100$

250. If the corrugated iron sheets undergo distempering or whitewashing, the plan area of the sheets while estimating is generally increased by:

(a) 8% (b) 14%
(c) 7% (d) 2%

JUVNL AE 2016

Ans. (b) : If the corrugated iron sheets undergo distempering or whitewashing, the plan area of the sheets while estimating is generally increased by 14%.

251. Correct match of Column I (types of occasional health hazards in civil engineering projects) with Column II (cause of hazard) is

Column I	Column II
P. Physical hazard	1. Inhalation of dust, fumes, vapor, gases etc.
Q. Chemical hazard	2. Exposure to noise, vibration, electrical shock
R. Biological hazard	3. Working away from home, frequent migration, etc.
S. Social hazard	4. Exposure to infectious bacteria and fungi

(a) P-4, Q-1, R-2, S-3 (b) P-1, Q-4, R-2, S-3
(c) P-3, Q-2, R-4, S-1 (d) P-2, Q-1, R-4, S-3

GPSC AE January 2018

Ans. (d) :

Physical hazard -	Exposure to noise, vibration, electrical shock
Chemical hazard -	Inhalation of dust, fumes, vapor, gases etc.
Biological hazard -	Exposure to infectious bacteria and fungi
Social hazard -	Working away from home, frequent migration, etc.

252. The order of following basic causes of accidents in civil engineering works starting from less severe to more severe is:

(i) Persons being trapped or struck by moving objects
(ii) Persons/material falling from height
(iii) Persons stepping on or striking against objects

(a) i - ii - iii (b) iii - i - ii
(c) iii - ii - i (d) ii - i - iii

GPSC AE January 2018

Ans. (d) : Causes of accident less severe to more severe
(1) persons/material falling from height
(2) persons being trapped or struck by moving objects
(3) persons stepping on or striking against objects

253. Deduction is made in the brick masonry for the opening exceeds:

(a) 0.10 sq.m (b) 0.5 sq.m
(c) 0.35 sq.m (d) 0.25 sq.m

JUVNL AE 2016

Ans. (a) : No deduction are made for opening up to 0.1 m^2, area, in the brick masonry.

254. The unit of measurement for mass concrete is usually:

(a) cubic meter (b) square meter
(c) metric tons (d) linear meter

NPCC AE 2017

Ans. (a) : According to IS-456:2000, measurement of mass concrete in m^3.

Search on Telegram @apna_pdf